

ST LEONARDS HEALTH ORGANISATION RELOCATION (SHOR)

Operational Noise & Vibration Assessment

23 May 2018

Savills Project Management

TJ514-03F02 Operational Noise & Vibration Assessment (rev C)

Document details

Detail	Reference
Doc reference:	TJ514-03F02 Operational Noise & Vibration Assessment (rev C)
Prepared for:	Savills Project Management
Address:	Level 7, 50 Bridge Street Sydney NSW 2000
Attention:	Andreas Winkelmeier

Document control

Date	Revision history	Non-issued revision	Issued revision	Prepared	Instructed	Authorised
22.11.2017	Prepare draft report	0		TW		
01.12.2017	Finalise draft & issue for comments		1	TW		TW
04.12.2017	Update cross references in Section 5.4		2	TW		TW
12.12.2017	SSD Submission		A	TW		TW
24.01.2018	Update Section 3		B	TW		TW
23.05.2018	Update report with additional background noise monitoring at nearest residence		C	THW/TW		TW

Important Disclaimer:

The work presented in this document was carried out in accordance with the Renzo Tonin & Associates Quality Assurance System, which is based on Australian Standard / NZS ISO 9001.

This document is issued subject to review and authorisation by the Team Leader noted by the initials printed in the last column above. If no initials appear, this document shall be considered as preliminary or draft only and no reliance shall be placed upon it other than for information to be verified later.

This document is prepared for the particular requirements of our Client referred to above in the 'Document details' which are based on a specific brief with limitations as agreed to with the Client. It is not intended for and should not be relied upon by a third party and no responsibility is undertaken to any third party without prior consent provided by Renzo Tonin & Associates. The information herein should not be reproduced, presented or reviewed except in full. Prior to passing on to a third party, the Client is to fully inform the third party of the specific brief and limitations associated with the commission.

In preparing this report, we have relied upon, and presumed accurate, any information (or confirmation of the absence thereof) provided by the Client and/or from other sources. Except as otherwise stated in the report, we have not attempted to verify the accuracy or completeness of any such information. If the information is subsequently determined to be false, inaccurate or incomplete then it is possible that our observations and conclusions as expressed in this report may change.

We have derived data in this report from information sourced from the Client (if any) and/or available in the public domain at the time or times outlined in this report. The passage of time, manifestation of latent conditions or impacts of future events may require further examination and re-evaluation of the data, findings, observations and conclusions expressed in this report.

We have prepared this report in accordance with the usual care and thoroughness of the consulting profession, for the sole purpose described above and by reference to applicable standards, guidelines, procedures and practices at the date of issue of this report. For the reasons outlined above, however, no other warranty or guarantee, whether expressed or implied, is made as to the data, observations and findings expressed in this report, to the extent permitted by law.

The information contained herein is for the purpose of acoustics only. No claims are made and no liability is accepted in respect of design and construction issues falling outside of the specialist field of acoustics engineering including and not limited to structural integrity, fire rating, architectural buildability and fit-for-purpose, waterproofing and the like. Supplementary professional advice should be sought in respect of these issues.

Contents

1	Introduction	1
2	Project Description	3
2.1	Background	3
2.2	Overview of Proposed Development	4
2.3	The Site	4
2.4	Operational Noise Sources	6
2.5	Nearest Affected Premises	6
3	Existing Noise Environment	8
4	Relevant Acoustic Criteria	9
4.1	NSW EPA Industrial Noise Policy	9
4.1.1	Building Services Noise Emission Limit	9
4.2	Childcare Outdoor Noise	10
4.2.1	Residential Receivers	10
4.2.2	Commercial Receivers	11
5	Noise Assessment of Mechanical Plant	12
5.1	Proposed Plant Equipment & Location	12
5.2	Noise Issues	13
5.3	Sound Power of Noise Sources	13
5.3.1	Sound Power Levels of Cooling Towers	13
5.3.2	Sound Power Levels of Fans	13
5.3.3	Sound Power Levels of Other Major Plant on Roof	14
5.4	Recommendations	15
5.4.1	Additional Plantroom Requirements	20
5.4.2	Vibration Isolation	20
5.4.3	Compliance certification	21
5.5	Predicted Noise Levels at Nearest Receivers	23
6	Noise Assessment of Childcare Outdoor Play Area	25
6.1	Proposed Child Care Centre	25
6.2	Operational Noise Issue	26
6.3	Sound Power of Noise Source	27
6.4	Predicted Noise Levels at Nearest Receivers	28
6.5	Assessment of Noise Levels at Nearest Receivers	29
7	Conclusion	31
APPENDIX A	Glossary of terminology	32
APPENDIX B	Location & Results of long-term noise surveys	34
B.1	Photographs of Long-term Noise Monitors	34

List of tables

Table 1:	Drawings and Documents Reviewed	1
Table 2:	Sensitive receiver locations	7
Table 3:	Measured Site Background Noise Level (L_{A90})	8
Table 4:	Building Services External Noise Emission Limits to Commercial Receivers (R1, R2 & R4)	9
Table 5:	Building Services External Noise Emission Limits to Receiver R3 (Residential)	10
Table 6:	Operation Noise Criterion at Residential Receivers for Use of Outdoor Play Area	11
Table 7:	Roof Mechanical Equipment Schedule	12
Table 8:	Selected Cooling Tower Sound Power levels (SWL)	13
Table 9:	Proposed Fan Sound Power levels (SWL)	13
Table 10:	Selected/Proposed Chillers, Pumps, Boilers & AHUs Sound Power levels (SWL)	15
Table 11:	Recommended Acoustic Treatment for Control of External Noise Emission from Proposed Mechanical Plant	16
Table 12:	Octave Band Insertion Loss of Recommended Silencers	18
Table 13:	Nearest Noise Sensitive Receivers to Outdoor Play area	26
Table 14:	L_{Aeq} Sound Power Level of Children Playing Outside in dB(A) re.1pW	27
Table 15:	Predicted Noise Levels at Nearest Affected Receivers	29

List of figures

Figure 1:	Site Location Context Plan	5
Figure 2:	Site and Precinct Boundary	5
Figure 3:	Proposed Precinct Plan	6
Figure 4:	Location of proposed building on site, surrounds and receiver & monitoring locations	7
Figure 5:	Recommended Acoustic Treatment to Roof Plant Compounds	19
Figure 6:	Predicted Noise Levels at Nearest Building Facades (3D) from Proposed Mechanical Plant	24
Figure 7:	Predicted Maximum Noise Levels at Nearest Buildings from Proposed Mechanical Plant	25
Figure 8:	Locality map showing child care outdoor area, surrounds and receiver locations	27
Figure 9:	Predicted Noise Levels at Nearest Building Facades (3D) from Outdoor Play Area	28
Figure 10:	Predicted Maximum Childcare Noise Levels at Nearest Buildings	29

1 Introduction

This report supports a State Significant Development Application (SSDA) submitted to the Department of Planning and Environment pursuant to Part 4 of the Environmental Planning and Assessment Act 1979 (EP&A Act) for the St Leonards Health Organisations Relocation (SHOR) Project at the Royal North Shore Hospital (RNSH).

The SSD Application relates to the Concept Plan Approval for the Royal North Shore Hospital, St Leonards which was approved in April 2007 (MP 06_0051). This application is SSD by way of Ministerial declaration pursuant to Section 89(C) of the EP&A Act, the order for which was published on 13 October 2017.

This proposal relates specifically to the construction of a new building on the south-western edge (identified as site 4A under the Concept Plan) of the RNSH Campus. Uses proposed include health-related commercial uses, retail and a child care centre.

This report has been prepared having regard to the Secretary's Environmental Assessment Requirements (SEARs) issued for the project.

Renzo Tonin & Associates were engaged by Savills Project Management to conduct an operational noise assessment in accordance with Condition 8 of the SEARs for the proposed St Leonards Health Organisation Relocation (SHOR) located on southern end of the Royal North Shores Hospital, Reserve Road, St. Leonards. More specifically, this report will provide in principle noise and vibration amelioration methods to reduce any potential acoustic impacts to nearby affected receivers during its operational usage.

The work documented in this report was carried out in accordance with the Renzo Tonin & Associates Quality Assurance System, which is based on Australian Standard / NZS ISO 9001. Appendix A contains a glossary of acoustic terms used in this report.

This assessment has been based on the following architectural and mechanical service drawings and specifications.

Table 1: Drawings and Documents Reviewed

Drawing/Document Title	Reference number	Date	Revision
Architectural Drawings prepared by BVN Architecture Pty Ltd			
Precinct Plan - Proposed	AR-A-00-10	01.06.17	A
Site Plan - Proposed	AR-A-00-11	01.06.17	A
Site Section – A & B	AR-A-00-13	23.02.17	A
Site Section – C & D	AR-A-00-14	23.02.17	A
Contract Site Plan – Proposed	AR-A-00-40	27.02.17	A
GA Plan – Basement Level 1	AR-B-B1-01	24.02.17	A
GA Plan – Basement Level 2	AR-B-B2-01	24.02.17	A

Drawing/Document Title	Reference number	Date	Revision
GA Plan - Ground Level	AR-B-00-01	30.10.17	B
GA Plan – Ground Level NLA Increase	AR-B-00-20	02.03.17	A
GA Plan – Level 1	AR-B-01-01	23.02.17	A
Access Floor Plan – Level 1	AR-B-01-02	03.03.17	A
GA Plan – Level 1 – NLA Increase	AR-B-01-20	02.03.17	A
GA Plan – Typical Level (levels 2-5, 7-9)	AR-B-02-01	23.02.17	A
GA Plan – Level 6 (Warm Shell)	AR-B-06-01	23.02.17	A
GA Plan – Plant Level 10	AR-B-10-01	28.02.17	A
GA Plan – Plant Level 10 with Skylight	AR-B-10-01	24.02.17	A
Roof Plan	AR-B-11-01	24.02.17	A
Roof Plan with Skylight	AR-B-11-02	24.02.17	A
Section A-A	AR-D-XX-01	24.02.17	A
Section B-B	AR-D-XX-02	24.02.17	A
Elevation – North West	AR-C-XX-01	24.02.17	A
Elevation – North East	AR-C-XX-02	24.02.17	A
Elevation – South West	AR-C-XX-03	24.02.17	A
Elevation – South East	AR-C-XX-04	08.11.17	C
Mechanical Services Drawing & Equipment Schedule prepare by Wood & Grieve Engineers			
Basement 1 HVAC Layout	M-20B1	02.03.17	A
Basement 2 HVAC Layout	M-20B2	02.03.17	A
Ground Floor HVAC Layout	M-2000	02.03.17	A
Level 1 HVAC Layout	M-2001	02.03.17	A
Typical Levels 2-5 & 7-9 HVAC Layout	M-2002	02.03.17	A
Level 6 HVAC Layout	M-2006	02.03.17	A
Plant Level HVAC Layout	M-2010	02.03.17	A
Roof Level HVAC Layout	M-2011	02.03.17	A
Air Schematic	M-4100	02.03.17	A
Heating Water Schematic	M-4010	02.03.17	A
Chilled and Condenser Water Schematic	M-4000	02.03.17	A
Mechanical Services Performance Specification	30833-SYD-M	02.03.17	A

2 Project Description

2.1 Background

The subject site is located within the hospital grounds of RNSH, and is identified as Site 4a, within Precinct 4.

The site forms part of a wider Concept Plan approval for the redevelopment and renewal of RNSH (MP 06_0051). On 13 April 2007, approval was granted for a Concept Plan, including proposed building envelopes (height, bulk, scale), associated GFA and land use, site preparatory works, and road networks.

The Concept Plan proposed staged renewal of the entire campus through the nomination of eight precincts and a six-stage construction and delivery strategy. Since concept approval, redevelopment of the following buildings has been completed:

- Kolling Institute Research Building;
- Acute Services Building;
- Clinical Services Building;
- Community Services Building; and
- Multi-Storey Car Park with capacity for 567 spaces.

Under the Concept plan, the subject site is identified as Precinct 4, comprising of Site 4a and Site 4b.

Approval for demolition of existing buildings currently located on Precinct 4 and adjoining areas of the RNSH Campus was obtained as part of a Review of Environmental Factors (REF) under Part 5 of the EP&A Act 1979, dated August 2016. The Part 5 approval also included regrading of land for landscaping purposes and some landscaping works. Other works that have been carried out on site, and were covered under the REF include refurbishment of the existing buildings (Building 33, 35, 36 and the Douglas Building) and other civil infrastructure upgrades.

The Concept Plan has undergone several modifications, with the most recent modification relating to the subject site. Modification 7 (MP 06_0051 MOD 7 - Modification to Concept Plan building footprint in Precinct 4a) was lodged on December 2016 and approved by the DP&E on 20 July 2017. The modification amended the building footprint originally approved for Site 4a under the Concept Plan and consolidated the commercial floor plate design, allowing a more efficient commercial floor plate and an improved design response for the site.

This report identifies and provide quantitative assessment of main noise and vibration generation sources during its operation and outlines measures to mitigate the potential noise impacts on surrounding residential and commercial premises.

2.2 Overview of Proposed Development

This SSD Application seeks approval for works proposed to Precinct 4 (Site 4A and Site 4B) and some adjoining public domain grounds. Specifically, consent is sought for the following:

- Construction of a 10-storey building with a total GFA of 30,977m² comprising of the following uses:
 - 28,615m² of health-related employment generating uses;
 - 658m² lobby;
 - 241m² café;
 - 902m² child care facility;
 - 561m² basement storage and miscellaneous.
- Construction of 2 basement levels with 115 car parking spaces and 1 car wash bay;
- Subdivision of the existing land parcel into the following additional allotments:
 - Proposed Lot 41 (Area 8,049 m2);
 - Proposed Lot 42 (Area 64 m2); and
 - Proposed Lot 40 (Residue Lot comprising the RNS hospital precinct)
- Improved east-west connectivity of the 4A+4B precinct through an at grade pedestrian access way interconnecting Herbert Street (east) to Reserve street (west);
- Creation of an additional easement along the southern alignment of the site for unrestricted vehicular access; and
- Associated public domain and landscaping works.

2.3 The Site

The RNSH Campus is situated approximately 6.5 km north of Sydney CBD and 3 km south west of Chatswood. The RNSH precinct is located within Willoughby City Council LGA, less than 200 metres from St Leonards Station.

The subject site (Precinct 4) is located at the southern edge of the RNSH Campus with direct frontage to Reserve Road (west of the site).

The land is owned by the Health Administration Corporation. Precinct 4 currently forms a part of the Royal North Shore Hospital campus, legally described as Lot 210 under DP 1172133. Total site area of the existing campus is 11.38 hectares.




Figure 1: Site Location Context Plan

Source: Ethos Urban




Figure 2: Site and Precinct Boundary

Source: Ethos Urban




Figure 3: Proposed Precinct Plan Source: BVN

2.4 Operational Noise Sources

Review of the development has identified the following components as the main sources of noise and vibration generation during its operation;

- Noise emission from mechanical and refrigeration plant located on the roof
- Noise emission from outdoor play area of the child care tenancy located on Level 1

It is our understanding the proposed health building will operate 24/7 with its major mechanical and refrigeration plant running continuously.

The proposed operating hours of the child centre will be Monday to Friday between 6:45am and 6:00pm. It is assumed the outdoor area of the child care will not be in full use until at least 15minute after its official opening time of 6:45am ie. operating time of outdoor play area is from 7am to 6pm.

2.5 Nearest Affected Premises

The following noise sensitive receivers were identified from our site inspection and using aerial photography of the surrounding area to be the nearest affected receivers.

Table 2: Sensitive receiver locations

Receiver	Address	Description
R1	Building 31 (Vanderfield Building) of the Royal North Shores Hospital, Reserve Road, St. Leonards	Two storey office building (RNSH Fundraising and Volunteers) located approximately 30m to the north of proposed building on site
R2	Building 36 of the Royal North Shores Hospital, Reserve Road, St. Leonards	Four storey office building (RNSH OH&S) located approximately 20m to the north-east of proposed building on site
R3	3 Herbert Street, St. Leonards	Multi-level residential building with retail shops the lower floors located approximately 82m east of the proposed building on site
R4	207 Pacific Highway, St. Leonards	Multi-storey commercial building located approximately 19m to south of the proposed building on subject site.

Figure 4 provides details of the site, surrounding environment and noise monitoring location.

**Figure 4: Location of proposed building on site, surrounds and receiver & monitoring locations**

3 Existing Noise Environment

One long-term noise logger was installed on site from 06/02/17 to 15/02/17 at Location M1 shown in Figure 4 and two long-term noise monitors were installed on balconies of the nearest residential building at Locations M2 & M3 as shown in Figure 4 from 05/05/18 to 19/05/18 to establish existing site background noise levels. The noise loggers records noise levels on a continuous basis and store data every fifteen minutes. The noise logger was calibrated before and after measurements and no significant deviation in calibration was noted. The noise monitoring equipment used here complies with Australian Standard 1259.2-1990 "Acoustics - Sound Level Meters" and is designated as Type 2 instruments suitable for field use. The graphical recorded outputs from long-term noise monitoring are attached in APPENDIX B including photographs of its locations.

The results of the long-term noise monitoring have been summarised in accordance with Industrial Noise Policy (INP) requirements published by NSW Environmental Protection Authority (EPA) and are presented in Table 3 below.

Table 3: Measured Site Background Noise Level (L_{A90})

Noise Monitoring		Representative Background Noise Levels in dB(A)		
Location	Duration	Day ¹	Evening ²	Night ³
M1 - Building 38 of the Royal North Shores Hospital, Reserve Road, St. Leonards	Monday 06/02/17 and Wednesday 15/02/17	50	46	43
M2 - West facing balcony of U1011 at 3 Herbert Street, St. Leonards	Saturday 05/05/18 and Saturday 19/05/18	58	55	52
M3 - West facing balcony of U2101 at 3 Herbert Street, St. Leonards	Saturday 05/05/18 and Sunday 13/05/18	58	55	52

Notes:

Day, Evening & Night assessment periods are defined in accordance NSW EPA's Industrial Noise Policy as follows.

1. Day is defined as 7:00am to 6:00pm, Monday to Saturday; 8:00am to 6:00pm Sundays & Public Holidays.
2. Evening is defined as 6:00pm to 10:00pm, Monday to Sunday & Public Holidays
3. Night is defined as 10:00pm to 7:00am, Monday to Saturday; 10:00pm to 8:00am Sundays & Public Holidays

The above representative background noise levels (L_{A90}) are used in defining external noise emission limits from the development such as mechanical ventilation and air-conditioning systems in accordance to relevant NSW Government authorities.

The acoustic environment at the location of the long-term noise monitoring M1 is similar to noise-sensitive receivers at R1, R2 and R4 therefore the background noise levels determined at M1 is suitable for defining noise emission limits at R1, R2 and R4.

Noise emission limits to nearest residential receivers R3 (3 Herbert Street) are determined from background noise levels at Locations M2 & M3.

4 Relevant Acoustic Criteria

4.1 NSW EPA Industrial Noise Policy

Noise from mechanical and refrigeration plant to other nearby buildings and surrounding environs shall be controlled to comply with the NSW EPA Industrial Noise Policy as required by Condition 8 of SEARs for the site.

The assessment procedure in terms of the NSW EPA 'Industrial Noise Policy' (INP) has two components:

- Controlling intrusive noise impacts in the short term for residences
- Maintaining noise level amenity for particular land uses for residences and other land uses.

Intrusive Noise Impacts – According to the EPA's INP, the intrusiveness of a mechanical noise source may generally be considered acceptable if the equivalent continuous (energy-average) A-weighted level of noise from the source (represented by the L_{Aeq} descriptor) does not exceed the background noise level measured in the absence of the source by more than 5dB(A).

The intrusiveness criterion is summarised as follows:

$$L_{Aeq} \leq L_{A90} \text{ background noise level plus 5dB(A)}$$

Protecting Noise Amenity – To limit continuing increases in noise levels, the maximum ambient noise level within an area from noise sources other than industrial (eg mechanical plant) should not normally exceed the acceptable noise levels specified in Table 2.1 of the policy.

Where the proposed noise source contains prominent impulsive or other annoying characteristics then adjustments to reduce the criteria shall be made as specified in NSW EPA 'Industrial Noise Policy' (INP).

4.1.1 Building Services Noise Emission Limit

Noise from building services equipment such as ventilation fan and air conditioning systems during the day and night periods are recommended to be pursuant to EPA INP 'intrusiveness criterion' discussed above. Based on the noise monitoring results presented in Table 3 appropriate day, evening and night noise limits were established for the development as shown in Table 4 and Table 5 below.

Table 4: Building Services External Noise Emission Limits to Commercial Receivers (R1, R2 & R4)

Assessment / Receiver Location	Noise Limits for Building Services Equipment Operating During		
	Day ¹	Evening ²	Night ³
Boundary of neighbouring commercial premises	50 plus 5 = 55 dB(A)	46 plus 5 = 51 dB(A)	43 plus 5 = 48 dB(A)

Assessment / Receiver Location	Noise Limits for Building Services Equipment Operating During		
	Day ¹	Evening ²	Night ³

Notes:

Day, Evening & Night assessment periods are defined in accordance NSW EPA's Industrial Noise Policy as follows.

1. Day is defined as 7:00am to 6:00pm, Monday to Saturday; 8:00am to 6:00pm Sundays & Public Holidays.
2. Evening is defined as 6:00pm to 10:00pm, Monday to Sunday & Public Holidays
3. Night is defined as 10:00pm to 7:00am, Monday to Saturday; 10:00pm to 8:00am Sundays & Public Holidays

Table 5: Building Services External Noise Emission Limits to Receiver R3 (Residential)

Assessment / Receiver Location	Noise Limits for Building Services Equipment Operating During		
	Day ¹	Evening ²	Night ³
Boundary of a nearest neighbouring residential property	58 plus 5 = 63 dB(A)	55 plus 5 = 60 dB(A)	52 plus 5 = 57 dB(A)

Notes:

Day, Evening & Night assessment periods are defined in accordance NSW EPA's Industrial Noise Policy as follows.

4. Day is defined as 7:00am to 6:00pm, Monday to Saturday; 8:00am to 6:00pm Sundays & Public Holidays.
5. Evening is defined as 6:00pm to 10:00pm, Monday to Sunday & Public Holidays
6. Night is defined as 10:00pm to 7:00am, Monday to Saturday; 10:00pm to 8:00am Sundays & Public Holidays

Given that the mechanical and refrigeration plant can operate during both day and night the more stringent assessment period is night-time. Therefore, by complying with the noise criterion at night, compliance is automatically achieved during the daytime and evening operations.

Where necessary, noise amelioration treatment will be provided to ensure the design complies with the noise levels recommended by EPA.

4.2 Childcare Outdoor Noise

The "AAAC Guideline for Child Care Centre Acoustic Assessment" published by the Association of Australian Acoustical Consultants is a relevant guide for the noise impact assessment of child care centres. The guideline sets criteria for noise generated in the outdoor play areas to protect reasonable acoustic privacy of nearby residential and commercial receivers.

4.2.1 Residential Receivers

The following noise criteria as presented in the AAAC guideline have been adopted for the operation of the outside play area of the proposed child care centre impacted nearby affected residences.

"Outdoor Play Up to 2 hours (total) per day - The $L_{Aeq,15\text{ min}}$ noise level emitted from the outdoor play area shall not exceed the background noise level by more than 10 dB at the assessment location.

More than 2 hours per day - The $L_{Aeq,15\text{ min}}$ noise level emitted from the outdoor play area shall not exceed the background noise level by more than 5 dB at the assessment location.

The assessment location is defined as the most affected point on or within any residential receiver property boundary. Examples of this location may be:

- 1.5 m above ground level, or
- on a balcony at 1.5 m above floor level, or
- outside a window on the ground or higher floors."

It is our understanding the outside play area will be used for more than 2 hours in total per day.

Therefore, the following criterion has been adopted for the proposed centre:

$$L_{Aeq,15minute} \leq \text{Background noise level} + 5dB(A)$$

Therefore, based on the above criterion and the background noise levels presented in Table 3, the applicable noise limits are as follows.

Table 6: Operation Noise Criterion at Residential Receivers for Use of Outdoor Play Area

Receiver Location	Time	Operational Criterion at Residential Receiver $L_{Aeq, 15minute}$
R3 – Apartment balconies and windows from Levels 4 to 27 of the residential tower at 3 Herbert St, St. Leonards.	Day Time (7am to 6pm)	$58 + 5 \leq 63 \text{ dB(A)}$

Notes:

Day assessment periods are defined in accordance NSW EPA's Industrial Noise Policy as follows.

1. Day is defined as 7:00am to 6:00pm, Monday to Saturday; 8:00am to 6:00pm Sundays & Public Holidays.
2. Proposed business hour of child care is 6:45am to 6pm. It is assumed full usage of outdoor play area is does not start till after 7am.
3. Minimum distance between proposed outdoor area on Level 1 and R3 is 82m.

The outdoor play area is only used during the day thus only day time criterion is applicable.

4.2.2 Commercial Receivers

The following noise criteria as presented in the AAAC guideline have been adopted for the operation of the outside play area of the proposed child care centre impacting nearby commercial receivers.

"The $L_{Aeq,15 \text{ min}}$ noise level emitted from the Child Care Centre shall not exceed 65dB(A) when assessed at the most affected point at of within any commercial property boundary."

Therefore, the applicable noise criterion for Receivers R1, R2, R3 (Levels 1 to 3) & R4 is **65dB(A)** inside any retail or commercial tenancy.

5 Noise Assessment of Mechanical Plant

5.1 Proposed Plant Equipment & Location

All major mechanical plant and equipment associated with the operation of the base building and tenancy spaces have been proposed to be located on the roof. Chillers, pumps, boilers and air handling units to be installed in plantrooms on the roof with louvred openings for discharge and outside air intakes. Fans, cooling towers and associated pumps are to be installed outside the plantrooms.

Table 7 below presents the schedule of proposed mechanical plant equipment for the roof and roof plant rooms.

Table 7: Roof Mechanical Equipment Schedule

Equipment Type	Schedule Plant Item ID	Proposed Location
Cooling Towers	CT-01, CT-02 & CT-03	Roof
Chillers	CH-01, CH-02	Roof plant room
	CH-03	Roof
Pumps	CDWP-01, CDWP-02, CDWP-03, CHWP-01, CHWP-02, CHWP-03, HHWP-01 & HHWP-02	Roof plant room
Air handling units	AHU-BB-W, AHU-BB-SE, AHU-BB-NE & AHU-TN-01	Roof plant room
Boilers	BU-01 & BU-02	Roof plant room
Fans		
Carpark Exhaust	CPXF-BB-01,	Roof
Carpark Supply	CPSF-BB-01	Basement fan room
Loading Dock Exhaust	LDXF-BB-01	Roof
Base Building General Exhaust	GNX-BB-01, GNX-BB-02	Roof
Tenant General Exhaust	GNXF-TN-01	Roof
Base Building Garbage Exhaust	GBXF-BB-01	Roof
Base Building Kitchen Exhaust	KXF-BB-01	Roof
Base Building Kitchen Make-up	KMUF-BB-01	Ground floor - Tenancy ceiling
Kitchenette Exhaust	KNXF-BB-01	Level 1 - Tenancy ceiling
Tenant Kitchen Exhaust	KXF-TN-01	Roof
Tenant Kitchen Make-up	KMUF-TN-01	Roof
Base Building Toilet Exhaust	TXF-BB-01, TXF-BB-02, TXF-BB-03	Roof
Tenant Toilet Exhaust	TXF-TN-01	Roof
Stair Pressurisation ¹	SPF-01, SPF-02	Roof
Smoke Exhaust ¹	SEF-01	Roof
Notes:		
1. Only used during fire emergence or scheduled testing therefore does not form part of assessment		

5.2 Noise Issues

Noise emission from the discharge and intake of the cooling towers and fans, and break-out noise from plantroom openings has potential to impact on nearby noise-sensitive neighbours to the proposed development. The nearest existing residential and commercial buildings potentially impacted by operation of roof top plant equipment has been identified and shown in Figure 4 and Table 2 above.

Plant and equipment on roof can operate any time during day or night, the worst-case scenario will be when all the base building and tenancy equipment are operating at the same time during the night time period (10pm and 7am). Our acoustic modelling and recommendations for noise mitigation are based on compliance with worst-case scenario.

5.3 Sound Power of Noise Sources

At this stage of the development majority of the mechanical plant items has not been finalised and therefore its sound power level data, where this is the case RT&A have selected specific plant from manufacturers catalogue based mechanical performance requirements (capacity and/or flow rates) specified in the Mechanical Services Performance Specification prepared by Wood & Grieve Engineers.

5.3.1 Sound Power Levels of Cooling Towers

The sound power levels associated with three cooling towers selected for this development are outlined in the Table 8 below.

Table 8: Selected Cooling Tower Sound Power levels (SWL)

Item Designation	Manufacturer/ Model	Octave Band Sound Power Level in dB								Sound Pressure Level @ in dB(A)
		63	125	250	500	1k	2k	4k	8k	
CT-01, CT-02 & CT-03	BAC PCT1116-P3-N	109	106	101	93	89	84	79	69	78 @1.5m

5.3.2 Sound Power Levels of Fans

The sound power levels associated with the building ventilation fans proposed for this development are outlined in the Table 9 below. Fan models and associated sound power spectra were selected from Fantech based on airflow rates specified in the Mechanical Services Specification.

Table 9: Proposed Fan Sound Power levels (SWL)

Item Designation	Model	Noise Type	Octave Band Sound Power Level in dB								Sound Pressure Level @3m in dB(A)
			63	125	250	500	1k	2k	4k	8k	
CPXF-BB-1 Carpark Exhaust	Fantech AP1004LP9/19	Inlet	85	85	90	92	95	99	92	78	82
		Outlet	84	84	88	91	94	96	90	77	79

Item Designation	Model	Noise Type	Octave Band Sound Power Level in dB								Sound Pressure Level @3m in dB(A)
			63	125	250	500	1k	2k	4k	8k	
CPSF-BB-1 Carpark Supply	Fantech AP1006CP12/37	Inlet	89	84	88	87	83	80	76	70	68
		Outlet	92	87	89	88	84	81	78	73	69
LDXF-BB-01 Loading dock exhaust	Fantech AP0502JP6/17	Inlet	78	77	84	79	82	83	82	79	68
		Outlet	79	72	83	79	81	83	81	79	68
GNXF-BB-01 & 02 Base building general exhaust	Fantech AP0504JP6/11	Inlet	71	81	80	75	70	67	64	57	57
		Outlet	70	81	81	74	70	68	64	58	57
GNXF-TN-01 Tenant general exhaust	Fantech AP0806BP14/15	Inlet	77	74	84	85	83	76	69	53	66
		Outlet	83	81	87	86	83	79	75	66	67
GBXF-BB-01 Base building garbage exhaust	Fantech AP0504AP5/16	Inlet	72	79	75	77	73	69	66	54	58
		Outlet	75	76	77	73	71	69	67	63	56
KXF-BB-01 Base building kitchen exhaust	Fantech AP0804AP10/14	Inlet	84	79	95	94	89	80	75	70	74
		Outlet	86	86	89	94	94	93	88	81	78
KMUF-BB-01 Base building kitchen make-up	Fantech AP0804AP10/10	Inlet	84	79	95	94	89	80	75	70	74
		Outlet	86	86	89	94	94	93	88	81	78
KNXF-BB-01 Kitchenette Exhaust	Fantech AP0312JP3/10	Inlet	75	84	83	81	77	70	67	63	62
		Outlet	77	83	84	81	76	69	67	64	61
KXF-TN-01 Tenant Kitchen Exhaust	Fantech AP0804AP10/10	Inlet	84	79	95	94	89	80	75	70	74
		Outlet	86	86	89	94	94	93	88	81	78
KMUF-TN-01 Tenant Kitchen Make-up	Fantech AP0804AP10/10	Inlet	84	79	95	94	89	80	75	70	74
		Outlet	86	86	89	94	94	93	88	81	78
TXF-BB-01,02,03 Base Building Toilet Exhaust	Fantech AP0806BP14/15	Inlet	77	74	84	85	83	76	69	53	66
		Outlet	83	81	87	86	83	79	75	66	67
TXF-TN-01 Tenant Toilet Exhaust	Fantech AP0806BP14/15	Inlet	77	74	84	85	83	76	69	53	66
		Outlet	83	81	87	86	83	79	75	66	67

5.3.3 Sound Power Levels of Other Major Plant on Roof

The sound power levels associated with chillers, pumps, boilers and air handling units selected for this development are outlined in the Table 10 below. Pump and AHU model and make were selected based on capacity and airflow rates specified in the Mechanical Services Specification.

Table 10: Selected/Proposed Chillers, Pumps, Boilers & AHUs Sound Power levels (SWL)

Item Designation	Manufacturer/ Model	Octave Band Sound Power Level in dB								Sound Pressure Level in dB(A)
		63	125	250	500	1k	2k	4k	8k	
CH-01,02	Smardt Water Cooled Chiller	83.4	82.4	85.4	85.4	90.4	86.4	79.4	83.4	85@1m
CH-03	Smardt Air Cooled Chiller	74.6	81.4	77.8	76	78.8	73.4	74	72.7	75@1m
CHWP-01, CHWP-02	Derived previous project measures of Grundfos pumps ¹	86	84	83	81	88	82	78	69	77@1m
CHWP-03	Derived previous project measures of Grundfos pumps ¹	80	78	77	75	82	76	72	63	71@1m
CDWP-01, CDWP-02, CDWP-03	Derived previous project measures of Grundfos pumps ¹	92	90	89	87	94	88	84	75	83@1m
HHWP-01, HHWP-02	Derived previous project measures of Grundfos pumps	80	78	77	75	82	76	72	63	71@1m
AHU-BB-W	GJ Walker AM 200 (ref Flakt Woods) ²	73	85	68	57	60	61	56	50	-
AHU-BB-SE	GJ Walker AM 200 (ref Flakt Woods) ²	73	85	68	57	60	61	56	50	-
AHU-BB-NE	GJ Walker AM 156 (ref Flakt Woods) ²	73	85	68	57	60	61	56	50	-
AHU-TN-01	GJ Walker AM 66 (ref Flakt Woods) ²	66	78	62	51	53	51	46	42	
BU-01, BU-02	Simons 800kW Boiler ²	100	85	86	81	80	78	73	69	75 @1m

Notes:

1. Calculated from previous project measurements of Grundfos pumps with similar flow rates to WGE performance specification
2. Sound power spectra from previous project based on similar kW capacity and/or flow rates to WGE performance specification
3. Boiler sound power spectra from previous project adjusted to match manufacturer's 75dB @1m sound pressure specification.

5.4 Recommendations

Based on the equipment selection outlined in Table 8, Table 9 and Table 10 and worst-case scenario where all plant are operating at design loads during night time period (10pm to 7am), the following recommendations are provided for control of external noise emission to comply noise levels outlined in Table 4 above.

Table 11: Recommended Acoustic Treatment for Control of External Noise Emission from Proposed Mechanical Plant

Plant Item	Recommended Acoustic Treatment		
	Case Radiated	Intake Side	Discharge Side
Cooling Towers & Associated Pumps			
Cooling Towers: CT-01, CT-02, CT-03	Install 6.3m height acoustic screen to east and south side of the plant area for the cooling and associated pumps as indicated in Figure 5 below. Acoustic screen shall be of solid construction such as fibre cement sheeting, Colorbond, masonry or Hebel and at least 1.5m higher than top of the cooling towers (4.8m height).		
And Pumps: CDWP-01, CDWP-02, CDWP-03	No acoustic treatment is required for west side of the plant area and standard visual louvres may be installed. No acoustic treatment is required for the open top of this plant area.		
Fans			
CPXF-BB-1 Carpark Exhaust	Wrap fan casing and ductwork/silencer 1m either side of fan with 1 layer of barium-loaded vinyl (minimum density of 4kg/m2) equivalent to Pyrotek Soundguard Wavebar	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.8m long circular silencer C2P-100 (refer to Silencer 1 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.8m long circular silencer C2P-100 (refer to Silencer 1 in Table 12 below).
CPSF-BB-1 Carpark Supply (Located in basement fan room)	Install fan inside fan room as per Mechanical Services Drawing M-20B1 Rev A	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech1.8m long circular silencer C2-100 (refer to Silencer 2 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.8m long circular silencer CP-100 (refer to Silencer 2 in Table 12 below).
LDXF-BB-01 Loading dock exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).
GNXF-BB-01 & 02 Base building general exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).
GBXF-BB-01 Base building garbage exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).
GNXF-TN-01 Tenant General Exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.15m long circular silencer C2-050 (refer to Silencer 3 in Table 12 below).

Plant Item	Recommended Acoustic Treatment		
	Case Radiated	Intake Side	Discharge Side
KXF-BB-01 Base building kitchen exhaust	Wrap fan casing and ductwork/silencer 1m either side of fan with 1 layer of barium-loaded vinyl (minimum density of 4kg/m ²) equivalent to Pyrotek Soundguard Wavebar	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
KMUF-BB-01 Base building kitchen make-up (Located in ceiling space of ground level tenancy)	Install fan inside ceiling or plant room of tenancy	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
KNXF-BB-01 Kitchenette Exhaust (Located in ceiling space of level 1 tenancy)	Install fan inside ceiling or plant room of tenancy	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 0.6m long circular silencer C2-031 (refer to Silencer 5 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 0.6m long circular silencer C2-031 (refer to Silencer 5 in Table 12 below).
KXF-TN-01 Tenant Kitchen Exhaust	Wrap fan casing and ductwork/silencer 1m either side of fan with 1 layer of barium-loaded vinyl (minimum density of 4kg/m ²) equivalent to Pyrotek Soundguard Wavebar	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
KMUF-TN-01 Tenant Kitchen Make-up	Wrap fan casing and ductwork/silencer 1m either side of fan with 1 layer of barium-loaded vinyl (minimum density of 4kg/m ²) equivalent to Pyrotek Soundguard Wavebar	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
TXF-BB-01,02,03 Base Building Toilet Exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
TXF-TN-01 Tenant Toilet Exhaust	No treatment required	Provide sound attenuator to intake side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).	Provide sound attenuator to discharge side of fan with equivalent insertion loss to a Fantech 1.5m long circular silencer C2-080 (refer to Silencer 4 in Table 12 below).
Chillers & Pumps			
Smardt Water Cooled Chiller: CH-01, 02 And Pumps: CHWP-01, CHWP-02, CHWP-03	Install chillers and pumps inside Chiller plantroom as per Mechanical Services Drawing M-2010 Rev A. Install an acoustic louvre with equivalent insertion loss to Fantech SLB2 (refer to Louvre 2 in Table 12 below) to external wall (north) opening as indicated in Figure 5 below. Walls and roof/ceiling of plantroom shall comply with Section 5.4.1.		

Plant Item	Recommended Acoustic Treatment		
	Case Radiated	Intake Side	Discharge Side
CH-03	Install Fantech SLB1 acoustic louvre to south side of CH-03 plant area as in Figure 5 below.		
Smardt Air Cooled Chiller	No acoustic treatment is required for the open top of this plant area.		
Boilers: BU-01, BU-02 Pumps: HHWP-01, HHWP-02	Install boilers and pumps inside boiler plantroom as per Mechanical Services Drawing M-2010 Rev A. Install an acoustic louvre with equivalent insertion loss to Fantech SLB2 (refer to Louvre 2 in Table 12 below) to external wall (south) opening as indicated in Figure 5 below. Walls and roof/ceiling of plantroom shall comply with Section 5.4.1.		
AHU-BB-NE & AHU-TN-01	Install AHUs inside AHU plantroom 1 as per Mechanical Services Drawing M-2010 Rev A. Install an acoustic louvre with equivalent insertion loss to Fantech SLB1 (refer to Louvre 1 in Table 12 below) to external wall (north) opening as indicated in Figure 5 below. Walls and roof/ceiling of plantroom shall comply with Section 5.4.1.		
AHU-BB-SE	Install AHUs inside AHU plantroom 2 as per Mechanical Services Drawing M-2010 Rev A. Install an acoustic louvre with equivalent insertion loss to Fantech SLB1 (refer to Louvre 1 in Table 12 below) to external wall (south) opening as indicated in Figure 5 below. Walls and roof/ceiling of plantroom shall comply with Section 5.4.1.		
AHU-BB-W	Install AHUs inside AHU plantroom 3 as per Mechanical Services Drawing M-2010 Rev A. Standard visual louvre may be installed to external wall (north) opening as indicated in Figure 5 below. Walls and roof/ceiling of plantroom shall comply with Section 5.4.1.		
Notes			
1. Treatment will require to be revised where Mechanical Contractor select different plant, plant location and/or duct work configuration			

The acoustic performance requirements of the recommended silencers and acoustic louvres to intake and discharge are outlined in the Table 12 below.

Table 12: Octave Band Insertion Loss of Recommended Silencers

Recommended Attenuator	OCTAVE BAND CENTRE FREQUENCY (Hz)							
	63	125	250	500	1K	2K	4K	8K
Silencer 1: Fantech C2P-100 1800mm long circular attenuator or approved equivalent	8	11	19	27	29	27	23	19
Silencer 2: Fantech C2-100 1800mm long circular attenuator or approved equivalent	6	8	13	22	19	13	12	10
Silencer 3: Fantech C2-050 1150mm long circular attenuator or approved equivalent	5	7	11	18	21	17	15	12
Silencer 4: Fantech C2-080 1500mm long circular attenuator or approved equivalent	5	8	12	22	23	16	15	10
Silencer 5: Fantech C2-031 600mm long circular attenuator or approved equivalent	3	6	9	15	21	17	14	13
Fantech SBL1 300mm deep acoustic louvre or approved equivalent	4	7	9	13	14	12	12	8
Fantech SBL2 600mm deep acoustic louvre or approved equivalent	5	10	14	22	27	25	21	17




Figure 5: Recommended Acoustic Treatment to Roof Plant Compounds

5.4.1 Additional Plantroom Requirements

- s1. Plant room walls as indicated in Table 6 above shall be of a solid construction such as masonry, Hebel or dry wall with insulation in cavity and full-height ie extending to roof
- s2. Roof of all plant rooms shall be of a solid construction such as concrete or metal deck roof with plasterboard ceiling and insulation in cavity.
- s3. Access door into plantrooms shall be minimum 45mm thick solid-core timber door with full perimeter acoustic seals
- s4. Any small gaps around frame of acoustic louvre shall be sealed on both sides with a mastic sealant. Large gaps shall be packed through its depth with acoustic insulation. Both sides of gap shall be sealed with metal angles using an approved acoustic sealant
- s5. All gaps and penetrations in the external wall and roof/ceiling of the plant room shall be sealed airtight using an approved mastic sealant equivalent to Promat Fyerguard Promoseal with specify gravity of 1.6.

5.4.2 Vibration Isolation

The following vibration isolation advice is provided for control of structure-borne noise into building structure;

- s1. Pumps, chillers and cooling towers should be vibration isolated off the roof slab with spring isolation mounts that incorporate neoprene rubber base and have a 50mm minimum static deflection. All associated duct and pipes shall be vibration isolated from support structure using resilient mounts
- s2. Fan shall be vibration isolated off slab soffit using neoprene/spring hangers having a minimum static deflection of 25mm
- s3. Air handling units shall be vibration isolated off plinth with neoprene mounts
- s4. Roof mounted fans shall be vibration isolated off roof slab or support structure with neoprene mounts
- s5. Fans shall be isolated from duct work on inlet and discharge side of fan with flexible connectors
- s6. Ductwork supported from the concrete soffit shall be isolated with neoprene hangers.
- s7. Ductwork associated with supply and exhaust fans shall not be fixed into riser walls adjoining apartments

- s8. If it is necessary to fix ductwork to walls of riser shafts, the fixings shall be minimised and ductwork shall be vibration isolated from the riser or any adjoining construction using neoprene mounts or equivalent. A clear gap shall be maintained between ductwork and riser walls.
- s9. Where applicable, fan plant room walls shall be of solid construction (full-height plasterboard or masonry) with sound-rated access door.
- s10. Where applicable, penetrations shall be sized for mechanical ducts passing through building slabs or plant room walls to allow a uniform clearance of 10-20mm around the item and this space shall be packed through its depth with acoustic insulation. The joints on both sides shall be sealed on both sides with metal angles using approved acoustic sealant.

5.4.3 Compliance certification

- s11. The levels shall be measured using a sound level meter complying with AS 1259, Part 2 – Sound Level Meters, Type 1 – Precision.
- s12. Internal noise compliance tests shall be conducted over a 1 minute period with all plant operating at normal rated speed. The ambient noise level shall also be obtained with all plant turned off. The measurements shall be carried out when ambient noise levels are sufficiently low to obtain a valid measurement and corrected for the ambient noise level. The noise level contribution from all plant when operating in isolation or in combination with any other plant shall not exceed the criteria in Section 4.1.
- s13. An allowance of 3 dB(A) (subtracted from the noise level contribution determined in accordance with the preceding clause) may be applied when measurements are made in rooms which are uncarpeted for the time being. However, this does not preclude the Sub-Contractor from complying with the requirements of Section Section 4.1 when the rooms are finally carpeted.
- s14. Where both mechanical and hydraulic plant noise are audible, the total noise level from all plant operating shall include noise contribution from all mechanical and all hydraulic plant running contemporaneously at normal rated speed.
- s15. Noise levels shall be conducted in typical spaces on every level within the building as directed by the Principal's acoustic consultant.
- s16. External noise compliance measurements shall be conducted over a 15-minute period with all plant operating at normal rated speed. The ambient noise level will all plant turned off shall be measured immediately after. Measurements shall only be conducted when ambient noise levels are sufficiently low to obtain a valid measurement and shall be corrected for the ambient noise level. The noise contribution from all measured mechanical services plant when operating in isolation or in combination with any other plant shall not exceed the criteria in Section 4.1.

- s17. The external noise emission criteria specified in Section 4.1 are applicable at any boundary or other noise sensitive location as determined by the Principal's acoustic consultant.
- s18. Where the ambient external noise level prevents noise levels being measured at the boundary of nearby affected premises, extrapolation of measurements closer to the noise source is permitted.
- s19. The Principal reserves the right to test plant noise emission and noise intrusion in order to determine their conformance with each of the criteria nominated in this specification.
- s20. A Noise Compliance Report detailing the results of mechanical plant noise levels measured in accordance with this specification shall be presented to the Principal.

5.5 Predicted Noise Levels at Nearest Receivers

External noise emissions from the proposed mechanical plant were predicted by modelling the noise sources, receiver locations, building facades, and possible noise control treatments using the internationally recognised environmental noise prediction computer program CadnaA (version 4.5).

The noise prediction models take into account:

- Location of noise sources and receiver locations;
- Height of sources and receivers;
- Separation distances between sources and receivers;
- Shielding from building and intervening structures;
- Break-out noise from plant room openings;
- Implementation of recommend noise mitigation measure in Section 5.4 above

Figure 6 and Figure 7 below are graphical representations of the predicted noise levels at facades of nearby residential and commercial buildings using CadnaA software.




Figure 6: Predicted Noise Levels at Nearest Building Facades (3D) from Proposed Mechanical Plant




Figure 7: Predicted Maximum Noise Levels at Nearest Buildings from Proposed Mechanical Plant

The predicted noise levels shown in Figure 6 and Figure 7 have demonstrated with the implementation of the noise and vibration mitigation measures described in Section 5.4 operational noise from proposed mechanical plant to comply with the Project noise criteria defined in Table 4 and Table 5 at the nearest affected residential and commercial receivers.

6 Noise Assessment of Childcare Outdoor Play Area

6.1 Proposed Child Care Centre

The child care facility is located on first floor with approximately 700m² of outdoor play area. The proposed facility will be used for the day care of up to 100 children. The proposed breakup of children in each age group is as follows:

- 16 x 0-2 year old
- 40 x 2-3 year old
- 44 x 3-6 year old

Children playrooms and amenities, administration areas and staff amenities will be located within the tenancy.

The proposed operating hours of the centre will be Monday to Friday between 6:45am and 6:00pm. Outside play area is assumed to be scheduled for use any time from 7am to 6pm.

6.2 Operational Noise Issue

Operational noise from the use of the outdoor play area has potential to impact on nearby existing neighbours to the child care centre.

The outdoor play area is situated on the southern part of the first floor and the nearest affected neighbours were identified as the commercial neighbours (R4) on the site southern boundary, commercial neighbours (R2) to the north-east of site, and residential/retail neighbour (R3) to the far east across Herbert Street as shown in Figure 8 and Table 13 below. Receivers R1 shown in Figure 4 above are not affected by noise emitted from the outdoor play area.

Table 13: Nearest Noise Sensitive Receivers to Outdoor Play area

Receiver	Description
R2	South-east façade of the 4-storey office building with windows facing new development
R3	Apartments with windows and balconies facing Herbert Street on Levels 4 to 26 and retails on Levels 1 to 3 with windows or glazed façade facing Herbert Street – at 3 Herbert Street, St. Leonards. Retail windows/glazed external wall are fixed glass.
R4	Northern facade of the 7-storey office buildings approximately 19m south of the outdoor play area – 207 Pacific Highway, St. Leonards. All windows of the office building are fixed glass.

The worst-case scenario will be when all the age groups are utilising the outdoor play area during the same outdoor play session.




Figure 8: Locality map showing child care outdoor area, surrounds and receiver locations

Noise impacts are assessed to these nearest receivers and where necessary noise mitigation measures are recommended to comply with noise criteria established in Section 4.2 above.

6.3 Sound Power of Noise Source

The AAAC Guideline for Child Care Centre Acoustic Assessment provides typical sound power levels of children of different age group playing. The sound power levels recommended in the AAAC guideline were used in the noise calculations for the outside play areas. The sound power levels obtained from the guideline are adjusted to take into consideration the number of children in each age group and in each outside play area to enable prediction of noise levels to receiver locations.

Based on the anticipated number of children in the outside play areas, the source noise levels used in this assessment are shown in Table 14 below in terms of sound power levels. As a worst-case scenario, it has been assumed that all age groups use the outdoor play area during the same play session and each group has half of the children engaged in active type play activities (ie children free play) and other half in passive activities.

Table 14: L_{Aeq} Sound Power Level of Children Playing Outside in dB(A) re.1pW

Noise Sources	L_{Aeq} Sound Power Level
16 x 0-2 year old	81 dB(A)
40 x 2-3 year old	92 dB(A)
44 x 3-6 year old	94 dB(A)

Notes: 1. Source noise levels based on 50% active type activities eg children free play and 50% passive type activities

6.4 Predicted Noise Levels at Nearest Receivers

Noise emissions from the proposed outdoor play area were predicted by modelling the noise sources, receiver locations, building facades, and possible noise control treatments using the internationally recognised environmental noise prediction computer program CadnaA (version 4.5).

The noise prediction models take into account:

- Location of noise sources and receiver locations;
- Height of sources and receivers;
- Separation distances between sources and receivers;
- Shielding from building and intervening structures;
- Attenuation from a minimum 1.2m height solid balustrade around perimeter of outdoor play area

Figure 9 and Figure 10 below are graphical representations of the predicted noise levels at facades of nearby residential and commercial buildings using CadnaA software.




Figure 9: Predicted Noise Levels at Nearest Building Facades (3D) from Outdoor Play Area




Figure 10: Predicted Maximum Childcare Noise Levels at Nearest Buildings

6.5 Assessment of Noise Levels at Nearest Receivers

Based on the sound power levels presented in Table 14 noise emitted to the nearest affected receivers (R2, R3 & R4) are calculated using modelling software and compared to its relevant acoustic criteria discussed in Section 4.2 above.

Table 15: Predicted Noise Levels at Nearest Affected Receivers

Assessment/Receiver Location	Level	Predicted Maximum Sound Pressure Level ¹ L_{Aeq} , dB(A)	Receiver Criterion L_{Aeq} , dB(A)	Compliance (Yes/No)
R2 – Office building within the hospital site	Ground to Level 3	24 ² [44 dB(A) externally]	65 or less	Yes
R3 – Residential levels of mixed-use building to east of development	Level 4 to 26	45	63	Yes
R3 – Commercial/retails levels of mixed-used building to east of development	Ground to Level 19	26 ² [46 dB(A) externally]	65 or less	Yes

Assessment/Receiver Location	Level	Predicted Maximum Sound Pressure Level ¹ L _{Aeq} , dB(A)	Receiver Criterion L _{Aeq} , dB(A)	Compliance (Yes/No)
R4 – Office buildings south of development	Ground to Level 9	37 ² [57dB(A) externally]	65 or less	Yes

Notes:

1. Predicted external noise levels are 1m from façade or window.
2. It is conservatively estimated that typical 6mm fixed glass window or façade provided a minimum 20dB sound reduction.

The predicted noise levels in Table 15 above have shown operational noise from the outdoor play area to comply with the Project noise criteria defined in Section 4.2.1 and 4.2.2 at the nearest affected residential and commercial receivers. Therefore additional acoustic treatment to the outdoor play area is not required.

7 Conclusion

Renzo Tonin & Associates have completed an operational noise assessment of the proposed Health Services Administration Building (Site 4A) at the Royal North Shore Hospital, St Leonards in accordance with Condition 8 of the SEARs.

Proposed mechanical and refrigeration plant located on the roof of the development has been identified as main source of noise impacts to existing surrounding residential and commercial premises. Details of noise and vibration mitigation measures has been provided in Section 5.4 of this report to ensure that plant equipment will not either singularly or in total emit noise levels which exceed the day or night time noise limits defined by EPA Industrial Noise Policy.

Our noise modelling of the outdoor play area of the proposed childcare has found operational noise emitted from the facility to comply with the AAAC Guideline for Child Care Centres Acoustic Assessment" published by the Association of Australian Acoustical Consultants. No additional acoustic measure is required for the proposed outdoor play area.

APPENDIX A Glossary of terminology

The following is a brief description of the technical terms used to describe noise to assist in understanding the technical issues presented.

Adverse weather	Weather effects that enhance noise (that is, wind and temperature inversions) that occur at a site for a significant period of time (that is, wind occurring more than 30% of the time in any assessment period in any season and/or temperature inversions occurring more than 30% of the nights in winter).
Ambient noise	The all-encompassing noise associated within a given environment at a given time, usually composed of sound from all sources near and far.
Assessment period	The period in a day over which assessments are made.
Assessment point	A point at which noise measurements are taken or estimated. A point at which noise measurements are taken or estimated.
Background noise	Background noise is the term used to describe the underlying level of noise present in the ambient noise, measured in the absence of the noise under investigation, when extraneous noise is removed. It is described as the average of the minimum noise levels measured on a sound level meter and is measured statistically as the A-weighted noise level exceeded for ninety percent of a sample period. This is represented as the L90 noise level (see below).
Decibel [dB]	The units that sound is measured in. The following are examples of the decibel readings of every day sounds: 0dB The faintest sound we can hear 30dB A quiet library or in a quiet location in the country 45dB Typical office space. Ambience in the city at night 60dB CBD mall at lunch time 70dB The sound of a car passing on the street 80dB Loud music played at home 90dB The sound of a truck passing on the street 100dB The sound of a rock band 115dB Limit of sound permitted in industry 120dB Deafening
dB(A)	A-weighted decibels. The A-weighting noise filter simulates the response of the human ear at relatively low levels, where the ear is not as effective in hearing low frequency sounds as it is in hearing high frequency sounds. That is, low frequency sounds of the same dB level are not heard as loud as high frequency sounds. The sound level meter replicates the human response of the ear by using an electronic filter which is called the "A" filter. A sound level measured with this filter switched on is denoted as dB(A). Practically all noise is measured using the A filter.
dB(C)	C-weighted decibels. The C-weighting noise filter simulates the response of the human ear at relatively high levels, where the human ear is nearly equally effective at hearing from mid-low frequency (63Hz) to mid-high frequency (4kHz), but is less effective outside these frequencies.
Frequency	Frequency is synonymous to pitch. Sounds have a pitch which is peculiar to the nature of the sound generator. For example, the sound of a tiny bell has a high pitch and the sound of a bass drum has a low pitch. Frequency or pitch can be measured on a scale in units of Hertz or Hz.
Impulsive noise	Having a high peak of short duration or a sequence of such peaks. A sequence of impulses in rapid succession is termed repetitive impulsive noise.
Intermittent noise	The level suddenly drops to that of the background noise several times during the period of observation. The time during which the noise remains at levels different from that of the ambient is one second or more.
L _{Max}	The maximum sound pressure level measured over a given period.
L _{Min}	The minimum sound pressure level measured over a given period.

L ₁	The sound pressure level that is exceeded for 1% of the time for which the given sound is measured.
L ₁₀	The sound pressure level that is exceeded for 10% of the time for which the given sound is measured.
L ₉₀	The level of noise exceeded for 90% of the time. The bottom 10% of the sample is the L90 noise level expressed in units of dB(A).
L _{eq}	The "equivalent noise level" is the summation of noise events and integrated over a selected period of time.
Reflection	Sound wave changed in direction of propagation due to a solid object obscuring its path.
SEL	Sound Exposure Level (SEL) is the constant sound level which, if maintained for a period of 1 second would have the same acoustic energy as the measured noise event. SEL noise measurements are useful as they can be converted to obtain L _{eq} sound levels over any period of time and can be used for predicting noise at various locations.
Sound	A fluctuation of air pressure which is propagated as a wave through air.
Sound absorption	The ability of a material to absorb sound energy through its conversion into thermal energy.
Sound level meter	An instrument consisting of a microphone, amplifier and indicating device, having a declared performance and designed to measure sound pressure levels.
Sound pressure level	The level of noise, usually expressed in decibels, as measured by a standard sound level meter with a microphone.
Sound power level	Ten times the logarithm to the base 10 of the ratio of the sound power of the source to the reference sound power.
Tonal noise	Containing a prominent frequency and characterised by a definite pitch.

APPENDIX B Location & Results of long-term noise surveys

B.1 Photographs of Long-term Noise Monitors

Long-term noise monitoring: M1 - Building 38 of the Royal North Shores Hospital, Reserve Road, St. Leonards.

Survey Period: 06/02/17 to 15/02/17



Long-term noise monitoring: M2 - West facing balcony of U1011 at 3 Herbert Street, St. Leonard

Survey Period: 05/05/18 and 19/05/18



Long-term noise monitoring: M3 - West facing balcony of U2101 at 3 Herbert Street, St. Leonards

Survey Period: 05/05/18 and 13/05/18



North of Building 38, Royal North Shore Hospital

Background & Ambient Noise Monitoring Results - NSW 'Industrial Noise Policy', 2000

Date	L _{A90} Background Noise Levels ⁴			L _{Aeq} Ambient Noise Levels		
	Day ¹	Evening ²	Night ³	Day ¹	Evening ²	Night ³
Monday-06-February-2017	-	46.7	-	-	51.9	-
Tuesday-07-February-2017	-	-	-	-	-	-
Wednesday-08-February-2017	-	45.9	43.1	-	53.5	47.2
Thursday-09-February-2017	51.2	45.9	42.6	60.6	51.1	47.1
Friday-10-February-2017	50.6	46.5	42.7	56.6	51.1	46.8
Saturday-11-February-2017	48.5	48.1	44.0	57.8	51.7	49.3
Sunday-12-February-2017	48.9	44.4	42.5	66.5	52.0	54.4
Monday-13-February-2017	49.8	44.6	42.2	63.0	51.0	46.7
Tuesday-14-February-2017	-	-	-	-	-	-
Wednesday-15-February-2017	-	-	-	-	-	-
Representative Weekday⁵	50.6	45.9	42.7	60.8	51.8	47.0
Representative Weekend⁵	48.7	46.3	43.2	64.0	51.8	52.6
Representative Week⁵	49.8	45.9	42.7	62.4	51.8	49.7

Notes:

1. Day is 8:00am to 6:00pm on Sunday and 7:00am to 6:00pm at other times

2. Evening is 6:00pm to 10:00pm

3. Night is the remaining periods

4. Assessment Background Level (ABL) for individual days


5. Rating Background Level (RBL) for L_{A90} and logarithmic average for L_{Aeq}

6. Leq is calculated in the free field. 2.5dB is subtracted from results if logger is placed at facade

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Monday, 6 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	46.7	-
LA _{eq}	-	51.9	-

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	66.7	to	69.4
L _{Max} - L _{eq} (Range)	18.2	to	21.8

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured in free-field; tabulated results facade corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	56.9	49.2
L _{eq} 1hr upper 10 percentile	61.7	51.8
L _{eq} 1hr lower 10 percentile	53.1	46.6


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Tuesday, 7 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	-	-
LA _{eq}	-	-	-

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	71.5	to	72.3
L _{Max} - L _{eq} (Range)	18.3	to	23.8

Notes:


1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
3. "Evening" is the period from 6pm till 10pm
4. "Night" relates to the remaining periods
6. Graphed data measured in free-field; tabulated results facade corrected
7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	57.5	50.3
L _{eq} 1hr upper 10 percentile	64.9	53.0
L _{eq} 1hr lower 10 percentile	53.3	47.7

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Wednesday, 8 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	45.9	43.1
LA _{eq}	-	53.5	47.2
Night Time Maximum Noise Levels			(see note 7)
L _{Max} (Range)	65.8	to	65.8
L _{Max} - L _{eq} (Range)	15.4	to	17.0

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- Graphed data measured in free-field; tabulated results facade corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	57.5	49.7
L _{eq} 1hr upper 10 percentile	61.1	52.9
L _{eq} 1hr lower 10 percentile	53.1	47.3

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Thursday, 9 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	51.2	45.9	42.6
LA _{eq}	60.6	51.1	47.1
Night Time Maximum Noise Levels (see note 7)			
L _{Max} (Range)	65.5	to	73.7
L _{Max} - L _{eq} (Range)	15.6	to	22.7

Notes:

- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- Graphed data measured in free-field; tabulated results facade corrected


NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.9	49.6
L _{eq} 1hr upper 10 percentile	68.3	53.5
L _{eq} 1hr lower 10 percentile	52.4	46.6

- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Friday, 10 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	50.6	46.5	42.7
LA _{eq}	56.6	51.1	46.8

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	71.0	to	72.4
L _{Max} - L _{eq} (Range)	16.5	to	23.3

Notes:

- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- Graphed data measured in free-field; tabulated results facade corrected


NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	58.2	49.3
L _{eq} 1hr upper 10 percentile	62.5	51.9
L _{eq} 1hr lower 10 percentile	52.5	46.4

- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Saturday, 11 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	48.5	48.1	44.0
LA _{eq}	57.8	51.7	49.3
Night Time Maximum Noise Levels (see note 7)			
L _{Max} (Range)	67.2	to	72.0
L _{Max} - L _{eq} (Range)	21.2	to	22.2

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured in free-field; tabulated results facade corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	59.3	50.8
L _{eq} 1hr upper 10 percentile	65.1	53.1
L _{eq} 1hr lower 10 percentile	53.4	48.2


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Sunday, 12 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	48.9	44.4	42.5
LA _{eq}	66.5	52.0	54.4
Night Time Maximum Noise Levels (see note 7)			
L _{Max} (Range)	69.4	to	79.8
L _{Max} - L _{eq} (Range)	15.5	to	20.2

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured in free-field; tabulated results facade corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	67.3	56.9
L _{eq} 1hr upper 10 percentile	73.8	63.8
L _{eq} 1hr lower 10 percentile	49.5	47.3


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Monday, 13 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	49.8	44.6	42.2
L _{Aeq}	63.0	51.0	46.7

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	73.0	to	73.0
L _{Max} - L _{eq} (Range)	16.4	to	23.0

Notes:

- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)


NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	64.2	49.2
L _{eq} 1hr upper 10 percentile	71.0	52.5
L _{eq} 1hr lower 10 percentile	51.0	46.9

- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Tuesday, 14 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	-	-
LA _{eq}	-	-	-

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	65.5	to	73.4
L _{Max} - L _{eq} (Range)	15.5	to	23.0

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured in free-field; tabulated results facade corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	63.4	49.7
L _{eq} 1hr upper 10 percentile	73.3	52.9
L _{eq} 1hr lower 10 percentile	50.4	46.9

Unattended Noise Monitoring Results

North of Building 38, Royal North Shore Hospital

Wednesday, 15 February 2017



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	-	-
LA _{eq}	-	-	-
Night Time Maximum Noise Levels (see note 7)			
L _{Max} (Range)	-	to	-
L _{Max} - L _{eq} (Range)	-	to	-

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured in free-field; tabulated results facade corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade) (see note 6)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.9	-
L _{eq} 1hr upper 10 percentile	64.7	-
L _{eq} 1hr lower 10 percentile	54.1	-

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Saturday, 5 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	-	52.8
LAeq (see note 6)	-	-	59.2
Night Time Maximum Noise Levels			(see note 7)
L _{Max} (Range)	76.2	to	89.0
L _{Max} - L _{eq} (Range)	16.4	to	30.5

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	58.4	60.5
L _{eq} 1hr upper 10 percentile	59.2	64.4
L _{eq} 1hr lower 10 percentile	57.2	56.1

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Sunday, 6 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	54.8	-	52.0
LAeq (see note 6)	58.9	-	56.4

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	73.3	to	80.9
L _{Max} - L _{eq} (Range)	15.2	to	24.5

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.7	58.9
L _{eq} 1hr upper 10 percentile	67.2	62.6
L _{eq} 1hr lower 10 percentile	57.7	54.3


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Monday, 7 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.4	54.9	52.0
LAeq (see note 6)	59.0	57.0	55.2

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	72.3	to	77.9
L _{Max} - L _{eq} (Range)	15.9	to	20.3

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.1	57.7
L _{eq} 1hr upper 10 percentile	63.6	60.5
L _{eq} 1hr lower 10 percentile	58.7	54.8


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Tuesday, 8 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.7	54.7	50.8
LAeq (see note 6)	59.6	56.8	54.1

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	70.0	to	76.5
L _{Max} - L _{eq} (Range)	15.8	to	20.2

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.6	56.6
L _{eq} 1hr upper 10 percentile	63.3	58.1
L _{eq} 1hr lower 10 percentile	58.6	54.2


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Wednesday, 9 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.1	55.2	52.3
LA _{eq} (see note 6)	59.3	57.0	54.9

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	74.5	to	78.8
L _{Max} - L _{eq} (Range)	16.2	to	21.6

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.3	57.4
L _{eq} 1hr upper 10 percentile	64.5	59.3
L _{eq} 1hr lower 10 percentile	58.9	54.8


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Thursday, 10 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.1	-	52.9
LAeq (see note 6)	67.2	-	70.2

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	95.3	to	100.6
L _{Max} - L _{eq} (Range)	24.2	to	31.7

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	71.9	72.7
L _{eq} 1hr upper 10 percentile	78.2	75.9
L _{eq} 1hr lower 10 percentile	61.2	63.8


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Friday, 11 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	57.1	53.7
LA _{eq} (see note 6)	-	67.3	67.8

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	82.8	to	99.1
L _{Max} - L _{eq} (Range)	21.9	to	31.8

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	78.1	70.3
L _{eq} 1hr upper 10 percentile	83.4	75.0
L _{eq} 1hr lower 10 percentile	64.4	60.5

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Saturday, 12 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	58.0	52.8
LA _{eq} (see note 6)	-	79.5	71.9

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	97.5	to	100.8
L _{Max} - L _{eq} (Range)	19.0	to	31.1

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	83.1	74.9
L _{eq} 1hr upper 10 percentile	85.7	81.8
L _{eq} 1hr lower 10 percentile	78.0	66.5

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Sunday, 13 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	55.1	55.8	51.7
LA _{eq} (see note 6)	64.5	63.2	64.6

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	90.0	to	99.7
L _{Max} - L _{eq} (Range)	20.5	to	34.6

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	66.4	67.1
L _{eq} 1hr upper 10 percentile	69.2	70.7
L _{eq} 1hr lower 10 percentile	63.2	60.9


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Monday, 14 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.2	55.9	51.5
LA _{eq} (see note 6)	60.8	58.5	60.8

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	77.9	to	87.4
L _{Max} - L _{eq} (Range)	18.7	to	25.7

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	62.8	63.3
L _{eq} 1hr upper 10 percentile	64.9	68.5
L _{eq} 1hr lower 10 percentile	60.4	57.3

2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

U1011 Balcony 3 Herbert St, St. Leonards


Night Time Maximum Noise Levels			(see note 7)
L _{Max} (Range)	76.1	to	82.2
L _{Max} - L _{eq} (Range)	16.0	to	20.7

QTE-26 (rev 17) Logger Graphs Program

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Wednesday, 16 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.3	54.7	52.6
LA _{eq} (see note 6)	60.0	57.6	58.4

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	74.9	to	85.7
L _{Max} - L _{eq} (Range)	16.0	to	22.9

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	62.0	60.9
L _{eq} 1hr upper 10 percentile	63.9	62.8
L _{eq} 1hr lower 10 percentile	59.4	57.5

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Thursday, 17 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.6	56.6	51.6
LA _{eq} (see note 6)	61.2	58.5	60.4

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	74.9	to	91.9
L _{Max} - L _{eq} (Range)	15.2	to	23.8

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	63.1	62.9
L _{eq} 1hr upper 10 percentile	65.5	68.4
L _{eq} 1hr lower 10 percentile	59.9	55.0

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Friday, 18 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.3	54.6	52.6
LA _{eq} (see note 6)	64.9	57.1	64.2

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	74.9	to	89.5
L _{Max} - L _{eq} (Range)	16.2	to	22.4

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	66.3	66.7
L _{eq} 1hr upper 10 percentile	72.1	70.6
L _{eq} 1hr lower 10 percentile	58.5	58.6

Unattended Noise Monitoring Results

U1011 Balcony 3 Herbert St, St. Leonards

Saturday, 19 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	-	-
LA _{eq} (see note 6)	-	-	-

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	-	to	-
L _{Max} - L _{eq} (Range)	-	to	-

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	68.3	-
L _{eq} 1hr upper 10 percentile	69.1	-
L _{eq} 1hr lower 10 percentile	65.1	-

2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Background & Ambient Noise Monitoring Results - NSW 'Industrial Noise Policy', 2000

Date	L _{A90} Background Noise Levels ⁴			L _{Aeq} Ambient Noise Levels		
	Day ¹	Evening ²	Night ³	Day ¹	Evening ²	Night ³
Saturday-05-May-2018	-	54.8	52.4	-	54.5	53.6
Sunday-06-May-2018	54.8	-	52.4	55.5	-	53.5
Monday-07-May-2018	57.5	54.7	52.5	57.8	55.0	54.9
Tuesday-08-May-2018	58.1	54.7	51.6	59.5	55.2	53.4
Wednesday-09-May-2018	57.1	-	52.2	58.2	-	53.8
Thursday-10-May-2018	58.0	-	52.3	58.4	-	54.6
Friday-11-May-2018	-	56.0	53.1	-	56.5	54.3
Saturday-12-May-2018	-	55.8	52.4	-	56.5	53.6
Sunday-13-May-2018	-	-	-	-	-	-
Representative Weekday⁵	57.8	54.7	52.3	58.5	55.6	54.2
Representative Weekend⁵	54.8	55.3	52.4	55.5	55.6	53.6
Representative Week⁵	57.5	54.8	52.4	58.1	55.6	54.0


Notes:

- Day is 8:00am to 6:00pm on Sunday and 7:00am to 6:00pm at other times
- Evening is 6:00pm to 10:00pm
- Night is the remaining periods
- Assessment Background Level (ABL) for individual days
- Rating Background Level (RBL) for L_{A90} and logarithmic average for L_{Aeq}
- Leq is calculated in the free field. 2.5dB is subtracted from results if logger is placed at facade

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Saturday, 5 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	54.8	52.4
LAeq (see note 6)	-	54.5	53.6

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	70.4	to	85.5
L _{Max} - L _{eq} (Range)	15.0	to	27.6

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	57.5	55.9
L _{eq} 1hr upper 10 percentile	59.3	57.9
L _{eq} 1hr lower 10 percentile	56.5	53.9

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Sunday, 6 May 2018



NSW Industrial Noise Policy (Free Field)

Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	54.8	-	52.4
LA _{eq} (see note 6)	55.5	-	53.5

Night Time Maximum Noise Levels

(see note 7)

L _{Max} (Range)	70.4	to	78.0
L _{Max} - L _{eq} (Range)	16.1	to	22.2

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)


NSW Road Noise Policy (1m from facade)

Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	58.0	56.0
L _{eq} 1hr upper 10 percentile	60.2	59.9
L _{eq} 1hr lower 10 percentile	56.4	54.1

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Monday, 7 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.5	54.7	52.5
LAeq (see note 6)	57.8	55.0	54.9

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	75.1	to	83.1
L _{Max} - L _{eq} (Range)	19.4	to	21.5

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected


2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
4. "Night" relates to the remaining periods
5. "Night" relates to period from 10pm on this graph to morning on the following graph.
7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	59.7	57.4
L _{eq} 1hr upper 10 percentile	61.6	61.6
L _{eq} 1hr lower 10 percentile	56.8	54.4

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Tuesday, 8 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.1	54.7	51.6
LAeq (see note 6)	59.5	55.2	53.4

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	70.5	to	77.5
L _{Max} - L _{eq} (Range)	15.3	to	21.7

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	61.2	55.9
L _{eq} 1hr upper 10 percentile	64.0	59.8
L _{eq} 1hr lower 10 percentile	57.0	53.4

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Wednesday, 9 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	57.1	-	52.2
LAeq (see note 6)	58.2	-	53.8

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	74.9	to	81.4
L _{Max} - L _{eq} (Range)	15.0	to	24.9

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	60.1	56.3
L _{eq} 1hr upper 10 percentile	62.1	59.9
L _{eq} 1hr lower 10 percentile	57.5	53.8

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Thursday, 10 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	58.0	-	52.3
LAeq (see note 6)	58.4	-	54.6

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	70.2	to	83.2
L _{Max} - L _{eq} (Range)	15.2	to	22.5

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	60.8	57.1
L _{eq} 1hr upper 10 percentile	61.8	60.7
L _{eq} 1hr lower 10 percentile	58.6	54.3

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Friday, 11 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	56.0	53.1
LAeq (see note 6)	-	56.5	54.3

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	71.4	to	75.1
L _{Max} - L _{eq} (Range)	15.4	to	17.8

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	60.7	56.8
L _{eq} 1hr upper 10 percentile	62.2	58.8
L _{eq} 1hr lower 10 percentile	58.5	54.7

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Saturday, 12 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4,5}
L ₉₀	-	55.8	52.4
LAeq (see note 6)	-	56.5	53.6

Night Time Maximum Noise Levels		(see note 7)	
L _{Max} (Range)	82.7	to	83.1
L _{Max} - L _{eq} (Range)	24.1	to	26.1

Notes:


- Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.
- "Day" is the period from 8am till 6pm on Sundays and 7am til 6pm on other days
- "Evening" is the period from 6pm till 10pm
- "Night" relates to the remaining periods
- "Night" relates to period from 10pm on this graph to morning on the following graph.
- Graphed data measured 1m from facade; tabulated results free-field corrected
- Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	59.9	56.0
L _{eq} 1hr upper 10 percentile	61.5	58.6
L _{eq} 1hr lower 10 percentile	57.9	54.2

Unattended Noise Monitoring Results

U2101 Balcony Balcony 3 Herbert St, St. Leonards

Sunday, 13 May 2018



NSW Industrial Noise Policy (Free Field)			
Descriptor	Day ²	Evening ³	Night ^{4 5}
L ₉₀	-	-	-
LAeq (see note 6)	-	-	-
Night Time Maximum Noise Levels (see note 7)			
L _{Max} (Range)	-	to	-
L _{Max} - L _{eq} (Range)	-	to	-

Notes:

1. Shaded periods denote measurements adversely affected by rain, wind or extraneous noise - data in these periods are excluded from calculations.

3. "Evening" is the period from 6pm till 10pm

6. Graphed data measured 1m from facade; tabulated results free-field corrected

4. "Night" relates to the remaining periods

7. Night time L_{Max} values are shown only where L_{Max} > 65dB(A) and where L_{Max} - L_{eq} ≥ 15dB(A)

NSW Road Noise Policy (1m from facade)		
Descriptor	Day	Night ⁵
	7am-10pm	10pm-7am
L _{eq} 15 hr and L _{eq} 9 hr	58.9	-
L _{eq} 1hr upper 10 percentile	60.0	-
L _{eq} 1hr lower 10 percentile	56.6	-

2. "Day" is the period from 8am till 6pm on Sundays and 7am till 6pm on other days

5. "Night" relates to period from 10pm on this graph to morning on the following graph.