



Traffic & Transportation Direction



## **Gregadoo Solar Farm and BESS**

Boiling Down Road, Gregadoo

Traffic Impact Assessment

18 September 2024

Reference: 388 rep 240918 final

# Gregadoo Solar Farm and BESS

Boiling Down Road, Gregadoo

## Traffic Impact Assessment

Prepared for: Premise

Status: Final report

Date: 18 September 2024

Reference: 388 rep 240918 final

Revision	Date	Description	Author	Reviewed	Approved
A	25/06/24	Draft 01	R. Kobelt	T. Dwyer, O. Mihaila	M. Willson
B	09/08/24	Final Draft for Review	R. Kobelt	T. Dwyer, O. Mihaila	M. Willson
C	18/09/24	Final	R. Kobelt	T. Dwyer, O. Mihaila	M. Willson

### Contact

Website: [www.amberorg.com.au](http://www.amberorg.com.au)

E: [info@amberorg.com.au](mailto:info@amberorg.com.au)

Phone: 1800 022 363

## Table of Contents

1.	Background .....	5
1.1	Introduction .....	5
1.2	Development Consent Condition Changes .....	7
1.3	Purpose of Document .....	7
2.	Existing Conditions .....	8
2.1	Site Location .....	8
2.2	Road Network .....	9
2.3	Traffic Volumes .....	9
2.4	Restricted Vehicle Access .....	10
2.5	Crash History .....	12
3.	Project Description .....	13
3.1	Proposed Modification .....	13
3.2	Construction Information .....	13
4.	Traffic Assessment .....	14
4.1	Previous Traffic Assessment .....	14
4.2	Traffic Generation .....	15
4.3	Traffic Distribution .....	16
4.4	Cumulative Traffic Impacts .....	18
4.5	Traffic Assessment .....	19
5.	OSOM Vehicles .....	21
5.1	OSOM Vehicle Definitions .....	21
5.2	Heavy Vehicles Requiring Escort .....	22
5.3	Port Botany Route .....	23
5.4	Port of Melbourne Route .....	26
6.	Intersection Assessment .....	30
6.1	Turn Treatment Assessment .....	30
6.2	Mitigation Measures .....	31
6.3	Site Access .....	31
6.4	Summary .....	31
7.	Conclusion .....	33

# Appendices

## **Appendix A**

*Survey Results*

## **Appendix B**

*Concept Plans – Road Upgrades*

## **Appendix C**

*Class 1 Load Carrying Vehicle Operator’s Guide NSW*

## **Appendix D**

*OSOM Route Assessment Port Botany to Site*

## **Appendix E**

*OSOM Route Assessment Port of Melbourne to Site*



# 1. Background

## 1.1 Introduction

Amber Organisation Pty Ltd has been engaged by Premise to prepare a Traffic Impact Assessment for the proposed development modification to the Gregadoo Solar Farm. The original Development Consent for the Gregadoo Solar Farm (SSD 8825) was approved by the Department of Planning and Environment under the delegation of the Minister for Planning on 11 December 2018, with three subsequent modifications since the original consent over 2021 and 2023.

The approved Solar Farm site is located at 123 Redbank Road and 50 Ashfords Road, Gregadoo, being Lot 11 DP1043022 and Lot 1 DP524499, approximately 13 kilometres southeast of the Wagga Wagga Central Business District (CBD). The site layout and project location are shown in Figure 1.

The modification considered by this report involves optimisation of the design to incorporate a Battery Energy Storage System ('BESS'), summarised as follows:

*The optimised design has been conceived to utilise the approved development footprint more effectively by incorporating a BESS while maintaining a power output of 65 MW(AC). The proposed BESS will have a generation capacity of 200MW<sub>AC</sub> and 400MWh. This optimisation assists to ensure the orderly and economic use of land, while assisting to achieve State and Federal renewable energy targets and objectives for renewable energy and grid firming.*

*In addition, Modification 4 seeks to include an additional access point and internal access track from Boiling Down Road to the approved overhead transmission line between the Gregadoo Solar Farm substation and the Transgrid substation. The access point and access track are required to ensure that the approved overhead and underground transmission line can be constructed and maintained without impacting on the Boiling Down Creek or the adjoining riparian corridor.*


As a result of the introduction of a BESS to the project there will be an increase in movements of heavy vehicles and heavy vehicles requiring escort to and from the site.

Construction is expected to commence in 2025 and take approximately 12 months, with the peak construction period expected to take 6 months. A maximum workforce of 150 people would be on-site during peak construction periods with the workforce expected to be primarily located in Wagga Wagga.

All specialist plant for the BESS is expected to be delivered from Port Botany or the Port of Melbourne. General construction materials and equipment will generally be sourced from within Wagga Wagga or the surrounding area where practicable.

The impacts for traffic generated by the proposed construction, operation and decommissioning phases of the BESS as a result of the modification are addressed in this report in accordance with relevant regulatory requirements and guidelines.

Figure 1. Site Layout



Source: Premise



## 1.2 Development Consent Condition Changes

Subject to approval, the modification would result in changes to the development consent to reflect the increase in traffic volumes through the addition of the BESS. Specifically, it involves:

- Amendment of *Schedule 3, Condition 2 (a)* to
  - increase the number of heavy vehicle movements per day from 50 to 120 to during construction, upgrading and decommissioning; and
  - to increase the number of over-dimension vehicles movement per day from 2 to 4.

The definition of a vehicle movement is *one vehicle entering and leaving the site* as outlined in the development consent.

In addition, it is recommended that references to “*Over-dimensional vehicle/s*” in the development consent be changed to “*Heavy vehicle/s requiring escort*” with the following definition:

*Any vehicle that requires a pilot vehicle and/or escort vehicle, as defined by the National Heavy Vehicle Regulator’s NSW Class 1 Load Carrying Vehicle Operator’s Guide*

This would better align with the intent of the conditions (which is to manage high-risk over-dimensional vehicles) and is consistent with the approach taken for other similar state significant renewable development projects (refer Section 5.1 for more detail).

## 1.3 Purpose of Document

This Traffic Impact Assessment has been prepared to assess the construction, operational and decommissioning traffic impacts of the proposed modification.

More specifically, the report addresses the following key matters:

- Details of both light and heavy vehicle traffic volumes and proposed transport routes;
- An assessment of the potential traffic impacts of the modification on road network function and safety;
- An assessment of the capacity of the existing road network to accommodate the type and volume of traffic generated by the modification;
- Details of measures to mitigate and/or manage potential impacts, including construction traffic control, road dilapidation surveys and measures to control dust generated by traffic volumes; and
- Details of access roads and how these connect to the existing road network and ongoing operational maintenance.


The traffic assessment has been undertaken in accordance with the *RTA Guide to Traffic Generating Developments* and relevant Austroads Guidelines.

## 2. Existing Conditions

### 2.1 Site Location

The site is located at 123 Redbank Road and 50 Ashfords Road, Gregadoo approximately 9 kilometres southeast of the Wagga Wagga CBD. Figure 2 shows the location of the site in relation to the surrounding transport and road network.

Figure 2: Site Location



Source: Open Street Map

The figure shows the site has access to the State Road network via Sturt Highway to the northeast of the site. Vehicles accessing the site from Sturt Highway are able to utilise Bakers Avenue, Inglewood Road, Mitchell Road, Ashfords Road, and Boiling Down Road.

Notable land uses near include the Gregadoo Waste Management Centre (GWMC), to the south of the site, and the Gregadoo TransGrid Substation located direct to the east of the project site. Works are currently being undertaken at the substation as part of the EnergyConnect project.

## 2.2 Road Network

**Sturt Highway** is a Regional road which generally runs in a northwest-southeast alignment in the vicinity of the site. It has one traffic lane in each direction which are approximately 3.9 metres wide, and the carriageway has a sealed width of approximately 9.3 metres.

**Bakers Lane** is a local road that runs in a north-south alignment between Sturt Highway in the north and Inglewood Road to the south. It has a sealed road width of approximately 6.0 metres, with one lane of traffic in each direction.

**Inglewood Road** is a local road that runs in an east-west alignment between Mitchell Road and Elizabeth Avenue. It has a sealed road width of approximately 7.0 metres, with one lane of traffic in each direction.

**Mitchell Road** is a local road that runs in a north-south alignment from its northern terminus to where it continues as **Gregadoo East Road** at the Mitchell Road / Ashfords Road intersection. It has a sealed road width of approximately 6.6 metres, with one lane of traffic in each direction.

**Ashfords Road** is a local road that runs in a north-south alignment. It has a sealed road width of approximately 6.2 metres and an unsealed shoulder on either side of the road. It provides access to the primary vehicular access of the Gregadoo Waste Management Centre (GWMC) which lies to the south of the site.

**Boiling Down Road** is an unsealed local road that runs in an east-west alignment, extending from its intersection with Ashfords Road in the east to its intersection with Plumpton Road to the west. It has a varying road width between approximately 6.0 to 7.2 metres.

## 2.3 Traffic Volumes

Traffic volume data was sourced for Mitchell Road and Ashfords Road from Wagga Wagga City Council. The data obtained was raw data files from the *Metrocount* tube count devices which was processed further to obtain hourly traffic count data and vehicle speeds.

The data recorded during the surveys is summarised in Table 1 with detailed extracts provided in Appendix A.

**Table 1: Local Road Traffic Volumes**

Road Name	7-day Survey Start Date	Weekday Traffic (vpd)	Average Speed	85 <sup>th</sup> Percentile Speed	Heavy Vehicle Percentage
<b>Mitchell Road</b>	20 January 2021	1,475	73.5 km/h	82.3 km/h	Approx. 30%
<b>Ashfords Road</b>	14 August 2023	496	70.0 km/h	77.9 km/h	Approx. 30%

The survey data indicates that Mitchell Road carries low levels of traffic with a high proportion of heavy vehicles. The volumes on Ashfords Road are very low which would be expected given the nature of the surrounding land uses

Traffic volumes on Boiling Down Road would be expected to be lower than that recorded on Ashfords Road.

The results also show vehicle speeds around 80 km/h being the applicable speed zone for both roads.

## 2.4 Restricted Vehicle Access

### 2.4.1 B-Doubles

The TfNSW Restricted Access Vehicle Map for the surrounding area is provided within Figure 3. The green lines indicate approved B-Double routes while the black lines represent approved routes with travel conditions. The figure shows that the Sturt Highway and the surrounding State road network are B-Double approved routes although travel conditions are applicable on some sections of the network. The site has access to the B-Double approved road network via Boiling Down Road, Ashfords Road, Mitchell Road, Inglewood Road and Bakers Lane being unrated.

Figure 3: TfNSW 26m B-Double Network Approved Roads



Source: TfNSW Restricted Access Vehicle Map

## 2.4.2 Class 1 OSOM Vehicles

The TfNSW Oversize Overmass (OSOM) Load Carrying Vehicles Network map for the surrounding area is provided within Figure 4. The map shows approved routes for eligible vehicles operating under the Multi-State Class 1 Load Carrying Vehicles Mass and Mass Exemption Notices.

A summary of the allowances under each exemption within New South Wales notice is provided below:

- Dimension: up to 5.0m wide, 5.0m high, 30.0m long and 7.5m rear overhang on approved (state owned) routes in NSW.
- Mass: up to 115.0 tonnes for rows of 8 tyres low loaders and up to 77.5 tonnes for rows of 4 tyres low loader combinations.

Vehicles operating in the daytime and not exceeding 3.5m wide or 26m long generally do not require a pilot vehicle.

The green lines indicate approved Class 1 OSOM Vehicle routes. Accordingly, the site has access to the Class 1 OSOM approved road network via Sturt Highway with Boiling Down Road, Ashfords Road, Mitchell Road, Inglewood Road and Bakers Lane being unrated.

Figure 4: TfNSW Class 1 Oversize Overmass Load Carrying Vehicles Network Approved Roads




Source: TfNSW Restricted Access Vehicle Map

## 2.5 Crash History

Amber has conducted a review of the TfNSW Centre for Road Safety Crash and Casualty Statistics database for all recorded crashes within the surrounding area of the Project. The crash database provides the location and severity of all crashes for the five-year period from 2018 to 2022. The search area is illustrated in Figure 5 and the results of the crash search are summarised in Table 2.

Figure 5: Crash Search Area



Source: TfNSW Crash Statistics and Open Street Map

Table 2: Crash Search Results

Road	Location	Severity	Crash Type	Date and Time	Light and Weather Conditions
Bakers Lane	Intersection with Inglewood Rd	Minor/Other Injury	Off road to the left	September 2020 (06:00 - 07:59)	Dawn (Raining)
Sturt Hwy	Intersection with Bakers Lane	Moderate Injury	Cross traffic crash	October 2018 (18:00 - 19:59)	Darkness (Fine)

The crash search indicates a total of two crashes with one resulting in a moderate injury and one minor / other injury.

Given the large search area, the road classifications, the severity, and the rural road environment, it is concluded that the road network is currently operating in a relatively safe manner.

## 3. Project Description

### 3.1 Proposed Modification

The modification involves optimisation of the design to incorporate a Battery Energy Storage System ('BESS') as part of the approved Solar Farm with a generation capacity of 200MW<sub>AC</sub> and 400MWh.

An additional access point and internal access track from Boiling Down Road to the approved overhead transmission line between the Gregadoo Solar Farm substation and the Transgrid substation is also proposed as part of the modification.

As a result of the introduction of a BESS to the project there will be an increase in movements of heavy vehicles and heavy vehicles requiring escort to and from the site.

### 3.2 Construction Information

Construction of the Solar Farm and BESS is expected to commence in 2025 and take approximately 12 months, with the peak construction period expected to take 6 months.

Construction activities would be undertaken during standard daytime construction hours, as follows:

- Monday to Friday: 7am – 6pm
- Saturday: 7am – 1pm
- No work on Sundays or public holidays.

Any construction outside of these normal working hours would only be undertaken with prior approval from relevant authorities and consultation with impacted road users.

A maximum workforce of 150 people would be on-site during peak construction periods with the workforce expected to be primarily located in Wagga Wagga.

A Traffic Management Plan (TMP) would be prepared and approved prior to construction commencing as required under *Schedule 3, Condition 8* of the development consent. It is noted that a TMP<sup>1</sup> has previously been approved in 2021 but does not cover changes to the construction methodology as a result of the modifications since that time.

---

<sup>1</sup> Gregadoo Traffic Management Plan, NGH, Revision 1.2 December 2020, Approved 22 January 2021

## 4. Traffic Assessment

### 4.1 Previous Traffic Assessment

#### 4.1.1 Construction

Traffic generated by the project was originally assessed as part of the Traffic Access Assessment<sup>2</sup> prepared for the original Solar Farm and subsequent modification (Modification 3). The total construction traffic is summarised in Table 3.

**Table 3: Total Traffic Generation During Construction – Modification 3**

Vehicle Type	Traffic Generation During Construction	
	Average Vehicles per Day	Peak Vehicles per Day
Light Vehicle	50	110
Heavy Vehicles	20	50
<b>Total</b>	<b>70</b>	<b>160</b>

A modification assessment letter<sup>3</sup> was prepared in relation to the traffic impact which summarised the following:

*The Traffic Impact Assessment for the Gregadoo Solar Farm noted the following with regard to the use of the local road network:*

*'Prior to construction, a pre-condition survey of the relevant sections of the existing road network be undertaken, in consultation with Council. During construction, the sections of the road network proposed to be utilised by the construction vehicles associated with the solar farm are to be monitored and maintained to ensure continued safe use by all road users, and any faults attributed to construction of the PV plant required to be rectified. At the end of construction, a post-condition survey would be undertaken to ensure that the road network is left in a similar condition as per the start of construction.*

*Construction of the proposal may result in increased dust on unsealed roads. During construction, water is to be used to minimise dust generation on the unsealed lanes.'*

*The above existing mitigation measures are considered to still be appropriate for the modification given the minor increase in traffic proposed.*

The modification was approved on 22 August 2023.

#### 4.1.2 Operations

The previously approved Traffic Management Plan<sup>4</sup> (TMP) anticipated two to three staff on-site at any one time to undertake maintenance activities, with up to six heavy vehicles required in a given day.

<sup>2</sup> Gregadoo Solar Farm – Traffic Access Assessment, TDG, 27 March 2018

<sup>3</sup> Gregadoo Solar Farm – Modification Assessment, Amber 7 July 2023

<sup>4</sup> Gregadoo Traffic Management Plan, NGH, Revision 1.2 December 2020, Approved 22 January 2021

### 4.1.3 Upgrading and Decommissioning

The approved TMP<sup>1</sup> anticipated traffic generation levels during upgrades and the project decommissioning up to that required for the construction of the Solar Farm.

### 4.1.4 Mitigation Measures

To manage the traffic impacts of the Solar Farm the following road upgrades are required under *Schedule 3, Condition 5* of the development consent:

- *Upgrade of the intersection of Mitchell Road and Ashfords Road, including providing a Basic Right Turn Treatment (BAR); and*
- *Upgrade the intersection of Ashfords Road and Boiling Down Road, including sealing Boiling Down Road a minimum length of 30 m from its intersection with Ashford’s Road.*

The upgrades would be undertaken prior to construction and to the satisfaction of the relevant road authority. Concept plans prepared as part of the original Traffic Impact Assessment (TDG, 27 March 2018) are included for reference in Appendix B.

### 4.1.5 Summary

The approved Solar Farm will generate a total of 160 vehicles per day inclusive of 50 heavy vehicles during the construction peak.

## 4.2 Traffic Generation

### 4.2.1 Construction

The average daily and peak daily traffic generation of the approved Solar Farm, the BESS, and the resultant total traffic volumes are summarised in Table 4. The traffic generation conservatively assumes that the Solar Farm and BESS construction are undertaken concurrently.

**Table 4: Daily Traffic Generation During Construction Solar and BESS**

Vehicle Type	Approved Solar Farm		BESS		Solar Farm and BESS Total	
	Average Vehicles per Day	Peak Vehicles per Day	Average Vehicles per Day	Peak Vehicles per Day	Average Vehicles per Day	Peak Vehicles per Day
Light Vehicle	50	110	+30	+64	80	174
Heavy Vehicles	20	50	+25	+70	45	120
<b>Total</b>	<b>70</b>	<b>160</b>	<b>+55</b>	<b>+134</b>	<b>125</b>	<b>294</b>

A review of the table shows that the increase as a result of the BESS is 134 additional vehicles per day during the construction peak, and 55 additional vehicles per day during the average construction period.



The Applicant has provided further information on the vehicle types and traffic generation over an hour during the construction peak for the Solar Farm and BESS as outlined in Table 5.

**Table 5: Hourly Traffic Generation During Peak Construction Period – Solar and BESS**

Vehicle Type		Approved Solar Farm	BESS	Solar Farm and BESS
Light Vehicles (LV)	Passenger vehicles	52	+30	82
	Shuttle Buses	3	+2	5
Heavy Vehicles (HV)	Rigid Trucks	4	+5	9
	Truck and Dog	4	+6	10
	Semitrailers	1	+2	3
	<i>HV Subtotal</i>	9	+13	22
<b>Total</b>		<b>64</b>	<b>+45</b>	<b>109</b>

The table shows that the increase during a peak hour as a result of the modification and inclusion of a BESS is 45 vehicles per hour which includes 32 light vehicles and 13 heavy vehicles.

The table also shows that the Solar Farm and BESS would be expected to generate 109 vehicles an hour during the construction peak. This would reduce outside the peak construction period.

Restricted Access Vehicles and heavy vehicles requiring escort (oversize/overmass vehicles) will also be required for the delivery of specialist equipment (cranes, excavators etc) as well the largest plant and equipment. They contribute the smallest percentage of vehicles accessing the project during the construction period and are subject to separate permit applications and regulations. The movement and impact of these vehicles are discussed within Section 5.

## 4.2.2 Operations

As a result of the inclusion of the BESS there is anticipated to be an increase of one to two staff, which represents up to four additional vehicle movements per day. This level of additional traffic can be readily accommodated on the surrounding road network without safety or operational impacts.

## 4.2.3 Upgrading and Decommissioning

The modification and introduction of the BESS will have a similar outcome with traffic generated during upgrades and the decommissioning of the Solar Farm and BESS less than that generated during the construction.


## 4.3 Traffic Distribution

It is anticipated that the majority of the workforce for the construction of the BESS would be located in Wagga Wagga. Materials and equipment will generally be sourced from within Wagga Wagga or the surrounding area where practicable, with all larger plant is to be delivered from Port Botany or the Port of Melbourne.

It is expected that all light vehicles accessing the site would travel from the north via Mitchell Road, Ashford Road and Boiling Downs Road.

All heavy vehicles and heavy vehicles requiring escort associated with the development will travel to and from the site via the Sturt Highway, Bakers Lane, Inglewood Road, Mitchell Road, Ashfords Road, Boiling Down Road and the site access point/s as shown in Figure 6.

Figure 6: Heavy Vehicle Access Route




The heavy vehicle access route is consistent with that outlined in *Schedule 3, Condition 4* of the development consent.

The peak hour for construction will occur at the start and end of the day when staff are transported to/from the site. The majority of staff will typically arrive on-site between 6:00am and 7:00am. However, staff generally have staggered finish times which results in the evening peak hour being less pronounced. For the purposes of this assessment, it has been assumed that all staff depart between 5:00pm and 6:00pm and the evening peak traffic volumes are the same as the morning peak volume.

During the morning peak all vehicle trips would be toward the site and in the evening peak all vehicle trips would be away from the site. The majority of heavy vehicle trips would be distributed throughout the day and would be split evenly between inbound and outbound trips.

The subsequent traffic volumes during the morning and evening peak hour at the Mitchell Road / Ashford Road intersection are provided within Figure 7.

Figure 7: Construction Peak Hour Volumes During Peak Construction



## 4.4 Cumulative Traffic Impacts

The primary traffic impact of the Solar Farm and BESS is generated during construction which is anticipated to start in 2025 and take approximately 12 months, with the peak construction period expected to take 6 months.

A review has been undertaken of all State Significant projects within four kilometres of the site which would share a traffic route with the project over this construction period.

The assessment showed that the only project is the Energy Connect project works which is currently underway at the TransGrid Substation directly east of the site. It is understood that the project works at the site in Gregadoo will be complete in 2026. It is also noted that the traffic volumes associated with this project would be reflected in the traffic volumes recorded on Ashfords Road (as shown in Table 1).


## 4.5 Traffic Assessment

The traffic volumes at the Mitchell Road / Ashford Road intersection have been calculated based on the following:

- The project traffic volumes presented within Figure 7.
- The existing local road traffic volumes have been based on the local road traffic count data summarised in Table 1 and Appendix A for the hours starting 6:00am and 5:00pm, to align with the periods when the majority of traffic will be generated to and from the site. A growth factor of 1.5% per annum has been applied to reflect 2025 volumes.

The subsequent traffic volumes are shown within Figure 8.

Figure 8: Total Construction Peak Hour Volumes During Peak Construction



Level of Service is a qualitative measure used to describe the operating conditions of a section of road or an intersection. Levels of Service are designated from A to F from best (free flow conditions) to worst (forced flow with stop start operation, long queues and delays) and represent the perception of the road conditions by motorists including speed and travel time, freedom to manoeuvre, traffic interruptions, comfort and convenience, and safety. The assessment of the level of service for sign-controlled intersections is based on the average delay (seconds/vehicle) of the critical movement.

The *RTA Guide to Traffic Generating Developments*, dated October 2002, suggests that ideally rural roads should not exceed service volumes at Level of Service C. At this level, whilst most drivers are restricted in their freedom to manoeuvre, operating speeds are still reasonable and acceptable

delays are experienced. Table 4.5 of the RTA Guide sets out two-way hourly road capacities for two-lane roads for different levels of service on different terrain types.

The traffic volumes expected to be accommodated on the surrounding road network during the peak hour are shown within Table 6 along with the traffic volumes during construction presented within Figure 8.

**Table 6: Expected Peak Hour Traffic Volumes During Construction**

Road	AM Peak (6:00am)			PM Peak (5:00pm)		
	Existing Volume	Expected Volume	LOS	Existing Volume	Expected Volume	LOS
Mitchell Road	42vph	158vph	A	92vph	200vph	A
Ashfords Road	23vph	115vph	A	10vph	103vph	A

The table shows that both Mitchell Road and Ashfords Road would be expected to operate at a LOS A during the peak construction period with minimal queueing or delays.



## 5. Heavy Vehicles

### 5.1 OSOM Vehicle Definitions

Oversize/Overmass (OSOM) vehicles are governed by the National Heavy Vehicle Regulator (NHVR). OSOM vehicles are vehicle configurations which exceed general mass or dimension limits and are classified as *Class 1 vehicles* under the Heavy Vehicle National Law.

There are a range of Class 1 OSOM examples, including<sup>5</sup>:

- agricultural machines such as harvesters and grain augers,
- vehicle combinations carrying large indivisible items like mining and construction vehicles, and
- special purpose vehicles like mobile cranes, concrete pump trucks, and drilling rigs.

Given the variety of OSOM vehicles, there are a range of risk profiles for travel on the road network with management requirements increasing with the vehicle combination size and mass.

In NSW, the management requirements are outlined in the *National Heavy Vehicle Regulator's NSW Class 1 Load Carrying Vehicle Operator's Guide*. The guide outlines the requirements for pilots and escorts, which generally only apply to vehicle combinations exceeding 3.5 meters in width and or 26 meters in length but depend on precise details including exact size, mass, time of travel, and route. This guide is attached for reference in Appendix C.

More detail related to pilots and escorts is available in *Additional Access Conditions Oversize and Overmass Heavy Vehicles and Loads* (TfNSW, October 2022)<sup>6</sup>. Section 3.2.1 of this guide shows the way in which the requirements for pilots and escorts increase with vehicle size. The table shows how the requirements for pilots and escorts increase for combinations exceeding 3.5 metres in width and 26 metres in length as the road safety risks increase.

The relevant conditions of the development consent aim to limit the movement of high-risk vehicles to the site. However, the current wording of the condition covers an extensive range of vehicles, many of which are not high-risk. To address this issue, it is recommended that references to “*Over-dimensional vehicle/s*” in the development consent be changed to “*Heavy vehicle/s requiring escort*” with the following definition:

*Any vehicle that requires a pilot vehicle and/or escort vehicle, as defined by the National Heavy Vehicle Regulator's NSW Class 1 Load Carrying Vehicle Operator's Guide*

Other lower risk OSOM vehicles are still defined as heavy vehicles<sup>7</sup> and managed under other relevant conditions. This approach is consistent with other similar solar farms in NSW<sup>8</sup>, and would not be expected to result in any notable road safety risks.

<sup>5</sup> <https://www.transport.nsw.gov.au/operations/roads-and-waterways/business-and-industry/heavy-vehicles/road-access/restricted-access-1>

<sup>6</sup> <https://www.transport.nsw.gov.au/system/files/media/documents/2022/osom-additional-access-conditions.pdf>

<sup>7</sup> Under relevant NSW legislation, a vehicle is defined as a heavy vehicle if it has a mass of more than 4.5 tonnes.

<sup>8</sup> For example: Marulan Solar Farm (SSD-13137914), Glenellen Solar Farm (SSD-9550), Glanmire Solar Farm (SSD-21208499)

## 5.2 Heavy Vehicles Not Requiring Escort

Heavy vehicles not requiring escort will access the site in a manner consistent with that previously considered and approved. This involves the use of approved State Roads and heavy vehicle access route in the development consent as shown in Figure 3.

The increase in heavy vehicles not requiring an escort as a result of the modification is modest and as a result the mitigation measures required in the development consent, including the intersection upgrades (as shown in Appendix B) and the sealing of Boiling Down Road for 30 metres are suitable.

## 5.3 Heavy Vehicles Requiring Escort

Heavy vehicles requiring escort and the corresponding travel routes were previously considered as part of the issued development consent and the previously approved TMP<sup>9</sup> for the Solar Farm.

A total of 2 additional heavy vehicles requiring escort will be required for the transportation of specialist plant for the BESS including the transformer. Similar to the previously approved routes for the Solar Farm, there are options for the delivery from Port Botany and the Port of Melbourne.

These OSOM vehicles will travel outside of the peak periods and would be subject to the road upgrades and mitigation measures discussed throughout this section which would be confirmed as part of specific permits that would be applied for prior to construction. The following provides a review of the proposed access route.

### 5.3.1 Transformer Vehicle

The largest component to be delivered to the site is expected to be the transformer. The Applicant has provided information regarding the expected specifications of the transformers which are outlined in Table 7.


**Table 7: Estimated Transformer Specifications**

Length (mm)	Width (mm)	Height (mm)	Mass	Trailer Specs
8400	3500	4500	~ 150 tonnes	10x8 + 10x8 Platform Trailer Beamset

An OSOM vehicle configuration has been identified for the expected transformer model. The vehicle used for the assessment is shown within Figure 9 and is based on feedback from a transport company which confirmed that the vehicle specification would be suitable for the mass and size of the transformer.

<sup>9</sup> Gregadoo Traffic Management Plan, NGH, Revision 1.2 December 2020, Approved 22 January 2021

Figure 9: OSOM Vehicle



The Applicant has advised that Port Botany or Port of Melbourne could be utilised as the origin point for the delivery of the transformer. In order to determine whether any civil works are required to accommodate the OSOM vehicle on the road network a route assessment has been undertaken for each potential delivery port. The OSOM vehicle would be provided with escort and pilot vehicles in accordance with relevant authority requirements.

The respective routes and the associated findings are documented below with both assessments presented in Appendix D and Appendix E.

## 5.4 Port Botany Route

The proposed OSOM route between Port Botany and the site is outlined in Table 8.


Table 8: OSOM Route – Access Roads

Road Name	Jurisdiction
Friendship Road	TfNSW
Bumborah Point Road	
Botany Road	
Bunnerong Road	
Gardeners Road	
M8 Motorway	
M5 East Motorway	
South Western Motorway (M5)	
Hume Motorway (M31)	
Sturt Highway (A20)	
Bakers Lane	Wagga Wagga City Council
Inglewood Road	
Mitchell Road	
Ashfords Road	
Boiling Down Road	

The access route, along with 19 identified truck rest areas that could be used along the route, are shown in Figure 10. It is noted that additional rest stop areas may also be available along the route.

A total of 10 points of interest for further assessment were identified as part of the assessment of the access route. The points of interest have been assessed in further detail, including the site access, with the full assessment provided within Appendix D.

Figure 10: OSOM Route – Port Botany



Source: Google Maps - [Link](#)

The assessment of the access route identified that the vehicle is able to access the site with minor civil works, signage relocation and suitable traffic management measures. A desktop assessment of bridge and rail infrastructure has been undertaken to determine their interfacing locations with the proposed OSOM route and is provided below with an overview of the proposed treatments and/or management measures.

### 5.4.1 Bridges and Overpasses

A detailed review of the load limits on all bridges and structures along the route will be undertaken as part of the permit process for the OSOM vehicles, however it is noted that the route predominantly utilises major highways between Port Botany and Gregadoo, with all State roads forming part of the approved Class 1 OSOM network. The State roads along the route have been utilised for other renewable energy projects in the area and no restricted structures have been identified based on the TfNSW Oversize Overmass Load Carrying Vehicles Network map. Accordingly, it is expected that the vehicle loading will be within the allowable limit for all bridges, culverts and other structures on the State Road network.



## 5.4.2 Underpasses

An assessment of the height clearances along the route was undertaken to confirm the suitability of the proposed route for a total proposed load height of approximately 4.5m. The overpass with the lowest clearance along the designated route is on the South-Western Motorway (M5) at Heathcote Road. The clearance at this location is 4.93 metres. It is also noted that some overhead electrical cables along the route may require lifting which would be confirmed prior to construction.

Accordingly, the available height clearance along the proposed route is appropriate to accommodate the OSOM vehicles.

## 5.4.3 Railway Level Crossings

No railway level crossings have been identified along the OSOM route.

## 5.4.4 Summary

The route assessment prepared for the OSOM vehicle from Port Botany identifies a number of road upgrades required in order to allow the vehicles to successfully access the site, with a summary provided in Table 9. Areas where road upgrades are required have been highlighted in the table. Escorts and spotters will be required at all locations to control traffic and ensure the vehicle and load are clear of infrastructure.

**Table 9: Road Upgrade Schedule - OSOM Vehicles - Port Botany**

Point of Interest	Location	Required Road Upgrades
<b>Sydney Metropolitan Area</b>		
01	Bumborah Point Road / Friendship Road (Port Botany, NSW)	No road upgrades required.
02	Botany Road / Bumborah Point Road (Matraville, NSW)	No road upgrades required.
03	Botany Road / Bunnerong Road (Matraville, NSW)	Temporary hardstand and mountable kerb to be provided.
04	Gardeners Road / Bunnerong Road (Matraville, NSW)	No road upgrades required.
<b>Regional NSW</b>		
05	Sturt Highway / Bakers Lane (Gumly Gumly, NSW)	No road upgrades required.
06	Bakers Lane / Inglewood Road (Lake Albert, NSW)	Temporary hardstand to be provided.
07	Inglewood Road / Mitchell Road (Lake Albert, NSW)	Temporary hardstand to be provided.
08	Mitchell Road / Ashfords Road (Gregadoo, NSW)	Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'.

Point of Interest	Location	Required Road Upgrades
09	Ashfords Road / Boiling Down Road (Gregadoo, NSW)	Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'. Temporary hardstand to be provided.
10	Boiling Down Road / Site Access (Gregadoo, NSW)	Temporary hardstand to be provided.

Accordingly, it is concluded that the proposed route is suitable for use by OSOM vehicles associated with the Project with permits to be applied for as part of the TMP. It is recommended that any OSOM movements be timed so they do not coincide with other OSOM vehicles within the surrounding area to limit the impact to the road network, which can be undertaken as part of the permit application.

## 5.5 Port of Melbourne Route

The proposed OSOM route between Port of Melbourne and the site is outlined in Table 10.


Table 10: OSOM Route – Access Roads

Road Name	Jurisdiction
Dock Link Road	DTP
Footscray Road (Docklands Highway)	
Moreland Street	
Whitehall Street (Docklands Highway)	
Somerville Road	
Geelong Road (Princes Highway)	
Somerville Road	
Fairbairn Road (State Road 32)	
Boundary Road (State Road 32)	
Metropolitan Ring Road (M80)	
Hume Freeway (M31)	DTP / TfNSW
Sturt Highway (A20)	TfNSW
Bakers Lane	Wagga Wagga City Council
Inglewood Road	
Mitchell Road	
Ashfords Road	
Boiling Down Road	

The access route, along with 23 identified truck rest areas that could be used along the route, are shown in Figure 11. It is noted that additional rest stop areas may also be available along the route.

A total of 15 points of interest for further assessment were identified as part of the assessment of the access route. The points of interest have been assessed in further detail, including the site access, with the full assessment provided within Appendix D.

Figure 11: OSOM Route – Port of Melbourne



Source: Google Maps - [Link](#)

The assessment of the access route identified that the vehicle is able to access the site with minor civil works, signage relocation and suitable traffic management measures. A desktop assessment of bridge and rail infrastructure has been undertaken to determine their interfacing locations with the proposed OSOM route and is provided below with an overview of the proposed treatments and/or management measures.

### 5.5.1 Bridges and Overpasses

A detailed review of the load limits on all bridges and structures along the route will be undertaken as part of the permit process for the OSOM vehicles, however it is noted that the route predominantly utilises major highways between Port of Melbourne and Gregadoo, with all State roads forming part of the approved Class 1 OSOM network. The State roads along the route have been utilised for other renewable energy projects in the area and no restricted structures have been identified based on DTP's Oversize/Overmass Network Map and the TfNSW Oversize Overmass Load Carrying Vehicles Network map. Accordingly, it is expected that the vehicle loading



will be within the allowable limit for all bridges, culverts and other structures on the State Road network.

## 5.5.2 Underpasses

An assessment of the height clearances along the route was undertaken to confirm the suitability of the proposed route for a total proposed load height of approximately 4.5m. No low-clearance underpasses were identified along the route.

Accordingly, the available height clearance along the proposed route is appropriate to accommodate the OSOM vehicles.

## 5.5.3 Railway Level Crossings

A total of 2 railway level crossings have been identified along the OSOM route as outlined in Table 11, which includes advice from the relevant rail authority for each crossing.

**Table 11: Railway Level Crossing Assessment**

Railway Crossing Location	Rail Authority	Authority Advice
Somerville Road, Brooklyn	V/Line and ARTC	Permit is given by DTP.
Somerville Road, Brooklyn	V/Line and ARTC	Permit is given by DTP.

Written approval will be sought from the relevant rail authorities for all level crossings as part of the TMP. Accordingly, the OSOM traffic is expected to have no major impact on the operation or safety of the railway level crossings.

## 5.5.4 Other Roadworks

At the time of this assessment, ongoing ad hoc Waste Gate Tunnel Project roadworks including nightly lane closures are taking place on the westbound direction of Footscray Road in the vicinity of Dock Link Road. Based on information available at this point in time, it is planned that this road closure will be completed June 2024, well before the OSOM vehicle is to be expected to utilise this route<sup>10</sup>.

## 5.5.5 Summary

The route assessment prepared for the OSOM vehicle from Port of Melbourne identifies a number of road upgrades required in order to allow the vehicles to successfully access the site, with a summary provided in Table 12. Areas where road upgrades are required have been highlighted in the table. Escorts and spotters will be required at all locations to control traffic and ensure the vehicle and load are clear of infrastructure.

<sup>10</sup> [https://bigbuild.vic.gov.au/disruptions/disruptions-map?dateRange=&disruption=14188&lat=-37.80733287841159&lng=144.9125201950981&ordering=-priority%2Cupdated\\_on&place=&project=&searchedPlace=&subtype=&type=&zoom=17](https://bigbuild.vic.gov.au/disruptions/disruptions-map?dateRange=&disruption=14188&lat=-37.80733287841159&lng=144.9125201950981&ordering=-priority%2Cupdated_on&place=&project=&searchedPlace=&subtype=&type=&zoom=17)



**Table 12: Road Upgrade Schedule - OSOM Vehicles – Port of Melbourne Route**

Point of Interest	Location	Required Road Upgrades
<b>Melbourne Metropolitan Area</b>		
01	Dock Link Road / Footscray Road (West Melbourne, VIC)	No road upgrades required.
02	Footscray Road / Moreland Street (Footscray, VIC)	No road upgrades required.
03	Whitehall Street / Somerville Road (Footscray, VIC)	Temporary removal of flexible traffic separators.
04	Somerville Road / Geelong Road (Kingsville, VIC)	No road upgrades required.
05	Somerville Road / Fairbairn Road (Sunshine West, VIC)	No road upgrades required.
06	Fairbairn Road / Boundary Road (Laverton North, VIC)	Temporary removal of four traffic signs.
07	Boundary Road / Western Ring Road (Derrimut, VIC)	No road upgrades required.
<b>Regional NSW</b>		
08	Hume Highway / Sturt Highway (Tarcutta, NSW)	No road upgrades required.
09	Sturt Highway (Tarcutta, NSW)	No road upgrades required.
10	Sturt Highway / Bakers Lane (Gumly Gumly, NSW)	No road upgrades required.
11	Bakers Lane / Inglewood Road (Lake Albert, NSW)	Temporary hardstand to be provided.
12	Inglewood Road / Mitchell Road (Lake Albert, NSW)	Temporary hardstand to be provided.
13	Mitchell Road / Ashfords Road (Gregadoo, NSW)	Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'.
14	Ashfords Road / Boiling Down Road (Gregadoo, NSW)	Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'. Temporary hardstand to be provided.
15	Boiling Down Road / Site Access (Gregadoo, NSW)	Temporary hardstand to be provided.


Accordingly, it is concluded that the proposed route is suitable for use by OSOM vehicles associated with the Project with permits to be applied for as part of the TMP. It is recommended that any OSOM movements be timed so they do not coincide with other OSOM vehicles within the surrounding area to limit the impact to the road network, which can be undertaken as part of the permit application.

## 6. Intersection Assessment

### 6.1 Turn Treatment Assessment

*Austrroads Guide to Traffic Management Part 6: Intersections, Interchanges, and Crossings* specifies the turning treatments required at intersections. An assessment has been undertaken for the intersection of Mitchell Road and Ashford Road to confirm the suitability of the mitigation measures required under *Schedule 3, Condition 5* of the development consent. Figure 3.25 of the guide specifies the required turn treatments on the major road at unsignalised intersections and is provided below in Figure 12 for a design speed between 70 and 100 km/h.

Figure 12: Figure 3.25 of *Austrroads Guide to Traffic Management Part 6*



The requirement to provide turn facilities at the intersection is primarily generated during the morning peak hour when the workforce access the site, which occurs from 6:00am to 7:00am. Table 13 identifies the required turning treatments based on the expected traffic volumes at the intersection (Figure 8) and the associated volumes have been plotted within Figure 12.

Table 13: Turning Volumes for Turn Treatment Calculations – Mitchell Road / Ashford Road

Turning Treatment	Traffic Volume (vph)		Requirement
	Turn Volume	Major Road	
Right Turn	104	44	BAR
Left Turn	2	28	BAL

Therefore, the intersection would require a Basic Right Turn (BAR) and Basic Left Turn (BAL) treatment, consistent with that required under *Schedule 3, Condition 5* of the development consent.

## 6.2 Mitigation Measures

The turn treatment assessment confirms the suitability of a Basic Right Turn (BAR) and Basic Left Turn (BAL) treatment at the intersection of Mitchell Road and Ashford Road. A concept plan of this treatment is included for reference in Appendix B.

A concept plan for the upgrade of the intersection of Ashfords Road and Boiling Down Road as required under *Schedule 3, Condition 5* is also included in Appendix B. Based on the modest increase in traffic volumes and mix of heavy vehicle types of the modification (which are consistent with the approved Solar Farm) the intersection upgrade is considered suitable.

## 6.3 Site Access

Boiling Down Road has a flat and straight alignment with clear visibility in both directions. *Schedule 3, Condition 6* of the development consent requires the following:

*Prior to the commencement of construction, the Applicant must upgrade the site access point off Boiling Down Road (shown in Appendix 1) with a Rural Property Access type treatment to cater for the largest vehicle accessing the site, in accordance with the Austroads Guide to Road Design, to the satisfaction of Council.*

The implementation of the site access points constructed in accordance with this condition is considered suitable for the proposed modification and will facilitate safe access to and from the site.

## 6.4 Summary

The traffic of the overall project inclusive of the modification is expected to generate the highest level of traffic during the peak construction period. The assessment presented above indicates that the road network is able to readily accommodate the traffic inclusive of the BESS during the peak construction period, including a review of the cumulative traffic generated by other major projects within the surrounding area.

During construction the vehicle trips throughout the middle of the day are expected to be predominantly associated with heavy vehicles with approximately 22 movements per hour. This increase in traffic can be readily accommodated without significant adverse safety or operational impacts.

The traffic generation characteristics of the modification for the operation, upgrading and decommissioning phases is anticipated to be consistent with that already considered and approved, and result in a negligible change to the traffic environment.

The mitigation measures required under *Schedule 3, Condition 5* of the development consent are therefore suitable to manage the impacts of the project and modification. The site access upgrade design provided is consistent with *Schedule 3, Condition 6* of the development consent and would facilitate safe access to the site.

A traffic management would be implemented in accordance with *Schedule 3, Condition 8* of the development consent which would manage the traffic impacts of the Solar Farm and BESS in a manner consistent with that previously approved, which is suitable.

Accordingly, the road network, mitigation measures, site access arrangements and further traffic management arrangements are suitable to accommodate the traffic generated by the modification during the construction, operation, and decommissioning periods.



## 7. Conclusion

Amber Organisation has assessed the traffic impacts of the proposed modification to the Gregadoo Solar Farm. The modification involves the incorporation of a BESS while with a generation capacity of 200MWAC and 400MWh.

The Solar Farm is proposed to have a capacity of up to 65MW and includes the construction of a substation transformer and a Battery Energy Storage System with a capacity of up to 200MW/400MWh.

The construction period for the overall project is expected to commence in 2025 and take approximately 12 months, with the peak construction period expected to take 6 months. A construction workforce of up to 150 full-time equivalent personnel would be on-site during the peak construction phase and would primarily be drawn from Wagga Wagga.

Specialist plant for the BESS will be delivered from Port Botany or the Port of Melbourne. General construction materials and equipment will generally be sourced from within Wagga Wagga or the surrounding area where practicable.

The above assessment determined the following:

- The overall project comprising the Solar Farm and BESS is expected to generate a total of 234 vehicles per day, including 120 heavy vehicles during the construction peak. Outside the construction peak the project is anticipated to 125 vehicles per day, including 45 heavy vehicles.
- Mitigation measures under *Schedule 3, Condition 5* of the development consent are suitable to manage impacts of the construction of the Solar Farm and BESS including the additional heavy vehicle volumes.
- The site access arrangements are appropriate noting the requirements under *Schedule 3, Condition 6* of the development consent.
- A traffic management plan implemented in accordance with *Schedule 3, Condition 8* of the development consent would appropriately manage the traffic impacts of the Solar Farm and BESS.
- Overall, the road network is able to accommodate the traffic generated by the project inclusive of the modification during the construction, operation and decommissioning stages.
- It is recommended that references to “*Over-dimensional vehicle/s*” in the development consent be changed to “*Heavy vehicle/s requiring escort*” with an updated definition to better align with the intent of the condition.
- The access route for heavy vehicles requiring escort required for the BESS is from Port Botany or the Port of Melbourne. The route assessments identify some minor civil works (e.g. temporary hard stand) and temporary traffic management measures to facilitate access to the site.

Accordingly, based on the assessment above, it is concluded that the surrounding road network and site access arrangements are suitable to accommodate additional traffic volumes of the modification during the construction, operational, upgrading and decommissioning phases.

# Appendix A

## Survey Results




### AUTOMATIC COUNT SUMMARY

<b>Street Name :</b>	Mitchell Rd	<b>Location :</b>	Between Gregaoo Rd and Butterbush Rd
<b>Suburb :</b>	Gregaoo	<b>Start Date :</b>	00:00 Wed 20/January/2021
<b>Machine ID:</b>	CY08VBR6	<b>Finish Date :</b>	00:00 Wed 27/January/2021
<b>Site ID:</b>		<b>Speed Zone :</b>	80 km/h
<b>Prepared By :</b>		<b>Email:</b>	

GPS information		Lat 35° 11' 16.02 South	<b>Direction of Travel</b>		
		Long 147° 23' 54.09 East	<b>Both directions</b>	<b>Northbound</b>	<b>Southbound</b>
<b>Traffic Volume : (Vehicles/Day)</b>	Weekdays Average		1,475	728	747
	7 Day Average		1,464	727	737
<b>Weekday</b>	<b>AM</b>	11:00	132	64	68
<b>Peak hour starts</b>	<b>PM</b>	12:00	124	55	69
<b>Speeds : (Km/Hr)</b>	85th Percentile		82.3	78.4	88.5
	Average		73.5	68.3	79.9
<b>Classification % :</b>	Light Vehicles up to 5.5m		70.5%	83.2%	58.0%

### Location

**GPS Information** [Load Google Map \(internet required\)](#)  
 (Latitude, Longitude) -35.187783, 147.398358



[Speed Data](#)      [Speed Graph](#)      [Speed Bin](#)  
[Volume Data](#)      [Volume Graph](#)      [Classification](#)

**AUTOMATIC COUNT SUMMARY**

<b>Street Name :</b>	Ashfords Rd	<b>Location :</b>	North of GWMC
<b>Suburb :</b>	Gregadoo	<b>Start Date :</b>	00:00 Mon 14/August/2023
<b>Machine ID:</b>	YN856WP9	<b>Finish Date :</b>	00:00 Mon 21/August/2023
<b>Site ID:</b>		<b>Speed Zone :</b>	80 km/h
<b>Prepared By :</b>		<b>Email:</b>	

GPS information		Lat 35° 12' 16.31 South	<b>Direction of Travel</b>		
		Long 147° 23' 43.02 East	<b>Both directions</b>	<b>Northbound</b>	<b>Southbound</b>
<b>Traffic Volume : (Vehicles/Day)</b>	Weekdays Average		496	249	247
	7 Day Average		528	265	263
<b>Weekday</b>	<b>AM</b>	11:00	60	30	30
<b>Peak hour starts</b>	<b>PM</b>	12:00	61	30	31
<b>Speeds : (Km/Hr)</b>	85th Percentile		77.9	83.2	71.9
	Average		70.0	74.1	64.3
<b>Classification % :</b>	Light Vehicles up to 5.5m		70.7%	68.3%	73.2%

**Location**

**GPS Information** [Load Google Map \(internet required\)](#)  
 (Latitude, Longitude) -35.204531, 147.395283



- [Speed Data](#)      [Speed Graph](#)      [Speed Bin](#)
- [Volume Data](#)      [Volume Graph](#)      [Classification](#)

## Appendix B

### Concept Plans – Road Upgrades





Monday, March 19, 2018 11:35:35

The following design details have been taken from *Austrroads Guide to Road Design Part 4A*:

- Rural Basic Right-turn Treatment (BAR) Section 7.5.1.
- 1: Design speed of 110km/h.
  - 2: 3.3m Lane widths have been used.
  - 3: Taper lengths calculate to 46m.
  - 4: Formation/carriageway widening is 3.0m.
  - 5: Storage length is 22.5m for one 19m design vehicle.

REV	DATE	DRN	CHK	DESCRIPTION
00	22/03/18	TJG		

**Gregadoo Solar Farm - Access Design**  
 Mitchell Road / Ashfords Road Intersection  
 Concept Intersection Treatment (BAR)

DRAWN: TJG	---	---
DATE: 22/03/18	STATUS: ---	
SCALE: 1:750 @ A3		
DWG NO: 15254-0S1A		





Monday, March 19, 2018 11:35:35

REV	DATE	DRN	CHK	DESCRIPTION
00	22/03/18	TJG		

**Gregadoo Solar Farm - Access Design**  
 Ashfords Road / Boiling Down Road Intersection  
 Proposed Intersection Layout Plan

DRAWN: TJG	---	---
DATE: 22/03/18	STATUS: ---	
SCALE: 1:500 @ A3		
DWG NO:15254-0S1A		



## Appendix C

### Class 1 Load Carrying Vehicle Operator's Guide NSW





## **New South Wales Class 1 Load Carrying Vehicle Operator's Guide**

### **Important:**

**This Operator's Guide is for three Notices separated by Part A, Part B and Part C. Please read sections carefully as separate conditions may apply.**

**For enquiries about roads and restrictions listed in this document, please contact Transport for NSW Road Access unit: [spu@transport.nsw.gov.au](mailto:spu@transport.nsw.gov.au)**

**21 December 2023**

## Contents

Purpose.....	3
Definitions.....	3
Part A – NSW Class 1 Load Carrying Vehicles Notice .....	7
About the Notice .....	7
1 Travel conditions.....	7
1.1 Pilot and escort requirements .....	7
1.2 Night travel.....	7
1.3 Daytime travel .....	8
1.4 Clearway and transit lane travel.....	9
1.5 Weekday and peak hour travel – Urban Zone .....	9
1.6 Weekday and peak hour travel restrictions – Regional Zone .....	9
1.7 State-wide public holiday restrictions.....	10
2 Limited Access Locations.....	14
2.1 Limited Access Locations and Zones – NSW Urban Zone .....	14
2.2 Limited Access Locations and Zones – NSW Regional Zone .....	20
3 Bridge mass restrictions .....	25
3.1 NSW Urban Zone – Bridge mass restrictions.....	25
3.2 NSW Regional Zone – Bridge Mass Restrictions .....	26
PART B – New South Wales Schedule of the Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice .....	31
About the Notice .....	31
Further information.....	31
Approved routes.....	31
4 Travel conditions.....	31
4.1 Pilot and escort requirements.....	31
4.2 Daytime travel – Sydney Metropolitan Zone.....	32
4.3 Weekday (excluding state-wide public holidays) daytime travel restrictions .....	32
4.4 Weekend and state-wide public holiday travel restrictions for Class 1 load carrying vehicles.....	33
4.5 Day time restrictions for Class 1 load carrying vehicles during the Christmas holiday period .....	34
4.6 General.....	35
PART C – New South Wales Schedule of the Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice.....	36
About the Notice.....	36
Approved routes.....	36
General conditions .....	36
Key contacts.....	36
PART D - NSW Bushfire Emergency Travel .....	37

## Purpose

The *New South Wales Class 1 Load Carrying Vehicle Operator's Guide* (the Operator's Guide), as amended from time to time, works in conjunction with the following Notices:

- *NSW Class 1 Load Carrying Vehicle Notice*
- *NSW Schedule of the Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice*
- *NSW Schedule of the Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice*

### Please note:

- There is a separate oversize and overmass Multi-State Class 1 Load Carrying Vehicles Notice.
- If you are both oversize and overmass, you must meet the requirements and comply with the conditions of both Notices.
- An eligible vehicle must comply with the requirements of the Notice is operating under, including Schedule 8 of the *Heavy Vehicle (Mass, Dimension and Loading) National Regulation*, and the Operator's Guide.

The Operator's Guide provides details of the approved routes and travel conditions for eligible vehicles operating under the three Notices mentioned above. The Operator's Guide contains **four** parts:

- **Part A – NSW Class 1 Load Carrying Vehicle Notice**
- **Part B – NSW Schedule of the Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice**
- **Part C – NSW Schedule of the Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice**
- **Part D – NSW Bushfire Emergency travel.**

Please note, these requirements were previously contained in Appendix 2 of the former New South Wales Class 1 Load Carrying Vehicle Notice 2014 and the NSW Schedule of the Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice 2016 and the Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice

## Definitions

Unless otherwise stated, words and expressions used in this Operator's Guide have the same meanings as those defined in the HVNL and the Notice. In this Operator's Guide:

**Christmas school holidays** means the holidays of that name set by the NSW Department of Education

**Newcastle Inner Zone** means the area displayed on the NSW Oversize Overmass Load Carrying Vehicle Network map.

**Newcastle Outer Zone** means the area displayed on the NSW Oversize Overmass Load Carrying Vehicle Network map.

**Public holiday** means a public holiday made under the Public Holidays Act for the whole State.

**Public holiday period** means:

- a) a period of three or more consecutive days covering a declared NSW Statewide public holiday and adjacent weekend days (for example Easter and every long weekend); and
- b) the period between 23 December and 3 January (inclusive).

**Regional Zone** means the area outside of the Urban Zone.

**Urban Zone** means the area displayed on the NSW Oversize Overmass Load Carrying Vehicle Network map.

The NSW Oversize Overmass Load Carrying Vehicles Network map displaying travel zones can be accessed at: <https://roads-waterways.transport.nsw.gov.au/business-industry/heavy-vehicles/maps/index.html>.

### Disclaimer

The NSW Oversize Overmass Load Carrying Vehicles Network map shows approved routes and restrictions as an overlay on top of Google maps. Transport for NSW has no responsibility for, and does not guarantee the accuracy of, the underlying Google maps.

Transport for NSW strives to be accurate in showing the NSW Oversize Overmass Load Carrying Vehicles Network map approved routes, restrictions and conditions; however, there may be errors and omissions caused by Google maps being incorrect or out of date. Transport for NSW is not responsible for errors or omissions.

## New South Wales Travel Zones

### NSW Urban Zone

For the purposes of this Section, the NSW Urban Zone is defined as the area bounded by and including the named roads,

- the Pacific Ocean and the North Channel of the Hunter River, then north from Stockton bridge along
- Nelson Bay Road to Williamtown, then west along
- Cabbage Tree Road to Masonite Road near Tomago, then along
- Masonite Road to the Pacific Highway at Heatherbrae, then south along the
- Pacific Highway to Hexham, then west along the
- New England Highway to Weakleys Drive Thornton, then south along
- Weakleys Drive to the M1 Pacific Motorway at Beresfield, then along the
- M1 Pacific Motorway to the Hawkesbury River bridge, then along the
- Hawkesbury River and the Nepean River to Cobbity, then a line drawn south from
- Cobbity to Picton, then via
- Picton Road and Mount Ousley Road to the start of the M1 Princes Motorway at Mount Ousley, then via the
- M1 Princes Motorway to the Princes Highway at West Wollongong, then the
- Princes Highway and Illawarra Highway to Albion Park with a branch west on West Dapto Road to Tubemakers, then
- Tongarra Road to the Princes Highway, then
- Princes Highway south to the intersection of South Kiama Drive at Kiama Heights



## Newcastle Outer Zone




## Newcastle Inner Zone



## Sydney Metropolitan Zone

This zone covers the area bounded by the Pacific Ocean, the Hawkesbury River and the Nepean River to its crossing of the Hume Highway at Menangle, then a line taken to the northern end of the F6 Southern freeway at Waterfall, and the western and northern boundaries of the Royal National Park.



## Part A – NSW Class 1 Load Carrying Vehicles Notice

### About the Notice

The NSW Class 1 Load Carrying Vehicle Notice allows eligible Class 1 load carrying vehicles in New South Wales to operate up to 3.5m wide, 4.6m high, 25.0m long, 5.5m rear overhang and total mass of 49.5 tonnes on approved (State and council) routes in New South Wales, and in compliance with the conditions of the Notice and this Operator's Guide.

Eligible vehicles may operate in the NSW Urban Zone and the NSW Regional Zone subject to the conditions set out in the Notice and any travel conditions or restrictions that apply in a Zone as set out in the Operator's Guide.

Eligible vehicles exceeding 4.3m in height must only be operated on routes approved for 4.6m high vehicles, as shown on the approved NSW Oversize Overmass Load Carrying Vehicles Network Map.

**Note:** For the purposes of section 11 of Schedule 8 of the MDL National Regulation –

- (a) the driver or operator of an eligible vehicle must undertake a route survey before travel to ensure that the vehicle can do so safely and without—
  - (i) damaging road, structure (including a bridge), rail crossing, tree, road infrastructure, or roadside furniture; or
  - (ii) disrupting essential services, including telecommunication, electricity, rail, gas, water or sewage services.
- (b) prior to commencing a journey a driver or operator of an eligible vehicle must check a route network map mentioned in the relevant Schedule of the Notice for updates and any restrictions or limitation applying to the proposed route.
- (c) For the purposes of section 11(1) of Schedule 8, the driver or operator must, before commencing the relevant journey, identify any relevant road closures and road conditions or restrictions that may inhibit the movement of the eligible vehicle.

## 1 Travel conditions

### 1.1 Pilot and escort requirements

Unless otherwise stated as a condition of travel in this operator's guide, an eligible vehicle operating in the daytime not exceeding 3.5m wide or 26m long does not require a pilot vehicle

An eligible vehicle operating at night wider than 2.5m or longer than 22m requires at least one pilot.

### 1.2 Night travel

- 1.2.1 Eligible vehicles not exceeding 2.5m wide or 22m long may travel within the NSW Urban Zone between sunset and sunrise.
- 1.2.2 Eligible vehicles exceeding 2.5m wide or 22m long may travel between 9.30pm and 5:30am on the roads or area as defined in the table below.

Road or area	Night travel permitted from 9:30pm to 5:30am
NSW Urban Zone	All approved routes within the NSW Urban Zone
Hume Highway	Between Picton Road interchange and the Victorian border and including an access road to any service area immediately adjacent to the Highway
Pacific Highway	Between Raymond Terrace and the Queensland border only on those sections of the Highway that are dual carriageway divided road and not subject to roadwork and an accessroad to any service area immediately adjacent to the Highway

Road or area	Night travel permitted from 9:30pm to 5:30am
Princes Highway	From 200m south of Pepper Road (the Log Cabin) near Tomerong north to the boundary of the NSW Urban Zone at South Kiama Drive, Kiama Heights.
Great Western Highway	Between Nepean River at Emu Plains and Yetholme. When exceeding 3.5m wide or 26.0m long, an eligible vehicle must be accompanied by at least three pilot vehicles (two pilot vehicles at the front and one at the rear).
Federal Highway	Between the intersection at the Hume Highway and the Australian Capital Territory (ACT) border south of Sutton
M1 Pacific Motorway	Between the Hawkesbury River and John Renshaw Drive near Beresfield
John Renshaw Drive	Between the M1 Pacific Motorway and the New England Highway at Beresfield
Weakleys Drive	Between the M1 Pacific Motorway and the New England Highway
New England Highway	Between Weakleys Drive at Beresfield and Thomas Mitchell Drive (for northbound travel) or Muscle Creek Road (for southbound travel) south of Muswellbrook
Hunter Expressway	Between the M1 Pacific Motorway (near Seahampton and the New England Highway) near Branxton
Golden Highway	Intersection of the New England Highway and parking bay on Jerry Plain Road near Warkworth

## 1.3 Daytime travel

### 1.3.1 Weekday Urban Zone

Eligible vehicles not exceeding 3.5m in width or 26m in length may operate in the daytime, Monday to Friday (except on state-wide public holidays), in the Urban Zone subject to peak hour and clearway and transit lane restrictions.

### 1.3.2 Weekends Urban Zone

Eligible vehicles not exceeding 3.5m in width or 26m in length may operate in the daytime subject to section 1.7 (State-wide public holiday restrictions) of this guide.

### 1.3.3 Newcastle Zone

Peak hour or transit lane restrictions do not apply to eligible vehicles not exceeding 3.2m in width or 26m in length in the Newcastle Zone.

### 1.3.4 Weekday Regional Zone

Daytime travel approved subject to peak hour restrictions outlined in 1.6.

## 1.4 Clearway and transit lane travel

An eligible vehicle that is wider than 2.5m or longer than 22m must not travel in a Clearway or Transit Lane in the NSW Urban Zone between Monday and Friday (except on a state-wide public holiday) between the hours of 5:30am and 10:00am and between the hours of 3:00pm and 7:00pm on a day when a clearway or transit lane restriction applies.

**Note:** Clearway and transit lane time restrictions can apply to just one side of the road or to both sides. Check prior to travel.

## 1.5 Weekday and peak hour travel – Urban Zone

1.5.1 An eligible vehicle that is wider than 2.5m or longer than 22m must not travel within the NSW Urban Zone on any classified State road between Monday and Friday (except on a state-wide public holiday) between the hours of 5:30am and 9:00am and between 4:00pm and 6:00pm.

1.5.2 Despite Clause 1.5.1, eligible vehicles not exceeding 3.2m wide may operate in the Newcastle Outer Zone during peak times between the hours of 5:30am and 9:00am and between the hours of 4:00pm and 6:00pm.

For the purposes of this clause, the Newcastle Outer Zone is defined as the area bounded by and including:

- A line drawn from the Pacific Ocean at Glenrock Lagoon to the intersection of Pacific Highway and Northcott Drive,
- Northcott Drive, Bridges Road, Turton Road, Hanbury Street
- along the northern railway line to Watt Street and the Hunter River
- the Pacific Ocean and the North Channel of the Hunter River, then north from Stockton bridge along
- Nelson Bay Road to Williamtown, then west along
- Cabbage Tree Road to Masonite Road near Tomago, then along
- Masonite Road to the Pacific Highway at Heatherbrae, then south along the
- Pacific Highway to Hexham, then west along the
- New England Highway to Weakleys Drive Thornton,
- Weakleys Drive to the F3 Sydney Newcastle Freeway at Beresfield, then south along
- F3 Sydney Newcastle Freeway, through the intersection of the F3 Sydney Newcastle Freeway and Palmers Road, to the crossing of MR217 at Dora Creek
- then Dora Creek and Lake Macquarie to the Pacific Ocean crossing the Pacific Highway at Swansea Bridge.

## 1.6 Weekday and peak hour travel restrictions – Regional Zone

Eligible vehicles that are oversize must not travel in the daytime contrary to the requirements of this table:

Location	Road or area	Travel not permitted
From Nepean River at Emu Plains to Katoomba	Great Western Highway	If wider than 2.5m – Monday–Friday 6:00 am to 9:00am and 4:00pm to 7:00pm (except on state-wide public holidays)
Nowra at Shoalhaven Bridge (southbound).	Princes Highway	If wider than 2.5m – Monday–Saturday 8:00am to 10:00am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays)
Moama Echuca Bridge	Cobb Highway	Monday–Friday 7:30am to 9:30am, noon to 1:00pm, and 3:00pm to 6:00pm Saturday and Sunday 7:30am to 9:00am, and noon to 1:00 pm

Location	Road or area	Travel not permitted
Macksville at Old Nambucca River Bridge	Giinagay Way	If wider than 2.5m – Monday–Saturday 7:30am to 9:30am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays)
Coffs Harbour City between Stadium Drive and West Korora Road	Pacific Highway	If wider than 2.5m – Monday–Saturday 7:30am to 9:30am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays)
Three Chain Road Lismore to Sneaths Road Wollongbar	Bruxner Highway	If wider than 3.2m Monday–Saturday 7:30am to 9:30am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays)
Old Grafton Bridge over Clarence River between Grafton City and South Grafton	Summerland Way	If wider than 2.5m – Monday–Saturday 7:30am to 9:30am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays)
Weakleys Drive to the Singleton side of the traffic lights at Magpie Street (Bunning's corner) (north of Singleton)	New England Highway	If wider than 3.2m – Monday–Friday 5:30am to 9:30am; and Monday–Friday 3:00pm to 6:00pm (except on state-wide public holidays).
Between the M1 Pacific Motorway near Seahampton and the New England Highway) near Branxton	Hunter Expressway	If wider than 3.2m – Monday to Friday 5:00am to 9:00am; and Monday to Friday 4:00pm to 6:00pm (except on state-wide public holidays).

## 1.7 State-wide public holiday restrictions

### 1.7.1 Sundays and state-wide public holidays

Travel is not permitted after 4:00pm on Sundays and state-wide public holidays on the following roads:

Road or area subject to restriction
Hume Highway between the Picton Road interchange and the M7 and M5 interchange at Prestons
Western Motorway (M4) between the Nepean River at Emu Plains and Prospect
M1 Pacific Motorway between the Hawkesbury River and the Central Coast Highway interchange at Kariong

### 1.7.2 Weekends and state-wide public holidays – Regional Zone

Eligible vehicles wider than 2.5m or longer than 22m are not permitted to travel in the daytime on weekends or state-wide public holidays on the following roads:

Road or area	Travel restriction applies
Burley Griffin Way	Between the Hume Highway west of Bowning and the Irrigation Way (MR80) at Yoogali east of Griffith
Snowy Mountains Highway	Between Tumut and Cooma during the official snow season from the Queen's Birthday weekend in June and the Labour Day weekend in October (inclusive)

Road or area	Travel restriction applies
Kings Highway	Between Braidwood and Batemans Bay from first day of November to last day of February (inclusive)
Princes Highway	From Tomerong to Bendalong Road after 8:00am
Great Western Highway	From Nepean River at Emu Plains to Little Hartley after 8:30am
Bells Line of Road	From North Richmond to Mount Victoria no travel after 8.30am for eligible vehicles over 2.9m wide or 19m long
Chifley Road	From Bell to Great Western Highway no travel after 8.30am
Putty Road	From Windsor to Golden Highway near Mount Thorley no travel after 8.30am
Barton Highway	Between the Hume Highway and the ACT border after 4:00pm Sundays or state-wide public holidays
Lachlan Valley Way	Between the Hume Highway northwest of Yass and Forbes after 4:00pm Sundays or state-wide holidays

### 1.7.3 Public holiday periods (including 23 December to 3 January)

For the purposes of this clause a public holiday period means a period of three or more consecutive days covering a declared NSW state-wide public holiday and adjacent weekend days (for example Easter and every long weekend); and the period between 23 December and 3 January (inclusive).

Eligible vehicles wider than 2.5m or longer than 22m are not permitted to travel in the daytime during public holiday periods on the roads listed in the table titled "Travel Restriction applies to":

The following exceptions to this restriction apply to vehicles that are:

1. driving across the road;
2. carrying agricultural equipment directly engaged in an agricultural task.

Travel restriction applies to
Princes Highway – no travel from Broadway Sydney to Victorian Border
Hume Highway – from Parramatta Rd Ashfield to Victorian Border Albury
Pacific Highway – from Warringah Freeway Sydney to Queensland border Tugan
New England Highway – from Hexham Bridge to Weakleys Drive
Central Coast Highway – from F3 at Kariong to Pacific Highway Doyalson
Newcastle Bypass – from Pacific Highway Windale to Pacific Highway Sandgate
Cumberland Highway – from Hume Highway Liverpool to Pacific Highway Wahroonga
Great Western Highway – from Broadway Sydney to Mitchell Highway Bathurst
Warringah Freeway – from Sydney Harbour Bridge to Willoughby Rd Naremburn
M2 Hills Motorway – from North Ryde to Seven Hills
M1 Pacific Motorway – from Wahroonga to Beresfield
M4 Western Motorway – from Concord Rd to Nepean River Leonay
M5 South Western Freeway – from Kyeemagh to Prestons
Princes Highway – from Waterfall to Yallah
M7 Westlink – from Seven Hills to Prestons
Gore Hill Freeway – Naremburn to Lane Co
M4 West Tunnel
M8 Tunnel

<b>Travel restriction applies to</b>
NorthConnex Tunnel
Pacific Highway – from Masonite Road at Heatherbrae to the Gold Coast Highway interchange at Tweed Heads Road West
New England Highway – from Weakleys Drive to Queensland border
Golden Highway – from New England Highway to Dubbo
Mitchell Highway – from Bathurst to Dubbo
Castlereagh Highway – from Marrangaroo to Gilgandra
Kamilaroi Highway – from Willow Tree to Narrabri
Newell Highway – from Tocumwal to Goondiwindi
Mid Western Highway – from Bathurst to Marsden
Sturt Highway – from Lower Tarcutta to Narrandera
Riverina Highway – from Bethanga to Finley
Monaro Highway – from ACT border to Victorian border near Rockton
Snowy Mountains Highway – from Bega to the Hume Highway
Oxley Highway – from Port Macquarie to Coonabarabran
Gwydir Highway – from South Grafton to Moree
Bruxner Highway – from Ballina to Boggabilla
Gold Coast Highway – from Tweed Interchange to Coolangatta
Illawarra Highway – from Albion Park to the Hume Highway
Federal Highway – from Hume Highway to ACT border
Barton Highway – from Hume Highway to ACT border
Burley Griffin Way (MR84) between the Hume Highway west of Bowning and the Irrigation Way (MR80) at Yoogali east of Griffith
Kidman Way (MR321 + MR80) between the Newell Highway 16km north of Jerilderie and the Mid Western Highway at Goolgowi
Lachlan Valley Way (MR56) between the Newell Highway at Forbes and its intersection with the Hume Highway northwest of Yass
Kings Highway (MR51) between Braidwood and Batemans Bay
Olympic Highway (MR78) between the Hume Highway north of Albury, and Cowra
Hunter Expressway (6011) between the M1 Pacific Motorway (6003) near Seahampton and the New England Highway (HW9) near Branxton

#### 1.7.4 Additional daytime restrictions for Class 1 load-carrying vehicles during the Christmas holiday period

In addition to the Christmas "no travel" restriction as stated in section 1.7.3 (Public holiday periods (including 23 December to 3 January)), the below additional travel restrictions are in place prior to 23 December and extend past 3 January each year during the school holiday period, (refer Start Date and End Date columns for details)

Road or area	Width	Length	Start point	Finish point	Start date	End date	Conditions
Princes Highway	Over 2.5m up to 3.5m	n/a	Bendalong Road, Conjola	Ulladulla	Weekday before the start of the Christmas school holidays	The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	1 pilot and contact police before travel. NSW Police contact details are available at: <a href="https://www.nhvr.gov.au/road-access/access-management/third-party-approvals">https://www.nhvr.gov.au/road-access/access-management/third-party-approvals</a>
Princes Highway	Over 2.5m up to 3.5m	n/a	Narooma	Cobargo	Weekday before the start of the Christmas school holidays	The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	1 pilot and contact police before travel. NSW Police contact details are available at: <a href="https://www.nhvr.gov.au/road-access/access-management/third-party-approvals">https://www.nhvr.gov.au/road-access/access-management/third-party-approvals</a>
Princes Highway	Over 2.5m up to 3.5m	n/a	Pambula	Eden	Weekday before the start of the Christmas school holidays	The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	1 pilot and contact police before travel. NSW Police contact details are available at: <a href="https://www.nhvr.gov.au/road-access/access-management/third-party-approvals">https://www.nhvr.gov.au/road-access/access-management/third-party-approvals</a>
Princes Highway	Over 3.2m	n/a	Bendalong Road, Conjola	Ulladulla	Weekday before the start of the Christmas school holidays	The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	No travel
Kings Highway	Over 2.5m up to 3.5m	n/a	Braidwood	Batemans Bay	Weekday before the start of the Christmas school holidays	The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	1 pilot and contact police before travel. NSW Police contact details are available at: <a href="https://www.nhvr.gov.au/road-access/access-management/third-party-approvals">https://www.nhvr.gov.au/road-access/access-management/third-party-approvals</a>

## 2 Limited Access Locations

### 2.1 Limited Access Locations and Zones – NSW Urban Zone

- Notwithstanding the dimension limits set out in the Notice travel on or through a Limited Access Location is not permitted if the eligible vehicle exceeds one or more of the limits that applies to a Limited Access Location as set out in this section.
- An eligible vehicle must comply with any access condition that applies to a Limited Access Location as set out in this section.
- An eligible vehicle which exceeds one or more of the stated dimension limits must comply with the Location Restriction and Condition of Access for any of the following Limited Access Locations in the NSW Urban Zone.
- Where a dimension limit states Not Applicable (N/A) the dimension limit set out in the Notice is the applicable dimension.

#### 2.1.1 Limited Access Zone: Sydney and Inner Suburbs

For the purposes of this part the Sydney CBD Zone is the area bounded by and including George Street from Railway Square to Hay Street, Hay Street from George Street to Sussex Street, Sussex Street from Hay Street to Erskine Street, Erskine Street from Sussex Street to Kent Street, Kent Street from Erskine Street to as far north as Jamison Street, then a line drawn to Jamison Street and along Jamison Street to York Street, York Street from Jamison Street to Grosvenor Street, Grosvenor Street from York Street to George Street, George Street from Grosvenor Street to Alfred Street, Alfred Street from George Street to Circular Quay East, Circular Quay East from Alfred Street to Macquarie Street, Macquarie Street from Circular Quay East to Prince Albert Road, Prince Albert Road from Macquarie Street to College Street, College Street from Prince Albert Road to Wentworth Avenue, Wentworth Avenue from College Street to Elizabeth Street, Elizabeth Street from Wentworth Avenue to Hay Street, Hay Street from Elizabeth Street to Pitt Street, Pitt Street from Hay Street to George Street at Railway Square.



### 2.1.2 Limited Access Locations: Sydney CBD and Inner Suburbs

Location/road	Dimension limit (m)			Location restriction and condition of access
	Width	Height	Length	
Sydney CBD Zone*	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Boundary Street Darlinghurst railway underpass	3.5	4.0	n/a	Height limited railway underpass. No access permitted.
Bradfield Highway from the Southern Toll Plaza to Lavender Street	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Cross City Tunnel from McLachlan Avenue Rushcutters Bay to Harbour Street at Darling Harbour	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Cahill Expressway from the Southern Toll Plaza to the Eastern Distributor toll road	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Frederick Street Ashfield railway underpass	3.0	4.2	n/a	Height limited railway underpass. No access permitted if exceeding Limited Access Location dimension limit.
Johnston Street Annandale railway underpass	3.5	4.0	n/a	Height limited railway underpass. No access permitted if exceeding Limited Access Location dimension limit.
King Street Newtown between Lord Street and Carillon Avenue*	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
M5 East Motorway (tunnel) between King Georges Road interchange Beverly Hills and General Holmes Drive Mascot	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Raw Square Strathfield railway underpass	3.5	3.9	n/a	Height limited railway underpass. No access permitted if exceeding Limited Access Location dimension limit.
(Old) Ryde Bridge from Concord Road to Church Street	N/A	4.5	n/a	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Sydney Harbour Bridge from the Southern Toll Plaza to Lavender Street North Sydney*	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

Location/road	Dimension limit (m)			Location restriction and condition of access
	Width	Height	Length	
Sydney Harbour Tunnel from Warringah Freeway to the Cahill Expressway	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Eastern Distributor from the Cahill Expressway to Baker Street, Kensington	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

\* Rule 300-3 of the NSW Road Rules also regulates the driving of long vehicles in the Sydney CBD and adjacent areas. This Notice does not provide exemption from its requirements. See [www.legislation.nsw.gov.au](http://www.legislation.nsw.gov.au) for NSW Road Rules.

### 2.1.3 Limited Access Location: Sydney North

Location/road	Dimension limit (m)			Location restriction and condition of access
	Width	Height	Length	
Lane Cove Tunnel from the Pacific Highway to Lane Cove River at Lane Cove North	2.5	4.3	25.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
M2 Motorway and tunnel from the toll plaza at Macquarie Park to Beecroft Road	2.5	4.3	25.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Berowra Waters Road at Berowra Ferry	2.5	4.3	12.5	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Boundary Street Roseville railway underpass	3.5	4.1	N/A	Height limited railway underpass.
Galston Road at Galston Gorge between Montview Parade Hornsby Heights and Calderwood Road Galston	2.5	4.3	7.5	No access permitted if exceeding Limited Access Location dimension limit.
McCarrs Creek Road from Church Point to Terrey Hills	2.5	4.3	12.5	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Strathallen Avenue at the suspension bridge (BN172), Northbridge	3.0	4.3	N/A	Mass Restricted Bridge. Class 1 permit if exceeding a Limited Access Location dimension.
Wisemans Ferry Road from Berecroy Road Mangrove Mountain to the Hawkesbury River Wisemans Ferry	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

Location/road	Dimension limit (m)			Location restriction and condition of access
	Width	Height	Length	
Barrenjoey Road at Bilgola Bends	3.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
NorthConnex (tunnel) from M1 Pacific Motorway Wahroonga and M2 Motorway West Pennant Hills	2.5	4.6	25	No access permitted if exceeding Limited Access Location dimension limit.

#### 2.1.4 Limited Access Location: Sydney South

Location/road	Dimension Limit (m)			Location restriction and condition of access
	Width	Height	Length	
Heathcote Road between New Illawarra Road Lucas Heights and the Princes Highway Heathcote	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Lady Wakehurst Drive, Sir Bertram Stevens Drive, Audley Road and Farnell Avenue between Bald Hill Lookout and the Princes Highway	2.5	4.3	14.5	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
McKell Avenue from Waterfall to the Royal National Park	2.5	4.3	14.5	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Princes Highway on (old) Tom Ugly's Bridge (northbound)	3.5	4.3	19.0	Mass Restricted Bridge. Class 1 permit if exceeding a Limited Access Location dimension.
Seven Ways Rockdale between the Princes Highway and Watkin Street	3.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Wollongong Road Arncliffe – railway underpass	3.5	3.5	19.0	Narrow height limited railway underpass. No access permitted if exceeding Limited Access Location dimension limit.

### 2.1.5 Limited Access Location: Sydney West

For the purposes of this part the Parramatta CBD Zone is defined as the area bounded by and including Phillip Street from the intersection with Marsden Road to the intersection with Charles Street, Charles Street to the intersection with Macquarie Street, Macquarie Street to the intersection with Smith Street, Smith Street to the intersection with Darcy Street, Darcy Street to the intersection with Church Street, Church Street Mall to the intersection with Macquarie Street, Macquarie Street to the intersection with Marsden Street and Marsden Street to the intersection with Phillip Street. The zone also includes Fitzwilliam Street from the intersection with Wentworth Street to the intersection with Church Street and Argyle Street from the intersection with Church Street to the intersection with Fitzwilliam Street.



Location/road	Dimension limit (m)			Location restriction and condition of access
	Width	Height	Length	
Parramatta CBD Zone	2.5	4.3	19	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Gasworks Bridge Parramatta	2.5	N/A	N/A	Load limited bridge 30t gross. No access permitted if exceeding Limited Access Location dimension limit.
Macquarie Street underpass Windsor	3.5	4.3	N/A	Railway underpass height limit 4.3m. No access permitted if exceeding Limited Access Location dimension limit.
Victoria Bridge over Nepean River at Penrith	2.5	4.3	19	No access permitted if exceeding Limited Access Location dimension limit.

**2.1.6 Limited Access Location: Wollongong**

For the purposes of this part the **Wollongong CBD Zone** is the area bounded by and including Smith Street from the intersection with Flinders Street to the intersection with Corrimal Street, the western side of Corrimal Street to the intersection with Bank Street, Bank Street to the intersection with Church Street, Church Street to the intersection with Ellen Street, and Ellen Street to the intersection with Auburn Street, then a straight line drawn from the intersection of Ellen Street and Auburn Street to the intersection of Rowland Avenue and Gladstone Avenue, Gladstone Avenue to the intersection with Crown Street, Crown Street and Denison Street to the intersection with Victoria Street, Victoria Street to the intersection with Keira Street, and Keira Street to the intersection with Smith Street.



Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Wollongong CBD Zone	2.5	4.3	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Broughton Pass (RR610) from Appin Road to Wilton Road		4.3		
Bulli Pass (HW1) from Mount Ousley Road to Lawrence Hargrave Drive		N/A		
Lawrence Hargrave Drive (MR185) from the Princes Highway at the foot of Bulli Pass via Thirroul, Austinmer, Clifton and Bald Hill to the Princes Highway south of Helensburgh		4.3		

### 2.1.7 Limited Access Locations: Newcastle and Central Coast

Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
George Booth Drive from the F3 Sydney Newcastle Freeway west to the Tasman Mine entrance	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Henry Parry Drive Gosford between York Street and Etna Street	2.5	4.3		
Old Pacific Highway from the Hawkesbury River to Kariong	3.0	N/A		
Woy Woy Bay Road from Woy Woy to Kariong	2.5	N/A		

## 2.2 Limited Access Locations and Zones – NSW Regional Zone

- This section provides information on Regional Roads that are identified as a Limited Access Location. Information is also available by viewing the NSW OSOM Map.
- Notwithstanding the dimension limits set out in the Notice, travel on or through a Limited Access Location is not permitted if the eligible vehicle exceeds one or more of the dimension limits which applies to a Limited Access Location as set out in this Section and also on the OSOM Map.
- An eligible vehicle must comply with any access condition that applies to a Limited Access Location as set out in this Section.
- An eligible vehicle which exceeds one or more of the stated dimension limits must comply with the Location Restriction and Condition of Access for any of the following Limited Access Locations in the NSW Regional Zone.
- Where a dimension limit states Not Applicable (N/A) the dimension limit set out in the Notice is the applicable dimension.

### 2.2.1 Limited Access Locations: Northern Ranges and North Coast NSW

Location/ Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Bruxner Highway between Tenterfield and Pacific Highway	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Coramba Road between Dorrigo and Coramba	2.5	N/A	19.0	
Waterfall Way between Church Street Bellingen and Maynards Plains Road Dorrigo	2.5	N/A	19.0	
Ebor to Grafton Road between Tyringham and Nymboida	2.5	N/A	19.0	
Gwydir Highway from Camp Creek (Peter Elks Bridge) west to Glen Elgin Prison Farm entrance	3.0	N/A	25.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit and contact Police prior to travel.
Oxley Highway from Kangaroo Flat Road to Ralfes Creek Bridge	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Tomewin Road from Murwillumbah to the Queensland border	2.5	N/A	19.0	
New England Highway southbound at Moonbi Range (defined from South of Bendemeer to Moonbi)	N/A	N/A	N/A	Police escort also required when width exceeds 3.5 metres. NSW Police contact details are <a href="#">available here</a> .
Summerland Way – Qld Border to Wiangaree	2.5	N/A	19	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

## 2.2.2 Limited Access Locations: Northern Ranges and North West NSW

Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Crookwell to Trunkey Creek (Binda Road) between Abercrombie Caves and Tuena	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Abercrombie Road (Taralga to Goulburn Road) for 5 km north and south of Abercrombie Bridge		N/A	19.0	
Bells Line of Road from Hermitage Road at Bellbird Hill to the Great Western Highway at Mount Victoria. (Darling Causeway is part of this road)	2.9	N/A	19.0	
The Chifley Road from Bells Line of Road at Bell to the Great Western Highway at Bowenfels	2.5	N/A	19.0	
Hawkesbury Road between the lookout near Roberts Parade and north to the Blue Mountains City Council boundary		N/A	12.5	
Jenolan Caves Road from 10km north of Jenolan Caves to 10km west of Jenolan Caves		4.3	12.5	
Putty Road from East Kurrajong Road to Milbrodale School		4.3	19.0	
Kamilaroi Highway at Gunnedah town centre between Warrabungle Street and Abbott Street		N/A	19.0	
Paytens Bridge over Lachlan River near Bandon	4.3	19.0	No oversize access permitted.	

### 2.2.3 Limited Access Location: Hunter and Central Coast

Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Edderton Road between Denman Road and Golden Highway	2.5	N/A	25.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

### 2.2.4 Limited Access Location: South Western and Southern NSW

Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Burley Griffin Way between Binalong and Stockinbingal	3.5	N/A	N/A	Contact Police before travel. NSW Police contact details are <a href="#">available here</a> . An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Grahamstown Road between Tumblong and Mt Horeb				Contact Police before travel. NSW Police contact details are <a href="#">available here</a> . An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Snowy Mountains Highway from Tumut Plains Road Tumut to Kosciusko Road Cooma	2.5		19.0	Contact Police for escort before travel. A <a href="#">Transport Management Plan (TMP)</a> must be submitted where a Police escort is required. NSW Police contact details are <a href="#">available here</a> . An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
'Old' Echuca Bridge on Meninya Street between Moama and Echuca.			N/A	Mass restricted bridge. An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel. Time restrictions apply Monday to Saturday.

### 2.2.5 Limited Access Location: Southern Ranges and South Coast NSW

Location / Road	Dimension Limit (metres)			Location Restriction and Condition of Access
	Width	Height	Length	
Illawarra Highway from the Broughton Avenue roundabout near Tullimbar westward to Jamberoo Mountain Road near Robertson.	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Moss Vale Road between Barfield Road Cambewarra to Myra Vale Rd Fitzroy Falls.	2.5	N/A	19.0	Contact Police before travel if wider than 2.5m. Police escort required if wider than 3.0m. A <a href="#">Transport Management Plan (TMP)</a> must be submitted where a Police escort is required. NSW Police contact details are <a href="#">available here</a> .  An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Kings Highway from Wallace Street Braidwood to Princes Highway Batemans Bay.	2.5	N/A	19.0	Contact Police before travel. NSW Police contact details are <a href="#">available here</a> .  An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Snowy Mountains Highway from Buckleys Road Bemboka to Monterey Road.	2.5	N/A	19.0	Contact Police before travel. NSW Police contact details are <a href="#">available here</a> .  An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Araluen Road from Majors Creek to Kiora.	2.5	N/A	19.0	An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Princes Highway between Jaspers Brush and the Victorian border.	4.0	N/A	26.0	If wider than 4.0m contact Police before travel. NSW Police contact details are <a href="#">available here</a> .  An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.
Princes Highway at Narooma bridge between Dalmeny Drive and Riverside Drive.	3.0	4.5	N/A	If wider than 3.0m or higher than 4.4m contact Police before travel. NSW Police contact details are <a href="#">available here</a> .  An eligible vehicle that exceeds a dimension limit must obtain a Class 1 permit before travel.

### 3 Bridge mass restrictions

#### 3.1 NSW Urban Zone – Bridge mass restrictions

An eligible vehicle must not operate on the bridges set out in this Section unless the total mass of the vehicle does not exceed the lesser of:

- a) The prescribed mass limits in the HVNL; or
- b) a sign-posted mass limit that applies to a bridge.

Bridge Number and Name	Description
BN226 Sydney Harbour Bridge	over Sydney Harbour on MR632
BN333 Victoria Bridge	over Nepean River on Great Western Highway (HW5) at Penrith.
BN50 The Spit Bridge	over Middle Harbour, south of Seaforth
BN51	bridge over Manly Road (MR164) at Balgowlah
BR135 Roseville Bridge on Warringah Road	over Middle Harbour, Roseville Chase
BN415 Windsor Bridge	over Hawkesbury River on Bridge Street (MR182) Windsor
BR390 Bridge on Galston Road	over Pearces (Tunks) Creek, Galston
BR1758	Maud Street, over main northern railway (1.08 km west of Mayfield West)
BR8495	Manns Road, Narara, over main northern railway (4.5km west of Gosford)
BN98 Bentley's Bridge	Park Creek (Channel), Rushcutters Bay (urban)
BN143	bridge on MR 393, over Flat Rock Creek No. 2, Royal National Park
BN291	northbound bridge, over Prospect Creek, at Lansdowne
BN292	southbound bridge over Prospect Creek, at Lansdowne
BN341 Peats Ferry Bridge	over Hawkesbury River, Peats Ferry
BN360 Lennox Bridge	Church Street, over Parramatta River, at Parramatta
BN388	bridge on Showground Road, over Cattai Creek, at Castle Hill
BN592 Gasworks Bridge	Macarthur Street, over Parramatta River, at Parramatta

## 3.2 NSW Regional Zone – Bridge Mass Restrictions

An eligible vehicle must not operate on the bridges set out in this Section unless the total mass of the vehicle does not exceed the lesser of:

- a) The prescribed mass limits in the HVNL; or
- b) a sign-posted mass limit that applies to a bridge.

### 3.2.1 Hunter Region

Bridge Number and Name	Description
BN413 St Albans Bridge	over Macdonald River, at St. Albans
BN1472 Coorei Bridge	over Williams River, Stroud Hill Road Dungog (1.18 km north of Dungog)
BN1477 Monkerai Bridge	over Karuah River on local road
BN1481 Morpeth Bridge	over Hunter River, Phoenix Park Road Morpeth (0.03 km north of Morpeth)
BN1484 Irrawang Bridge	Hunter River (2.69 km north of Raymond Terrace)
BN1489	main northern rail line (17.24 km west of Raymond Terrace)
BN1527 Beckers Bridge	over Webbers Creek, Gresford Road Glendon Brook (20.14 km north of Singleton)
BN1535 Vacy Bridge	over Paterson River, Tocal Road Vacy.
BN1557 Kayuga Bridge	over Hunter River, Kayuga Road Muswellbrook (2.27 km north of Muswellbrook)
BN1567	bridge over Goulburn River (0.8 km south of Sandy Hollow)
BN1625	bridge over South Maitland-Cessnock rail line near Government Road on Northcote Street (3.07 km west of Kurri)
BN1661 Elderslie Bridge	over Hunter River, Elderslie Road Elderslie (5.55 km north of Branxton)
BN1683 Dunmore Bridge	over Paterson River, Paterson Road Woodville.
BN1727	bridge over Macdonald River (111.4 km north of Windsor)
BN1737 Bulga Bridge	over Wollombi Brook, Putty Road Bulga (152.4 km north of Windsor)
BN1752 O'Johnston Bridge	over Williams River, at Clarencetown
BN1776	bridge over Paterson River, Dourebang, Paterson
BN1779 Yarrawa Bridge	over Goulburn River, at Yarrawa (Denman)
BN1780 Luskintyre Bridge	over Hunter River, Luskintyre Road, Luskintyre
BN1784 Glennies Creek Bridge	over Glennies Creek, Middle Falbrook Road Middle Falbrook
BN2082 Barrington Bridge	over Barrington River, Thunderbolts Way Barrington
BN1461 Gostwyck Bridge	over Paterson River (23.75 km north of Maitland)

### 3.2.2 Northern Region

Bridge Number and Name	Description
BN2090	bridge on local road, Bellinger River, North Arm at Raleigh
BN2266 Tabulam Bridge	over Clarence River, Bruxner Highway Tabulam (55.49 km west of Casino)
BN2295 Pollack Bridge	RR74, Nymboida River, Nymboida
BN2462 Glebe Bridge	over Richmond River, Dawson Street Coraki (0.60 km north of Coraki)
BN2531	bridge over Sportsmans Creek, Bridge Street Lawrence (0.72 km south of Lawrence)
BN2537 McFarlane Bridge	over Clarence River, Lawrence Road Maclean (0.98 km south of Maclean)
BN2581 Korn's Bridge	over Rous River, Numinbah Road Crystal Creek
BN2594 Colemans Bridge	over Leycester Creek, Union Street Lismore (0.02 km west of Lismore)
BN2676 Bawdens Bridge	over Orara River, Old Glen Innes Road, Chambigne
BN2680 Briner Bridge	over Upper Coldstream River (7.7 km east of Ulmarra)
BN2948	bridge on SR63, over Halls Creek (0.75 km north of Bingara)
BN2949	bridge on SR63, over Gwydir River, (0.87 km north of Bingara)
BN3140 Fladbury Bridge	RR7706, Severn River (29.83 km north of Glen Innes)
BN3142 Wyalabah Bridge	Old Grafton Road, over Mann River, near Newton Boyd
BN3655 Namoi River Bridge	on SR63, over Namoi River (0.20 km north of Manilla)
BN3656	bridge on SR63, Manilla River, near Upper Manilla (12.19 km north of Manilla)
BN3665 Manilla River Bridge	on SR63, over Manilla River (0.80 km north of Barraba)
BN3670	bridge on SR63, Oaky Creek (25.83 km north of Barraba)
BN3763	bridge over Gwydir River (0.46 km north of Bundarra)
BN4050 Cohens Bridge	on local road, Namoi River, Gunnedah
BN1832 Dennis Bridge	over Hastings River (39.83 km south of Kempsey)

### 3.2.3 Western Region

Bridge Number and Name	Description
BN971	bridge on Hawkesbury Road over western rail line and Great Western Highway at Springwood
BN1015 Abercrombie Bridge	over Abercrombie River (67 km north of Crookwell)
BR1141	bridge on Bells Line of Road, western rail line, Bell
BN1185 Wallaby Rocks Bridge	over Turon River, Hill End Road west of Sofala
BN1208 Queen Charlotte Bridge	over Vale Creek on Bridge Street at Perthville
BN1278	bridge over Duckmaloi River (11.17 km west of MR253)
BN1302 McKane's Bridge	over Cox's River, west of Bowenfels
BN1304 Beryl Bridge	over Wialdra Creek, near Gulgong
BN3970 Iron Bridge	over Namoi River, Boggabri to Manilla Road, north of Boggabri.
BN4148 L.H. Ford Bridge	over Macquarie River, at Dubbo
BN4285 Iron Bridge	over Lachlan River, Cowra Road Forbes.
BN4469 Holman Bridge	over Lachlan River, at Gooloogong on Grenfell – Canowindra Road
BN4523	bridge over Macquarie River (16.75 km northeast of Trangie) at Gin
BN4645 Rawsonville Bridge	over Macquarie River, North Minore Road, Minore
BN4658 Waroo Bridge	over Lachlan River, Hodges Road, west of Warroo
BN4659 Paytens Bridge	over Lachlan River, at Colletts Crossing
BN4660 Scabbing Flat Bridge	over Macquarie River, Ponto Road Geurie.

### 3.2.4 Southern Region

Bridge Number and Name	Description
BN875 Hampden Bridge	over Kangaroo River, Moss Vale – Nowra Road, Kangaroo Valley
BN965 Victoria Bridge	timber bridge over Stonequarry Creek, at Picton
BN6129 Crankies Plain Bridge	over Coolumbooka River, Cathcart Road Bombala
BN6168 Bridge	bridge over Wallaga Lake, Bermagui – Tathra Road Wallaga Lake
BN6235 Buckley's Crossing	over the Snowy River at Dalgety
BN6237 New Buildings Bridge	over Towamba River, New Buildings Road New Buildings
BN6506 Charleyong Bridge	over Mongarlowe River, Nerriga Road Charleyong
BN6675 Lansdowne Bridge	over Mulwaree Ponds, Bungonia Road Goulburn
BN6677 Mummel Bridge	over Wollondilly Creek at Mummel
BN6678 Rossis Crossing	over Wollondilly River, at Goulburn
BN713	bridge over Shoalhaven River, southbound at Nowra
BN935	bridge over Tongarra Creek at Shellharbour
BN3318 Barmah Bridge	over the Murray River, near Barmah (Vic)
BN5950 Batemans Bay Bridge	over Clyde River at Batemans Bay
BN5974	bridge over Corunna Lake, Corunna

### 3.2.5 South Western Region

Bridge Number and Name	Description
BN3184 Echuca Bridge	over Murray River, Cobb Highway Echuca – Moama
BN3215 Swan Hill Bridge	over Murray River, McCallum Street at Swan Hill
BN3220 Jacksons Bridge	over Lachlan River, Mossgiel Road Hillston
BN3235 Gee Gee Approach Bridge	over Wakool River North, Swan Hill – Barham Road Wetuppa
BN3237 Gee Gee Bridge	over Wakool River North, Swan Hill – Barham Road Wetuppa
BN3244 Tooleybuc Bridge	over Murray River, Kyalite Road at Tooleybuc
BN3248 Carrathool Bridge	over Murrumbidgee River, south of Carrathool
BN3256 Koondrook Bridge	over Murray River, Thule Street at Barham.

Bridge Number and Name	Description
BN3315 Coonamit Bridge	over Wakool River, Moulamein Road, Swan Hill
BN3375 Gonn Crossing	over Murray River, Murrabit Road at Gonn Crossing
BN3377 Nyah Bridge	over Murray River, Nyah Road at Nyah
BN5184	Murray River approach, Bridge No. 3 at Robinvale
BN5575 Bethanga Bridge	over Murray River, Riverina Highway at Hume Weir
BN5689	bridge, Tumbarumba Creek, Tumbarumba
BN5695 John Foord Bridge	steel truss bridge, Murray River at Corowa (MR86)
BN5792 Tintaldra Bridge	extended bridge, Murray River at Tintaldra
BN5818	bridge over Little Billabong Creek on Little Billabong Road (0.1 km east of the Hume Highway near Little Billabong)
BN5819 Mulwala Bridge	over Murray River, Yarrawonga Road at Mulwala
BN5909 Mundowry Bridge	over Murrumbidgee River on The Rock-Coolamon Road, 8 km north of Collingullie
BN5943 Island Bridge	over Murray River near Albury
BN5944 Goldsworthy Bridge	over Murray River, Indi Road at Biggara
BN5947 Towong Bridge	over Murray River, Towong Road at Towong
BN6633 Wee Jasper Bridge	over Goodradigbee River, Tumut – Yass Road, Wee Jasper
BN6637 Prince Alfred Bridge	over Murrumbidgee River at Gundagai
BN8317	bridge over Khancoban Creek, near Khancoban

## PART B – New South Wales Schedule of the Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice

### About the Notice

The Multi-State Class 1 Load Carrying Vehicles Dimension Exemption Notice allows eligible Class 1 load carrying vehicles in NSW to operate up to 5.0m wide, 5.0m high, 30.0m long and 7.5m rear overhang on approved (state owned) routes in NSW, and in compliance with the conditions of the Notice and this Operator's Guide.

**Please note the following conditions are in addition to all conditions as set down in Part A of this Operator's Guide.**

### Further information

This section of this Operator's Guide is advisory information for operators.

Telematics conditions will be added to the Notice in 2021. An eligible vehicle may be required to participate in a telematics application from 1 July 2021. Further consultation will be undertaken with industry prior to the implementation of a telematics condition.

It is strongly recommended that the operator of an eligible vehicle operating under this Notice should:

1. Subscribe to the Transport for NSW Oversize and overmass vehicles mailing list for email alerts for travel and road restrictions for oversize and/or overmass heavy vehicles.
2. Check NSW Live Traffic at <https://www.service.nsw.gov.au/transaction/live-traffic-nsw>.

### Approved routes

An eligible vehicle:

- a) may operate on 'NSW Oversize Overmass Load Carrying Vehicles Network Approved Routes' specified on the map titled 'NSW Oversize Overmass Load Carrying Vehicles Network' published by Transport for NSW (TfNSW); and
- b) that is higher than 4.3 metres may only operate on a route that is also approved for 4.6 metres high vehicles as displayed on the 'NSW Oversize Overmass Load Carrying Vehicles Network' map published by TfNSW; and
- c) that is higher than 4.6 metres may only operate on a route that is approved for 4.6m high vehicles as displayed on the 'NSW Oversize Overmass Load Carrying Vehicles Network' map published by TfNSW contingent to the operator satisfying Section 11 of Schedule 8 of the MDL National Regulation.

**Note:** The NSW Oversize Overmass Load Carrying Vehicles Network map can be accessed at <https://nswroads.work/osommap>

## 4 Travel conditions

All travel conditions noted in Part A of the Operators Guide must be adhered to with the addition of:

### 4.1 Pilot and escort requirements

1. An eligible vehicle operating in the daytime that is:
  - a) wider than 3.5m or longer than 26.0m requires at least one pilot vehicle; and
  - b) wider than 4.6 metres requires at least two pilot vehicles.
2. An eligible vehicle operating at night that is:
  - a) wider than 2.5m or longer than 22.0m requires one pilot vehicle; and
  - b) wider than 3.5m or longer than 26.0m requires two pilot vehicles.

## 4.2 Daytime travel – Sydney Metropolitan Zone

An eligible vehicle that is wider than 3.5m or longer than 26m must not travel on any State Road within the Sydney Metropolitan Zone between Monday and Friday (except on state-wide public holidays) between sunrise and sunset.

An eligible vehicle that is wider than 3.5m or longer than 26m must not travel on any State Road within the Sydney Metropolitan Zone between 8:30am and sunset on a weekend or a public holiday.

## 4.3 Weekday (excluding state-wide public holidays) daytime travel restrictions

Road or Area	Width	Length	Start Point	Finish Point	Conditions
Great Western Highway	Over 3.5m upto 4.5m	Over 12.5m (vehicle) Over 26.0m (combination)	Nepean River, Emu Plains	Katoomba	No travel from 6:00am to 9:00am and from 4:00pm to 7:00pm. Two pilot vehicles must accompany travel
	Over 4.5m		Nepean River, Emu Plains	Katoomba	No travel between sunrise and sunset
M1 Pacific Motorway	Over 3.5m	Over 12.5m (vehicle) Over 26.0m (combination)	Hawkesbury River	Kariong interchange with the Central Coast Highway	No travel between sunrise and 9:00am and between 4:00pm and sunset
Sturt Highway	Over 3.5m		Murray River	George Chaffey Bridge, Baronga	No travel between 8am to 10:00am and between 3:00pm and 6:00pm
Sturt Highway, Wagga Wagga	Over 4.6m		Kapooka road San Isidore	Smith St, Forest Hill	No travel between 7:00am to 9:30am and between 3:30pm and 6:30pm
Olympic Highway, Wagga Wagga	Over 4.6m		Coolamon Rd, Cartwrights Hill	Old Station Rd, Uranquinty	No travel between 7:00am to 9:30am and between 3:30pm and 6:30pm
Silver City Highway	Over 3.5m		Darling River	Wentworth Lift Span Bridge, Wentworth	No travel between 8am to 10:00am and between 3:00pm and 6:00pm
Hume Highway, Albury	4.6m		NSW/Vic Border	Thurgoona Dr, Thurgoona	No travel between 7:00am to 9:30am and between 3:30pm and 6:00pm
Riverina Highway, Albury	4.6m		Pemberton St, West Albury	Elizabeth Mitchell Rd, East of Albury	No travel between 7:00am to 9:30am and between 3:30pm and 6:30pm

#### 4.4 Weekend and state-wide public holiday travel restrictions for Class 1 load carrying vehicles

Road or Area	Width	Length	Start Point	Finish Point	Conditions
Hume Motorway	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	M5 South West Motorway interchange at Casula	Sutton Forest	No travel after 8:30am
Pacific Highway	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Hexham	Sydney	
New England Highway	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Hexham	Weakleys Drive	
Princes Motorway	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Waterfall	Yallah	
Princes Highway	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Yallah	Gerringong	No travel after 8:00am
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Gerringong	Berry	No travel
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Berry	Bendalong Road turnoff, Conjola	No travel after 8:00am
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Bendalong Road turnoff, Conjola	Ulladulla	No travel
	Over 3.5m	Over 12.5m (vehicle)	Ulladulla	Narooma	No travel after 8:00am

Road or Area	Width	Length	Start Point	Finish Point	Conditions
		Over 25.0m (combination)			
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Narooma	Cobargo	No travel
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Cobargo	Pambula	No travel after 8:00am
	Over 3.5m	Over 12.5m (vehicle) Over 25.0m (combination)	Pambula	Eden	No travel

#### 4.5 Day time restrictions for Class 1 load carrying vehicles during the Christmas holiday period

The following vehicles are exempt:

- A vehicle driving across the road.
- A vehicle carrying agricultural equipment used to conduct an agricultural task

Road or Area	Width	Length	Start Point	Finish Point	Start Date	End Date	Conditions
All State Roads east of and including the Newell Highway	Over 3.5m	Over 25.0m	All State Roads		Sunrise 23 December	Sunset 3 January	No travel
Kidman Way	Over 3.5m	Over 25.0m	North of Jerilderie	Goolgowi	Sunrise 23 December	Sunset 3 January	
Burley Griffin Way	Over 3.5m	Over 25.0m	Ardlethan	Griffith	Sunrise 23 December	Sunset 3 January	
Lachlan Valley Way	Over 3.5m	Over 25.0m	Lake Cargelligo	Booligal	Sunrise 23 December	Sunset 3 January	

Road or Area	Width	Length	Start Point	Finish Point	Start Date	End Date	Conditions
Pacific Highway/M1 Pacific Motorway	Over 3.5m up to 4.2m	N/A	Queensland border	Richardson Road intersection, Raymond Terrace	Weekday before the start of the Christmas school holidays	Sunday at the end of the fourth week of the Christmas school holidays	
	Over 4.2m					The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	
Princes Highway	Over 3.5m	N/A	Narooma	Cobargo		The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	
			Pambula	Eden			
			Bendalong Road, Conjola	Ulladulla			
Kings Highway	Over 3.5m	N/A	Braidwood	Batemans Bay		The last Sunday of the NSW Christmas school holidays as set by the NSW Department of Education	

## 4.6 General

Eligible vehicles operators must notify the affected motorway operators of their intended travel at least 5 working days before travel:

- For operation on the M5 West Motorway or M7 Motorway – any vehicles equal to or greater than 4.3m wide.
- For operation on the M2 Motorway - any vehicles exceeding 3.5m wide.

Contact details for the M2, M5 and M7 Motorway operators are [found here](#).

## PART C – New South Wales Schedule of the Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice

### About the Notice

The Multi-State Class 1 Load Carrying Vehicles Mass Exemption Notice allows eligible Class 1 load carrying vehicles in NSW to operate up to 115.0 tonnes for rows of 8 tyres low loaders and up to 77.5 tonnes for rows of 4 tyres low loader combinations.

### Approved routes

An eligible vehicle may operate on 'NSW Oversize Overmass Load Carrying Vehicles Network Approved Routes' specified on the map titled 'NSW Oversize Overmass Load Carrying Vehicles Network' published by New South Wales Transport for NSW (TfNSW)

**Note:** The NSW Oversize Overmass Load Carrying Vehicles Network map can be accessed at <https://nswroads.work/osommap>

### General conditions

1. An eligible vehicle must only travel on a route specified in section 2 of Part C of this Operator's Guide for that category of vehicle and in accordance with any condition, including any restriction on the hours or days of operation, specified for that route if operating under Multi-State LCV Dimension Notice.
2. An eligible vehicle exceeding 93.5 tonnes must not cross any bridge:
  - a) while any other vehicle is on the bridge; and
  - b) except along the centreline of the bridge; and
  - c) unless the vehicle is kept to a speed of less than 10 km/h with no sudden braking or acceleration.
3. Where a grid is installed on any road, the vehicle where possible shall pass through the gates provided and not over the grid.

### Key contacts

Key third party contacts and their contact details are available here.

#### Further Information

Please refer to the 'New South Class 1 Load Carrying Vehicle Exemption Notice' which can be found at <https://www.nhvr.gov.au/law-policies/notices-and-permit-based-schemes/state-hvnl-notices>.

## PART D - NSW Bushfire Emergency Travel

Part D allows for exemption to travel times and travel in low visibility for emergency deployment of equipment to bushfires. Travel is only on approved roads and when must comply with any conditions displayed on the NSW Bushfire Emergency Map. A link to this Map will be provided in the Digital Approval issued by NSW Rural Fire Service.

If travel is required over the following Rail Level Crossings, you must contact the Rail Infrastructure Manager as per details provided in the NSW Bushfire Map prior to travel over the crossing:

- Rail Level Crossing ID 204 on Burley Griffin Way at Stockinbingal
- Rail Level Crossing ID 269 on Golden Hwy at Dubbo
- Rail Level Crossing ID 600 on Olympic Wat north of Bethungra
- Rail Level Crossing ID 601 on Olympic Way at Bethungra
- Rail Level Crossing ID 603 on Olympic Way at Illabo
- Rail Level Crossing ID 607 on Olympic Way at Junee
- Rail Level Crossing ID 629 on Olympic Way at Culcairn
- Rail Level Crossing ID 1528 on Olympic Way at Cootamundra
- Rail Level Crossing ID 1029 on Kidman Way at Mount Hope / Matakana

When travelling at the direction of and only when carrying the digital approval authorisation email, issued by NSW Rural Fire Service for travel in Bushfire Emergency situations, the OSOM vehicle and driver are exempt from all travel time restrictions in Part A and Part B of this Guide.

When travelling under Part D of this Guide, the vehicle is exempt from Clause 8 No Travel if low visibility, Schedule 8 of the Heavy Vehicle (Mass, Dimension & Loading) National Regulation.

### For more information:

Visit: [www.nhvr.gov.au](http://www.nhvr.gov.au)

Email: [info@nhvr.gov.au](mailto:info@nhvr.gov.au)

Phone: 13 NHVR (13 64 87) \*

\* Standard 13 XX XX call charges apply. Please check with your phone provider.  
© Copyright National Heavy Vehicle Regulator 2023, [creativecommons.org/licenses/by-sa/3.0/au](https://creativecommons.org/licenses/by-sa/3.0/au)  
Disclaimer: This information is only a guide and should not be relied upon as legal advice.


## Appendix D

### OSOM Route Assessment Port Botany to Site





### OSOM Truck Specifications

10x8 Platform Trailer 946 Beamset Short



Overall Length 56.633m  
 Track width 4.200m  
 Beamset width 5.740m  
 Load Height 4.500m  
 Axle spacing 1.800m

OSOM Configuration calibrated against similar OSOM configurations and is based on information available at the time of assessment



10 Points of interest tested  
[Online Map Link](#)

Route Assessment - Sydney  
 Gregadoo Solar Farm - Modification 4  
 Overall Route Summary and OSOM Details

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: NTS





- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path


**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 All kerbs are mountable.

**Location:**  
 Port Botany, NSW 2036  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:1000



- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path


**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 All kerbs are mountable.

**Location:**  
 Port Botany/Matraville, NSW 2036  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500



- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**

Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 Only median island verges are mountable.  
 Provide hardstand and mountable kerbing as required at yellow highlighted areas.


**Location:**  
 Matraville, NSW 2036  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:750





Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 All median kerbs are mountable.

**Location:**  
 Daceyville, NSW 2032  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:750



- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 Ensure road shoulders are clear.

**Location:**  
 Gumly Gumly NSW 2652  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500



- Light/power pole
- Traffic sign
- Fence pole
- Area to be made trafficable

- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**

- Escorts to control traffic as required.
- Provide hardstand as required at yellow highlighted area.
- Reinstate reflective guide posts if damaged.
- Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**

Lake Albert NSW 2650  
[Online Map Link](#)



Route Assessment - Sydney  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500





Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic as required.

Provide hardstand as required at yellow highlighted area.

Reinstate reflective guide posts if damaged.

Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**

Lake Albert NSW 2650

[Online Map Link](#)

**Route Assessment - Sydney**

Gregadoo Solar Farm - Modification 4



Swept Path Assessment



DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500





 Traffic sign  
 Fence pole

Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted area, subject to intersection design.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.



**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



Route Assessment - Sydney  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:750



 Fence pole  
 Area to be made trafficable

Temporary hardstand to be provided

Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'

Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted area, subject to intersection design.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



Route Assessment - Sydney  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500





- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted areas, subject to intersection design.

**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



**Route Assessment - Sydney**  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 21/06/2024  
 DWG NO: 388 RA01B Sydney  
 SCALE at A3: 1:500


## Appendix E

### OSOM Route Assessment Port of Melbourne to Site




### OSOM Truck Specifications

10x8 Platform Trailer 946 Beamset Short



Overall Length 56.633m  
Track width 4.200m  
Beamset width 5.740m  
Load Height 4.500m  
Axle spacing 1.800m

OSOM Configuration calibrated against similar OSOM configurations and is based on information available at the time of assessment



1, 2, 3, 4, 5, 6, 7

Port of Melbourne

11, 12

10

Project Site

13, 14, 15


8, 9

15 Points of interest tested  
[Online Map Link](#)

Route Assessment - Melbourne  
Gregador Solar Farm - Modification 4  
Overall Route Summary and OSOM Details

DRAWN: RK  
DATE: 24/06/2024  
DWG NO: 388 RA02B Melbourne  
SCALE at A3: NTS





- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Footscray Road availability subject to demobilisation of roadworks occupation.

**Location:**  
 West Melbourne VIC 3003  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:1000





- Light/power pole
- △ Traffic sign
- Traffic signal

Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.

**Location:**  
 Footscray VIC 3011  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:1500





- Light/power pole
- △ Traffic sign
- Traffic signal
- ☁ Traffic separators

- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**


Escorts to control traffic as required and facilitate use of opposing lane on Somerville Road.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 Temporary relocate flexible traffic separators and sockets in yellow highlighted area.

**Location:**  
 Footscray VIC 3011  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:750



- ◇ Metal pole
- Light/power pole
- △ Traffic sign
- Traffic signal

- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 Ensure parking spaces on Somerville Road on approach to intersection are vacant.

**Location:**  
 Kingsville VIC 3012  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:1000





- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 All kerbs are mountable.


**Location:**  
 Sunshine West VIC 3012  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment


DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500





06a

Swept path continues on 6b



06b

Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic and facilitate use of opposing lanes.  
Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

Four traffic signs in swept path to be temporarily relocated.

Central median island is mountable.

**Location:**

Laverton North VIC 3012

[Online Map Link](#)

**Route Assessment - Melbourne**


Gregador Solar Farm - Modification 4

Swept Path Assessment



DRAWN: RK  
DATE: 24/06/2024  
DWG NO: 388 RA02B Melbourne  
SCALE at A3: 1:750





- Light/power pole
- △ Traffic sign
- Traffic signal

- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
Escorts to control traffic as required.

**Location:**  
Derrimut VIC 3030  
[Online Map Link](#)



**Route Assessment - Melbourne**  
Gregador Solar Farm - Modification 4  
Swept Path Assessment

DRAWN: RK  
DATE: 24/06/2024  
DWG NO: 388 RA02B Melbourne  
SCALE at A3: 1:750





Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic as required.  
Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**  
Tarcutta NSW 2652  
[Online Map Link](#)



Route Assessment - Melbourne  
Gregador Solar Farm - Modification 4  
Swept Path Assessment

DRAWN: RK  
DATE: 24/06/2024  
DWG NO: 388 RA02B Melbourne  
SCALE at A3: 1:750





Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**

Tarcutta NSW 2652  
[Online Map Link](#)



Route Assessment - Melbourne  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:750





- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.  
 Ensure road shoulders are clear.

**Location:**  
 Gumly Gumly NSW 2652  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500





- Light/power pole
- Traffic sign
- Fence pole
- Area to be made trafficable

Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic as required.

Provide hardstand as required at yellow highlighted area.

Reinstate reflective guide posts if damaged.

Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**

Lake Albert NSW 2650

[Online Map Link](#)



**Route Assessment - Melbourne**

Gregador Solar Farm - Modification 4

Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500





- Light/power pole
- Traffic sign
- Fence pole
- Area to be made trafficable

Vehicle Envelope

0.5m Clearance

Load Outlines

Load Path

**Notes:**

Escorts to control traffic as required.

Provide hardstand as required at yellow highlighted area.

Reinstate reflective guide posts if damaged.

Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**

Lake Albert NSW 2650

[Online Map Link](#)



**Route Assessment - Melbourne**

Gregador Solar Farm - Modification 4

Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500



 Traffic sign  
 Fence pole

Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted area, subject to intersection design.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



Route Assessment - Melbourne  
 Gregadoo Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:750



Temporary hardstand to be provided

Road widening as outlined in TDG Concept plan DWG 'NO:15254-0S1A'

◇ Fence pole  
 Area to be made trafficable

Vehicle Envelope  
 0.5m Clearance  
 Load Outlines  
 Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted area, subject to intersection design.  
 Spotter(s) to assist to ensure vehicle and load are clear of infrastructure.

**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



Route Assessment - Melbourne  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500



- Vehicle Envelope
- 0.5m Clearance
- Load Outlines
- Load Path

**Notes:**  
 Escorts to control traffic as required.  
 Provide hardstand as required at yellow highlighted areas, subject to intersection design.

**Location:**  
 Gregadoo NSW 2650  
[Online Map Link](#)



**Route Assessment - Melbourne**  
 Gregador Solar Farm - Modification 4  
 Swept Path Assessment

DRAWN: RK  
 DATE: 24/06/2024  
 DWG NO: 388 RA02B Melbourne  
 SCALE at A3: 1:500