



Catholic Church Diocese of Maitland Newcastle

Operational Waste Management Plan

Stage 1- Catherine McAuley Catholic College

December 2020

ENGINEERING
PLANNING
PROJECT MANAGEMENT
SURVEYING
CERTIFICATION



© Copyright Barker Ryan Stewart Pty Ltd 2020 All Rights Reserved

Project No.	CC190045
Author	ВМ
Checked	LW
Approved	ВМ

Rev No.	Status	Date	Comments
1	Draft	26/11/2020	
2	Final	04/12/2020	

COPYRIGHT

Barker Ryan Stewart reserves all copyright of intellectual property in any or all of Barker Ryan Stewart's documents. No permission, licence or authority is granted by Barker Ryan Stewart to any person or organisation to use any of Barker Ryan Stewart's documents for any purpose without the written consent of Barker Ryan Stewart.

REPORT DISCLAIMER

This report has been prepared for the client identified in section 1.0 only and cannot be relied on or used by any third party. Any representation, statement, opinion or advice, expressed or implied in this report is made in good faith but on the basis that Barker Ryan Stewart are not liable (whether by reason of negligence, lack of care or otherwise) to any person for any damage or loss whatsoever which has occurred or may occur in relation to that person taking or not taking (as the case may be) action in any respect of any representation, statement, or advice referred to above.

This report is for development application purposes only and is not to be relied upon for construction purposes. The waste calculations included in the report are an estimate only, based on the plans and documents supplied by the client and waste generation guidelines from Council, the EPA and other third parties. This report is a guideline only and should not be used as a basis for feasibility studies, safety procedures, operational costs, demolition / construction estimates or bills of quantities. Should waste generation be higher than expected, the site manager shall make appropriate adjustments to accommodate additional waste. Any equipment recommended in this report shall be assessed by the supplier and site manager to determine it is fit for the intended purpose.



SYDNEY
P (02) 9659 0005
E sydney@brs.com.au

CENTRAL COAST P (02) 4325 5255 E coast@brs.com.au HUNTER
P (02) 4966 8388
E hunter@brs.com.au

SOUTH EAST QUEENSLAND P (07) 5582 6555 E seqld@brs.com.au



TABLE OF CONTENTS

Page numbers 1 Author and Project Details4 2 Purpose of Report4 3 Council Requirements5 Demolition and Construction......5 5 Ongoing Operation5 Waste Generation5 5.1 5.2 Waste Storage & Management......6 5.3 On-going Waste Removal Procedures......7 5.4 Education......8 Waste Collection.....8

Appendices

Appendix A – Waste Management Site Plan

Author and Project Details

AUTHOR DETAILS

Name Barker Ryan Stewart

Address Studio 5, 78 York Street, East Gosford

Phone number(s) 02 4325 5255

Email coast@brs.com.au

DEVELOPMENT DETAILS

Project Details Stage 1 - Catherine McAuley Catholic College

2 Kingfisher Close, Medowie; and Address of Development

507 Medowie Road, Medowie

Stage 1: Early Education Centre (40 children), high school (one

Description of development building accommodating interim occupation of 270 students) and

chapel.

This development achieves the waste objectives set out in the DCP. The details on this form are the provisions and intentions for minimising waste relating to this project. All records demonstrating lawful disposal of waste will be retained and kept readily accessible for inspection by regulatory authorities such as council, OEH or WorkCover NSW.

Contact Name Ben Miller

Date 26/11/2020

Purpose of Report

This report has been prepared to address the following condition of Development Consent as detailed below:

Operational Waste Management Plan

E23. Prior to the issue of an Occupation Certificate, the Applicant must prepare a Waste Management Plan for the development and submit it to the Principal Certifying Authority. The Waste Management Plan must:

- detail the type and quantity of waste to be generated during operation of the development:
- describe the handling, storage and disposal of all waste streams generated on site, consistent with the Protection of the Environment Operations Act 1997. Protection of the Environment Operations (Waste) Regulation 2014 and the Waste Classification Guideline (Department of Environment, Climate Change and Water, 2009);
- detail the materials to be reused or recycled, either on or off site; and
- include the Management and Mitigation Measures included in Part 10.13 of the EIS and as modified in the Response to Submissions.

Operational Waste Storage and Processing

E24. Prior to the issue of an Occupation Certificate, the Applicant must obtain agreement from Council for the design of the operational waste storage area where waste removal is undertaken by Council.

3 Council Requirements

As Port Stephens Council do not provide waste management objectives within the Port Stephens Development Control Plan 2014, this WMP has been prepared having regard for the specific waste management objectives of the NSW Waste Avoidance and Resource Recovery Strategy 2014- 21 Guidelines, which are:

- Avoid and reduce waste generation;
- Increase recycling;
- Divert more waste from landfill;
- Manage problem wastes better;
- Reduce litter; and
- Reduce illegal dumping

Further the Environment Protection Authority (EPA) and other Council's guidelines have been used to guide waste generation rates and options for waste management and collection.

4 Demolition and Construction

Demolition and construction waste generation has been addressed in the approved WMP prepared by Barker Ryan Stewart dated 16/04/2019 as part of the original development application.

5 Ongoing Operation

5.1 Waste Generation

The tables below show the expected waste generation from Stage 1 of the development.

As Port Stephens Council do not have waste generation rates for school developments within their DCP, the waste generation rates were taken from Randwick City Council Waste Management Guidelines as they provide a comprehensive range of uses and rates.

Waste for the school has been determined on a per student basis of 0.5L per student per day (recycling) and 1.5L per student per day (general waste). This does not account for waste generated by teachers however so an allowance has been provided to ensure the bins can accommodate total waste generated.

Waste associated with the Chapel building has been determined on a per square metre basis utilising Randwick Council guidelines for places of worship. Note the chapel will service an interim Stage 1 number of visitors/ students therefore the inclusion of the entire GFA represents a conservative estimate of waste requirements.

Waste associated with the early learning centre has been determined on a per child basis guided by the following:

- 0-2 years 1L per child per day (recycling) and 7L per child per day (general waste); and
- 3-5 years 1L per child per day (recycling) and 1.5L per child per day (general waste).

This is based on experience with other early learning centres and associated waste management.

DCP REQUIREMENTS	RECYCLABLES	GENERAL WASTE	GREEN WASTE	
High School - 270 Stude	ents (Block A)			
Amount generated (L per day)	135L	405L	Green waste will be reused on site or removed in the following bins	
Amount generated (L per week)	675L based on a 5 day week	2,025L based on a 5 day week		
Waste bins to be provided - High School	1 x 1,100L 2 x 240L (Food/ Organic) Removed weekly	2 x 1,100L Removed weekly	provided: 2 x 1,100L	
Early Learning Centre -	40 Children (20 x 0-2 years aı	nd 20 x 3-5 years) (Block Q)		
Amount generated (L per day)	40L	170L	Green waste will be reused on site or removed with the green waste bins	
Amount generated (L per week)	200L based on a 5 day week	850L based on a 5 day week		
Waste bins to be provided - ELC	1 x 360L Removed weekly	1 x 1,100L Removed weekly	provided for the high school.	
Chapel - 762m² (Block	B)			
Amount generated (L 76.2L 381L per day)		381L	Green waste will be reused on site or	
Amount generated (L per week)	152.4L based on usage of the facility 2 days per week	762L based on usage of the facility 2 days per week at full capacity	removed with the green waste bins provided for the high	
Waste bins to be	1 x 360L	2 x 360L	school.	
provided - Chapel	Removed weekly	Removed weekly Note the chapel will operate at a reduced capacity until further stages are completed therefore 720L bin volume will comfortably accommodate general waste generation associated with Stage 1.		

5.2 Waste Storage & Management

WASTE STORAGE and MANAGEMENT REQUIREMENTS		
Area for storage of bins	Block A, B and Q - bins will be stored external to the buildings within separate waste storage areas, refer to Appendix A for confirmation of locations. Storage areas have been designed to facilitate manoeuvring of bins to assist with kerbside collection.	
Green Waste	2 x 1100L bins will be stored adjacent to Block A to service Stage 1. Other blocks will have access to these bins as required. As detailed above, any additional green waste will be reused on site as mulch or removed by a landscaping contractor as required or.	
Food / Organic Waste	2 x 240L bins for food/ organic waste will be provided at Block A. Other blocks will have access to these bins as required.	

WASTE STORAGE and MANAGEMENT REQUIREMENTS		
Specialised Waste	Specialised waste associated with science, woodwork, metalwork and art will be managed and disposed of separately within future stages as required by the EPA and other safety guidelines.	
Bulky Waste	The school will be responsible for the disposal of waste that is too bulky to fit within their bins. Although this scenario is unlikely due to the large size of the waste and recycling bins, a specialised contractor or Groundsman can dispose to a recognised waste facility if required.	
Floor area required for manoeuvrability	The storage areas have been designed to accommodate bins of the proposed size. This area incorporates sufficient room for safe bin lifting (with the use of a mechanical bin lift) and collection.	
Height required for manoeuvrability	Provides sufficient overhead clearance, for bin lifters to transfer waste to larger bins and for manoeuvring by tugs or other vehicles to collection point.	
Path of travel to bin collection points	Block A - path of travel is clear from storage area to the collection point in the main car park. Block B - path of travel is clear from the storage area to the collection point in the main car park.	
	Block Q - path of travel is clear from the storage area to the collection point at the front of the building.	
Comment	Recycle: This development will provide adequate recycling bins to meet the minimum recycle requirements.	
	General Waste: This development will generally provide adequate waste bins to meet the minimum waste requirements. Provision of chapel waste will be slightly under the required bin numbers for occupancy of the entire building, however the chapel will function at approximately half capacity within Stage 1 and provided bin volume will be sufficient to service the building.	

5.3 On-going Waste Removal Procedures

- The Groundsman will transport waste from classroom/ internal and play area bins to the respective waste storage areas external to school buildings.
- The Groundsman will be allocated the responsibility of transporting the bins from Building A, B and Q storage areas to the kerbside collection points.
- The general, recycled, food and green waste will then be collected by a private waste contractor from the designated collection points prior to the school operating hours as identified in Figure 1 and Appendix A. The out of school hours collection is to ensure no conflicts with parents, staff or students.
- The path of travel from waste storage areas to collection points is level with no obstructions by way of fencing, stairs or unsuitable kerb profile.
- Details of the waste storage and collection points are shown on the waste plan in Appendix A.
- **Maintenance**: Management and cleaners shall be responsible for the maintenance of bin storage areas, signage and the security of the storage areas.
- Hygiene:
 - o The site manager / cleaners should provide regular bin cleaning. This should include a specialised filtration service to ensure pollutants are collected and appropriately disposed in accordance with EPA Guidelines. A specialised contractor can be employed if required in this regard.
 - A bin cleaning area has been provided.

5.4 Education

- Intelligible signage will be erected in the garbage storage areas to identify which bins should be used for different waste and recyclable materials in accordance with the Councils waste minimisation policy.
- The Groundsman and cleaners will be supplied with a copy of this waste management plan to inform them on the concepts of waste minimisation and recycling.
- The Groundsman and cleaners will monitor the waste areas and report to school / site management on any issues that require rectification.

6 Waste Collection

An extract from the Site Plan identifying waste storage areas and kerbside collection points is provided in Figure 1. Refer to Appendix A for further detail.

Waste vehicles will enter the site from Medowie Road and collect bins from the kerb in the locations identified in Figure 1. The internal road network and turning facilities are capable of accommodating the private waste vehicles proposed to service the site.




Figure 1: Extract from Site Waste Plan

CC190045 - Catherine McAuley Ca	utholic College Medowie	Waste Management Plan
	Appendix A – Waste Mai	nagement Site Plan

