

# Consolidated Consent

Wagga Wagga Base Hospital Redevelopment Stage 3 (SSD 9033)

[As modified by SSD-9033-Mod-1 – 12/06/19]

[As modified by SSD-9033-Mod-2 – 25/08/19]

[As modified by SSD-9033-Mod-3 – 19/12/19]

[As modified by SSD-9033-Mod-4 – 08/07/20]

## SCHEDULE 1

**Application Number:** SSD 9033

**Applicant:** Health Administration Corporation

**Consent Authority:** Minister for Planning and Public Spaces

**Site:** Wagga Wagga Rural Referral Hospital, Corner Edward and Docker Streets, Wagga Wagga  
Lot 334 in DP 1190643

**Development:** Construction of a six storey Ambulatory Care Building, including a rooftop plant room, car parking, ground level and bridge connection to the existing hospital building, site landscaping, removal of 11 demountable buildings, signage associated building services.

## DEFINITIONS

<b>Aboriginal object</b>	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
<b>Aboriginal place</b>	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
<b>Advisory Notes</b>	Advisory information relating to the consent but do not form a part of this consent
<b>Applicant</b>	NSW Health Infrastructure, or any person carrying out any development to which this consent applies
<b>Approved disturbance area</b>	The area identified as such on the development layout
<b>BCA</b>	Building Code of Australia
<b>BC Act</b>	<i>Biodiversity Conservation Act 2016</i>
<b>CEMP</b>	Construction Environmental Management Plan
<b>Certifying Authority</b>	Professionals that are accredited by the Building Professionals Board to issue construction, occupation, subdivision, strata, compliance and complying development certificates under the EP&A Act, <i>Strata Schemes (Freehold Development) Act 1973</i> and <i>Strata Schemes (Leasehold Development) Act 1986</i> or in the case of Crown development, a person qualified to conduct a Certification of Crown Building works.
<b>Conditions of this consent</b>	Conditions contained in Schedule 2 of this document
<b>Construction</b>	All physical works to enable operation, including but not limited to the demolition and removal of buildings, the carrying out of works for the purposes of the development, including bulk earthworks, and erection of buildings and other infrastructure permitted by this consent, but excluding the following: <ul style="list-style-type: none"> <li>• building and road dilapidation surveys;</li> <li>• investigative drilling, investigative excavation or Archaeological Salvage;</li> <li>• establishing temporary site offices (in locations identified by the conditions of this consent);</li> <li>• installation of environmental impact mitigation measures, fencing, enabling works; and</li> <li>• minor adjustments to services or utilities.</li> </ul>
<b>Council</b>	Wagga City Council
<b>Day</b>	The period from 7am to 6pm on Monday to Saturday, and 8am to 6pm on Sundays and Public Holidays
<b>Demolition</b>	The deconstruction and removal of buildings, sheds and other structures on the site
<b>Department</b>	NSW Department of Planning and Environment
<b>Development</b>	The development described in the EIS and Response to Submissions, including the works and activities comprising the redevelopment of the Wagga Wagga Hospital, as modified by the conditions of this consent.
<b>Earthworks</b>	Bulk earthworks, site levelling, import and compaction of fill material, excavation for installation of drainage and services, to prepare the site for construction
<b>EIS</b>	The Environmental Impact Statement titled <i>Wagga Wagga Base Hospital Redevelopment Stage 3</i> , prepared by Ethos Urban dated 28 June 2018, submitted with the application for consent for the development, including any additional information provided by the Applicant in support of the application
<b>Environment</b>	Includes all aspects of the surroundings of humans, whether affecting any human as an individual or in his or her social groupings
<b>EPA</b>	NSW Environment Protection Authority

<b>EP&amp;A Act</b>	<i>Environmental Planning and Assessment Act 1979</i>
<b>EP&amp;A Regulation</b>	<i>Environmental Planning and Assessment Regulation 2000</i>
<b>Evening</b>	The period from 6pm to 10pm.
<b>Feasible</b>	Means what is possible and practical in the circumstances
<b>Incident</b>	An occurrence or set of circumstances that causes or threatens to cause material harm and which may or may not be or cause a non-compliance <i>Note: "material harm" is defined in this consent</i>
<b>Land</b>	Has the same meaning as the definition of the term in section 1.4 of the EP&A Act
<b>Management and mitigation measures</b>	The management and mitigation measures set out in Chapter 9 of the EIS
<b>Material harm</b>	Is harm that: <ul style="list-style-type: none"> <li>a) involves actual or potential harm to the health or safety of human beings or to the environment that is not trivial; or</li> <li>b) results in actual or potential loss or property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment)</li> </ul>
<b>Minister</b>	NSW Minister for Planning (or delegate)
<b>Mitigation</b>	Activities associated with reducing the impacts of the development prior to or during those impacts occurring
<b>Monitoring</b>	Any monitoring required under this consent must be undertaken in accordance with section 9.40 of the EP&A Act
<b>Night</b>	The period from 10pm to 7am on Monday to Saturday, and 10pm to 8am on Sundays and Public Holidays
<b>Non-compliance</b>	An occurrence, set of circumstances or development that is a breach of this consent
<b>OEH</b>	NSW Office of Environment and Heritage
<b>Operation</b>	The carrying out of the approved purpose of the development upon completion of construction.
<b>PA</b>	Means a planning agreement within the meaning of the term in section 7.4 of the EP&A Act.
<b>Planning Secretary</b>	Planning Secretary under the EP&A Act, or nominee
<b>Reasonable</b>	Means applying judgement in arriving at a decision, taking into account: mitigation benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements.
<b>Rehabilitation</b>	The restoration of land disturbed by the development to a good condition, to ensure it is safe, stable and non-polluting.
<b>Response to submissions</b>	The Applicant's response to issues raised in submissions received in relation to the application for consent for the development under the EP&A Act.
<b>RMS</b>	NSW Roads and Maritime Services
<b>Sensitive receivers</b>	A location where people are likely to work, occupy or reside, including a dwelling, school, hospital, office or public recreational area.
<b>Site</b>	The land defined in Schedule 1
<b>TfNSW</b>	Transport for New South Wales
<b>Waste</b>	Has the same meaning as the definition of the term in the Dictionary to the POEO Act
<b>Year</b>	A period of 12 consecutive months

**SCHEDULE 2**  
**PART A ADMINISTRATIVE CONDITIONS**

**Obligation to Minimise Harm to the Environment**

A1. In addition to meeting the specific performance measures and criteria in this consent, all reasonable and feasible measures must be implemented to prevent, and if prevention is not reasonable and feasible, minimise, any material harm to the environment that may result from the construction and operation of the development.

**Terms of Consent**

- A2. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
  - (b) in accordance with all written directions of the Planning Secretary;
  - (c) generally in accordance with the EIS and Response to Submissions;
  - (d) in accordance with the approved plans in the table below:

<b>Architectural Plans prepared by Jacobs</b>			
<b>Dwg No.</b>	<b>Rev</b>	<b>Name of Plan</b>	<b>Date</b>
IA172202-ACB-RB-DRG-0100	<del>4</del> <b>P</b>	Site Plan – Proposed	<del>05/10/18</del> <b>28/04/20</b>
<b><u>IA172202-ACB-RB-DRG-0102</u></b>	<b><u>E</u></b>	<b><u>Generator Elevations</u></b>	<b><u>17/04/20</u></b>
IA172202-ACB-RB-DRG-1500	<del>E</del> <b>N</b>	General Arrangement Plan – Basement	<del>21/09/18</del> <b>05/06/19</b>
IA172202-ACB-RB-DRG-1501	E	General Arrangement Plan – Ground	21/09/18
IA172202-ACB-RB-DRG-1502	E	General Arrangement Plan – Level 1	21/09/18
IA172202-ACB-RB-DRG-1503	E	General Arrangement Plan – Level 2	21/09/18
IA172202-ACB-RB-DRG-1504	E	General Arrangement Plan – Level 3	21/09/18
IA172202-ACB-RB-DRG-1505	E	General Arrangement Plan – Level 4	21/09/18
IA172202-ACB-RB-DRG-1506	E	General Arrangement Plan – Level 5	21/09/18
IA172202-ACB-RB-DRG-1507	E	General Arrangement Plan – Roof	21/09/18
IA172202-ACB-RB-DRG-4000	D	Elevations	21/09/18
IA172202-ACB-RB-DRG-4001	D	Elevations	21/09/18
IA172202-ACB-RB-DRG-4002	<del>D</del> <b>I</b>	Sections	<del>21/09/18</del> <b>05/06/19</b>
IA172202-ACB-RB-DRG-4003	D	Sections	21/09/18
IA172202-ACB-RB-DRG-4004	<del>D</del> <b>I</b>	Sections	<del>21/09/18</del>

			<b>05/06/19</b>
<b>Landscape Plans prepared by <i>Site Image</i></b>			
<b>Dwg No.</b>	<b>Rev</b>	<b>Name of Plan</b>	<b>Date</b>
002	C	Landscape Plan	31/08/18
003	C	Northern Lineal Landscape and Terrace	31/08/18
004	C	Northeast Pocket Park	31/08/18
005	C	Eastern Covered Space	31/08/18
006	C	North Western Park	31/08/18
007	C	Western Park	31/08/18
008	C	Southern Courtyard	31/08/18
009	C	Cultural Courtyard	31/08/18
010	C	Level 2 Mental Health Terraces	31/08/18
011	C	Level 4 Rehabilitation Terrace	31/08/18
012	C	Indicative Planting	31/08/18

[SSD-9033-Mod-2 – 25/08/19]

[SSD-9033-Mod-4 – 08/07/20]

- A3. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary; and
  - the implementation of any actions or measures contained in any such document referred to in (a) above.
- A4. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition A2(c). In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition A2(c), the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.

#### **Limits of Consent**

- A5. This consent lapses five years after the date of consent unless the works associated with the development have physically commenced.

#### **Planning Secretary as Moderator**

- A6. In the event of a dispute between the Applicant and a public authority, in relation to an applicable requirement in this approval or relevant matter relating to the Development, either party may refer the matter to the Planning Secretary for resolution. The Planning Secretary's resolution of the matter must be binding on the parties.

#### **Long Service Levy**

- A7. For work costing \$25,000 or more, a Long Service Levy must be paid. For further information please contact the Long Service Payments Corporation Helpline on 131 441.

#### **Legal Notices**

- A8. Any advice or notice to the consent authority must be served on the Planning Secretary.

## Evidence of Consultation

- A9. Where conditions of this consent require consultation with an identified party, the Applicant must:
- (a) consult with the relevant party prior to submitting the subject document for information or approval; and
  - (b) provide details of the consultation undertaken including:
    - (i) the outcome of that consultation, matters resolved and unresolved; and
    - (ii) details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

## Staging, Combining and Updating Strategies, Plans or Programs

- A10. With the approval of the Planning Secretary, the Applicant may:
- (a) prepare and submit any strategy, plan or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan or program);
  - (b) combine any strategy, plan or program required by this consent (if a clear relationship is demonstrated between the strategies, plans or programs that are proposed to be combined); and
  - (c) update any strategy, plan or program required by this consent (to ensure the strategies, plans and programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).
- A11. If the Planning Secretary agrees, a strategy, plan or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.
- A12. If approved by the Planning Secretary, updated strategies, plans or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan or program.

## Demolition

- A13. Demolition work must comply with *Australian Standard AS 2601-2001 The demolition of structures* (Standards Australia, 2001). The work plans required by AS 2601-2001 must be accompanied by a written statement from a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the statement of compliance must be submitted to the Certifying Authority before the commencement of works.

## Structural Adequacy

- A14. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, must be constructed in accordance with the relevant requirements of the BCA

### Notes:

- *Part 8 of the EP&A Regulation sets out the requirements for the certification of the development.*
- *Under section 21 of the Coal Mine Subsidence Compensation Act 2017, the Applicant is required to obtain the Chief Executive of Subsidence Advisory NSW's approval before carrying out certain development in a Mine Subsidence District.*

## External Walls and Cladding

- A15. The external walls of all buildings including additions to existing buildings must comply with the relevant requirements of the BCA.

## Applicability of Guidelines

- A16. References in the conditions of this consent to any guideline, protocol, Australian Standard or policy are to such guidelines, protocols, Standards or policies in the form they are in as at the date of this consent.

However, consistent with the conditions of this consent and without altering any limits or criteria in this consent, the Planning Secretary may, when issuing directions under this consent in respect of ongoing monitoring and management obligations, require compliance with an updated or revised version of such a guideline, protocol, Standard or policy, or a replacement of them.

### **Monitoring and Environmental Audits**

A17. Any condition of this consent that requires the carrying out of monitoring or an environmental audit, whether directly or by way of a plan, strategy or program, is taken to be a condition requiring monitoring or an environmental audit under Division 9.4 of Part 9 of the EP&A Act. This includes conditions in respect of incident notification, reporting and response, non-compliance notification, compliance reporting and independent auditing.

**Note:** For the purposes of this condition, as set out in the EP&A Act, “monitoring” is monitoring of the development to provide data on compliance with the consent or on the environmental impact of the development, and an “environmental audit” is a periodic or particular documented evaluation of the development to provide information on compliance with the consent or the environmental management or impact of the development.

### **Access to Information**

A18. At least 48 hours before the commencement of construction until the completion of all works under this consent, or such other time as agreed by the Planning Secretary, the Applicant must:

- (a) make the following information and documents (as they are obtained or approved) publicly available on its website:
  - (i) the documents referred to in condition A2 of this consent;
  - (ii) all current statutory approvals for the development;
  - (iii) all approved strategies, plans and programs required under the conditions of this consent;
  - (iv) regular reporting on the environmental performance of the development in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent;
  - (v) a comprehensive summary of the monitoring results of the development, reported in accordance with the specifications in any conditions of this consent, or any approved plans and programs;
  - (vi) a summary of the current stage and progress of the development;
  - (vii) contact details to enquire about the development or to make a complaint;
  - (viii) a complaints register, updated monthly;
  - (ix) audit reports prepared as part of any independent environmental audit of the development and the Applicant’s response to the recommendations in any audit report;
  - (x) any other matter required by the Planning Secretary; and
- (b) keep such information up to date, to the satisfaction of the Planning Secretary.

### **Compliance**

A19. The Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development.

### **Staging**

A20. **The project may be constructed and operated in stages. Where staged construction or operation is proposed (to the extent to which it relates to the requirements set out in this instrument), a Staging Report (for either or both construction and operation as the case may be) must be prepared and submitted for the approval of the Planning Secretary.**

A21. **A Staging Report prepared in accordance with condition A20 must:**

- (a) **if staged construction is proposed, set out how the construction of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when construction of each stage will commence and finish;**

- (b) if staged operation is proposed, set out how the operation of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when operation of each stage will commence and finish (if relevant);
  - (c) specify how compliance with conditions will be achieved across and between each of the stages of the project; and
  - (d) set out mechanisms for managing any cumulative impacts arising from the proposed staging.
- A22. Where staging is proposed, the project must be staged in accordance with the Staging Report, as approved by the Planning Secretary.
- A23. Where staging is proposed, the terms of this approval that apply or are relevant to the works or activities to be carried out in a specific stage must be complied with at the relevant time for that stage.

[SSD-9033-Mod-3 – 19/12/19]

#### ADVISORY NOTES

- AN1. All licences, permits, approvals and consents as required by law must be obtained and maintained as required for the development. No condition of this consent removes any obligation to obtain, renew or comply with such licences, permits, approvals and consents.



## PART B PRIOR TO COMMENCEMENT OF CONSTRUCTION

### Notification of Commencement

- B1. The Department must be notified in writing of the dates of commencement of physical work and operation at least 48 hours before those dates.

If the construction or operation of the development is to be staged, the Department must be notified in writing at least 48 hours before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

### Certified Drawings

- B2. Prior to the commencement of the relevant work, the Applicant must submit to the satisfaction of the Certifier structural drawings prepared and signed by a suitably qualified practising Structural Engineer that demonstrates compliance with:

- (a) the relevant clauses of the BCA; and
- (b) this development consent.

### Water Sensitive Urban Design

- B3. Prior to the commencement the relevant works, Water Sensitive Urban Design measures are to be incorporated into the design consistent with the *Australian Rainfall and Runoff, Australian Runoff Quality – a Guide to Water Sensitive Urban Design* guideline.

### External Walls and Cladding

- B4. Prior to the commencement of construction, the Applicant must provide the Certifying Authority with documented evidence that the products and systems proposed for use in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the requirements of the BCA.

The Applicant must provide a copy of the documentation given to the Certifying Authority to the Planning Secretary within seven days after the Certifying Authority accepts it.

### Reflectivity

- B5. The building materials used on the facades of all buildings will be designed so as not to result in glare that causes discomfort or threatens the safety of pedestrians or drivers. A report/statement demonstrating consistency with this requirement will be submitted to the satisfaction of the Certifying Authority prior to the commencement of above ground works.

### Protection of Public Infrastructure

- B6. Before the commencement of construction, the Applicant must:
- (a) consult with the relevant owner and provider of services that are likely to be affected by the development to make suitable arrangements for access to, diversion, protection and support of the affected infrastructure;
  - (b) prepare a dilapidation report identifying the condition of all public infrastructure in the vicinity of the site (including roads, gutters and footpaths); and
  - (c) submit a copy of the dilapidation report to the Planning Secretary, Certifying Authority and Council.

### Unexpected Contamination Procedure

- B7. Prior to the commencement of earthworks, the Applicant must prepare an unexpected contamination procedure to ensure that potentially contaminated material is appropriately managed. The procedure must form part of the of the CEMP in accordance with condition B20 and ~~must ensure any material identified as contaminated must be disposed off-site~~ **where any material identified as contaminated is to be disposed off-site**, with the disposal location and results of testing submitted to the Planning Secretary, prior to its removal from the site.

[SSD-9033-Mod-1 – 12/06/19]

## Utilities and Services

- B8. Before the construction of any utility works associated with the development, the Applicant must obtain relevant approvals from service providers.
- B9. Prior to the commencement of above ground works written advice must be obtained from the electricity supply authority, an approved telecommunications carrier and an approved gas carrier (where relevant) stating that satisfactory arrangements have been made to ensure provisions of adequate services.

## Traffic Upgrade Works

- B10. Before the commencement of construction, a Traffic and Transport Consultative Committee (TTCC) must be established for the development to develop the following upgrade works to resolve impacts on key intersections surrounding the hospital site.
- (a) The intersection of Edward Street and Murray Street is to be upgraded to achieve a Level of Service C or better forecasting to the year 2031. The intersection treatment is to be designed and constructed in accordance with the Austroads Guide to Road Design as amended by the supplements adopted by Roads and Maritime Services.
  - (b) The intersection of Murray Street and Brookong Avenue is to be upgraded for traffic calming purposes.
  - (c) Phasing and lane reconfiguration works to the Edward Street and Docker Street intersection as outlined in the Transport Impact Assessment, Issue B, dated 3 October 2018 and prepared by GTA Consultants.

**Note:** The Committee must comprise an independent chair and appropriate representation from the Applicant, Council, RMS and if required, TfNSW

## Road Design and Traffic Facilities

- B11. All roads and traffic facilities must be designed to meet the requirements of Council or RMS (whichever is applicable). The necessary permits and approvals from the relevant road authority must be obtained prior to the commencement of road or pavement construction works.
- B12. For works on the State Road network the developer is required to enter into a Works Authorisation Deed (WAD) with Roads and Maritime Services before finalising the design or undertaking any construction work within or connecting to the road reserve.

*Note: The applicant is to contact the Land Use Manager for the South West Region on Ph. 02 6938 1111 for further detail.*

## Community Communication Strategy

- B13. A Community Communication Strategy must be prepared to provide mechanisms to facilitate communication between the Applicant, the relevant Council and the community (including adjoining affected landowners and businesses, and others directly impacted by the development), during the design and construction of the development and for a minimum of 12 months following the completion of construction.

The Community Communication Strategy must:

- (a) identify people to be consulted during the design and construction phases;
- (b) set out procedures and mechanisms for the regular distribution of accessible information about or relevant to the development;
- (c) provide for the formation of community-based forums, if required, that focus on key environmental management issues for the development;
- (d) set out procedures and mechanisms:
  - (i) through which the community can discuss or provide feedback to the Applicant;
  - (ii) through which the Applicant will respond to enquiries or feedback from the community; and
  - (iii) to resolve any issues and mediate any disputes that may arise in relation to construction and operation of the development, including disputes regarding rectification or compensation.

The Community Communication Strategy must be submitted to the Planning Secretary for approval no later than two weeks before the commencement of any work.

Work for the purposes of the development must not commence until the Community Communication Strategy has been approved by the Planning Secretary, or within another timeframe agreed with the Planning Secretary.

### **Ecologically Sustainable Development**

- B14. Prior to the commencement of the relevant work, the Applicant must submit details of all design measures to the satisfaction of the Certifying Authority demonstrating the proposal incorporates ecologically sustainable development initiatives as outlined in NSW Health Infrastructure Engineering Services Guidelines and Section J of the National Construction Code 2012 to achieve the equivalent of a minimum 4 Star Green Star rating.

### **Landscaping**

- B15. Prior to commencement of the relevant work, the Applicant must prepare a Landscape Management Plan to manage the revegetation and landscaping works on-site, to the satisfaction of the Certifying Authority. The plan must:
- (a) be generally in accordance with the approved landscape plans prepared by Site Image, dated 31 August 2018;
  - (b) provide for the planting of a minimum of 68 new trees of species of at least 20 must be endemic to the area;
  - (c) detail all species to be planted on-site;
  - (d) describe the monitoring and maintenance measures to manage revegetation and landscaping works; and
  - (e) be consistent with the Applicant's Management and Mitigation Measures in the EIS and RfS.
- B16. The Applicant must not commence the relevant work until the Landscape Management Plan is submitted to the satisfaction of the Certifying Authority.

### **Water Supply**

- B17. All applicable fees and charges must be paid in full prior to RWCC commencing any on-site works or issuing a 'Certificate of Compliance for Water Supply' for the stage 3 development.

### **Outdoor Lighting**

- B18. Prior to commencement of the relevant work, all outdoor lighting within the site must comply with AS 1158.3.1:2005 Lighting for roads and public spaces – Pedestrian area (Category P) lighting – Performance and design requirements and AS 4282-1997 Control of the obtrusive effects of outdoor lighting. Details demonstrating compliance with these requirements must be submitted to the satisfaction of the Certifying Authority.

### **Access for People with Disabilities**

- B19. The works that are the subject of this application must be designed and constructed to provide access and facilities for people with a disability in accordance with the BCA. Prior to the commencement of the relevant work, the Certifying Authority must ensure that evidence of compliance with this condition from an appropriately qualified person is provided and that the requirements are referenced on any certified plans.

### **Construction Environmental Management Plan**

- B20. Prior to commencement of construction, the Applicant must prepare a **Construction Environmental Management Plan** (CEMP) and it must include, but not be limited to, the following:
- (a) Details of:
    - (i) hours of work;
    - (ii) 24-hour contact details of site manager;
    - (iii) management of dust and odour to protect the amenity of the neighbourhood;
    - (iv) stormwater control and discharge;

- (v) measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site;
  - (vi) external lighting in compliance with AS 4282-1997 Control of the obtrusive effects of outdoor lighting;
  - (vii) community consultation and complaints handling;
  - (b) Construction Traffic and Pedestrian Management Sub-Plan (see condition B22);
  - (c) Construction Noise and Vibration Management Sub-Plan (see condition B23);
  - (d) Construction Waste Management Sub-Plan (see condition B24);
  - (e) Construction Dust Management Sub-Plan;
  - (f) Construction Soil and Water Management Sub-Plan including Erosion and Sediment Control Plan;
  - (g) an unexpected finds protocol for Aboriginal and non-Aboriginal heritage and associated communications procedure;
  - (h) details of tree protection areas to ensure no secondary impacts to extant trees not to be removed;
  - (i) waste classification (for materials to be removed) and validation (for materials to remain) be undertaken to confirm the contamination status in these areas of the site.
- B21. The Applicant must not commence construction of the development until the CEMP is approved by the Certifying Authority and a copy submitted to the Planning Secretary.
- B22. The **Construction Traffic and Pedestrian Management Sub-Plan (CTPMSP)** must be prepared in consultation with Council and submitted to the satisfaction of the Certifying Authority. The CPTMP must specify, but not limited to, the following:
- (a) be prepared by a suitably qualified and experienced person(s);
  - (b) be prepared in consultation with Council, RMS and TfNSW;
  - (c) detail the measures that are to be implemented to ensure road safety and network efficiency during construction in consideration of potential impacts on general traffic, cyclists and pedestrians and bus services;
  - (d) assess cumulative impacts associated with other construction activities (if any);
  - (e) assess the road safety at key intersections and locations subject to heavy vehicle movements and high pedestrian activity;
  - (f) detail construction program, the anticipated construction duration and milestones and events during the construction process;
  - (g) detail anticipated peak hour and daily truck movements to and from the site;
  - (h) detail access arrangements for workers to/from the site, emergency vehicles and service vehicle movements;
  - (i) detail temporary cycling and pedestrian access during construction;
  - (j) detail proposed construction vehicle access arrangements at all stages; and
  - (k) detail heavy vehicle routes, access and parking arrangements including that required by condition B25;
  - (l) include a Driver Code of Conduct to:
    - (i) minimise the impacts of earthworks and construction on the local and regional road network;
    - (ii) minimise conflicts with other road users;
    - (iii) minimise road traffic noise; and
    - (iv) ensure truck drivers use specified routes;
  - (m) detail temporary traffic controls, including detours and signage;
  - (n) include procedures for notifying the local community about project-related traffic impacts;
  - (o) include procedures for managing impacts to bus stops;

- (p) include procedures for receiving and addressing complaints from the community about development-related traffic;
- (q) include measures for minimising potential for conflict with school buses, school zone operating times, emergency vehicles and other motorists as far as practicable;
- (r) include procedures for responding to any emergency repair or maintenance requirements;
- (s) include a program to monitor the effectiveness of these measures; and
- (t) if necessary, detail procedures for notifying residents and the community (including local schools), of any potential disruptions to routes.

B23. The **Construction Noise and Vibration Management Sub-Plan** must address, but not be limited to, the following:

- (a) be prepared by a suitably qualified and experienced noise expert;
- (b) describe procedures for achieving the noise management levels in EPA's *Interim Construction Noise Guideline* (DECC, 2009);
- (c) describe the measures to be implemented to manage high noise generating works such as piling, in close proximity to sensitive receivers;
- (d) include strategies that have been developed with the community for managing high noise generating works;
- (e) describe the community consultation undertaken to develop the strategies in condition B23(d); and
- (f) include a complaints management system that would be implemented for the duration of the construction.

B24. The **Construction Waste Management Sub-Plan** (CWMS) must address, but not be limited to, the following:

- (a) detail the quantities of each waste type generated during construction and the proposed reuse, recycling and disposal locations;
- (b) The CWMS must include a Hazardous Materials Management Plan and Asbestos Removal Control Plan;
- (c) removal of hazardous materials, particularly the method of containment and control of emission of fibres to the air, and disposal at an approved waste disposal facility in accordance with the requirements of the relevant legislation, codes, standards and guidelines, prior to the commencement of any building works.

### **Construction Parking**

B25. Prior to the commencement of construction, the Applicant must demonstrate to the satisfaction of the Certifying Authority that sufficient off-street parking has been provided, including for heavy vehicles and for site personnel, to ensure that construction traffic associated with the development reduces the utilisation of public and residential streets or public parking facilities.

### **Stormwater Management System**

B26. Prior to the commencement of the relevant work, the Applicant must design a stormwater management system for the development and submit it to the satisfaction of the Certifying Authority. The system must:

- (a) be designed by a suitably qualified and experienced person(s);
- (b) be generally in accordance with the conceptual design in the EIS;
- (c) be in accordance with applicable Australian Standards; and
- (d) ensure that the system capacity has been designed in accordance with *Australian Rainfall and Runoff* (Engineers Australia, 2016) and *Managing Urban Stormwater: Council Handbook* (EPA, 1997) guidelines.

## Operational Noise – Design of Mechanical Plant and Equipment

B27. Prior to commencement of the relevant work, the Applicant must incorporate the noise mitigation recommendations in the Noise Impact Assessment **and Acoustic Brief (dated 19 December 2019)**, into the detailed design drawings. The Certifying Authority must verify that all reasonable and feasible noise mitigation measures have been incorporated into the design to ensure the development will not exceed the recommended operational noise levels identified in the Noise Impact Assessment **and Acoustic Brief**.

[SSD-9033-Mod-4 – 08/07/20]

## Mechanical Ventilation

B28. All mechanical ventilation systems must be designed in accordance with Part F4.5 of the BCA and must comply with the AS 1668.2-2012 *The use of air-conditioning in buildings – Mechanical ventilation in buildings* and AS/NZS 3666.1:2011 *Air handling and water systems of buildings– Microbial control* to ensure adequate levels of health and amenity to the occupants of the building and to ensure environment protection. Details must be submitted to the satisfaction of the Certifying Authority prior to the commencement of the relevant works.

## Bicycle Parking and End-of-Trip Facilities

B29. Compliance with the following requirements for secure bicycle parking and end-of-trip facilities must be submitted to the satisfaction of the Certifying Authority prior to the commencement of construction:

- the provision of a minimum 28 bicycle parking spaces;
- the layout, design and security of bicycle facilities must comply with the minimum requirements of AS 2890.3:2015 *Parking facilities - Bicycle parking*, and be located in easy to access, well-lit areas that incorporate passive surveillance;
- the provision of end-of-trip facilities for staff in accordance with the ESD Design & As Built rating tool;
- appropriate pedestrian and cyclist advisory signs are to be provided; and
- all works/regulatory signposting associated with the proposed developments shall be at no cost to the relevant roads authority.

## Compliance Reporting

B30. No later than two weeks before the date notified for the commencement of construction, a Compliance Monitoring and Reporting Program prepared in accordance with the Compliance Reporting Post Approval Requirements (Department 2018) must be submitted to the Department and the Certifying Authority.

Compliance Reports of the project must be carried out in accordance with the Compliance Reporting Post Approval Requirements (Department 2018).

The Applicant must make each Compliance Report publicly available 60 days after submitting it to the Department and notify the Department and the Certifying Authority in writing at least seven days before this is done.

B31. Notwithstanding the requirements of the Compliance Reporting Post Approval Requirements (Department 2018), the Planning Secretary may approve a request for ongoing annual operational compliance reports to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that an operational compliance report has demonstrated operational compliance.

## PART C DURING CONSTRUCTION

### Approved Plans to be On-site

- C1. A copy of the approved and certified plans, specifications and documents incorporating conditions of approval and certification must be kept on the Site at all times and must be readily available for perusal by any officer of the Department, Council or the Certifying Authority.

### Site Notice

- C2. A site notice(s):
- (a) must be prominently displayed at the boundaries of the site for the purposes of informing the public of project details including, but not limited to the details of the Builder, Certifying Authority and Structural Engineer.
  - (b) is to satisfy all but not be limited to, the following requirements:
    - (i) minimum dimensions of the notice must measure 841 mm x 594 mm (A1) with any text on the notice to be a minimum of 30-point type size;
    - (ii) the notice is to be durable and weatherproof and is to be displayed throughout the works period;
    - (iii) the approved hours of work, the name of the site/ project manager, the responsible managing company (if any), its address and 24-hour contact phone number for any inquiries, including construction/ noise complaint must be displayed on the site notice; and
    - (iv) the notice(s) is to be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted.

### Operation of Plant and Equipment

- C3. All plant and equipment used on site, or to monitor the performance of the development must be:
- a) maintained in a proper and efficient condition; and
  - b) operated in a proper and efficient manner.

### Demolition

- C4. Demolition work must comply with *Australian Standard AS 2601-2001* The demolition of structures (Standards Australia, 2001). The work plans required by AS 2601-2001 must be accompanied by a written statement from a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the statement of compliance must be submitted to the Certifying Authority before the commencement of works.

### Construction Hours

- C5. Construction, including the delivery of materials to and from the site, may only be carried out between the following hours:
- (a) between 7am and 6pm, Mondays to Fridays inclusive; and
  - (b) between 7.30am and 5pm, Saturdays.

No work may be carried out on Sundays or public holidays.

- C6. Activities may be undertaken outside of the hours in condition C5 if required:
- (a) by the Police or a public authority for the delivery of vehicles, plant or materials; or
  - (b) in an emergency to avoid the loss of life, damage to property or to prevent environmental harm; or
  - (c) where the works are inaudible at the nearest sensitive receivers; or
  - (d) where a variation is approved in advance in writing by the Planning Secretary or her nominee if appropriate justification is provided for the works.

Notification of such activities must be given to affected residents before undertaking the activities or as soon as is practical afterwards.

- C7. Rock breaking, rock hammering, sheet piling, pile driving and similar activities may only be carried out between the following hours:
- (a) 9am to 12pm, Monday to Friday;
  - (b) 2pm to 5pm Monday to Friday; and
  - (c) 9am to 12pm, Saturday.

#### **Implementation of Management Plans**

- C8. The Applicant must carry out the construction of the development in accordance with the most recent version of the approved CEMP (including Sub-Plans).

#### **Construction Traffic**

- C9. All construction vehicles (excluding worker vehicles) are to be contained wholly within the site, except if located in an approved on-street work zone, and vehicles must enter the site before stopping.

#### **Road Occupancy Licence**

- C10. A Road Occupancy Licence must be obtained from the relevant road authority for any works that impact on traffic flows during construction activities and/or any works in the road reserve.

#### **SafeWork Requirements**

- C11. To protect the safety of work personnel and the public, the work site must be adequately secured to prevent access by unauthorised personnel, and work must be conducted at all times in accordance with relevant SafeWork requirements.

#### **Hoarding Requirements**

- C12. The following hoarding requirements must be complied with:
- (a) no third-party advertising is permitted to be displayed on the subject hoarding/ fencing;
  - (b) the construction site manager must be responsible for the removal of all graffiti from any construction hoardings or the like within the construction area within 48 hours of its application; and
  - (c) the Applicant must submit a hoarding application to Council for the installation of any hoardings over Council footways or road reserve.

#### **No Obstruction of Public Way**

- C13. The public way (outside of any approved construction works zone) must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances. Non-compliance with this requirement will result in the issue of a notice by the relevant Authority to stop all works on site.

#### **Construction Noise Limits**

- C14. The development must be constructed to achieve the construction noise management levels detailed in *the Interim Construction Noise Guideline* (DECC, 2009). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the management and mitigation measures identified in the approved Construction Noise and Vibration Management Plan.
- C15. The Applicant must ensure construction vehicles (including concrete agitator trucks) do not arrive at the site or surrounding residential precincts outside of the construction hours of work outlined under condition C5.
- C16. The Applicant must implement, where practicable and without compromising the safety of construction staff or members of the public, the use audible movement alarms of a type that would minimise noise impacts on surrounding noise sensitive receivers.
- C17. Any noise generated during construction of the development must not be offensive noise within the meaning of the *Protection of the Environment Operations Act 1997* or exceed approved noise limits for the site.



## Vibration Criteria

- C18. Vibration caused by construction at any residence or structure outside the site must be limited to:
- (a) for structural damage, the latest version of *DIN 4150-3 (1992-02) Structural vibration - Effects of vibration on structures* (German Institute for Standardisation, 1999); and
  - (b) for human exposure, the acceptable vibration values set out in the *Environmental Noise Management Assessing Vibration: a technical guideline* (DEC, 2006) (as may be updated or replaced from time to time).
- C19. Vibratory compactors must not be used closer than 30 metres from residential buildings unless vibration monitoring confirms compliance with the vibration criteria specified in condition C18.
- C20. The limits in conditions C18 and C19 apply unless otherwise outlined in a Construction Noise and Vibration Management Plan, approved as part of the CEMP required by condition B23 of this consent.

## Tree Protection

- C21. For the duration of the construction works:
- (a) street trees must not be trimmed or removed unless it forms a part of this development consent or prior written approval from Council is obtained or is required in an emergency to avoid the loss of life or damage to property;
  - (b) all street trees must be protected at all times during construction. Any tree on the footpath, which is damaged or removed during construction due to an emergency, must be replaced, to the satisfaction of Council;
  - (c) all trees on the site that are not approved for removal must be suitably protected during construction as per recommendations of the Tree Assessment Report prepared for the EIS; and
  - (d) if access to the area within any protective barrier is required during the works, it must be carried out under the supervision of a qualified arborist. Alternative tree protection measures must be installed, as required. The removal of tree protection measures, following completion of the works, must be carried out under the supervision of a qualified arborist and must avoid both direct mechanical injury to the structure of the tree and soil compaction within the canopy or the limit of the former protective fencing, whichever is the greater.

## Dust Minimisation

- C22. The Applicant must take all reasonable steps to minimise dust generated during all works authorised by this consent.
- C23. During construction, the Applicant must ensure that:
- (a) exposed surfaces and stockpiles are suppressed by regular watering;
  - (b) all trucks entering or leaving the site with loads have their loads covered;
  - (c) trucks associated with the development do not track dirt onto the public road network;
  - (d) public roads used by these trucks are kept clean; and
  - (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

## Erosion and Sediment Control

- C24. All erosion and sediment control measures, must be effectively implemented and maintained at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works have been stabilised and rehabilitated so that it no longer acts as a source of sediment.

## **Disposal of Seepage and Stormwater**

- C25. Any seepage or rainwater collected on-site during construction or groundwater must not be pumped to the street stormwater system unless separate prior approval is given in writing by the EPA in accordance with the *Protection of the Environment Operations Act 1997*.

## **Unexpected Finds Protocol – Aboriginal Heritage**

- C26. In the event that surface disturbance identifies a new Aboriginal object, all works must halt in the immediate area to prevent any further impacts to the object(s). A suitably qualified archaeologist and the registered Aboriginal representatives must be contacted to determine the significance of the objects. The site is to be registered in the Aboriginal Heritage Information Management System (AHIMS) which is managed by OEH and the management outcome for the site included in the information provided to AHIMS. The Applicant must consult with the Aboriginal community representatives, the archaeologists and OEH to develop and implement management strategies for all objects/sites. Works shall only recommence with the written approval of OEH.

## **Unexpected Finds Protocol – Historic Heritage**

- C27. If any unexpected archaeological relics are uncovered during the work, then all works must cease immediately in that area and the OEH Heritage Division contacted. Depending on the possible significance of the relics, an archaeological assessment and management strategy may be required before further works can continue in that area. Works may only recommence with the written approval of Heritage Division of the OEH.

## **Waste Storage and Processing**

- C28. Waste must be secured and maintained within designated waste storage areas at all times and must not leave the site onto neighbouring public or private properties.
- C29. All waste generated during construction must be assess, classified and managed in accordance with the Waste Classification Guidelines Part 1: Classifying Waste (EPA, 2014).
- C30. The body of any vehicle or trailer used to transport waste or excavation spoil must be covered before leaving the premises to prevent any spillage or escape of any dust, waste of spoil. Mud, splatter, dust and other material likely to fall from or be cast off the wheels, underside or body of any vehicle, trailer or motorised plant leaving the site must be removed before leaving the premises.
- C31. The Applicant must ensure that concrete waste and rinse water are not disposed of on the site and are prevented from entering any natural or artificial watercourse.

## **Handling of Asbestos**

- C32. The Applicant is to consult with SafeWork NSW concerning the handling of any asbestos waste that may be encountered during construction. The requirements of the Protection of the Environment Operations (Waste) Regulation 2014 with particular reference to Part 7 – ‘Transportation and management of asbestos waste’ must also be complied with.

## **Independent Environmental Audit**

- C33. The proposed independent auditors must be agreed to in writing by the Planning Secretary prior to the preparation of an Independent Audit Program or commencement of an Independent Audit.
- C34. No later than 4 weeks after the date notified for the commencement of construction, an Independent Audit Program prepared in accordance with the Independent Audit Post Approval Requirements (Department 2018) must be submitted to the Department and the Certifying Authority.
- C35. Table 1 of the Independent Audit Post Approval Requirements (Department 2018) is amended so that the frequency of audits required in the construction phase is:
- (a) an initial construction Independent Audit must be undertaken within 8 weeks of the notified commencement date of construction; and
  - (b) a subsequent Independent Audit of construction must be undertaken no later than 26 weeks from the date of the initial construction Independent Audit.

In all other respects Table 1 remains the same. The Planning Secretary may require the initial and subsequent Independent Audits to be undertaken at different times to those specified above, upon giving at least 4 weeks' notice to the applicant of the date upon which the audit must be commenced.

- C36. Independent Audits of the development must be carried out in accordance with:
- the Independent Audit Program submitted to the Department and the Certifying Authority under condition C34 of this consent; and
  - the requirements for an Independent Audit Methodology and Independent Audit Report in the Independent Audit Post Approval Requirements (Department 2018).
- C37. In accordance with the specific requirements in the Independent Audit Post Approval Requirements (Department 2018), the Applicant must:
- review and respond to each Independent Audit Report prepared under condition C36 of this consent;
  - submit the response to the Department and the Certifying Authority; and
  - make each Independent Audit Report and response to it publicly available within 60 days after submission to the Department and notify the Department and the Certifying Authority in writing at least seven days before this is done.
- C38. Notwithstanding the requirements of the Independent Audit Post Approval Requirements (Department 2018), the Planning Secretary may approve a request for ongoing annual operational audits to cease, where it has been demonstrated to the Planning Secretary's satisfaction that ongoing operational audits are no longer required.

#### **Incident Notification, Reporting and Response**

- C39. The Department must be notified in writing to [compliance@planning.nsw.gov.au](mailto:compliance@planning.nsw.gov.au) immediately after the Applicant becomes aware of an incident. The notification must identify the development (including the development application number and the name of the development if it has one), and set out the location and nature of the incident.

Subsequent notification must be given and reports submitted in accordance with the requirements set out in **Appendix 1**.

#### **Non-Compliance Notification**

- C40. The Department must be notified in writing to [compliance@planning.nsw.gov.au](mailto:compliance@planning.nsw.gov.au) within seven days after the Applicant becomes aware of any non-compliance. The Certifying Authority must also notify the Department in writing to [compliance@planning.nsw.gov.au](mailto:compliance@planning.nsw.gov.au) within seven days after they identify any non-compliance.

The notification must identify the development and the application number for it, set out the condition of consent that the development is non-compliant with, the way in which it does not comply and the reasons for the non-compliance (if known) and what actions have been, or will be, undertaken to address the non-compliance.

A non-compliance which has been notified as an incident does not need to also be notified as a non-compliance.

#### **Revision of Strategies, Plans and Programs**

- C41. Within three months of:
- the submission of a compliance report under condition B30;
  - the submission of an incident report under condition C39;
  - the submission of an Independent Audit under condition C36;
  - the issue of a direction of the Planning Secretary under condition A2 which requires a review,

the strategies, plans and programs required under this consent must be reviewed, and the Department and the Certifying Authority must be notified in writing that a review is being carried out.

C42. If necessary to either improve the environmental performance of the development, cater for a modification or comply with a direction, the strategies, plans and programs required under this consent must be revised, to the satisfaction of the Certifying Authority. Where revisions are required, the revised document must be submitted to the Certifying Authority for approval within six weeks of the review.

**Note:** *This is to ensure strategies, plans and programs are updated on a regular basis and to incorporate any recommended measures to improve the environmental performance of the development.*

## PART D PRIOR TO OCCUPATION OR COMMENCEMENT OF USE

### Notification of Occupation

- D1. The date of commencement of the occupation of the development must be notified to the Department in writing, at least one month before occupation. If the operation of the development is to be staged, the Department must be notified in writing at least one month before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

### External Walls and Cladding

- D2. Prior to the occupation of the building, the Applicant must provide the Certifying Authority with documented evidence that the products and systems used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the requirements of the BCA.
- D3. The Applicant must provide a copy of the documentation given to the Certifying Authority to the Planning Secretary within seven days after the Certifying Authority accepts it.

### Post-construction Dilapidation Report

- D4. Prior to occupation of the building, the Applicant must engage a suitably qualified person to prepare a post-construction dilapidation report at the completion of construction. This report is:
- a) to ascertain whether the construction created any structural damage to adjoining buildings or infrastructure.
  - b) to be submitted to the Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings or infrastructure, the Certifying Authority must:
    - i) compare the post-construction dilapidation report with the pre-construction dilapidation report required by these conditions; and
    - ii) have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.
  - c) to be forwarded to Council.

### Protection of Public Infrastructure

- D5. Unless the Applicant and the applicable authority agree otherwise, the Applicant must:
- (a) repair, or pay the full costs associated with repairing, any public infrastructure that is damaged by carrying out the development; and
  - (b) relocate, or pay the full costs associated with relocating any infrastructure that needs to be relocated as a result of the development.

### Landscaping

- D6. Prior to occupation of the building, the Applicant must undertake all landscape works detailed in the Landscape Management Plan required by condition B15B15 to the satisfaction of the Certifying Authority.

### Utilities and Services

- D7. Prior to occupation of the building, a compliance certificate under the section 307 of the *Water Management Act 2000* must be obtained from Council and submitted to the Certifying Authority.

### Green Travel Plan

- D8. Prior to the commencement of operation, a Green Travel Plan (GTP), must be prepared and be submitted to the Secretary to promote the use of active and sustainable transport modes. The plan must:
- (a) be prepared by a suitably qualified traffic consultant in consultation with TfNSW;
  - (b) include objectives and modes share targets (i.e. Site and land use specific, measurable and achievable and timeframes for implementation) to define the direction and purpose of the GTP;
  - (c) include specific tools and actions to help achieve the objectives and mode share targets;

- (d) include measures to promote and support the implementation of the plan, including financial and human resource requirements, roles and responsibilities for relevant employees involved in the implementation of the GTP; and
- (e) include details regarding the methodology and monitoring/review program to measure the effectiveness of the objectives and mode share targets of the GTP, including the frequency of monitoring and the requirement for travel surveys to identify travel behaviours of staff to and from the hospital campus.

### **Mechanical Ventilation**

- D9. Following completion, installation and testing of all mechanical ventilation systems, the Applicant must provide evidence to the satisfaction of the Certifying Authority, prior to the final occupation, that the installation and performance of the mechanical systems complies with:
- (a) the BCA;
  - (b) *AS 1668.2-2012 The use of air-conditioning in buildings – Mechanical ventilation in buildings* and other relevant codes;
  - (c) the development consent and any relevant modifications; and
  - (d) any dispensation granted by the NSW Fire Brigade.

### **Fire Safety Certification**

- D10. Prior to the final occupation, a Fire Safety Certificate must be obtained for all the Essential Fire or Other Safety Measures forming part of this consent. A copy of the Fire Safety Certificate must be submitted to the relevant authority and Council. The Fire Safety Certificate must be prominently displayed in the building.

### **Structural Inspection Certificate**

- D11. A Structural Inspection Certificate or a Compliance Certificate must be submitted to the satisfaction of the Certifying Authority prior to the occupation of the relevant parts of any new or refurbished buildings. A copy of the Certificate with an electronic set of final drawings (contact approval authority for specific electronic format) must be submitted to the approval authority and the Council after:
- (a) the site has been periodically inspected and the Certifying Authority is satisfied that the structural works is deemed to comply with the final design drawings; and
  - (b) the drawings listed on the Inspection Certificate have been checked with those listed on the final Design Certificate/s.
  - (c) person/s authorised to, for the life of the development.

### **Warm Water Systems and Cooling Systems**

- D12. The installation, operation and maintenance of warm water systems and water cooling systems (as defined under the *Public Health Act 2010*) must comply with the *Public Health Act 2010*, Public Health Regulation 2012 and Parts 1 and 2 (or Part 3 if a Performance-based water cooling system) of *AS/NZS 3666.2:2011 Air handling and water systems of buildings – Microbial control – Operation and maintenance* and the NSW Health Code of Practice for the Control of Legionnaires' Disease.

### **Signage**

- D13. Wayfinding signage and signage identifying the location of staff car parking must be installed prior to occupation.
- D14. Bicycle wayfinding signage must be installed within the site to direct cyclists from footpaths to designated bicycle parking areas prior to occupation.

### **Traffic Upgrade Works**

- D15. Prior to the commencement of operation, the following intersection works as required by condition B10 must be completed:
- (a) upgrade of the intersection of Edward Street and Murray Street to achieve a Level of Service C or better forecasting to the year 2031 designed and constructed in accordance

with the Austroads Guide to Road Design as amended by the supplements adopted by Roads and Maritime Services.

- (b) upgrade of the Murray Street and Brookong Avenue for traffic calming purposes to be designed and constructed in consultation Council.
- (c) phasing and lane reconfiguration works to the Edward Street and Docker Street intersection to be designed and constructed in consultation with RMS.

### **Art Strategy and Community Participation**

D16. Prior to the commencement of operation, the Applicant must finalise and implement the Art Strategy in consultation with local artists and the community to allow for local participation and integration.

### **Car Park Management Plan**

D17. Prior to commencement of operation, the Applicant must prepare a Car Park Management Plan (CPMP) for the hospital campus and submit it to the satisfaction of the Certifying Authority. The CPMP is to provide an overview for the efficient management of car parking across the campus, with a view to minimising the use of on-street parking by both staff and visitors to the hospital.

### **Operational Waste Management Plan**

D18. Prior to the commencement of operation, the Applicant must update the 'Wagga Wagga Hospital Waste Management Plan' to reflect the additional requirements of servicing the development. The updated plan is to be submitted to the satisfaction of the Certifying Authority. The updated plan must:

- (a) detail the type and quantity of waste to be generated during operation of the development;
- (b) describe the handling, storage and disposal of all waste streams generated on site, consistent with the *Protection of the Environment Operations Act 1997*, *Protection of the Environment Operations (Waste) Regulation 2014* and the *Waste Classification Guideline* (Department of Environment, Climate Change and Water, 2009);
- (c) detail the materials to be reused or recycled, either on or off site; and
- (d) include the Management and Mitigation Measures included in EIS.

### **Site Audit Report and Site Audit Statement**

D19. Prior to occupation of the building, the Applicant must obtain from an EPA accredited Site Auditor, a Site Audit Statement and a Site Audit Report which demonstrates that the site is suitable for its intended use(s).

## PART E POST OCCUPATION

### Operation of Plant and Equipment

- E1. All plant and equipment used on site, or to monitor the performance of the development must be:
- (a) maintained in a proper and efficient condition; and
  - (b) operated in a proper and efficient manner.

### Community Communication Strategy

- E2. The Community Communication Strategy, as approved by the Planning Secretary, must be implemented for a minimum of 12 months following the completion of construction.

### Operational Noise Limits

- E3. The Applicant must ensure that noise generated by operation of the development does not exceed the noise limits in the Noise Impact Assessment prepared as part of the EIS.
- E4. The Applicant must undertake short term noise monitoring in accordance with the *Noise Policy for Industry* where valid data is collected following the commencement of use of each stage of the development. The monitoring program must be carried out by an appropriately qualified person and a monitoring report must be submitted to the Planning Secretary within two months of commencement use of each stage of the development to verify that operational noise levels do not exceed the recommended noise levels for mechanical plant identified in the Noise Impact Assessment dated August 2018 and the **Acoustic Brief dated December 2019**. Should the noise monitoring program identify any exceedance of the recommended noise levels referred to above, the Applicant is required to implement appropriate noise attenuation measures so that operational noise levels do not exceed the recommended noise levels or provide attenuation measures at the affected noise sensitive receivers.

[SSD-9033-Mod-4 – 08/07/20]

### Work Place Travel Plan

- E5. The Work Place Travel Plan must be updated annually and implemented.

### Lighting

- E6. The Applicant must ensure the lighting associated with the development:
- (a) complies with the latest version of AS 4282-1997 - *Control of the obtrusive effects of outdoor lighting* (Standards Australia, 1997); and
  - (b) is mounted, screened and directed in such a manner that it does not create a nuisance to surrounding properties or the public road network.

### Fire Safety Certificate

- E7. The owner must submit to Council an Annual Fire Safety Statement, each 12 months after the final Safety Certificate is issued. The certificate must be on, or to the effect of, Council's Fire Safety Statement.

### Landscaping

- E8. The Applicant must maintain the landscaping and vegetation on the site for the duration of occupation of the development.

### Hazard Audit

- E9. Within twelve months after the commencement of operation and every three years thereafter, or at such intervals as the Planning Secretary may agree, the Applicant must carry out a comprehensive Hazard Audit of the development. The audits must:
- (a) be carried out at the Applicant's expense by a qualified person or team, who have been approved by the Planning Secretary and are independent of the development;
  - (b) be carried out in accordance with the Department's *Hazardous Industry Planning Advisory Paper No. 5, 'Hazard Audit Guidelines'*; and



- (c) include a review of the site Safety Management System and a review of all entries made in the incident register since the previous audit.

E10. Within one month of completing each audit carried out in accordance with condition C36, the Applicant must submit a report to the satisfaction of the Planning Secretary for information. The audit report must be accompanied by a program for the implementation of all recommendations made in the audit report. If the Applicant intends to defer the implementation of a recommendation, reasons must be documented.

#### **Hazards and Risk**

E11. The Applicant must store all chemicals, fuels and oils used on-site in accordance with:

- (a) the requirements of all relevant Australian Standards; and
- (b) the NSW EPA's *Storing and Handling of Liquids: Environmental Protection – Participants Manual* if the chemicals are liquids.

E12. In the event of an inconsistency between the requirements of condition E11(a) and E11(b), the most stringent requirement must prevail to the extent of the inconsistency.

#### **Dangerous Goods**

E13. The Applicant must ensure that the quantities of dangerous goods present within the development or transported to and from the development remain below the screening threshold quantities listed in Department's Hazardous and Offensive Development Guidelines Applying SEPP 33 (January 2011) at all times.

E14. The Applicant must store and handle all chemicals, fuels and oils in accordance with all relevant Australian Standards, including and not limited to *AS 1894: The storage and handling of non-flammable cryogenic and refrigerated liquids*.

## **APPENDIX 1 WRITTEN INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS**

### **Written Incident Notification Requirements**

1. A written incident notification addressing the requirements set out below must be emailed to the Department at the following address: [compliance@planning.nsw.gov.au](mailto:compliance@planning.nsw.gov.au) within seven days after the Applicant becomes aware of an incident. Notification is required to be given under this condition even if the Applicant fails to give the notification required under condition C39 or, having given such notification, subsequently forms the view that an incident has not occurred.
2. Written notification of an incident must:
  - a. identify the development and application number;
  - b. provide details of the incident (date, time, location, a brief description of what occurred and why it is classified as an incident);
  - c. identify how the incident was detected;
  - d. identify when the applicant became aware of the incident;
  - e. identify any actual or potential non-compliance with conditions of consent;
  - f. describe what immediate steps were taken in relation to the incident;
  - g. identify further action(s) that will be taken in relation to the incident; and
  - h. identify a project contact for further communication regarding the incident.
3. Within 30 days of the date on which the incident occurred or as otherwise agreed to by the Planning Secretary, the Applicant must provide the Planning Secretary and any relevant public authorities (as determined by the Planning Secretary) with a detailed report on the incident addressing all requirements below, and such further reports as may be requested.
4. The Incident Report must include:
  - a. a summary of the incident;
  - b. outcomes of an incident investigation, including identification of the cause of the incident;
  - c. details of the corrective and preventative actions that have been, or will be, implemented to address the incident and prevent recurrence; and
  - d. details of any communication with other stakeholders regarding the incident.