



WestConnex M4-M5 Link

Rozelle Interchange - Modification: The Crescent overpass and active transport links

Modification report

August 2019

NSW Roads and Maritime Services

WestConnex - M4-M5 Link

Rozelle Interchange – Modification: The Crescent overpass and active transport links

Modification report

August 2019

Prepared for

NSW Roads and Maritime Services

Prepared by

AECOM Australia

© NSW Roads and Maritime Services

The concepts and information contained in this document are the property of NSW Roads and Maritime Services. You must not reproduce any part of this document without the prior written approval of NSW Roads and Maritime Services.

Table of Contents

Glossary and terms of abbreviations	v
Executive summary	ix
1 Introduction.....	1-1
1.1 Purpose of this report.....	1-1
1.2 Overview of WestConnex	1-1
1.3 M4-M5 Link project.....	1-3
1.4 The proposed modification.....	1-6
1.5 Structure of this report	1-7
2 Assessment process	2-1
2.1 Approval framework	2-1
2.2 Environmental planning instruments.....	2-2
2.3 Other NSW legislation.....	2-3
2.4 Commonwealth legislation	2-3
3 Approved project	3-1
3.1 The Project.....	3-1
3.2 Stage 2 overview.....	3-1
3.3 Road network changes	3-8
3.4 Active and public transport.....	3-9
3.5 Landscape and urban design outcomes	3-9
3.6 Drainage infrastructure	3-10
4 Proposed modification.....	4-1
4.1 Project design development.....	4-1
4.2 Overview of the proposed modification.....	4-1
4.3 Design options considered.....	4-4
4.4 Detail of the proposed modification.....	4-12
4.5 Construction	4-24
4.6 Operation	4-26
4.7 Conditions of Approval.....	4-26
5 Consultation	5-1
5.1 Introduction	5-1
5.2 WestConnex communication and engagement channels and tools.....	5-1
5.3 M4-M5 Link project consultation	5-3
5.4 Consultation for the proposed modification	5-5
5.5 Future consultation for the proposed modification.....	5-9
6 Environmental assessment	6-1
6.1 Introduction	6-1
6.2 Environmental scoping.....	6-1
6.3 Traffic and transport.....	6-3
6.4 Noise and vibration	6-20
6.5 Air quality	6-39
6.6 Urban design and access	6-43
6.7 Landscape and visual amenity.....	6-46

6.8	Non-Aboriginal heritage	6-67
6.9	Surface water, flooding and drainage	6-73
6.10	Contamination and groundwater	6-76
6.11	Social and economic	6-77
6.12	Utilities	6-81
6.13	Cumulative impacts	6-81
7	Conditions of approval	7-1
7.1	Conditions to be amended or removed	7-1
8	Environmental management measures	8-1
9	Justification and conclusion	9-1
9.1	Need for the modification	9-1
9.2	Design options considered	9-1
9.3	Environmental assessment	9-2
9.4	Environmental management measures and Conditions of Approval	9-4
9.5	Community and stakeholder consultation	9-4
10	References	10-1

List of Figures

Figure 1-1	Overview of WestConnex and related projects	1-2
Figure 1-2	Overview of the M4-M5 Link approved project	1-5
Figure 3-1	Overview of the approved project	3-2
Figure 3-2	Overview of the approved project during construction	3-6
Figure 3-3	Approved project during construction – The Crescent civil site (C6) and minor construction ancillary facility (C6a)	3-7
Figure 4-1	Overview of proposed modification	4-3
Figure 4-2	Pedestrian and cyclist infrastructure options	4-8
Figure 4-3	The Crescent, Johnston Street and Chapman Road intersection options	4-10
Figure 4-4	Elevation: Indicative view of The Crescent overpass	4-13
Figure 4-5	Proposed The Crescent/Johnston Street/Chapman Road intersection	4-17
Figure 4-6	Elevation: Indicative view of Rozelle Rail Yards Pedestrian and Cycling Green Link	4-19
Figure 4-7	Elevation: Indicative view of the shared user path bridge	4-19
Figure 4-8	Proposed modification during construction – The Crescent civil site (C6) and construction ancillary facility (C6a)	4-21
Figure 4-9	Approach to Anzac Bridge layout in EIS and proposed modification	4-23
Figure 5-1	Overview of the project consultation process	5-4
Figure 6-1	VISSM Traffic model coverage	6-5
Figure 6-2	Existing and proposed connectivity around the Rozelle Rail Yards and Bicentennial Park	6-19
Figure 6-3	Noise catchment areas and sensitive receivers	6-24
Figure 6-4	Updated CoA 87 treatment zone and out of hours works (roadworks) impacts	6-34
Figure 6-5	Representative view locations	6-50
Figure 6-6	Non-Aboriginal heritage items	6-71

List of Tables

Table 3-1	Indicative construction program for Stage 2 works and C6 site	3-3
Table 4-1	The Crescent/City West Link intersection options	4-5
Table 4-2	Pedestrian and cyclist infrastructure options	4-6
Table 4-3	The Crescent/Johnston Street/Chapman Road intersection options.....	4-9
Table 4-4	Indicative construction activities.....	4-24
Table 4-5	Indicative program of works – proposed modification.....	4-26
Table 5-1	Consultation channels and tools	5-1
Table 5-2	Community notification summary for the proposed modification to date	5-5
Table 5-3	WestConnex Community Reference Group engagement summary for the proposed modification to date	5-6
Table 5-4	Stakeholder engagement summary for the proposed modification to date	5-7
Table 6-1	Scoping assessment.....	6-1
Table 6-2	Average weekday travel mode share for Inner West LGA.....	6-4
Table 6-3	Rozelle Interchange network performance – 2015 AM and PM peak hour	6-7
Table 6-4	Existing LoS at key intersections	6-7
Table 6-5	Rozelle Interchange network performance – AM peak hour (2023 ‘with project’ EIS vs ‘with project’ modification scenario)	6-10
Table 6-6	Rozelle Interchange network performance – AM peak hour (2023 ‘cumulative’ EIS vs ‘cumulative’ modification scenario)	6-11
Table 6-7	Rozelle Interchange network performance – AM peak hour (2033 ‘with project’ EIS vs ‘with project’ modification scenario)	6-11
Table 6-8	Rozelle Interchange network performance – AM peak hour (2033 ‘cumulative’ EIS vs ‘cumulative’ modification scenario)	6-12
Table 6-9	Rozelle Interchange network performance – PM peak hour (2023 ‘with project’ EIS vs ‘with project’ modification scenario)	6-13
Table 6-10	Rozelle Interchange network performance – PM peak hour (2023 ‘cumulative’ EIS vs ‘cumulative’ modification scenario)	6-13
Table 6-11	Rozelle Interchange network performance – PM peak hour (2033 ‘with project’ EIS vs ‘with project’ modification scenario)	6-14
Table 6-12	Rozelle Interchange network performance – PM peak hour (2033 ‘cumulative’ EIS vs ‘cumulative’ modification scenario)	6-14
Table 6-13	Rozelle Interchange: key intersection performance (LoS) – Peak hour	6-16
Table 6-14	Noise catchment areas and surrounding land uses.....	6-22
Table 6-15	Summary of unattended noise logging results.....	6-25
Table 6-16	NML exceedance bands and corresponding subjective response to impacts.....	6-26
Table 6-17	NMLs for sensitive receivers.....	6-27
Table 6-18	Predicted worst case noise levels.....	6-28
Table 6-19	Overview of NML exceedances	6-32
Table 6-20	Construction vibration assessment summary	6-35
Table 6-21	Comparison of EIS triggers with the proposed modification.....	6-37
Table 6-22	Characteristics of assumed background concentrations (2015).....	6-41
Table 6-23	Total traffic emissions near the proposed modification.....	6-42
Table 6-24	Absolute changes in total traffic emissions near the proposed modification	6-42
Table 6-25	Sensitivity of views	6-48
Table 6-26	Landscape character impact summary	6-51
Table 6-27	Summary of potential impacts on visual amenity during construction	6-53
Table 6-28	Summary of potential impacts on visual amenity during operation	6-56

Table 6-29	Identified heritage items relevant to the proposed modification	6-68
Table 7-1	Conditions of approval to be amended or removed.....	7-2
Table 8-1	Environmental management measures to be amended by proposed modification...	8-2

Appendices

Appendix A	Environmental assessment requirements
Appendix B	Traffic and transport assessment
Appendix C	Noise and vibration assessment
Appendix D	Air quality assessment