

PCT TARGET SPECIES LIST (Species listed for active rehabilitation)

Note: Primary species have been selected due to their ease of propagation, size and function in an ecological community, dominance in a PCT, growth rate and provision of ecological services (colonising species, nitrogen/phosphorus fixing, shade, litter and microniches).

Secondary species will still be used in each PCT and will be used to augment biodiversity and strata layers. Secondary species commonly require some level of ecological function, such as shade or microbes that need to grow symbiotically with colonising species.

\*Denotes seed in stock – September 2023.

| PCT 285                                              | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Bulbine bulbosa</i>                               | 0.08       |              |                             | *p                                           |
| <i>Dianella longifolia</i>                           |            | 125          |                             | *p                                           |
| <i>Dianella revoluta</i>                             |            | 625          |                             | *p                                           |
| <i>Dianella revoluta</i> var. <i>revoluta</i>        |            | 125          |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                          | 0.02       |              |                             | *s                                           |
| <i>Ranunculus lappaceus</i>                          | 0.03       |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                        | 0.02       |              |                             | s                                            |
| <i>Stylidium graminifolium</i>                       | 0.02       |              |                             | *s                                           |
| <i>Juncus australis</i>                              |            | 1250         |                             | *s                                           |
| <i>Juncus filicaulis</i>                             |            | 375          |                             | *s                                           |
| <i>Lomandra filiformis</i>                           | 0.06       |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                           | 0.07       |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i>  | 0.01       |              |                             | *s                                           |
| <i>Luzula densiflora</i>                             |            | 250          |                             | s                                            |
| <i>Luzula modesta</i>                                |            | 1250         |                             | s                                            |
| <i>Carex appressa</i>                                | 0.02       |              |                             | *p                                           |
| <i>Carex breviculmis</i>                             | 0.42       |              |                             | *p                                           |
| <i>Carex gaudichaudiana</i>                          |            | 275          |                             | s - C                                        |
| <i>Carex inomitata</i>                               | 0.02       |              |                             | s                                            |
| <i>Carex inversa</i>                                 | 0.02       |              |                             | s                                            |
| <i>Anthosachne scabra</i>                            | 0.08       |              |                             | *p                                           |
| <i>Dichelachne micrantha</i>                         | 1.2        |              |                             | s                                            |
| <i>Microlaena stipoides</i>                          | 0.53       |              |                             | *p                                           |
| <i>Poa clivicola</i>                                 | 0.33       |              |                             | *p                                           |
| <i>Poa helmsii</i>                                   | 0.03       |              |                             | *p                                           |
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.02       |              |                             | s                                            |
| <i>Poa sieberiana</i>                                | 0.02       |              |                             | *p                                           |
| <i>Rytidosperma caespitosum</i>                      | 0.83       |              |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                           |              |              |  |       |
|-------------------------------------------|--------------|--------------|--|-------|
| <i>Rytidosperma penicillatum</i>          | 0.08         |              |  | *s    |
| <i>Rytidosperma pilosum</i>               | 0.66         |              |  | *s    |
| <i>Themeda triandra</i>                   | 2            |              |  | *p    |
| <b>Total</b>                              | <b>6.49</b>  |              |  |       |
|                                           |              |              |  |       |
| <b>Shrubs</b>                             |              |              |  |       |
| <i>Brachyloma daphnoides</i>              |              | 100          |  | s - C |
| <i>Epacris breviflora</i>                 |              | 55           |  | s - C |
| <i>Acacia pravissima</i>                  |              | 160          |  | *p    |
| <i>Acacia rubida</i>                      |              | 215          |  | *p    |
| <i>Banksia canei</i>                      |              | 50           |  | *p    |
| <i>Bursaria spinosa</i>                   |              | 50           |  | *p    |
| <i>Cassinia aculeata</i>                  |              | 55           |  | *p    |
| <i>Cassinia arcuata</i>                   |              | 200          |  | s     |
| <i>Cassinia longifolia</i>                |              | 50           |  | *p    |
| <i>Leptospermum myrtifolium</i>           |              | 275          |  | *p    |
| <i>Leptospermum obovatum</i>              |              | 50           |  | s     |
| <i>Mirbelia oxylobioides</i>              |              | 30           |  | *p    |
| <i>Pimelea linifolia</i>                  |              | 275          |  | s - C |
| <i>Rubus parvifolius</i>                  |              | 40           |  | s – C |
|                                           |              |              |  |       |
| <b>Trees</b>                              |              |              |  |       |
| <i>Acacia dealbata</i>                    |              | 250          |  | *p    |
| <i>Acacia dealbata subsp. subalpina</i>   |              | 50           |  | s     |
| <i>Acacia melanoxylon</i>                 |              | 125          |  | *p    |
| <i>Eucalyptus camphora</i>                |              | 400          |  | p     |
| <i>Eucalyptus camphora subsp. humeana</i> |              | 750          |  | s     |
| <i>Eucalyptus dives</i>                   |              | 170          |  | *p    |
| <i>Eucalyptus mannifera</i>               |              | 300          |  | *p    |
| <i>Eucalyptus rubida</i>                  |              | 125          |  | p     |
| <i>Eucalyptus viminalis</i>               |              | 10           |  | *p    |
|                                           | <b>Total</b> | <b>8,060</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 296                                             | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                          |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Chrysocephalum semipapposum</i>                  | 0.01         |              |                             | p                                            |
| <i>Plantago gaudichaudii</i>                        | 0.005        |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                       | 0.01         |              |                             | s                                            |
| <i>Stellaria pungens</i>                            |              | 4725         |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                      | 0.03         |              |                             | *s                                           |
| <i>Xerochrysum bracteatum</i>                       | 0.005        |              |                             | s                                            |
| <i>Juncus usitatus</i>                              |              | 150          |                             | *s                                           |
| <i>Lomandra filiformis</i>                          | 0.025        |              |                             | *p                                           |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>   | 0.155        |              |                             | s                                            |
| <i>Lomandra filiformis</i> subsp. <i>filiformis</i> | 0.02         |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                          | 0.015        |              |                             | *p                                           |
| <i>Carex appressa</i>                               | 0.055        |              |                             | *p                                           |
| <i>Anthosachne scabra</i>                           | 0.415        |              |                             | *p                                           |
| <i>Microlaena stipoides</i>                         | 1.85         |              |                             | *p                                           |
| <i>Poa sieberiana</i>                               | 0.05         |              |                             | *p                                           |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>       | 0.015        |              |                             | s                                            |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>        | 0.01         |              |                             | s                                            |
| <i>Rytidosperma caespitosum</i>                     | 0.05         |              |                             | *p                                           |
| <i>Rytidosperma erianthum</i>                       | 0.31         |              |                             | s                                            |
| <i>Rytidosperma pallidum</i>                        | 0.005        |              |                             | *s                                           |
| <i>Rytidosperma penicillatum</i>                    | 0.05         |              |                             | *s                                           |
| <i>Themeda triandra</i>                             | 0.2          |              |                             | *p                                           |
| <b>Total</b>                                        | <b>3.285</b> |              |                             |                                              |
|                                                     |              |              |                             |                                              |
| <b>Shrubs</b>                                       |              |              |                             |                                              |
| <i>Platylobium formosum</i>                         |              | 100          |                             | p                                            |
| <i>Brachyloma daphnoides</i>                        |              | 27.5         |                             | s - C                                        |
| <i>Epacris celata</i>                               |              | 25           |                             | s - C                                        |
| <i>Monotoca scoparia</i>                            |              | 10           |                             | s - C                                        |
| <i>Acacia dealbata</i>                              |              | 5            |                             | *p                                           |
| <i>Acacia gunnii</i>                                |              | 5            |                             | p                                            |
| <i>Acacia obliquinervia</i>                         |              | 50           |                             | *p                                           |
| <i>Acacia pravissima</i>                            |              | 70           |                             | *p                                           |
| <i>Acacia saliciformis</i>                          |              | 10           |                             | p                                            |
| <i>Acacia siculiformis</i>                          |              | 7.5          |                             | p                                            |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                        |              |              |  |       |
|----------------------------------------|--------------|--------------|--|-------|
| <i>Baekkea utilis</i>                  |              | 5            |  | s - C |
| <i>Banksia canei</i>                   |              | 40           |  | *p    |
| <i>Bursaria spinosa subsp. spinosa</i> |              | 25           |  | s     |
| <i>Cassinia aculeata</i>               |              | 2.5          |  | *p    |
| <i>Cassinia longifolia</i>             |              | 30           |  | *p    |
| <i>Daviesia latifolia</i>              |              | 7.5          |  | *p    |
| <i>Daviesia leptophylla</i>            |              | 12.5         |  | s     |
| <i>Daviesia ulicifolia</i>             |              | 25           |  | *p    |
| <i>Dillwynia phyllicoides</i>          |              | 50           |  | s     |
| <i>Hardenbergia violacea</i>           |              | 50           |  | *p    |
| <i>Indigofera australis</i>            |              | 10           |  | *p    |
| <i>Leptospermum brevipes</i>           |              | 10           |  | *p    |
| <i>Leptospermum continentale</i>       |              | 100          |  | *p    |
| <i>Mirbelia oxylobioides</i>           |              | 20           |  | *p    |
| <i>Pimelea linifolia</i>               |              | 25           |  | s - C |
| <i>Rubus parvifolius</i>               |              | 125          |  | s - C |
|                                        |              |              |  |       |
| <b>Trees</b>                           |              |              |  |       |
| <i>Acacia dealbata</i>                 |              | 375          |  | *p    |
| <i>Acacia melanoxylon</i>              |              | 50           |  | *p    |
| <i>Eucalyptus camphora</i>             |              | 50           |  | p     |
| <i>Eucalyptus dives</i>                |              | 500          |  | *p    |
| <i>Eucalyptus macrorhyncha</i>         |              | 50           |  | *p    |
| <i>Eucalyptus mannifera</i>            |              | 600          |  | *p    |
| <i>Eucalyptus robertsonii</i>          |              | 150          |  | p     |
| <i>Eucalyptus rubida</i>               |              | 750          |  | p     |
|                                        | <b>Total</b> | <b>8,235</b> |  |       |

| PCT 299                                             | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                          |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Chrysocephalum semipapposum</i>                  | 0.01       |              |                             | p                                            |
| <i>Stellaria pungens</i>                            |            | 1250         |                             | p - C                                        |
| <i>Lomandra longifolia</i>                          | 0.035      |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i> | 0.005      |              |                             | s                                            |
| <i>Anthosachne scabra</i>                           | 3          |              |                             | *p                                           |
| <i>Poa sieberiana</i>                               | 1          |              |                             | *p                                           |
| <i>Rytidosperma penicillatum</i>                    | 0.55       |              |                             | *s                                           |
| <i>Themeda triandra</i>                             | 0.01       |              |                             | *p                                           |
| <b>Total</b>                                        | <b>4.6</b> |              |                             |                                              |
|                                                     |            |              |                             |                                              |
| <b>Shrubs</b>                                       |            |              |                             |                                              |
| <i>Brachyloma daphnoides</i>                        |            | 150          |                             | s - C                                        |
| <i>Monotoca scoparia</i>                            |            | 100          |                             | s - C                                        |
| <i>Acacia obliquinervia</i>                         |            | 100          |                             | *p                                           |
| <i>Acacia pravissima</i>                            |            | 600          |                             | *p                                           |
| <i>Acacia siculiformis</i>                          |            | 50           |                             | p                                            |
| <i>Bursaria spinosa</i>                             |            | 275          |                             | *p                                           |
| <i>Cassinia aculeata</i>                            |            | 50           |                             | *p                                           |
| <i>Cassinia longifolia</i>                          |            | 150          |                             | *p                                           |
| <i>Daviesia leptophylla</i>                         |            | 25           |                             | s                                            |
| <i>Grevillea arenaria</i>                           |            | 100          |                             | p - C                                        |
| <i>Indigofera australis</i>                         |            | 75           |                             | *p                                           |
| <i>Mirbelia oxylobioides</i>                        |            | 75           |                             | *p                                           |
| <i>Olearia myrsinoides</i>                          |            | 225          |                             | s                                            |
| <i>Platylobium formosum</i>                         |            | 175          |                             | s                                            |
| <i>Rubus parvifolius</i>                            |            | 100          |                             | s – C                                        |
|                                                     |            |              |                             |                                              |
| <b>Trees</b>                                        |            |              |                             |                                              |
| <i>Acacia dealbata</i>                              |            | 475          |                             | *p                                           |
| <i>Acacia melanoxylon</i>                           |            | 185          |                             | *p                                           |
| <i>Eucalyptus dives</i>                             |            | 250          |                             | *p                                           |
| <i>Eucalyptus macrorhyncha</i>                      |            | 425          |                             | *p                                           |
| <i>Eucalyptus nortonii</i>                          |            | 50           |                             | p                                            |
| <i>Eucalyptus robertsonii</i>                       |            | 625          |                             | p                                            |
| <i>Eucalyptus rubida</i>                            |            | 475          |                             | p                                            |
| <i>Eucalyptus viminalis</i>                         |            | 625          |                             | *p                                           |
| <b>Total</b>                                        |            | <b>6,610</b> |                             |                                              |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 300                                             | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                          |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>                     | 0.04       |              |                             | *s                                           |
| <i>Brachyscome decipiens</i>                        | 0.06       |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                       | 0.02       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                              | 0.02       |              |                             | *p                                           |
| <i>Chrysocephalum semipapposum</i>                  | 0.06       |              |                             | p                                            |
| <i>Craspedia jamesii</i>                            | 0.12       |              |                             | s                                            |
| <i>Dianella longifolia</i>                          |            | 25           |                             | *p                                           |
| <i>Erigeron conyzoides</i>                          | 0.02       |              |                             | s                                            |
| <i>Picris angustifolia</i>                          | 0.58       |              |                             | s                                            |
| <i>Plantago gaudichaudii</i>                        | 0.02       |              |                             | s                                            |
| <i>Plantago varia</i>                               | 0.1        |              |                             | s                                            |
| <i>Podolepis jaceoides</i>                          | 0.32       |              |                             | *p                                           |
| <i>Ranunculus collinus</i>                          | 0.04       |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                         | 0.3        |              |                             | s                                            |
| <i>Senecio gunnii</i>                               | 0          |              |                             | p                                            |
| <i>Senecio prenanthoides</i>                        | 0.18       |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                       | 0.02       |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                         | 0.02       |              |                             | s                                            |
| <i>Stellaria pungens</i>                            |            | 375          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                      | 0.02       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                          | 0.1        |              |                             | *s                                           |
| <i>Lomandra bracteata</i>                           | 0.04       |              |                             | p                                            |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>   | 0.06       |              |                             | s                                            |
| <i>Lomandra filiformis</i>                          | 0.04       |              |                             | p                                            |
| <i>Lomandra filiformis</i> subsp. <i>filiformis</i> | 0.12       |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                          | 0.1        |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i> | 0.02       |              |                             | s                                            |
| <i>Luzula densiflora</i>                            |            | 25           |                             | s                                            |
| <i>Luzula flaccida</i>                              |            | 25           |                             | s                                            |
| <i>Carex appressa</i>                               | 0.02       |              |                             | *p                                           |
| <i>Carex breviculmis</i>                            | 0.04       |              |                             | *p                                           |
| <i>Carex incomitata</i>                             | 0          |              |                             | s                                            |
| <i>Anthosachne scabra</i>                           | 0.26       |              |                             | *p                                           |
| <i>Austrostipa scabra</i>                           | 0.06       |              |                             | *p                                           |
| <i>Dichelachne micrantha</i>                        | 0.3        |              |                             | s                                            |
| <i>Microlaena stipoides</i>                         | 0.42       |              |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                              |              |     |  |       |
|--------------------------------------------------------------|--------------|-----|--|-------|
| <i>Microlaena stipoides</i> var. <i>stipoides</i>            | 0.6          |     |  | p     |
| <i>Poa helmsii</i>                                           | 0.04         |     |  | *p    |
| <i>Poa labillardierei</i> var. <i>labillardierei</i>         | 0.62         |     |  | p     |
| <i>Poa phillipsiana</i>                                      | 0.04         |     |  | *p    |
| <i>Poa sieberiana</i>                                        | 0.98         |     |  | *p    |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>                | 3.46         |     |  | s     |
| <i>Poa sieberiana</i> var. <i>hirtella</i>                   | 0.18         |     |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>                 | 1.9          |     |  | s     |
| <i>Rytidosperma caespitosum</i>                              | 0.24         |     |  | p     |
| <i>Rytidosperma erianthum</i>                                | 1.22         |     |  | s     |
| <i>Rytidosperma pallidum</i>                                 | 1.16         |     |  | *s    |
| <i>Rytidosperma penicillatum</i>                             | 0.26         |     |  | *s    |
| <i>Rytidosperma pilosum</i>                                  | 0.86         |     |  | *s    |
| <i>Themeda triandra</i>                                      | 0.16         |     |  | *p    |
| <b>Total</b>                                                 | <b>15.24</b> |     |  |       |
|                                                              |              |     |  |       |
| <b>Shrubs</b>                                                |              |     |  |       |
| <i>Brachyloma daphnoides</i>                                 |              | 2.5 |  | s - C |
| <i>Epacris celata</i>                                        |              | 205 |  | s - C |
| <i>Monotoca scoparia</i>                                     |              | 5   |  | s - C |
| <i>Acacia floribunda</i>                                     |              | 10  |  | p     |
| <i>Acacia melanoxylon</i>                                    |              | 5   |  | *p    |
| <i>Acacia obliquinervia</i>                                  |              | 5   |  | *p    |
| <i>Acacia pravissima</i>                                     |              | 35  |  | *p    |
| <i>Banksia canei</i>                                         |              | 10  |  | *p    |
| <i>Bursaria spinosa</i>                                      |              | 25  |  | *p    |
| <i>Cassinia aculeata</i>                                     |              | 10  |  | *p    |
| <i>Cassinia arcuata</i>                                      |              | 5   |  | s     |
| <i>Cassinia longifolia</i>                                   |              | 25  |  | *p    |
| <i>Clematis aristata</i>                                     |              | 5   |  | s     |
| <i>Coprosma quadrifida</i>                                   |              | 25  |  | s - C |
| <i>Daviesia latifolia</i>                                    |              | 80  |  | *p    |
| <i>Daviesia mimosoides</i>                                   |              | 75  |  | *p    |
| <i>Grevillea arenaria</i> subsp. <i>canescens</i>            |              | 5   |  | p - C |
| <i>Grevillea rosmarinifolia</i>                              |              | 20  |  | p - C |
| <i>Grevillea rosmarinifolia</i> subsp. <i>rosmarinifolia</i> |              | 5   |  | s - C |
| <i>Indigofera australis</i>                                  |              | 50  |  | *p    |
| <i>Leptospermum brevipes</i>                                 |              | 10  |  | *p    |
| <i>Lomatia myricoides</i>                                    |              | 5   |  | s     |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                              |              |              |  |       |
|--------------------------------------------------------------|--------------|--------------|--|-------|
| <i>Mirbelia oxylobioides</i>                                 |              | 25           |  | *p    |
| <i>Olearia myrsinoides</i>                                   |              | 75           |  | s     |
| <i>Olearia phlogopappa</i>                                   |              | 25           |  | s     |
| <i>Olearia phlogopappa</i> var.<br><i>flavescens</i>         |              | 25           |  | s     |
| <i>Ozothamnus thyrsoideus</i>                                |              | 25           |  | *s    |
| <i>Pimelea linifolia</i>                                     |              | 25           |  | s - C |
| <i>Platylobium formosum</i>                                  |              | 20           |  | p     |
| <i>Polyscias sambucifolia</i>                                |              | 50           |  | s - C |
| <i>Rubus parvifolius</i>                                     |              | 50           |  | s - C |
|                                                              |              |              |  |       |
| <b>Trees</b>                                                 |              |              |  |       |
| <i>Acacia dealbata</i>                                       |              | 800          |  | *p    |
| <i>Acacia dealbata</i> subsp. <i>dealbata</i>                |              | 1500         |  | s     |
| <i>Acacia melanoxylon</i>                                    |              | 300          |  | *p    |
| <i>Eucalyptus dalrympleana</i>                               |              | 200          |  | *p    |
| <i>Eucalyptus delegatensis</i> subsp.<br><i>Delegatensis</i> |              | 75           |  | *p    |
| <i>Eucalyptus dives</i>                                      |              | 200          |  | *p    |
| <i>Eucalyptus mannifera</i>                                  |              | 75           |  | *p    |
| <i>Eucalyptus mannifera</i> subsp.<br><i>mannifera</i>       |              | 75           |  | s     |
| <i>Eucalyptus pauciflora</i>                                 |              | 250          |  | *p    |
| <i>Eucalyptus radiata</i>                                    |              | 75           |  | *p    |
| <i>Eucalyptus robertsonii</i>                                |              | 600          |  | p     |
| <i>Eucalyptus robertsonii</i> subsp.<br><i>robertsonii</i>   |              | 300          |  | s     |
| <i>Eucalyptus rubida</i>                                     |              | 175          |  | p     |
| <i>Eucalyptus rubida</i> x <i>viminalis</i>                  |              | 375          |  | s     |
| <i>Eucalyptus viminalis</i>                                  |              | 225          |  | *p    |
|                                                              | <b>Total</b> | <b>6,620</b> |  |       |



## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 302                                              | kgs per ha  | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|-------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |             |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Bulbine bulbosa</i>                               | 0.01        |              |                             | *p                                           |
| <i>Chrysocephalum semipapposum</i>                   | 0.08        |              |                             | p                                            |
| <i>Dianella revoluta</i> var. <i>revoluta</i>        |             |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                        | 0.03        |              |                             | s                                            |
| <i>Stellaria pungens</i>                             |             | 150          |                             | p - C                                        |
| <i>Juncus sarophorus</i>                             |             |              |                             | *s                                           |
| <i>Lomandra filiformis</i>                           | 0.03        |              |                             | *p                                           |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>    | 0.02        |              |                             | s                                            |
| <i>Lomandra longifolia</i>                           | 0.02        |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i>  | 0.01        |              |                             | s                                            |
| <i>Luzula flaccida</i>                               |             |              |                             | s                                            |
| <i>Carex appressa</i>                                | 0.03        |              |                             | *p                                           |
| <i>Carex breviculmis</i>                             | 0.06        |              |                             | *p                                           |
| <i>Carex inomitata</i>                               | 0.13        |              |                             | s                                            |
| <i>Carex inversa</i>                                 | 0.62        |              |                             | s                                            |
| <i>Anthosachne scabra</i>                            | 0.4         |              |                             | *p                                           |
| <i>Austrostipa scabra</i>                            | 0.07        |              |                             | *p                                           |
| <i>Microlaena stipoides</i>                          | 0.07        |              |                             | *p                                           |
| <i>Microlaena stipoides</i> var. <i>stipoides</i>    | 0.29        |              |                             | s                                            |
| <i>Poa helmsii</i>                                   | 0.32        |              |                             | *p                                           |
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.1         |              |                             | p                                            |
| <i>Poa sieberiana</i>                                | 0.03        |              |                             | *p                                           |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>        | 0.66        |              |                             | s                                            |
| <i>Poa sieberiana</i> var. <i>hirtella</i>           | 0.77        |              |                             | s                                            |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>         | 0.1         |              |                             | s                                            |
| <i>Rytidosperma laeve</i>                            | 0.33        |              |                             | s                                            |
| <i>Rytidosperma penicillatum</i>                     | 0.23        |              |                             | *s                                           |
| <i>Rytidosperma pilosum</i>                          | 0.16        |              |                             | *s                                           |
| <i>Themeda triandra</i>                              | 1           |              |                             | *p                                           |
| <b>Total</b>                                         | <b>6.03</b> |              |                             |                                              |
|                                                      |             |              |                             |                                              |
| <b>Shrubs</b>                                        |             |              |                             |                                              |
| <i>Platylobium formosum</i>                          |             | 50           |                             | p                                            |
| <i>Brachyloma daphnoides</i>                         |             | 50           |                             | s - C                                        |
| <i>Monotoca scoparia</i>                             |             | 25           |                             | s - C                                        |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                                 |              |              |  |       |
|-----------------------------------------------------------------|--------------|--------------|--|-------|
| <i>Acacia obliquinervia</i>                                     |              | 375          |  | *p    |
| <i>Acacia pravissima</i>                                        |              | 1250         |  | *p    |
| <i>Acacia siculiformis</i>                                      |              | 225          |  | p     |
| <i>Banksia canei</i>                                            |              | 100          |  | *p    |
| <i>Banksia spinulosa</i> var. <i>collina</i>                    |              | 25           |  | s     |
| <i>Bursaria spinosa</i>                                         |              | 175          |  | *p    |
| <i>Cassinia aculeata</i>                                        |              | 250          |  | *p    |
| <i>Cassinia aculeata</i> subsp. <i>aculeata</i>                 |              | 125          |  | s     |
| <i>Cassinia longifolia</i>                                      |              | 350          |  | *p    |
| <i>Grevillea arenaria</i> subsp. <i>canescens</i>               |              | 175          |  | p - C |
| <i>Grevillea rosmarinifolia</i>                                 |              | 275          |  | p - C |
| <i>Grevillea rosmarinifolia</i> subsp. <i>rosmarinifolia</i>    |              | 325          |  | s - C |
| <i>Indigofera australis</i>                                     |              | 100          |  | *p    |
| <i>Leptospermum grandifolium</i>                                |              | 25           |  | *p    |
| <i>Leptospermum polygalifolium</i> subsp. <i>polygalifolium</i> |              | 250          |  | *p    |
| <i>Lomatia myricoides</i>                                       |              | 50           |  | s - C |
| <i>Mirbelia oxylobioides</i>                                    |              | 200          |  | *p    |
| <i>Olearia myrsinoides</i>                                      |              | 75           |  | s     |
| <i>Olearia phlogopappa</i>                                      |              | 75           |  | s     |
| <i>Prostanthera lasianthos</i>                                  |              | 75           |  | *s    |
| <i>Rubus parvifolius</i>                                        |              | 250          |  | s - C |
| <b>Trees</b>                                                    |              |              |  |       |
| <i>Acacia dealbata</i>                                          |              | 75           |  | *p    |
| <i>Acacia dealbata</i> subsp. <i>subalpina</i>                  |              | 50           |  | s     |
| <i>Acacia melanoxylon</i>                                       |              | 125          |  | *p    |
| <i>Eucalyptus camphora</i>                                      |              | 150          |  | p     |
| <i>Eucalyptus camphora</i> subsp. <i>humeana</i>                |              | 100          |  | s     |
| <i>Eucalyptus dives</i>                                         |              | 75           |  | *p    |
| <i>Eucalyptus macrorhyncha</i>                                  |              | 225          |  | *p    |
| <i>Eucalyptus mannifera</i>                                     |              | 375          |  | *p    |
| <i>Eucalyptus nortonii</i>                                      |              | 50           |  | p     |
| <i>Eucalyptus robertsonii</i>                                   |              | 150          |  | p     |
| <i>Eucalyptus robertsonii</i> subsp. <i>robertsonii</i>         |              | 50           |  | p     |
| <i>Eucalyptus rubida</i>                                        |              | 50           |  | p     |
| <i>Eucalyptus stellulata</i>                                    |              | 225          |  | *p    |
| <i>Eucalyptus viminalis</i>                                     |              | 250          |  | *p    |
|                                                                 | <b>Total</b> | <b>9,500</b> |  |       |

| PCT 303                                              | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Brachyscome aculeata</i>                          | 0.1        |              |                             | s                                            |
| <i>Brachyscome decipiens</i>                         | 0.05       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                               | 0.15       |              |                             | *p                                           |
| <i>Chrysocephalum semipapposum</i>                   | 0.15       |              |                             | p                                            |
| <i>Coronidium monticola</i>                          | 3.05       |              |                             | s                                            |
| <i>Coronidium scorpioides</i>                        | 0.05       |              |                             | s                                            |
| <i>Craspedia canens</i>                              | 0.45       |              |                             | s                                            |
| <i>Craspedia coolaminica</i>                         | 0.4        |              |                             | *s                                           |
| <i>Craspedia costiniana</i>                          | 0.1        |              |                             | s                                            |
| <i>Craspedia jamesii</i>                             | 0.05       |              |                             | s                                            |
| <i>Leptorhynchus squamatus</i> subsp. <i>Alpinus</i> | 0.2        |              |                             | s                                            |
| <i>Microseris lanceolata</i>                         | 0.25       |              |                             | *p                                           |
| <i>Oreomyrrhis argentea</i>                          | 0.05       |              |                             | s                                            |
| <i>Oreomyrrhis ciliata</i>                           | 0.15       |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                          | 0.25       |              |                             | *s                                           |
| <i>Plantago antarctica</i>                           | 0.05       |              |                             | s                                            |
| <i>Plantago euryphylla</i>                           | 0.05       |              |                             | s                                            |
| <i>Podolepis hieracioides</i>                        | 0.05       |              |                             | s                                            |
| <i>Podolepis jaceoides</i>                           | 0.5        |              |                             | *p                                           |
| <i>Podolepis laciniata</i>                           | 0.05       |              |                             | s                                            |
| <i>Podolepis robusta</i>                             | 0.05       |              |                             | *s                                           |
| <i>Ranunculus lappaceus</i>                          | 0.05       |              |                             | s                                            |
| <i>Ranunculus pimpinellifolius</i>                   | 0.1        |              |                             | s                                            |
| <i>Rhodanthe anthemoides</i>                         | 0.05       |              |                             | p                                            |
| <i>Scleranthus biflorus</i>                          |            | 625          |                             | s - C                                        |
| <i>Senecio gunnii</i>                                | 0.05       |              |                             | p                                            |
| <i>Senecio lageniformis</i>                          | 0.2        |              |                             | s                                            |
| <i>Senecio longipilus</i>                            | 0.1        |              |                             | s                                            |
| <i>Stellaria pungens</i>                             |            | 750          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                       | 0.05       |              |                             | *s                                           |
| <i>Xerochrysum bracteatum</i>                        | 0.45       |              |                             | s                                            |
| <i>Luzula densiflora</i>                             |            | 625          |                             | s                                            |
| <i>Luzula flaccida</i>                               |            | 625          |                             | s                                            |
| <i>Carex breviculmis</i>                             | 0.15       |              |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                                  |              |     |  |       |
|------------------------------------------------------------------|--------------|-----|--|-------|
| <i>Carex hebes</i>                                               | 0.05         |     |  | s     |
| <i>Carex incomitata</i>                                          | 0.45         |     |  | s     |
| <i>Anthosachne scabra</i>                                        | 0.05         |     |  | *p    |
| <i>Microlaena stipoides</i>                                      | 0.05         |     |  | *p    |
| <i>Poa clivicola</i>                                             | 0.65         |     |  | *s    |
| <i>Poa costiniana</i>                                            | 0.05         |     |  | p     |
| <i>Poa labillardierei</i>                                        | 0.05         |     |  | *p    |
| <i>Poa phillipsiana</i>                                          | 0.05         |     |  | *p    |
| <i>Poa sieberiana</i>                                            | 0.25         |     |  | *p    |
| <i>Poa sieberiana</i> var.<br><i>cyanophylla</i>                 | 0.2          |     |  | s     |
| <i>Poa sieberiana</i> var.<br><i>sieberiana</i>                  | 0.55         |     |  | s     |
| <i>Poa sieberiana</i> var.<br><i>sieberiana</i> (fine leaf form) | 0.3          |     |  | s     |
| <i>Rytidosperma caespitosum</i>                                  | 0.95         |     |  | p     |
| <i>Rytidosperma penicillatum</i>                                 | 0.1          |     |  | *s    |
| <i>Rytidosperma pilosum</i>                                      | 0.05         |     |  | *s    |
| <i>Rytidosperma racemosum</i><br>var. <i>racemosum</i>           | 3.8          |     |  | *s    |
| <i>Themeda triandra</i>                                          | 0.2          |     |  | *p    |
| <b>Total</b>                                                     | <b>14.75</b> |     |  |       |
|                                                                  |              |     |  |       |
| <b>Shrubs</b>                                                    |              |     |  |       |
| <i>Epacris breviflora</i>                                        |              | 50  |  | s - C |
| <i>Epacris impressa</i>                                          |              | 25  |  | s - C |
| <i>Epacris paludosa</i>                                          |              | 25  |  | s - C |
| <i>Monotoca scoparia</i>                                         |              | 25  |  | s - C |
| <i>Bossiaea foliosa</i>                                          |              | 375 |  | *s    |
| <i>Cassinia aculeata</i>                                         |              | 175 |  | *p    |
| <i>Daviesia ulicifolia</i>                                       |              | 50  |  | *p    |
| <i>Derwentia perfoliata</i>                                      |              | 250 |  | p     |
| <i>Grevillea lanigera</i>                                        |              | 500 |  | p - C |
| <i>Hakea microcarpa</i>                                          |              | 500 |  | *p    |
| <i>Kunzea muelleri</i>                                           |              | 375 |  | p     |
| <i>Leptospermum myrtifolium</i>                                  |              | 200 |  | *p    |
| <i>Leptospermum obovatum</i>                                     |              | 150 |  | p     |
| <i>Mirbelia oxylobioides</i>                                     |              | 25  |  | *p    |
| <i>Olearia myrsinoides</i>                                       |              | 125 |  | s     |
| <i>Ozothamnus secundiflorus</i>                                  |              | 25  |  | *p    |
| <i>Pimelea linifolia</i>                                         |              | 250 |  | s - C |
| <i>Rubus parvifolius</i>                                         |              | 125 |  | s - C |
|                                                                  |              |     |  |       |

PCT TARGET SPECIES LIST      (Species listed for active rehabilitation)

| <b>Trees</b>                   |              |              |  |    |
|--------------------------------|--------------|--------------|--|----|
| <i>Eucalyptus dalrympleana</i> |              | 50           |  | *p |
| <i>Eucalyptus pauciflora</i>   |              | 75           |  | *p |
| <i>Eucalyptus rubida</i>       |              | 250          |  | p  |
| <i>Eucalyptus stellulata</i>   |              | 75           |  | *p |
|                                | <b>Total</b> | <b>6,325</b> |  |    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 311                                             | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                          |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Dianella longifolia</i>                          |            | 375          |                             | *p                                           |
| <i>Dianella nervosa</i>                             |            | 250          |                             | s                                            |
| <i>Dianella revoluta</i> var. <i>revoluta</i>       |            | 375          |                             | s                                            |
| <i>Erigeron conyzoides</i>                          | 0.01       |              |                             | s                                            |
| <i>Leucochrysum albicans</i> subsp. <i>albicans</i> | 0.02       |              |                             | *s                                           |
| <i>Ranunculus collinus</i>                          | 0.1        |              |                             | s                                            |
| <i>Stellaria pungens</i>                            |            | 500          |                             | p - C                                        |
| <i>Lomandra filiformis</i>                          | 0.04       |              |                             | *p                                           |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>   | 0.11       |              |                             | s                                            |
| <i>Lomandra longifolia</i>                          | 0.07       |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i> | 0.03       |              |                             | s                                            |
| <i>Carex appressa</i>                               | 0.06       |              |                             | *p                                           |
| <i>Carex breviculmis</i>                            | 0.26       |              |                             | *p                                           |
| <i>Carex incomitata</i>                             | 0.01       |              |                             | s                                            |
| <i>Anthosachne scabra</i>                           | 0.11       |              |                             | *p                                           |
| <i>Bothriochloa macra</i>                           | 0.39       |              |                             | s                                            |
| <i>Poa phillipsiana</i>                             | 0.44       |              |                             | *p                                           |
| <i>Poa sieberiana</i>                               | 1.1        |              |                             | *p                                           |
| <i>Poa sieberiana</i> var. <i>hirtella</i>          | 0.22       |              |                             | s                                            |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>        | 0.02       |              |                             | s                                            |
| <i>Rytidosperma erianthum</i>                       | 0.15       |              |                             | s                                            |
| <i>Rytidosperma pallidum</i>                        | 0.21       |              |                             | s                                            |
| <i>Rytidosperma penicillatum</i>                    | 0.22       |              |                             | s                                            |
| <i>Themeda triandra</i>                             | 0.76       |              |                             | *p                                           |
| <b>Total</b>                                        | <b>5</b>   |              |                             |                                              |
|                                                     |            |              |                             |                                              |
| <b>Shrubs</b>                                       |            |              |                             |                                              |
| <i>Brachyloma daphnoides</i>                        |            | 300          |                             | s - C                                        |
| <i>Melichrus urceolatus</i>                         |            | 75           |                             | s - C                                        |
| <i>Monotoca scoparia</i>                            |            | 125          |                             | s - C                                        |
| <i>Acacia amoena</i>                                |            | 175          |                             | s                                            |
| <i>Acacia floribunda</i>                            |            | 125          |                             | p                                            |
| <i>Acacia gunnii</i>                                |            | 25           |                             | p                                            |
| <i>Acacia obliquinervia</i>                         |            | 75           |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                         |              |              |  |       |
|---------------------------------------------------------|--------------|--------------|--|-------|
| <i>Acacia obtusifolia</i>                               |              | 250          |  | p     |
| <i>Acacia pravissima</i>                                |              | 625          |  | *p    |
| <i>Acacia siculiformis</i>                              |              | 25           |  | p     |
| <i>Banksia canei</i>                                    |              | 250          |  | *p    |
| <i>Bursaria spinosa</i>                                 |              | 625          |  | *p    |
| <i>Cassinia aculeata</i>                                |              | 75           |  | *p    |
| <i>Cassinia longifolia</i>                              |              | 425          |  | *p    |
| <i>Correa lawrenceana</i> var.<br><i>rosea</i>          |              | 125          |  | s - C |
| <i>Daviesia mimosoides</i>                              |              | 150          |  | *p    |
| <i>Dillwynia phyllicoides</i>                           |              | 375          |  | s     |
| <i>Grevillea arenaria</i> subsp.<br><i>canescens</i>    |              | 250          |  | p - C |
| <i>Grevillea neurophylla</i>                            |              | 75           |  | s - C |
| <i>Indigofera australis</i>                             |              | 125          |  | *p    |
| <i>Kunzea ericoides</i>                                 |              | 150          |  | p     |
| <i>Leptospermum brevipes</i>                            |              | 875          |  | *p    |
| <i>Melaleuca armillaris</i> subsp.<br><i>Armillaris</i> |              | 50           |  | s     |
| <i>Mirbelia oxylobioides</i>                            |              | 875          |  | *p    |
| <i>Pimelea linifolia</i>                                |              | 125          |  | s - C |
| <i>Platylobium formosum</i>                             |              | 75           |  | p     |
|                                                         |              |              |  |       |
| <b>Trees</b>                                            |              |              |  |       |
| <i>Acacia dealbata</i>                                  |              | 75           |  | *p    |
| <i>Acacia melanoxylon</i>                               |              | 125          |  | *p    |
| <i>Brachychiton populneus</i>                           |              | 50           |  | s     |
| <i>Eucalyptus dives</i>                                 |              | 475          |  | *p    |
| <i>Eucalyptus macrorhyncha</i>                          |              | 125          |  | *p    |
| <i>Eucalyptus nortonii</i>                              |              | 125          |  | p     |
| <i>Eucalyptus robertsonii</i>                           |              | 75           |  | p     |
| <i>Eucalyptus rubida</i>                                |              | 50           |  | p     |
|                                                         | <b>Total</b> | <b>9,025</b> |  |       |

| PCT 637                                              | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Aciphylla glacialis</i>                           | 0.05       |              |                             | *s                                           |
| <i>Arthropodium milleflorum</i>                      | 0.05       |              |                             | *s                                           |
| <i>Brachyscome decipiens</i>                         | 0.05       |              |                             | s                                            |
| <i>Brachyscome obovata</i>                           | 0.05       |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                        | 0.1        |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                               | 0.05       |              |                             | *p                                           |
| <i>Celmisia pugioniformis</i>                        | 0.05       |              |                             | s                                            |
| <i>Coronidium monticola</i>                          | 0.15       |              |                             | s                                            |
| <i>Coronidium scorpioides</i>                        | 0.1        |              |                             | s                                            |
| <i>Myriophyllum pedunculatum</i>                     | 0.2        |              |                             | s – C (division)                             |
| <i>Neopaxia australasica</i>                         | 0.25       |              |                             | s                                            |
| <i>Oreomyrrhis ciliata</i>                           | 0.15       |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                          | 0.05       |              |                             | *s                                           |
| <i>Plantago antarctica</i>                           | 0.15       |              |                             | s                                            |
| <i>Ranunculus graniticola</i>                        | 0.1        |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                          | 0.05       |              |                             | s                                            |
| <i>Ranunculus millanii</i>                           | 0.35       |              |                             | s                                            |
| <i>Ranunculus pimpinellifolius</i>                   | 0.4        |              |                             | s                                            |
| <i>Senecio gunnii</i>                                | 0.05       |              |                             | p                                            |
| <i>Stellaria angustifolia</i>                        |            | 1250         |                             | s                                            |
| <i>Stellaria pungens</i>                             |            | 250          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                       | 0.15       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                           | 0.15       |              |                             | *s                                           |
| <i>Juncus australis</i>                              |            | 250          |                             | s                                            |
| <i>Juncus phaeanthus</i>                             |            | 250          |                             | *s                                           |
| <i>Juncus sarophorus</i>                             |            | 500          |                             | *s                                           |
| <i>Juncus usitatus</i>                               |            | 375          |                             | *s                                           |
| <i>Luzula modesta</i>                                |            | 300          |                             | s                                            |
| <i>Carex appressa</i>                                | 0.4        |              |                             | *p                                           |
| <i>Carex gaudichaudiana</i>                          | 0.5        |              |                             | s                                            |
| <i>Carex hebes</i>                                   | 0.35       |              |                             | s                                            |
| <i>Anthosachne scabra</i>                            | 0.1        |              |                             | *p                                           |
| <i>Deyeuxia brachyathera</i>                         | 0.05       |              |                             | s                                            |
| <i>Poa costiniana</i>                                | 0.8        |              |                             | p                                            |
| <i>Poa ensiformis</i>                                | 0.25       |              |                             | p                                            |
| <i>Poa labillardierei</i>                            | 0.1        |              |                             | *p                                           |
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.9        |              |                             | s                                            |



## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                 |              |              |  |       |
|-------------------------------------------------|--------------|--------------|--|-------|
| <i>Poa sieberiana</i>                           | 2            |              |  | *p    |
| <i>Poa sieberiana</i> var.<br><i>sieberiana</i> | 0.1          |              |  | s     |
| <b>Total</b>                                    | <b>8.25</b>  |              |  |       |
|                                                 |              |              |  |       |
| <b>Shrubs</b>                                   |              |              |  |       |
| <i>Epacris breviflora</i>                       |              | 625          |  | s - C |
| <i>Epacris celata</i>                           |              | 250          |  | s - C |
| <i>Epacris glacialis</i>                        |              | 25           |  | s - C |
| <i>Epacris microphylla</i>                      |              | 375          |  | s - C |
| <i>Epacris paludosa</i>                         |              | 1250         |  | s - C |
| <i>Monotoca scoparia</i>                        |              | 100          |  | s - C |
| <i>Baeckea gunniana</i>                         |              | 175          |  | s - C |
| <i>Baeckea utilis</i>                           |              | 750          |  | s - C |
| <i>Bossiaea foliosa</i>                         |              | 25           |  | *s    |
| <i>Callistemon ptyoides</i>                     |              | 250          |  | *p    |
| <i>Cassinia monticola</i>                       |              | 250          |  | *p    |
| <i>Grevillea australis</i>                      |              | 50           |  | p - C |
| <i>Grevillea lanigera</i>                       |              | 100          |  | p - C |
| <i>Hakea microcarpa</i>                         |              | 300          |  | *p    |
| <i>Leptospermum grandifolium</i>                |              | 550          |  | *p    |
| <i>Leptospermum myrtifolium</i>                 |              | 25           |  | *p    |
| <i>Olearia algida</i>                           |              | 75           |  | s     |
| <i>Ozothamnus secundiflorus</i>                 |              | 25           |  | *p    |
| <i>Ozothamnus thyrsoideus</i>                   |              | 25           |  | *s    |
| <i>Rubus parvifolius</i>                        |              | 50           |  | s - C |
|                                                 |              |              |  |       |
| <b>Trees</b>                                    |              |              |  |       |
| <i>Eucalyptus dalrympleana</i>                  |              | 100          |  | *p    |
| <i>Eucalyptus pauciflora</i>                    |              | 75           |  | *p    |
| <i>Eucalyptus rubida</i>                        |              | 275          |  | p     |
| <i>Eucalyptus stellulata</i>                    |              | 75           |  | *p    |
|                                                 | <b>Total</b> | <b>9,725</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 639                                        | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                     |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>                | 0.15       |              |                             | *s                                           |
| <i>Brachyscome aculeata</i>                    | 0.01       |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                  | 0.04       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                         | 0.01       |              |                             | *p                                           |
| <i>Coronidium monticola</i>                    | 1.8        |              |                             | s                                            |
| <i>Helichrysum rutidolepis</i>                 | 0.59       |              |                             | s                                            |
| <i>Dianella tasmanica</i>                      |            | 75           |                             | *p                                           |
| <i>Goodenia hederacea</i>                      |            | 625          |                             | s – C (division)                             |
| <i>Microseris lanceolata</i>                   | 0.01       |              |                             | *p                                           |
| <i>Oreomyrrhis eriopoda</i>                    | 0.02       |              |                             | *s                                           |
| <i>Picris angustifolia</i>                     | 0.04       |              |                             | s                                            |
| <i>Picris angustifolia subsp. merxmuelleri</i> | 0.01       |              |                             | s                                            |
| <i>Pratia surrepens</i>                        |            | 100          |                             | s – C (division)                             |
| <i>Ranunculus lappaceus</i>                    | 0.02       |              |                             | s                                            |
| <i>Senecio gunnii</i>                          | 0.04       |              |                             | p                                            |
| <i>Senecio prenanthoides</i>                   | 0.02       |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                  | 0.01       |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                    | 0.02       |              |                             | s                                            |
| <i>Stellaria palustris</i>                     |            | 2500         |                             | s                                            |
| <i>Stellaria pungens</i>                       |            | 1325         |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                 | 0.1        |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                     | 0.25       |              |                             | *s                                           |
| <i>Lomandra filiformis</i>                     | 0.01       |              |                             | *p                                           |
| <i>Lomandra filiformis subsp. coriacea</i>     | 0.02       |              |                             | s                                            |
| <i>Lomandra filiformis subsp. filiformis</i>   | 0.05       |              |                             | p                                            |
| <i>Lomandra longifolia</i>                     | 0.05       |              |                             | *p                                           |
| <i>Luzula densiflora</i>                       |            | 125          |                             | s                                            |
| <i>Luzula flaccida</i>                         |            | 250          |                             | s                                            |
| <i>Luzula novae-cambriae</i>                   |            | 300          |                             | s                                            |
| <i>Carex breviculmis</i>                       | 0.07       |              |                             | *p                                           |
| <i>Anthosachne scabra</i>                      | 0.28       |              |                             | *p                                           |
| <i>Deyeuxia monticola</i>                      | 0.11       |              |                             | s                                            |
| <i>Microlaena stipoides</i>                    | 0.44       |              |                             | *p                                           |
| <i>Poa ensiformis</i>                          | 0.02       |              |                             | p                                            |
| <i>Poa helmsii</i>                             | 0.35       |              |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                      |          |     |  |       |
|------------------------------------------------------|----------|-----|--|-------|
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.09     |     |  | p     |
| <i>Poa sieberiana</i>                                | 0.31     |     |  | *p    |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>        | 0.24     |     |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>         | 0.65     |     |  | s     |
| <i>Rytidosperma pallidum</i>                         | 0.04     |     |  | *s    |
| <i>Rytidosperma penicillatum</i>                     | 0.11     |     |  | *s    |
| <i>Themeda triandra</i>                              | 0.02     |     |  | *p    |
| <b>Total</b>                                         | <b>6</b> |     |  |       |
|                                                      |          |     |  |       |
| <b>Shrubs</b>                                        |          |     |  |       |
| <i>Brachyloma daphnoides</i>                         |          | 5   |  | s - C |
| <i>Acacia dealbata</i> subsp. <i>subalpina</i>       |          | 50  |  | s     |
| <i>Acacia obliquinervia</i>                          |          | 35  |  | *p    |
| <i>Acacia siculiformis</i>                           |          | 125 |  | p     |
| <i>Bossiaea foliosa</i>                              |          | 200 |  | *s    |
| <i>Cassinia aculeata</i>                             |          | 100 |  | *p    |
| <i>Cassinia longifolia</i>                           |          | 150 |  | *p    |
| <i>Coprosma hirtella</i>                             |          | 450 |  | s - C |
| <i>Daviesia latifolia</i>                            |          | 375 |  | *p    |
| <i>Daviesia mimosoides</i>                           |          | 50  |  | *p    |
| <i>Daviesia mimosoides</i> subsp. <i>mimosoides</i>  |          | 50  |  | s     |
| <i>Daviesia ulicifolia</i>                           |          | 45  |  | *p    |
| <i>Hakea lissosperma</i>                             |          | 25  |  | *p    |
| <i>Hakea microcarpa</i>                              |          | 50  |  | *p    |
| <i>Leptospermum lanigerum</i>                        |          | 125 |  | p     |
| <i>Leptospermum myrtifolium</i>                      |          | 125 |  | *p    |
| <i>Lomatia myricoides</i>                            |          | 200 |  | s - C |
| <i>Olearia erubescens</i>                            |          | 175 |  | *p    |
| <i>Olearia phlogopappa</i>                           |          | 75  |  | s     |
| <i>Pimelea linifolia</i>                             |          | 105 |  | s - C |
| <i>Platylobium formosum</i>                          |          | 105 |  | p     |
| <i>Podolobium alpestre</i>                           |          | 325 |  | p     |
| <i>Polyscias sambucifolia</i>                        |          | 300 |  | s - C |
| <i>Rubus parvifolius</i>                             |          | 25  |  | s - C |
|                                                      |          |     |  |       |
| <b>Trees</b>                                         |          |     |  |       |
| <i>Acacia dealbata</i>                               |          | 300 |  | *p    |
| <i>Eucalyptus dalrympleana</i>                       |          | 325 |  | *p    |

PCT TARGET SPECIES LIST      (Species listed for active rehabilitation)

|                                                  |              |              |  |    |
|--------------------------------------------------|--------------|--------------|--|----|
| Eucalyptus delegatensis<br>subsp. Delegatensis - |              | 675          |  | *p |
| Eucalyptus pauciflora                            |              | 275          |  | *p |
|                                                  | <b>Total</b> | <b>9,345</b> |  |    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 643                                   | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| Stellaria pungens                         |              | 125          |                             | p - C                                        |
|                                           |              |              |                             |                                              |
| <b>Shrubs</b>                             |              |              |                             |                                              |
| Cassinia longifolia                       |              | 250          |                             | *p                                           |
| Indigofera australis                      |              | 75           |                             | *p                                           |
| Polyscias sambucifolia subsp. leptophylla |              | 25           |                             | s - C                                        |
|                                           |              |              |                             |                                              |
| <b>Trees</b>                              |              |              |                             |                                              |
| Acacia dealbata subsp. subalpina          |              | 125          |                             | s                                            |
| Acacia melanoxylon                        |              | 75           |                             | *p                                           |
| Eucalyptus viminalis                      |              | 25           |                             | *p                                           |
|                                           | <b>Total</b> | <b>700</b>   |                             |                                              |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 644                                         | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                      |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Aciphylla simplicifolia</i>                  | 0.005      |              |                             | *s                                           |
| <i>Arthropodium milleflorum</i>                 | 0.09       |              |                             | *s                                           |
| <i>Brachyscome aculeata</i>                     | 0.045      |              |                             | s                                            |
| <i>Brachyscome decipiens</i>                    | 0.01       |              |                             | s                                            |
| <i>Brachyscome scapigera</i>                    | 0          |              |                             | s                                            |
| <i>Brachyscome tenuiscapa</i>                   | 0.02       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                          | 0.02       |              |                             | *p                                           |
| <i>Celmisia tomentella</i>                      | 0.01       |              |                             | s                                            |
| <i>Chrysocephalum semipapposum</i>              | 0.045      |              |                             | p                                            |
| <i>Coronidium scorpioides</i>                   | 0.035      |              |                             | s                                            |
| <i>Coronidium monticola</i>                     | 0.095      |              |                             | s                                            |
| <i>Helichrysum rutidolepis</i>                  | 0.035      |              |                             | s                                            |
| <i>Craspedia canens</i>                         | 0.02       |              |                             | s                                            |
| <i>Craspedia costiniana</i>                     | 0.005      |              |                             | s                                            |
| <i>Craspedia jamesii</i>                        | 0.005      |              |                             | s                                            |
| <i>Craspedia variabilis</i>                     | 0.005      |              |                             | s                                            |
| <i>Goodenia hederacea</i>                       |            |              |                             | s – C (division)                             |
| <i>Leptorhynchos squamatus</i>                  | 0.03       |              |                             | *s                                           |
| <i>Leptorhynchos squamatus subsp. Alpinus</i>   | 0.015      |              |                             | s                                            |
| <i>Leptorhynchos squamatus subsp. squamatus</i> | 0.01       |              |                             | s                                            |
| <i>Leucochrysum albicans</i>                    | 0.035      |              |                             | s                                            |
| <i>Leucochrysum albicans subsp. albicans</i>    | 0.02       |              |                             | *s                                           |
| <i>Microseris lanceolata</i>                    | 0.015      |              |                             | *p                                           |
| <i>Oreomyrrhis argentea</i>                     | 0.005      |              |                             | s                                            |
| <i>Oreomyrrhis brevipes</i>                     | 0.055      |              |                             | s                                            |
| <i>Oreomyrrhis ciliata</i>                      | 0.01       |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                     | 0.005      |              |                             | *s                                           |
| <i>Picris angustifolia</i>                      | 0.005      |              |                             | s                                            |
| <i>Picris angustifolia subsp. merxmuelleri</i>  | 0.005      |              |                             | s                                            |
| <i>Plantago antarctica</i>                      | 0.02       |              |                             | s                                            |
| <i>Plantago euryphylla</i>                      | 0.025      |              |                             | s                                            |
| <i>Plantago gaudichaudii</i>                    | 0.01       |              |                             | s                                            |
| <i>Plantago varia</i>                           | 0.005      |              |                             | s                                            |
| <i>Podolepis hieracioides</i>                   | 0.005      |              |                             | s                                            |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                         |       |  |  |       |
|---------------------------------------------------------|-------|--|--|-------|
| <i>Podolepis jaceoides</i>                              | 0.035 |  |  | *p    |
| <i>Podolepis robusta</i>                                | 0.01  |  |  | *p    |
| <i>Ranunculus graniticola</i>                           |       |  |  | s     |
| <i>Ranunculus lappaceus</i>                             | 0.01  |  |  | s     |
| <i>Scleranthus biflorus</i>                             | 0.035 |  |  | s     |
| <i>Senecio gunnii</i>                                   | 0.005 |  |  | p     |
| <i>Senecio linearifolius</i>                            | 0.005 |  |  | p     |
| <i>Senecio longipilus</i>                               | 0.005 |  |  | s     |
| <i>Senecio pinnatifolius</i> var.<br><i>alpinus</i>     | 0.03  |  |  | s     |
| <i>Senecio prenanthoides</i>                            | 0.02  |  |  | s     |
| <i>Senecio quadridentatus</i>                           | 0.04  |  |  | s     |
| <i>Stackhousia monogyna</i>                             | 0.005 |  |  | s     |
| <i>Stellaria pungens</i>                                |       |  |  | p - C |
| <i>Stylidium graminifolium</i>                          | 0.06  |  |  | *s    |
| <i>Stylidium lineare</i>                                | 0.045 |  |  | s     |
| <i>Viola betonicifolia</i>                              | 0.02  |  |  | *s    |
| <i>Xerochrysum bracteatum</i>                           | 0.005 |  |  | s     |
| <i>Xerochrysum subundulatum</i>                         | 0.005 |  |  | *s    |
| <i>Lomandra filiformis</i>                              | 0.005 |  |  | *p    |
| <i>Lomandra filiformis</i> subsp.<br><i>coriacea</i>    | 0.005 |  |  | s     |
| <i>Lomandra filiformis</i> subsp.<br><i>filiformis</i>  | 0.005 |  |  | *p    |
| <i>Lomandra longifolia</i>                              | 0.005 |  |  | *p    |
| <i>Luzula densiflora</i>                                |       |  |  | s     |
| <i>Luzula flaccida</i>                                  |       |  |  | s     |
| <i>Luzula modesta</i>                                   |       |  |  | s     |
| <i>Luzula novae-cambriae</i>                            |       |  |  | s     |
| <i>Carex appressa</i>                                   | 0.005 |  |  | *p    |
| <i>Carex breviculmis</i>                                | 0.03  |  |  | *p    |
| <i>Carex hebes</i>                                      | 0.005 |  |  | s     |
| <i>Anthosachne scabra</i>                               | 0.025 |  |  | *p    |
| <i>Microlaena stipoides</i>                             | 0.005 |  |  | *p    |
| <i>Poa clivicola</i>                                    | 0.01  |  |  | *s    |
| <i>Poa costiniana</i>                                   | 0.005 |  |  | p     |
| <i>Poa fawcettiae</i>                                   | 0.1   |  |  | *p    |
| <i>Poa helmsii</i>                                      | 0.135 |  |  | *p    |
| <i>Poa labillardierei</i>                               | 0.005 |  |  | *p    |
| <i>Poa labillardierei</i> var.<br><i>labillardierei</i> | 0.11  |  |  | p     |
| <i>Poa petrophila</i>                                   | 0.09  |  |  | s     |
| <i>Poa phillipsiana</i>                                 | 0.185 |  |  | *s    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                   |             |     |  |       |
|---------------------------------------------------|-------------|-----|--|-------|
| <i>Poa sieberiana</i>                             | 0.05        |     |  | *p    |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>     | 0.5         |     |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>      | 0.05        |     |  | s     |
| <i>Poa sieberiana</i> var. <i>hirtella</i>        | 0.065       |     |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>      | 0.135       |     |  | s     |
| <i>Rytidosperma caespitosum</i>                   | 0.055       |     |  | p     |
| <i>Rytidosperma erianthum</i>                     | 0.02        |     |  | s     |
| <i>Rytidosperma monticola</i>                     | 0.005       |     |  | s     |
| <i>Rytidosperma penicillatum</i>                  | 0.02        |     |  | *s    |
| <i>Rytidosperma pilosum</i>                       | 0.05        |     |  | *s    |
| <i>Themeda triandra</i>                           | 0.03        |     |  | *p    |
| <b>Total</b>                                      | <b>2.76</b> |     |  |       |
|                                                   |             |     |  |       |
| <b>Shrubs</b>                                     |             |     |  |       |
| <i>Brachyloma daphnoides</i>                      |             | 15  |  | s - C |
| <i>Acacia alpina</i>                              |             | 50  |  | s     |
| <i>Acacia obliquinervia</i>                       |             | 50  |  | *p    |
| <i>Asterolasia trymalioides</i>                   |             | 25  |  | s - C |
| <i>Baeckea utilis</i>                             |             | 15  |  | s - C |
| <i>Bossiaea foliosa</i>                           |             | 50  |  | *s    |
| <i>Cassinia aculeata</i>                          |             | 75  |  | *p    |
| <i>Cassinia monticola</i>                         |             | 500 |  | s     |
| <i>Coprosma hirtella</i>                          |             | 250 |  | s - C |
| <i>Daviesia latifolia</i>                         |             | 300 |  | *p    |
| <i>Daviesia mimosoides</i>                        |             | 350 |  | *p    |
| <i>Daviesia ulicifolia</i>                        |             | 300 |  | *p    |
| <i>Grevillea australis</i>                        |             | 25  |  | p - C |
| <i>Grevillea lanigera</i>                         |             | 15  |  | p - C |
| <i>Grevillea parviflora</i>                       |             | 300 |  | s - C |
| <i>Hakea microcarpa</i>                           |             | 650 |  | *p    |
| <i>Leptospermum myrtifolium</i>                   |             | 75  |  | *p    |
| <i>Lomatia myricoides</i>                         |             | 350 |  | s - C |
| <i>Mirbelia oxylobioides</i>                      |             | 150 |  | *p    |
| <i>Olearia brevipedunculata</i>                   |             | 150 |  | s     |
| <i>Olearia erubescens</i>                         |             | 150 |  | *p    |
| <i>Olearia myrsinoides</i>                        |             | 275 |  | s     |
| <i>Olearia phlogopappa</i>                        |             | 25  |  | s     |
| <i>Olearia phlogopappa</i> var. <i>flavescens</i> |             | 55  |  | s     |
| <i>Oxylobium ellipticum</i>                       |             | 150 |  | *p    |
| <i>Ozothamnus secundiflorus</i>                   |             | 150 |  | *p    |



## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                           |              |              |  |       |
|-----------------------------------------------------------|--------------|--------------|--|-------|
| <i>Ozothamnus thyrsoides</i>                              |              | 150          |  | *p    |
| <i>Phebalium squamulosum</i>                              |              | 225          |  | s - C |
| <i>Pimelea ligustrina</i> subsp. <i>ciliata</i>           |              | 250          |  | s - C |
| <i>Pimelea ligustrina</i> subsp. <i>ligustrina</i>        |              | 25           |  | s - C |
| <i>Pimelea linifolia</i>                                  |              | 35           |  | s - C |
| <i>Podocarpus lawrencei</i>                               |              | 5            |  | s - C |
| <i>Podolobium alpestre</i>                                |              | 50           |  | *p    |
| <i>Polyscias sambucifolia</i>                             |              | 5            |  | s - C |
| <i>Rubus parvifolius</i>                                  |              | 50           |  | s - C |
| <i>Tasmannia lanceolata</i>                               |              | 5            |  | s - C |
| <i>Tasmannia xerophila</i>                                |              | 10           |  | s - C |
|                                                           |              |              |  |       |
| <b>Trees</b>                                              |              |              |  |       |
| <i>Eucalyptus niphophila</i>                              |              | 750          |  | p     |
| <i>Eucalyptus dalrympleana</i>                            |              | 275          |  | *p    |
| <i>Eucalyptus dalrympleana</i> subsp. <i>dalrympleana</i> |              | 100          |  | p     |
| <i>Eucalyptus delegatensis</i> subsp. <i>Delegatensis</i> |              | 300          |  | *p    |
| <i>Eucalyptus lacrimans</i>                               |              | 150          |  | *p    |
| <i>Eucalyptus pauciflora</i>                              |              | 375          |  | *p    |
| <i>Eucalyptus rubida</i>                                  |              | 75           |  | p     |
| <i>Eucalyptus stellulata</i>                              |              | 100          |  | *p    |
|                                                           | <b>Total</b> | <b>9,560</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 679                                              | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Aciphylla simplicifolia</i>                       | 0.09         |              |                             | *s                                           |
| <i>Arthropodium milleflorum</i>                      | 0.03         |              |                             | *s                                           |
| <i>Brachyscome decipiens</i>                         | 0.18         |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                               | 0.06         |              |                             | *p                                           |
| <i>Chrysocephalum apiculatum</i>                     | 0.03         |              |                             | p                                            |
| <i>Craspedia costiniana</i>                          | 0.21         |              |                             | s                                            |
| <i>Goodenia hederacea</i>                            |              | 250          |                             | s - C                                        |
| <i>Leptorhynchos squamatus</i>                       | 0.42         |              |                             | *s                                           |
| <i>Microseris lanceolata</i>                         | 6.6          |              |                             | *p                                           |
| <i>Oreomyrrhis argentea</i>                          | 0.06         |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                          | 0.03         |              |                             | *s                                           |
| <i>Plantago euryphylla</i>                           | 0.18         |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                          | 0.09         |              |                             | s                                            |
| <i>Senecio gunnii</i>                                | 0.18         |              |                             | p                                            |
| <i>Senecio quadridentatus</i>                        | 0.06         |              |                             | s                                            |
| <i>Stellaria pungens</i>                             |              | 125          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                       | 0.06         |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                           | 0.03         |              |                             | *s                                           |
| <i>Lomandra bracteata</i>                            | 0.03         |              |                             | *p                                           |
| <i>Luzula densiflora</i>                             |              | 250          |                             | s                                            |
| <i>Anthosachne scabra</i>                            | 0.36         |              |                             | *p                                           |
| <i>Microlaena stipoides</i>                          | 0.51         |              |                             | *p                                           |
| <i>Poa clivicola</i>                                 | 1.32         |              |                             | *p                                           |
| <i>Poa helmsii</i>                                   | 0.06         |              |                             | *p                                           |
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.03         |              |                             | p                                            |
| <i>Poa phillipsiana</i>                              | 3.3          |              |                             | *p                                           |
| <i>Poa sieberiana</i>                                | 3.3          |              |                             | *p                                           |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>         | 1.23         |              |                             | s                                            |
| <i>Rytidosperma penicillatum</i>                     | 0.03         |              |                             | *s                                           |
| <i>Themeda triandra</i>                              | 0.69         |              |                             | *p                                           |
| <b>Total</b>                                         | <b>19.17</b> |              |                             |                                              |
|                                                      |              |              |                             |                                              |
| <b>Shrubs</b>                                        |              |              |                             |                                              |
| <i>Brachyloma daphnoides</i>                         |              | 125          |                             | s - C                                        |
| <i>Acacia alpina</i>                                 |              | 750          |                             | s                                            |
| <i>Acacia obliquinervia</i>                          |              | 75           |                             | *p                                           |
| <i>Daviesia latifolia</i>                            |              | 100          |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                 |              |              |  |       |
|---------------------------------|--------------|--------------|--|-------|
| <i>Daviesia ulicifolia</i>      |              | 375          |  | *p    |
| <i>Hakea microcarpa</i>         |              | 50           |  | *p    |
| <i>Leptospermum myrtifolium</i> |              | 500          |  | *p    |
| <i>Pimelea linifolia</i>        |              | 50           |  | s - C |
| <i>Podolobium alpestre</i>      |              | 625          |  | *p    |
| <i>Rubus parvifolius</i>        |              | 50           |  | s - C |
| <i>Tasmannia xerophila</i>      |              | 125          |  | s - C |
|                                 |              |              |  |       |
| <b>Trees</b>                    |              |              |  |       |
| <i>Eucalyptus pauciflora</i>    |              | 50           |  | *p    |
| <i>Eucalyptus rubida</i>        |              | 150          |  | p     |
| <i>Eucalyptus stellulata</i>    |              | 2500         |  | *p    |
|                                 | <b>Total</b> | <b>6,150</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 729                                             | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                          |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>                     | 0.06       |              |                             | *s                                           |
| <i>Brachyscome spathulata</i>                       | 0.03       |              |                             | s                                            |
| <i>Chrysocephalum semipapposum</i>                  | 0.15       |              |                             | p                                            |
| <i>Dianella revoluta</i>                            |            | 25           |                             | *p                                           |
| <i>Dianella revoluta</i> var. <i>revoluta</i>       |            | 50           |                             | s                                            |
| <i>Erigeron conyzoides</i>                          | 0.03       |              |                             | s                                            |
| <i>Leptorhynchus squamatus</i>                      | 0.12       |              |                             | *s                                           |
| <i>Oreomyrrhis eriopoda</i>                         | 0.06       |              |                             | *s                                           |
| <i>Plantago gaudichaudii</i>                        | 0.09       |              |                             | s                                            |
| <i>Ranunculus collinus</i>                          | 0.27       |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                         | 0.12       |              |                             | s                                            |
| <i>Senecio diaschides</i>                           | 0.03       |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                         | 0.03       |              |                             | s                                            |
| <i>Stellaria pungens</i>                            |            | 500          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                      | 0.06       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                          | 0.03       |              |                             | *s                                           |
| <i>Lomandra bracteata</i>                           | 0.12       |              |                             | *p                                           |
| <i>Lomandra confertifolia</i>                       | 0.12       |              |                             | s                                            |
| <i>Lomandra filiformis</i>                          | 0.33       |              |                             | *p                                           |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>   | 0.18       |              |                             | s                                            |
| <i>Lomandra filiformis</i> subsp. <i>filiformis</i> | 0.12       |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                          | 0.06       |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i> | 0.15       |              |                             | s                                            |
| <i>Luzula densiflora</i>                            |            | 100          |                             | s                                            |
| <i>Luzula flaccida</i>                              |            | 200          |                             | s                                            |
| <i>Carex appressa</i>                               | 0.09       |              |                             | *p                                           |
| <i>Carex breviculmis</i>                            | 0.09       |              |                             | *p                                           |
| <i>Anthosachne scabra</i>                           | 1.29       |              |                             | *p                                           |
| <i>Austrostipa scabra</i>                           | 0.15       |              |                             | *p                                           |
| <i>Dichelachne micrantha</i>                        | 0.21       |              |                             | s                                            |
| <i>Microlaena stipoides</i>                         | 0.33       |              |                             | *p                                           |
| <i>Poa helmsii</i>                                  | 0.03       |              |                             | *p                                           |
| <i>Poa labillardierei</i>                           | 0.18       |              |                             | *p                                           |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                              |              |     |  |       |
|--------------------------------------------------------------|--------------|-----|--|-------|
| <i>Poa labillardierei</i> var. <i>labillardierei</i>         | 0.06         |     |  | s     |
| <i>Poa phillipsiana</i>                                      | 1.29         |     |  | *p    |
| <i>Poa sieberiana</i>                                        | 0.75         |     |  | *p    |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>                | 1.41         |     |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>                 | 0.18         |     |  | s     |
| <i>Rytidosperma caespitosum</i>                              | 0.18         |     |  | p     |
| <i>Rytidosperma erianthum</i>                                | 0.96         |     |  | s     |
| <i>Rytidosperma laeve</i>                                    | 0.12         |     |  | *s    |
| <i>Rytidosperma pallidum</i>                                 | 0.03         |     |  | *s    |
| <i>Rytidosperma penicillatum</i>                             | 1.35         |     |  | *s    |
| <i>Rytidosperma pilosum</i>                                  | 0.39         |     |  | *s    |
| <i>Themeda triandra</i>                                      | 3            |     |  | *p    |
| <b>Total</b>                                                 | <b>14.25</b> |     |  |       |
|                                                              |              |     |  |       |
| <b>Shrubs</b>                                                |              |     |  |       |
| <i>Brachyloma daphnoides</i>                                 |              | 50  |  | s - C |
| <i>Epacris celata</i>                                        |              | 500 |  | s - C |
| <i>Melichrus urceolatus</i>                                  |              | 25  |  | s - C |
| <i>Monotoca scoparia</i>                                     |              | 50  |  | s - C |
| <i>Acacia gunnii</i>                                         |              | 50  |  | p     |
| <i>Acacia obliquinervia</i>                                  |              | 25  |  | *p    |
| <i>Acacia pravissima</i>                                     |              | 40  |  | *p    |
| <i>Acacia rubida</i>                                         |              | 25  |  | *p    |
| <i>Acacia saliciformis</i>                                   |              | 475 |  | p     |
| <i>Acacia siculiformis</i>                                   |              | 25  |  | p     |
| <i>Banksia canei</i>                                         |              | 25  |  | *p    |
| <i>Bossiaea foliosa</i>                                      |              | 75  |  | *s    |
| <i>Bursaria spinosa</i>                                      |              | 25  |  | *p    |
| <i>Cassinia aculeata</i>                                     |              | 10  |  | *p    |
| <i>Cassinia longifolia</i>                                   |              | 400 |  | *p    |
| <i>Daviesia latifolia</i>                                    |              | 200 |  | *p    |
| <i>Daviesia leptophylla</i>                                  |              | 100 |  | s     |
| <i>Dillwynia phyllicoides</i>                                |              | 75  |  | s     |
| <i>Dillwynia sericea</i>                                     |              | 50  |  | s     |
| <i>Grevillea arenaria</i> subsp. <i>canescens</i>            |              | 50  |  | p - C |
| <i>Grevillea neurophylla</i>                                 |              | 75  |  | p - C |
| <i>Grevillea rosmarinifolia</i>                              |              | 50  |  | p - C |
| <i>Grevillea rosmarinifolia</i> subsp. <i>rosmarinifolia</i> |              | 25  |  | s - C |
| <i>Indigofera australis</i>                                  |              | 25  |  | *p    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                           |              |              |  |       |
|-------------------------------------------|--------------|--------------|--|-------|
| <i>Kunzea muelleri</i>                    |              | 475          |  | s     |
| <i>Leptospermum brevipes</i>              |              | 150          |  | *p    |
| <i>Leptospermum micromyrtus</i>           |              | 50           |  | p     |
| <i>Lomatia myricoides</i>                 |              | 2.5          |  | s - C |
| <i>Mirbelia oxylobioides</i>              |              | 120          |  | *p    |
| <i>Olearia erubescens</i>                 |              | 25           |  | *p    |
| <i>Pimelea linifolia</i>                  |              | 40           |  | s - C |
| <i>Platylobium formosum</i>               |              | 10           |  | p     |
| <i>Podolobium alpestre</i>                |              | 50           |  | *p    |
| <i>Rubus parvifolius</i>                  |              | 50           |  | s - C |
|                                           |              |              |  |       |
| <b>Trees</b>                              |              |              |  |       |
| <i>Acacia dealbata</i>                    |              | 1475         |  | *p    |
| <i>Acacia dealbata subsp. subalpina</i>   |              | 200          |  | s     |
| <i>Callitris endlicheri</i>               |              | 25           |  | s     |
| <i>Eucalyptus camphora</i>                |              | 100          |  | p     |
| <i>Eucalyptus camphora subsp. humeana</i> |              | 25           |  | s     |
| <i>Eucalyptus dalrympleana</i>            |              | 25           |  | *p    |
| <i>Eucalyptus dives</i>                   |              | 375          |  | *p    |
| <i>Eucalyptus macrorhyncha</i>            |              | 750          |  | *p    |
| <i>Eucalyptus mannifera</i>               |              | 50           |  | *p    |
| <i>Eucalyptus nortonii</i>                |              | 500          |  | p     |
| <i>Eucalyptus pauciflora</i>              |              | 75           |  | *p    |
| <i>Eucalyptus robertsonii</i>             |              | 150          |  | p     |
| <i>Eucalyptus rubida</i>                  |              | 200          |  | p     |
| <i>Eucalyptus stellulata</i>              |              | 400          |  | *p    |
| <i>Eucalyptus viminalis</i>               |              | 125          |  | *p    |
|                                           | <b>Total</b> | <b>8,095</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 952                                      | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|----------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                   |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>              | 0.21         |              |                             | *s                                           |
| <i>Brachyscome spathulata</i>                | 0.03         |              |                             | s                                            |
| <i>Coronidium scorpioides</i>                | 0.06         |              |                             | s                                            |
| <i>Craspedia paludicola</i>                  | 0.03         |              |                             | s                                            |
| <i>Goodenia hederacea</i>                    |              | 100          |                             | s - C                                        |
| <i>Plantago varia</i>                        | 0.18         |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                  | 0.15         |              |                             | s                                            |
| <i>Scleranthus biflorus</i>                  | 3.6          | 1300         |                             | s – C (division)                             |
| <i>Senecio gunnii</i>                        | 0.15         |              |                             | p                                            |
| <i>Senecio prenanthoides</i>                 | 0.39         |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                | 0.09         |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                  | 0.03         |              |                             | s                                            |
| <i>Stellaria pungens</i>                     | 0.09         | 100          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>               |              |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                   | 0.15         |              |                             | *s                                           |
| <i>Lomandra bracteata</i>                    | 0.06         |              |                             | p                                            |
| <i>Lomandra filiformis</i>                   | 0.06         |              |                             | *p                                           |
| <i>Lomandra filiformis subsp. coriacea</i>   | 0.09         |              |                             | s                                            |
| <i>Lomandra filiformis subsp. filiformis</i> | 0.06         |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                   | 0.15         |              |                             | *p                                           |
| <i>Lomandra multiflora subsp. Multiflora</i> | 0.03         |              |                             | s                                            |
| <i>Luzula flaccida</i>                       |              | 500          |                             | s                                            |
| <i>Carex appressa</i>                        | 0.03         |              |                             | *p                                           |
| <i>Anthosachne scabra</i>                    | 0.15         |              |                             | *p                                           |
| <i>Microlaena stipoides</i>                  | 0.42         |              |                             | *p                                           |
| <i>Poa sieberiana</i>                        | 3.6          |              |                             | *p                                           |
| <i>Poa sieberiana var. cyanophylla</i>       | 0.51         |              |                             | s                                            |
| <i>Poa sieberiana var. sieberiana</i>        | 2.4          |              |                             | s                                            |
| <i>Rytidosperma laeve</i>                    | 0.15         |              |                             | *s                                           |
| <i>Rytidosperma penicillatum</i>             | 0.99         |              |                             | *s                                           |
| <i>Themeda triandra</i>                      | 2.1          |              |                             | *p                                           |
| <b>Total</b>                                 | <b>12.27</b> |              |                             |                                              |
|                                              |              |              |                             |                                              |
| <b>Shrubs</b>                                |              |              |                             |                                              |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                              |              |              |  |       |
|----------------------------------------------|--------------|--------------|--|-------|
| <i>Brachyloma daphnoides</i>                 |              | 50           |  | s - C |
| <i>Epacris breviflora</i>                    |              | 25           |  | s - C |
| <i>Bossiaea foliosa</i>                      |              | 825          |  | *s    |
| <i>Cassinia aculeata</i>                     |              | 50           |  | *p    |
| <i>Daviesia latifolia</i>                    |              | 1250         |  | *p    |
| <i>Daviesia mimosoides</i>                   |              | 225          |  | *p    |
| <i>Daviesia mimosoides subsp. mimosoides</i> |              | 50           |  | s     |
| <i>Daviesia ulicifolia</i>                   |              | 250          |  | *p    |
| <i>Leptospermum myrtifolium</i>              |              | 325          |  | *p    |
| <i>Lomatia myricoides</i>                    |              | 500          |  | s - C |
| <i>Olearia phlogopappa</i>                   |              | 150          |  | s     |
| <i>Pimelea linifolia</i>                     |              | 75           |  | s - C |
| <i>Platylobium formosum</i>                  |              | 300          |  | p     |
|                                              |              |              |  |       |
| <b>Trees</b>                                 |              |              |  |       |
| <i>Acacia dealbata</i>                       |              | 325          |  | *p    |
| <i>Eucalyptus camphora</i>                   |              | 50           |  | p     |
| <i>Eucalyptus dalrympleana</i>               |              | 250          |  | *p    |
| <i>Eucalyptus dives</i>                      |              | 250          |  | *p    |
| <i>Eucalyptus pauciflora</i>                 |              | 450          |  | *p    |
| <i>Eucalyptus radiata</i>                    |              | 625          |  | *p    |
| <i>Eucalyptus radiata subsp. radiata</i>     |              | 275          |  | s     |
| <i>Eucalyptus robertsonii</i>                |              | 875          |  | p     |
| <i>Eucalyptus rubida</i>                     |              | 50           |  | p     |
| <i>Eucalyptus stellulata</i>                 |              | 50           |  | *p    |
|                                              | <b>Total</b> | <b>9,275</b> |  |       |



| PCT 953                                      | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|----------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                   |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>              | 0.06       |              |                             | *s                                           |
| <i>Brachyscome aculeata</i>                  | 0.045      |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                | 0.015      |              |                             | s                                            |
| <i>Chrysocephalum apiculatum</i>             | 0.015      |              |                             | p                                            |
| <i>Chrysocephalum semipapposum</i>           | 0.03       |              |                             | p                                            |
| <i>Coronidium monticola</i>                  | 0.15       |              |                             | s                                            |
| <i>Coronidium scorpioides</i>                | 0.105      |              |                             | s                                            |
| <i>Craspedia jamesii</i>                     | 0.015      |              |                             | s                                            |
| <i>Dianella longifolia</i>                   |            | 250          |                             | *p                                           |
| <i>Dianella revoluta</i>                     |            | 500          |                             | *p                                           |
| <i>Leptorhynchos squamatus</i>               | 0.06       |              |                             | *s                                           |
| <i>Picris angustifolia</i>                   | 0.015      |              |                             | s                                            |
| <i>Plantago gaudichaudii</i>                 | 0.435      |              |                             | s                                            |
| <i>Podolepis jaceoides</i>                   | 0.015      |              |                             | *p                                           |
| <i>Ranunculus lappaceus</i>                  | 0.06       |              |                             | s                                            |
| <i>Senecio prenanthoides</i>                 | 0.015      |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                | 0.03       |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                  | 0.03       |              |                             | s                                            |
| <i>Stellaria pungens</i>                     |            | 275          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>               | 0.06       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                   | 0.075      |              |                             | *s                                           |
| <i>Lomandra bracteata</i>                    | 0.03       |              |                             | p                                            |
| <i>Lomandra filiformis</i>                   | 0.165      |              |                             | *p                                           |
| <i>Lomandra filiformis subsp. coriacea</i>   | 0.57       |              |                             | s                                            |
| <i>Lomandra filiformis subsp. filiformis</i> | 0.03       |              |                             | *p                                           |
| <i>Lomandra longifolia</i>                   | 0.045      |              |                             | *p                                           |
| <i>Lomandra multiflora subsp. Multiflora</i> | 0.075      |              |                             | s                                            |
| <i>Carex breviculmis</i>                     | 0.075      |              |                             | *p                                           |
| <i>Carex incomitata</i>                      | 0.09       |              |                             | s                                            |
| <i>Anthosachne scabra</i>                    | 0.075      |              |                             | *p                                           |
| <i>Microlaena stipoides</i>                  | 0.045      |              |                             | *p                                           |
| <i>Poa helmsii</i>                           | 0.015      |              |                             | *p                                           |
| <i>Poa sieberiana</i>                        | 2.1        |              |                             | *p                                           |
| <i>Poa sieberiana var. cyanophylla</i>       | 0.405      |              |                             | s                                            |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                |              |     |  |       |
|------------------------------------------------|--------------|-----|--|-------|
| <i>Poa sieberiana</i> var. <i>sieberiana</i>   | 1.65         |     |  | s     |
| <i>Rytidosperma pallidum</i>                   | 0.03         |     |  | *s    |
| <i>Rytidosperma penicillatum</i>               | 0.195        |     |  | *s    |
| <i>Themeda triandra</i>                        | 0.48         |     |  | *p    |
| <b>Total</b>                                   | <b>7.305</b> |     |  |       |
|                                                |              |     |  |       |
| <b>Shrubs</b>                                  |              |     |  |       |
| <i>Epacris breviflora</i>                      |              | 125 |  | s - C |
| <i>Monotoca scoparia</i>                       |              | 375 |  | s - C |
| <i>Acacia falciformis</i>                      |              | 250 |  | *p    |
| <i>Acacia gunnii</i>                           |              | 150 |  | p     |
| <i>Acacia obliquinervia</i>                    |              | 300 |  | *p    |
| <i>Acacia pravissima</i>                       |              | 325 |  | *p    |
| <i>Acacia ulicifolia</i>                       |              | 350 |  | *p    |
| <i>Banksia canei</i>                           |              | 100 |  | *p    |
| <i>Bossiaea foliosa</i>                        |              | 25  |  | *s    |
| <i>Cassinia aculeata</i>                       |              | 550 |  | *p    |
| <i>Cassinia longifolia</i>                     |              | 750 |  | *p    |
| <i>Coprosma hirtella</i>                       |              | 25  |  | s - C |
| <i>Daviesia latifolia</i>                      |              | 375 |  | *p    |
| <i>Daviesia ulicifolia</i>                     |              | 250 |  | *p    |
| <i>Derwentia perfoliata</i>                    |              | 50  |  | p     |
| <i>Dillwynia phyllicoides</i>                  |              | 25  |  | s     |
| <i>Grevillea neurophylla</i>                   |              | 675 |  | p - C |
| <i>Hakea microcarpa</i>                        |              | 25  |  | *p    |
| <i>Leptospermum myrtifolium</i>                |              | 125 |  | *p    |
| <i>Mirbelia oxylobioides</i>                   |              | 750 |  | *p    |
| <i>Mirbelia platylobioides</i>                 |              | 750 |  | s     |
| <i>Olearia erubescens</i>                      |              | 25  |  | *p    |
| <i>Pimelea linifolia</i>                       |              | 125 |  | s - C |
| <i>Platylobium formosum</i>                    |              | 375 |  | p     |
| <i>Platylobium montanum</i>                    |              | 300 |  | s     |
| <i>Polyscias sambucifolia</i>                  |              | 250 |  | s - C |
| <i>Rubus parvifolius</i>                       |              | 200 |  | s - C |
|                                                |              |     |  |       |
| <b>Trees</b>                                   |              |     |  |       |
|                                                |              |     |  |       |
| <i>Acacia dealbata</i>                         |              | 50  |  | *p    |
| <i>Acacia dealbata</i> subsp. <i>subalpina</i> |              | 75  |  | s     |
| <i>Acacia melanoxylon</i>                      |              | 300 |  | *p    |
| <i>Eucalyptus dalrympleana</i>                 |              | 75  |  | *p    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                              |              |               |  |    |
|--------------------------------------------------------------|--------------|---------------|--|----|
| <i>Eucalyptus dalrympleana</i><br><i>subsp. dalrympleana</i> |              | 50            |  | s  |
| <i>Eucalyptus dives</i>                                      |              | 550           |  | *p |
| <i>Eucalyptus macrorhyncha</i>                               |              | 175           |  | *p |
| <i>Eucalyptus pauciflora</i>                                 |              | 275           |  | *p |
| <i>Eucalyptus robertsonii</i>                                |              | 125           |  | p  |
| <i>Eucalyptus rubida</i>                                     |              | 50            |  | p  |
| <i>Eucalyptus rubida</i> x<br><i>dalrympleana</i>            |              | 125           |  | s  |
| <i>Eucalyptus viminalis</i>                                  |              | 50            |  | *p |
|                                                              | <b>Total</b> | <b>10,550</b> |  |    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 999                                              | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|------------------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                           |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Chrysocephalum semipapposum</i>                   | 0.09         |              |                             | p                                            |
| <i>Dianella longifolia</i>                           | 0.005        |              |                             | *p                                           |
| <i>Dianella revoluta</i>                             | 0.005        |              |                             | *p                                           |
| <i>Leucochrysum albicans</i> subsp. <i>albicans</i>  | 0.015        |              |                             | *s                                           |
| <i>Plantago hispida</i>                              | 0.09         |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                        | 0.03         |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                          | 0.015        |              |                             | s                                            |
| <i>Stellaria pungens</i>                             |              | 250          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                       | 0.24         |              |                             | *s                                           |
| <i>Xerochrysum viscosum</i>                          | 0.03         |              |                             | s                                            |
| <i>Lomandra bracteata</i>                            | 0.09         |              |                             | p                                            |
| <i>Lomandra filiformis</i>                           | 0.15         |              |                             | *p                                           |
| <i>Lomandra filiformis</i> subsp. <i>coriacea</i>    | 0.075        |              |                             | s                                            |
| <i>Lomandra longifolia</i>                           | 0.15         |              |                             | *p                                           |
| <i>Lomandra multiflora</i> subsp. <i>Multiflora</i>  | 0.12         |              |                             | s                                            |
| <i>Carex appressa</i>                                | 0.03         |              |                             | *p                                           |
| <i>Carex breviculmis</i>                             | 0.15         |              |                             | *p                                           |
| <i>Anthosachne scabra</i>                            | 0.15         |              |                             | *p                                           |
| <i>Austrostipa scabra</i>                            | 0.06         |              |                             | *p                                           |
| <i>Poa labillardierei</i> var. <i>labillardierei</i> | 0.195        |              |                             | s                                            |
| <i>Poa sieberiana</i>                                | 1.335        |              |                             | *p                                           |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>         | 1.185        |              |                             | s                                            |
| <i>Rytidosperma caespitosum</i>                      | 0.615        |              |                             | *p                                           |
| <i>Rytidosperma erianthum</i>                        | 0.48         |              |                             | s                                            |
| <i>Rytidosperma pallidum</i>                         | 0.36         |              |                             | *s                                           |
| <i>Rytidosperma pilosum</i>                          | 0.09         |              |                             | *s                                           |
| <i>Themeda triandra</i>                              | 0.87         |              |                             | *p                                           |
| <b>Total</b>                                         | <b>6.625</b> |              |                             |                                              |
|                                                      |              |              |                             |                                              |
| <b>Shrubs</b>                                        |              |              |                             |                                              |
| <i>Brachyloma daphnoides</i>                         |              | 625          |                             | s - C                                        |
| <i>Melichrus urceolatus</i>                          |              | 150          |                             | s - C                                        |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                           |              |               |  |       |
|-----------------------------------------------------------|--------------|---------------|--|-------|
| <i>Monotoca scoparia</i>                                  |              | 200           |  | s - C |
| <i>Acacia buxifolia</i>                                   |              | 400           |  | s     |
| <i>Acacia buxifolia</i> subsp.<br><i>buxifolia</i>        |              | 175           |  | s     |
| <i>Acacia gunnii</i>                                      |              | 275           |  | p     |
| <i>Acacia obliquinervia</i>                               |              | 175           |  | *p    |
| <i>Acacia penninervis</i> var.<br><i>penninervis</i>      |              | 400           |  | p     |
| <i>Acacia pravissima</i>                                  |              | 500           |  | *p    |
| <i>Acacia siculiformis</i>                                |              | 350           |  | p     |
| <i>Banksia canei</i>                                      |              | 750           |  | *p    |
| <i>Bursaria spinosa</i>                                   |              | 325           |  | *p    |
| <i>Cassinia aculeata</i>                                  |              | 275           |  | *p    |
| <i>Cassinia longifolia</i>                                |              | 425           |  | *p    |
| <i>Daviesia ulicifolia</i>                                |              | 50            |  | *p    |
| <i>Dillwynia phyllicoides</i>                             |              | 500           |  | s     |
| <i>Grevillea arenaria</i>                                 |              | 275           |  | p - C |
| <i>Grevillea neurophylla</i>                              |              | 450           |  | p - C |
| <i>Grevillea neurophylla</i><br>subsp. <i>neurophylla</i> |              | 750           |  | s - C |
| <i>Indigofera australis</i>                               |              | 200           |  | *p    |
| <i>Kunzea parvifolia</i>                                  |              | 375           |  | p     |
| <i>Mirbelia oxyllobioides</i>                             |              | 550           |  | *p    |
| <i>Olearia myrsinoides</i>                                |              | 125           |  | s     |
| <i>Pimelea linifolia</i>                                  |              | 250           |  | s - C |
| <i>Platylobium formosum</i>                               |              | 25            |  | p     |
| <i>Podolobium alpestre</i>                                |              | 25            |  | *p    |
| <i>Rubus parvifolius</i>                                  |              | 100           |  | s - C |
|                                                           |              |               |  |       |
| <b>Trees</b>                                              |              |               |  |       |
| <i>Acacia dealbata</i>                                    |              | 150           |  | *p    |
| <i>Acacia dealbata</i> subsp.<br><i>subalpina</i>         |              | 75            |  | s     |
| <i>Acacia melanoxylon</i>                                 |              | 250           |  | *p    |
| <i>Eucalyptus dives</i>                                   |              | 350           |  | *p    |
| <i>Eucalyptus macrorhyncha</i>                            |              | 275           |  | *p    |
| <i>Eucalyptus nortonii</i>                                |              | 250           |  | p     |
| <i>Eucalyptus robertsonii</i>                             |              | 250           |  | p     |
| <i>Eucalyptus viminalis</i>                               |              | 125           |  | *p    |
|                                                           | <b>Total</b> | <b>10,675</b> |  |       |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 1191                                     | kgs per ha   | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|----------------------------------------------|--------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                   |              |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>              | 0.05         |              |                             | *s                                           |
| <i>Chrysocephalum semipapposum</i>           | 1.275        |              |                             | p                                            |
| <i>Senecio prenanthoides</i>                 | 0.075        |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                | 0.025        |              |                             | s                                            |
| <i>Stellaria pungens</i>                     |              | 625          |                             | p - C                                        |
| <i>Stylidium graminifolium</i>               | 0.175        |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                   | 0.025        |              |                             | *s                                           |
| <i>Lomandra filiformis</i>                   | 0.1          |              |                             | *p                                           |
| <i>Lomandra filiformis subsp. coriacea</i>   | 0.175        |              |                             | s                                            |
| <i>Lomandra filiformis subsp. filiformis</i> | 0.075        |              |                             | *p                                           |
| <i>Lomandra multiflora subsp. Multiflora</i> | 0.125        |              |                             | s                                            |
| <i>Luzula flaccida</i>                       |              | 250          |                             | s                                            |
| <i>Carex appressa</i>                        | 0.05         |              |                             | *p                                           |
| <i>Carex breviculmis</i>                     | 0.175        |              |                             | *p                                           |
| <i>Carex incomitata</i>                      | 0.075        |              |                             | s                                            |
| <i>Anthosachne scabra</i>                    | 1.075        |              |                             | *p                                           |
| <i>Austrostipa scabra</i>                    | 0.25         |              |                             | *p                                           |
| <i>Poa costiniana</i>                        | 0.425        |              |                             | *p                                           |
| <i>Poa helmsii</i>                           | 0.025        |              |                             | *p                                           |
| <i>Poa sieberiana</i>                        | 0.225        |              |                             | *p                                           |
| <i>Poa sieberiana var. cyanophylla</i>       | 0.9          |              |                             | s                                            |
| <i>Poa sieberiana var. hirtella</i>          | 0.175        |              |                             | s                                            |
| <i>Poa sieberiana var. sieberiana</i>        | 3            |              |                             | s                                            |
| <i>Rytidosperma erianthum</i>                | 0.65         |              |                             | s                                            |
| <i>Rytidosperma penicillatum</i>             | 8            |              |                             | *s                                           |
| <i>Themeda triandra</i>                      | 2.125        |              |                             | *p                                           |
| <b>Total</b>                                 | <b>19.25</b> |              |                             |                                              |
|                                              |              |              |                             |                                              |
| <b>Shrubs</b>                                |              |              |                             |                                              |
| <i>Brachyloma daphnoides</i>                 |              | 875          |                             | s - C                                        |
| <i>Melichrus urceolatus</i>                  |              | 100          |                             | s - C                                        |
| <i>Acacia gunnii</i>                         |              | 125          |                             | p                                            |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                       |              |              |  |       |
|-------------------------------------------------------|--------------|--------------|--|-------|
| <i>Acacia pravissima</i>                              |              | 1375         |  | *p    |
| <i>Banksia canei</i>                                  |              | 225          |  | *p    |
| <i>Bursaria spinosa</i>                               |              | 175          |  | *p    |
| <i>Cassinia longifolia</i>                            |              | 75           |  | *p    |
| <i>Grevillea arenaria</i>                             |              | 100          |  | p - C |
| <i>Grevillea arenaria subsp. canescens</i>            |              | 625          |  | s - C |
| <i>Grevillea rosmarinifolia subsp. rosmarinifolia</i> |              | 500          |  | p - C |
| <i>Indigofera australis</i>                           |              | 100          |  | *p    |
| <i>Mirbelia oxylobioides</i>                          |              | 625          |  | *p    |
| <i>Olearia myrsinoides</i>                            |              | 500          |  | s     |
| <i>Pimelea linifolia</i>                              |              | 625          |  | s - C |
| <i>Rubus parvifolius</i>                              |              | 250          |  | s - C |
|                                                       |              |              |  |       |
| <b>Trees</b>                                          |              |              |  |       |
| <i>Acacia dealbata</i>                                |              | 250          |  | *p    |
| <i>Acacia melanoxylon</i>                             |              | 75           |  | *p    |
| <i>Eucalyptus dalrympleana</i>                        |              | 275          |  | *p    |
| <i>Eucalyptus dives</i>                               |              | 75           |  | *p    |
| <i>Eucalyptus mannifera</i>                           |              | 100          |  | *p    |
| <i>Eucalyptus pauciflora</i>                          |              | 350          |  | *p    |
| <i>Eucalyptus rubida</i>                              |              | 200          |  | p     |
| <i>Eucalyptus stellulata</i>                          |              | 75           |  | *p    |
|                                                       | <b>Total</b> | <b>8,550</b> |  |       |

| PCT 1196                                      | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                    |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Arthropodium milleflorum</i>               | 0.39       |              |                             | *s                                           |
| <i>Brachyscome decipiens</i>                  | 0.03       |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                 | 0.03       |              |                             | s                                            |
| <i>Brachyscome tenuiscapa</i>                 | 0.03       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                        | 0.06       |              |                             | *p                                           |
| <i>Chrysocephalum apiculatum</i>              | 0.06       |              |                             | p                                            |
| <i>Coronidium scorpioides</i>                 | 0.06       |              |                             | s                                            |
| <i>Craspedia jamesii</i>                      | 0.06       |              |                             | s                                            |
| <i>Craspedia variabilis</i>                   | 0.03       |              |                             | s                                            |
| <i>Dianella longifolia</i>                    |            | 125          |                             | *p                                           |
| <i>Dianella revoluta</i>                      |            | 200          |                             | *p                                           |
| <i>Dianella tasmanica</i>                     |            | 75           |                             | *p                                           |
| <i>Goodenia hederacea</i>                     |            | 175          |                             | s – C (division)                             |
| <i>Helichrysum rutidolepis</i>                | 0.09       |              |                             | s                                            |
| <i>Leptorhynchos squamatus</i>                | 0.06       |              |                             | *s                                           |
| <i>Leptorhynchos squamatus subsp. Alpinus</i> | 0.12       |              |                             | s                                            |
| <i>Leucochrysum albicans</i>                  | 0.03       |              |                             | s                                            |
| <i>Microseris lanceolata</i>                  | 0.03       |              |                             | *p                                           |
| <i>Oreomyrrhis argentea</i>                   | 0.24       |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                   | 0.06       |              |                             | *s                                           |
| <i>Picris angustifolia</i>                    | 0.06       |              |                             | s                                            |
| <i>Picris angustifolia subsp. merxmulleri</i> | 0.06       |              |                             | s                                            |
| <i>Podolepis laciniata</i>                    | 0.12       |              |                             | s                                            |
| <i>Ranunculus collinus</i>                    | 0.03       |              |                             | s                                            |
| <i>Ranunculus graniticola</i>                 | 0.06       |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                   | 0.03       |              |                             | s                                            |
| <i>Scleranthus biflorus</i>                   |            | 500          |                             | s – C (division)                             |
| <i>Senecio gunnii</i>                         | 0.06       |              |                             | p                                            |
| <i>Senecio lageniformis</i>                   | 0.06       |              |                             | s                                            |
| <i>Senecio phelleus</i>                       | 0.03       |              |                             | s                                            |
| <i>Senecio prenanthoides</i>                  | 0.03       |              |                             | s                                            |
| <i>Senecio quadridentatus</i>                 | 0.03       |              |                             | s                                            |
| <i>Stackhousia monogyna</i>                   | 0.03       |              |                             | s                                            |
| <i>Stellaria pungens</i>                      |            | 1125         |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                | 0.06       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                    | 0.12       |              |                             | *s                                           |



## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                        |             |     |  |       |
|--------------------------------------------------------|-------------|-----|--|-------|
| <i>Xerochrysum bracteatum</i>                          | 0.09        |     |  | s     |
| <i>Xerochrysum viscosum</i>                            | 0.15        |     |  | s     |
| <i>Lomandra bracteata</i>                              | 0.03        |     |  | p     |
| <i>Lomandra confertifolia</i>                          | 0.12        |     |  | s     |
| <i>Lomandra filiformis</i>                             | 0.18        |     |  | *p    |
| <i>Lomandra filiformis subsp. coriacea</i>             | 0.03        |     |  | s     |
| <i>Lomandra filiformis subsp. filiformis</i>           | 0.42        |     |  | p     |
| <i>Lomandra longifolia</i>                             | 0.12        |     |  | *p    |
| <i>Lomandra multiflora subsp. Multiflora</i>           | 0.03        |     |  | s     |
| <i>Luzula densiflora</i>                               |             | 200 |  | s     |
| <i>Luzula flaccida</i>                                 |             | 25  |  | s     |
| <i>Luzula novae-cambriae</i>                           |             | 300 |  | s     |
| <i>Carex appressa</i>                                  | 0.09        |     |  | *p    |
| <i>Carex breviculmis</i>                               | 0.12        |     |  | *p    |
| <i>Carex hebes</i>                                     | 0.15        |     |  | s     |
| <i>Carex incomitata</i>                                | 0.03        |     |  | s     |
| <i>Carex inversa</i>                                   | 0.15        |     |  | s     |
| <i>Anthosachne scabra</i>                              | 0.39        |     |  | *p    |
| <i>Deyeuxia monticola</i>                              | 0.03        |     |  | s     |
| <i>Microlaena stipoides</i>                            | 0.21        |     |  | p     |
| <i>Poa clivicola</i>                                   | 1.23        |     |  | *p    |
| <i>Poa costiniana</i>                                  | 0.33        |     |  | *p    |
| <i>Poa ensiformis</i>                                  | 0.24        |     |  | p     |
| <i>Poa helmsii</i>                                     | 0.03        |     |  | *p    |
| <i>Poa labillardierei var. labillardierei</i>          | 0.27        |     |  | p     |
| <i>Poa sieberiana</i>                                  | 2.58        |     |  | *p    |
| <i>Poa sieberiana var. cyanophylla</i>                 | 0.18        |     |  | s     |
| <i>Poa sieberiana var. hirtella</i>                    | 1.26        |     |  | s     |
| <i>Poa sieberiana var. sieberiana</i>                  | 0.81        |     |  | s     |
| <i>Poa sieberiana var. sieberiana (fine leaf form)</i> | 0.09        |     |  | s     |
| <i>Rytidosperma caespitosum</i>                        | 0.09        |     |  | p     |
| <i>Rytidosperma pallidum</i>                           | 0.03        |     |  | s     |
| <i>Rytidosperma penicillatum</i>                       | 0.09        |     |  | *s    |
| <i>Rytidosperma pilosum</i>                            | 0.69        |     |  | *s    |
| <i>Themeda triandra</i>                                | 0.18        |     |  | *p    |
| <b>Total</b>                                           | <b>12.6</b> |     |  |       |
|                                                        |             |     |  |       |
| <b>Shrubs</b>                                          |             |     |  |       |
| <i>Brachyloma daphnoides</i>                           |             | 10  |  | s - C |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                  |  |     |  |       |
|----------------------------------|--|-----|--|-------|
| <i>Epacris breviflora</i>        |  | 40  |  | s - C |
| <i>Epacris paludosa</i>          |  | 25  |  | s - C |
| <i>Monotoca scoparia</i>         |  | 75  |  | s - C |
| <i>Acacia falciformis</i>        |  | 25  |  | *p    |
| <i>Acacia obliquinervia</i>      |  | 25  |  | *p    |
| <i>Acacia pravissima</i>         |  | 25  |  | *p    |
| <i>Acacia siculiformis</i>       |  | 25  |  | p     |
| <i>Baeckea utilis</i>            |  | 100 |  | s - C |
| <i>Banksia canei</i>             |  | 25  |  | *p    |
| <i>Bossiaea foliosa</i>          |  | 75  |  | *s    |
| <i>Callistemon ptyoides</i>      |  | 50  |  | *p    |
| <i>Cassinia aculeata</i>         |  | 25  |  | *p    |
| <i>Cassinia longifolia</i>       |  | 50  |  | *p    |
| <i>Coprosma hirtella</i>         |  | 10  |  | s - C |
| <i>Daviesia latifolia</i>        |  | 100 |  | *p    |
| <i>Daviesia mimosoides</i>       |  | 140 |  | *p    |
| <i>Daviesia ulicifolia</i>       |  | 25  |  | *p    |
| <i>Grevillea australis</i>       |  | 10  |  | p - C |
| <i>Grevillea lanigera</i>        |  | 10  |  | p - C |
| <i>Grevillea neurophylla</i>     |  | 175 |  | p - C |
| <i>Hakea microcarpa</i>          |  | 50  |  | *p    |
| <i>Leptospermum brevipes</i>     |  | 50  |  | *p    |
| <i>Leptospermum grandifolium</i> |  | 25  |  | *p    |
| <i>Leptospermum myrtifolium</i>  |  | 25  |  | *p    |
| <i>Leptospermum obovatum</i>     |  | 160 |  | p     |
| <i>Lomatia myricoides</i>        |  | 15  |  | s - C |
| <i>Mirbelia oxylobioides</i>     |  | 20  |  | *p    |
| <i>Olearia erubescens</i>        |  | 10  |  | *p    |
| <i>Olearia megalophylla</i>      |  | 30  |  | s     |
| <i>Olearia myrsinoides</i>       |  | 50  |  | s     |
| <i>Olearia phlogopappa</i>       |  | 50  |  | s     |
| <i>Oxylobium ellipticum</i>      |  | 50  |  | *p    |
| <i>Ozothamnus thyrsoides</i>     |  | 25  |  | *p    |
| <i>Pimelea linifolia</i>         |  | 75  |  | s - C |
| <i>Podolobium alpestre</i>       |  | 40  |  | *p    |
| <i>Polyscias sambucifolia</i>    |  | 25  |  | s - C |
| <i>Rubus parvifolius</i>         |  | 25  |  | s - C |
| <i>Tasmannia lanceolata</i>      |  | 25  |  | s - C |
|                                  |  |     |  |       |
| <b>Trees</b>                     |  |     |  |       |
| <i>Acacia dealbata</i>           |  | 350 |  | *p    |
| <i>Acacia melanoxylon</i>        |  | 100 |  | *p    |
| <i>Eucalyptus dalrympleana</i>   |  | 425 |  | *p    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                              |              |              |  |    |
|--------------------------------------------------------------|--------------|--------------|--|----|
| <i>Eucalyptus dalrympleana</i><br>subsp. <i>dalrympleana</i> |              | 200          |  | s  |
| <i>Eucalyptus delegatensis</i><br>subsp. <i>Delegatensis</i> |              | 200          |  | *p |
| <i>Eucalyptus dives</i>                                      |              | 500          |  | *p |
| <i>Eucalyptus paniculata</i>                                 |              | 200          |  | s  |
| <i>Eucalyptus pauciflora</i>                                 |              | 800          |  | *p |
| <i>Eucalyptus radiata</i>                                    |              | 700          |  | *p |
| <i>Eucalyptus robertsonii</i>                                |              | 300          |  | p  |
| <i>Eucalyptus robertsonii</i><br>subsp. <i>robertsonii</i>   |              | 850          |  | s  |
| <i>Eucalyptus rubida</i>                                     |              | 100          |  | p  |
| <i>Eucalyptus stellulata</i>                                 |              | 125          |  | *p |
| <i>Eucalyptus viminalis</i>                                  |              | 550          |  | *p |
|                                                              | <b>Total</b> | <b>7,720</b> |  |    |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

| PCT 1224                                      | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|-----------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                    |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Aciphylla glacialis</i>                    | 0.05       |              |                             | *s                                           |
| <i>Aciphylla simplicifolia</i>                | 0.05       |              |                             | *s                                           |
| <i>Arthropodium milleflorum</i>               | 0.05       |              |                             | *s                                           |
| <i>Brachyscome aculeata</i>                   | 0.05       |              |                             | s                                            |
| <i>Brachyscome ciliaris</i>                   | 0.1        |              |                             | s                                            |
| <i>Brachyscome decipiens</i>                  | 0.05       |              |                             | s                                            |
| <i>Brachyscome scapigera</i>                  | 0.1        |              |                             | s                                            |
| <i>Brachyscome spathulata</i>                 | 0.1        |              |                             | s                                            |
| <i>Brachyscome tenuiscapa</i>                 | 0.25       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                        | 0.05       |              |                             | *p                                           |
| <i>Celmisia pugioniformis</i>                 | 0.05       |              |                             | s                                            |
| <i>Chrysocephalum semipapposum</i>            | 0.15       |              |                             | p                                            |
| <i>Coronidium monticola</i>                   | 2          |              |                             | s                                            |
| <i>Coronidium scorpioides</i>                 | 0.05       |              |                             | s                                            |
| <i>Craspedia aurantia</i>                     | 0.65       |              |                             | s                                            |
| <i>Craspedia coolaminica</i>                  | 0.3        |              |                             | s                                            |
| <i>Craspedia crocata</i>                      | 2.3        |              |                             | s                                            |
| <i>Craspedia jamesii</i>                      | 0.1        |              |                             | s                                            |
| <i>Craspedia variabilis</i>                   | 0.05       |              |                             | s                                            |
| <i>Erigeron bellidioides</i>                  | 0.05       |              |                             | s                                            |
| <i>Leptorhynchos elongatus</i>                | 0.05       |              |                             | s                                            |
| <i>Leptorhynchos squamatus</i>                | 0.05       |              |                             | s                                            |
| <i>Leptorhynchos squamatus subsp. Alpinus</i> | 0.15       |              |                             | *s                                           |
| <i>Microseris lanceolata</i>                  | 0.15       |              |                             | *p                                           |
| <i>Myriophyllum alpinum</i>                   |            | 250          |                             | s– C (division)                              |
| <i>Neopaxia spp.</i>                          |            | 500          |                             | s – C (division)                             |
| <i>Oreomyrrhis argentea</i>                   | 0.15       |              |                             | s                                            |
| <i>Oreomyrrhis ciliata</i>                    | 0.05       |              |                             | s                                            |
| <i>Oreomyrrhis eriopoda</i>                   | 0.05       |              |                             | *s                                           |
| <i>Plantago antarctica</i>                    | 0.05       |              |                             | s                                            |
| <i>Plantago euryphylla</i>                    | 0.1        |              |                             | s                                            |
| <i>Plantago gaudichaudii</i>                  | 0.9        |              |                             | s                                            |
| <i>Plantago varia</i>                         | 0.25       |              |                             | s                                            |
| <i>Podolepis jaceoides</i>                    | 0.55       |              |                             | *p                                           |
| <i>Podolepis laciniata</i>                    | 0.05       |              |                             | s                                            |
| <i>Ranunculus collinus</i>                    | 0.05       |              |                             | s                                            |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                                               |      |     |  |                  |
|---------------------------------------------------------------|------|-----|--|------------------|
| <i>Ranunculus graniticola</i>                                 | 0.1  |     |  | s                |
| <i>Ranunculus lappaceus</i>                                   | 0.05 |     |  | s                |
| <i>Ranunculus millanii</i>                                    | 0.2  |     |  | s                |
| <i>Rhodanthe anthemoides</i>                                  | 0.2  |     |  | p                |
| <i>Scleranthus biflorus</i>                                   |      | 375 |  | s – C (division) |
| <i>Senecio lageniformis</i>                                   | 0.05 |     |  | s                |
| <i>Senecio prenanthoides</i>                                  | 0.05 |     |  | s                |
| <i>Senecio quadridentatus</i>                                 |      |     |  | s                |
| <i>Stellaria pungens</i>                                      | 0.1  | 375 |  | p – C            |
| <i>Stylidium graminifolium</i>                                | 0.05 |     |  | *s               |
| <i>Viola betonicifolia</i>                                    | 0.05 |     |  | *s               |
| <i>Xerochrysum subundulatum</i>                               | 0.05 |     |  | *s               |
| <i>Juncus falcatus</i>                                        |      | 75  |  | *s               |
| <i>Juncus sarophorus</i>                                      |      | 500 |  | *s               |
| <i>Lomandra filiformis subsp. coriacea</i>                    | 0.05 |     |  | s                |
| <i>Luzula densiflora</i>                                      |      | 750 |  | s                |
| <i>Luzula flaccida</i>                                        |      | 625 |  | s                |
| <i>Luzula modesta</i>                                         |      | 25  |  | s                |
| <i>Luzula novae-cambriae</i>                                  |      | 250 |  | s                |
| <i>Carex breviculmis</i>                                      | 0.15 |     |  | *p               |
| <i>Carex gaudichaudiana</i>                                   |      | 250 |  | s – C (division) |
| <i>Carex incomitata</i>                                       | 0.05 |     |  | s                |
| <i>Isolepis inundata</i>                                      |      | 25  |  | s – C (division) |
| <i>Anthosachne scabra</i>                                     | 0.1  |     |  | *p               |
| <i>Deyeuxia monticola</i>                                     | 0.1  |     |  | s                |
| <i>Microlaena stipoides</i>                                   | 0.05 |     |  | *p               |
| <i>Poa clivicola</i>                                          | 0.5  |     |  | *p               |
| <i>Poa costiniana</i>                                         | 0.2  |     |  | p                |
| <i>Poa phillipsiana</i>                                       | 0.5  |     |  | *p               |
| <i>Poa sieberiana</i>                                         | 0.8  |     |  | *p               |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>                 | 0.15 |     |  | s                |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>                  | 0.35 |     |  | s                |
| <i>Poa sieberiana</i> var. <i>sieberiana</i> (fine leaf form) | 0.9  |     |  | s                |
| <i>Rytidosperma caespitosum</i>                               | 0.9  |     |  | p                |
| <i>Rytidosperma erianthum</i>                                 | 0.1  |     |  | s                |
| <i>Rytidosperma fulvum</i>                                    | 0.15 |     |  | s                |
| <i>Rytidosperma laeve</i>                                     | 0.25 |     |  | s                |
| <i>Rytidosperma nudiflorum</i>                                | 0.25 |     |  | s                |
| <i>Rytidosperma penicillatum</i>                              | 0.25 |     |  | *s               |
| <i>Rytidosperma pilosum</i>                                   | 0.45 |     |  | *s               |

## PCT TARGET SPECIES LIST

(Species listed for active rehabilitation)

|                                 |              |              |  |       |
|---------------------------------|--------------|--------------|--|-------|
| <i>Themeda triandra</i>         | 0.25         |              |  | *p    |
| <b>Total</b>                    | <b>16.45</b> |              |  |       |
| <b>Shrubs</b>                   |              |              |  |       |
| <i>Epacris breviflora</i>       |              | 70           |  | s- C  |
| <i>Epacris gunnii</i>           |              | 75           |  | s- C  |
| <i>Epacris microphylla</i>      |              | 25           |  | s- C  |
| <i>Epacris paludosa</i>         |              | 100          |  | s- C  |
| <i>Asterolasia trymalioides</i> |              | 50           |  | s- C  |
| <i>Baeckea utilis</i>           |              | 210          |  | s- C  |
| <i>Bossiaea foliosa</i>         |              | 25           |  | *s    |
| <i>Cassinia aculeata</i>        |              | 25           |  | *p    |
| <i>Cassinia monticola</i>       |              | 100          |  | s     |
| <i>Comesperma retusum</i>       |              | 25           |  | s- C  |
| <i>Daviesia ulicifolia</i>      |              | 625          |  | *p    |
| <i>Grevillea australis</i>      |              | 800          |  | p - C |
| <i>Grevillea lanigera</i>       |              | 500          |  | p - C |
| <i>Grevillea parviflora</i>     |              | 750          |  | s- C  |
| <i>Hakea microcarpa</i>         |              | 300          |  | *p    |
| <i>Kunzea muelleri</i>          |              | 25           |  | p - C |
| <i>Leptospermum myrtifolium</i> |              | 100          |  | *p    |
| <i>Mirbelia oxylobioides</i>    |              | 200          |  | *p    |
| <i>Olearia algida</i>           |              | 150          |  | s     |
| <i>Olearia myrsinoides</i>      |              | 150          |  | s     |
| <i>Olearia phlogopappa</i>      |              | 25           |  | s     |
| <i>Ozothamnus cupressoides</i>  |              | 10           |  | *p    |
| <i>Ozothamnus secundiflorus</i> |              | 15           |  | *p    |
| <i>Pimelea linifolia</i>        |              | 25           |  | s - C |
| <i>Podolobium alpestre</i>      |              | 25           |  | *p    |
|                                 |              |              |  |       |
| <b>Trees</b>                    |              |              |  |       |
| <i>Eucalyptus lacrimans</i>     |              | 125          |  | *p    |
| <i>Eucalyptus pauciflora</i>    |              | 25           |  | *p    |
| <i>Eucalyptus stellulata</i>    |              | 75           |  | *p    |
|                                 | <b>Total</b> | <b>7,880</b> |  |       |

| PCT 1225                                                | kgs per ha | Stems per ha | Reference site presence Y/N | Primary (p) or Secondary (s) Rehab Species   |
|---------------------------------------------------------|------------|--------------|-----------------------------|----------------------------------------------|
| <b>Forbs &amp; Grasses</b>                              |            |              |                             | <b>*Seed available<br/>C = cutting grown</b> |
| <i>Aciphylla glacialis</i>                              | 0.05       |              |                             | *s                                           |
| <i>Aciphylla simplicifolia</i>                          | 0.1        |              |                             | *s                                           |
| <i>Arthropodium milleflorum</i>                         | 0.95       |              |                             | *s                                           |
| <i>Brachyscome decipiens</i>                            | 0.15       |              |                             | s                                            |
| <i>Brachyscome scapigera</i>                            | 0.95       |              |                             | s                                            |
| <i>Bulbine bulbosa</i>                                  | 0.05       |              |                             | *p                                           |
| <i>Celmisia pugioniformis</i>                           | 0.05       |              |                             | s                                            |
| <i>Chrysocephalum apiculatum</i>                        | 0.1        |              |                             | p                                            |
| <i>Coronidium monticola</i>                             | 1.25       |              |                             | s                                            |
| <i>Craspedia aurantia</i>                               | 0.45       |              |                             | s                                            |
| <i>Craspedia costiniana</i>                             | 0.25       |              |                             | s                                            |
| <i>Erigeron bellidioides</i>                            | 0.05       |              |                             | s                                            |
| <i>Leptorhynchus squamatus</i><br>subsp. <i>Alpinus</i> | 0.05       |              |                             | *s                                           |
| <i>Leucochrysum albicans</i>                            | 0.25       |              |                             | s                                            |
| <i>Microseris lanceolata</i>                            | 0.05       |              |                             | *p                                           |
| <i>Myriophyllum alpinum</i>                             |            | 550          |                             | s – C (division)                             |
| <i>Neopaxia australasica</i>                            |            | 550          |                             | s – C (division)                             |
| <i>Oreomyrrhis eriopoda</i>                             | 0.05       |              |                             | *s                                           |
| <i>Ranunculus graniticola</i>                           | 0.1        |              |                             | s                                            |
| <i>Ranunculus inundatus</i>                             | 0.1        |              |                             | s                                            |
| <i>Ranunculus lappaceus</i>                             | 0.1        |              |                             | s                                            |
| <i>Ranunculus millanii</i>                              | 0.25       |              |                             | s                                            |
| <i>Ranunculus pimpinellifolius</i>                      | 0.15       |              |                             | s                                            |
| <i>Scleranthus biflorus</i>                             |            | 300          |                             | s – C (division)                             |
| <i>Senecio gunnii</i>                                   | 0.05       |              |                             | p                                            |
| <i>Senecio quadridentatus</i>                           | 0.15       |              |                             | s                                            |
| <i>Stellaria angustifolia</i>                           |            | 250          |                             | s - C                                        |
| <i>Stellaria pungens</i>                                |            | 1250         |                             | p - C                                        |
| <i>Stylidium graminifolium</i>                          | 1.05       |              |                             | *s                                           |
| <i>Viola betonicifolia</i>                              | 0.15       |              |                             | *s                                           |
| <i>Carex appressa</i>                                   | 0.65       |              |                             | *p                                           |
| <i>Carex breviculmis</i>                                | 0.9        |              |                             | *p                                           |
| <i>Carex gaudichaudiana</i>                             | 1          |              |                             | s – C (division)                             |
| <i>Carex inversa</i>                                    | 0.05       |              |                             | s                                            |
| <i>Poa clivicola</i>                                    | 0.7        |              |                             | *p                                           |
| <i>Poa costiniana</i>                                   | 1.4        |              |                             | p                                            |

PCT TARGET SPECIES LIST (Species listed for active rehabilitation)

|                                                         |              |              |  |       |
|---------------------------------------------------------|--------------|--------------|--|-------|
| <i>Poa helmsii</i>                                      | 0.05         |              |  | *p    |
| <i>Poa labillardierei</i>                               | 1.8          |              |  | *p    |
| <i>Poa labillardierei</i> var.<br><i>labillardierei</i> | 0.85         |              |  | p     |
| <i>Poa phillipsiana</i>                                 | 0.1          |              |  | *p    |
| <i>Poa sieberiana</i>                                   | 0.7          |              |  | *p    |
| <i>Poa sieberiana</i> var. <i>cyanophylla</i>           | 1            |              |  | s     |
| <i>Poa sieberiana</i> var. <i>sieberiana</i>            | 0.4          |              |  | s     |
| <i>Themeda triandra</i>                                 | 0.15         |              |  | *p    |
| <b>Total</b>                                            | <b>16.65</b> |              |  |       |
|                                                         |              |              |  |       |
| <b>Shrubs</b>                                           |              |              |  |       |
| <i>Epacris breviflora</i>                               |              | 250          |  | s - C |
| <i>Epacris gunnii</i>                                   |              | 150          |  | s - C |
| <i>Epacris microphylla</i>                              |              | 45           |  | s - C |
| <i>Richea continentis</i>                               |              | 30           |  | p - C |
| <i>Bossiaea foliosa</i>                                 |              | 25           |  | *s    |
| <i>Cassinia monticola</i>                               |              | 55           |  | s     |
| <i>Hakea microcarpa</i>                                 |              | 25           |  | *p    |
| <i>Olearia myrsinoides</i>                              |              | 35           |  | s     |
| <i>Ozothamnus cupressoides</i>                          |              | 125          |  | *p    |
|                                                         | <b>Total</b> | <b>3,590</b> |  |       |

Note:

1. Tables to be updated following first round of rehabilitation monitoring to included species presence
2. Stems per hectare used as a guide, to be updated to reflect interquartile range from reference sites.
3. KG per Ha to be re-evaluated after monitoring.