

Weekly Vehicle-320 - English (ENA)

Datasets:

Site: [Elderslie Road] 235m south of Stanhope Road Intersection
Attribute: [-32.607995 +151.347356]
Direction: 7 - North bound A>B, South bound B>A. Lane: 0
Survey Duration: 10:02 Wednesday, 26 July 2023 => 12:57 Monday, 21 August 2023,

Filter time: 0:00 Monday, 31 July 2023 => 0:00 Monday, 7 August 2023
Scheme: Vehicle classification (ARX)
Filter: CIs(1-12) Dir(NESW) Sp(10,160) Headway(>0) Span(0 - 100) Lane(0-16)

	Mon 31 Jul	Tue 01 Aug	Wed 02 Aug	Thu 03 Aug	Fri 04 Aug	Sat 05 Aug	Sun 06 Aug	Averages 1 - 5	1 - 7
Hour									
0000-0100	5	2	2	5	4	4	6	3.6	4.0
0100-0200	1	2	2	2	4	5	1	2.2	2.4
0200-0300	1	5	3	1	2	2	1	2.4	2.1
0300-0400	3	1	2	2	1	1	3	1.8	1.9
0400-0500	44	43	57	54	50	9	6	49.6	37.6
0500-0600	148	164	154	144	108	15	8	143.6	105.9
0600-0700	79	105	106	100	76	24	10	93.2	71.4
0700-0800	112	107	135	121	118	64	44	118.6	100.1
0800-0900	120	133	120	103	131	111	57	121.4	110.7
0900-1000	92	70	86	87	102	128	92	87.4	93.9
1000-1100	71	112	83	81	117	121	90	92.8	96.4
1100-1200	78	75	96	90	94	119	114	86.6	95.1
1200-1300	86	67	76	80	98	132	107	81.4	92.3
1300-1400	90	81	84	87	104	110	103	89.2	94.1
1400-1500	110	102	119	117	384	121	88	166.4	148.7
1500-1600	164	174	247	219	607	94	115	282.2	231.4
1600-1700	304	431	466	488	499	118	108	437.6	344.9
1700-1800	241	340	382	369	277	104	78	321.8	255.9
1800-1900	90	92	102	91	92	61	41	93.4	81.3
1900-2000	24	45	41	45	55	29	27	42.0	38.0
2000-2100	23	20	16	25	36	31	11	24.0	23.1
2100-2200	10	12	12	25	29	39	23	17.6	21.4
2200-2300	4	7	10	5	5	13	8	6.2	7.4
2300-2400	4	5	3	3	17	17	5	6.4	7.7
Totals									
0700-1900	1558	1784	1996	1933	2623	1283	1037	1978.8	1744.9
0600-2200	1694	1966	2171	2128	2819	1406	1108	2155.6	1898.9
0600-0000	1702	1978	2184	2136	2841	1436	1121	2168.2	1914.0
0000-0000	1904	2195	2404	2344	3010	1472	1146	2371.4	2067.9
AM Peak	0500 148	0500 164	0500 154	0500 144	0800 131	0900 128	1100 114		
PM Peak	1600 304	1600 431	1600 466	1600 488	1500 607	1200 132	1500 115		

Friday

3-4

607
Ph.

Wed

4-5 466

Thurs

4-5-488

Peak times
morning 100ph
regular
avo.
200ph.

Proposal:

It is proposed to:

- Request that TfNSW arrange for Elderslie Bridge is brought up to current delineation standards for a one lane bridge.
- Install temporary traffic signals at either end of the bridge operating at AM an peak times.

TGS 'Elderslie Bridge – Temporary Traffic Signals' attached as AT-1 shows the pro layout of the temporary traffic signals and associated temporary signage.

Outside of peak times, the temporary traffic signals would not be in operation and the permanent GIVE WAY sign on the north-westbound approach would be operational