

14 September 2020

Our Ref: 186831

Susan Fox

Senior Environmental Assessment Officer

Industry Assessments

Department of Planning, Industry and Environment

4 Parramatta Square, 12 Darcy Street, Parramatta NSW 2150

E: susan.fox@planning.nsw.gov.au

RE: State Significant Development – Chullora Material Recycling Facility (SSD-10401)

Thank you for notifying Sydney Water of abovementioned SSD which proposes the construction and operation of a materials recovery facility (MRF) with a maximum throughput up to 172,000 tonnes per annum of waste. Sydney Water has reviewed the application based on the information supplied and provides the following comments to assist in planning the servicing needs of the proposed development.

Water and Wastewater Servicing

- Sydney Water has no objection to the proposal.
- The proponent will require a Section 73 application via a WSC and when they lodge the application, **they must include a plan showing where the development intends to connect.**
- Depending on the proposed connection / discharge location a wastewater minor extension may also be required.
- Amplification and/or extensions of the water network may be required.

Critical Assets:

- Sydney Water has a significant 2400mm SCL IBL trunk wastewater main (laid in 1957) within the property boundary and located directly underneath the proposed development.
- Sydney Water has a significant 525mm CONC branch wastewater main (laid in 1960) within the property boundary and the proposed development may encroach on this main's easement.
- The proponent will need to engage a WSC to submit mark-up easements plans for the proposed development in relation to these critical assets.
- Due to the age, material and significance of these assets, an out of scope Building Over and Adjacent application may be required to ensure there is no impact to the asset. The proponent must follow the Building Plan Approval process outlined in Attachment 1.

Stormwater

Building over or adjacent to stormwater assets

- As the subject development is adjacent to Sydney Water's stormwater channel, following requirements would apply:
- No building or permanent structure is to be proposed over the stormwater channel / pipe or within **1m** from the outside wall of the channel / pipe or within Sydney Water easement

whichever is larger. Permanent structures include (but are not limited to) basement car park, hanging balcony, roof eaves, hanging stairs, stormwater pits, stormwater pipes, elevated driveway, basement access or similar structures. This clearance requirement would apply for unlimited depth and height.

- The applicant is required to submit the elevation drawings with the stormwater channel, to ensure that the proposed buildings and permanent structures are 1m away from the outside face of the stormwater channel and away from the Sydney Water easement.

Stormwater connections to Sydney Water's Stormwater Channel

- Stormwater discharge from the development site is to be according to Sydney Water's stormwater connection requirements. Details of these connection requirements would be provided as part of the Section 73 application for this development.

This advice is not formal approval of our servicing requirements. Detailed requirements, including any potential extensions or amplifications, will be provided once the development is referred to Sydney Water for a Section 73 application. More information about the Section 73 application process is available on our web page in the [Land Development Manual](#).

Further advice and requirements for this proposal are in Attachments 1 & 2. If you require any further information, please contact the Growth Planning Team at urbangrowth@sydneywater.com.au.

Yours sincerely,



Kristine Leitch

Growth Intelligence Manager

City Growth and Development, Business Development Group

Sydney Water, 1 Smith Street, Parramatta NSW 2150

Attachment 1

Sydney Water Servicing

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water.

The proponent is advised to make an early application for the certificate, as there may be water and wastewater pipes to be built that can take some time. This can also impact on other services and buildings, driveways or landscape designs.

Applications must be made through an authorised Water Servicing Coordinator. For help either visit www.sydneywater.com.au > Plumbing, building and developing > Developing > Land development or telephone 13 20 92.

Building Plan Approval

The approved plans must be submitted to the Sydney Water [Tap in™](#) online service to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met.

The Sydney Water [Tap in™](#) online self-service replaces our Quick Check Agents as of 30 November 2015.

The [Tap in™](#) service provides 24/7 access to a range of services, including:

- building plan approvals
- connection and disconnection approvals
- diagrams
- trade waste approvals
- pressure information
- water meter installations
- pressure boosting and pump approvals
- changes to an existing service or asset, e.g. relocating or moving an asset.

Sydney Water's [Tap in™](#) online service is available at:

<https://www.sydneywater.com.au/SW/plumbing-building-developing/building/sydney-water-tap-in/index.htm>

Attachment 2

Requirements for **Business Customers for Commercial and Industrial Property Developments.**

Trade Wastewater Requirements

If this development is going to generate trade wastewater, the property owner must submit an application requesting permission to discharge trade wastewater to Sydney Water's sewerage system. You must obtain Sydney Water approval for this permit before any business activities can commence. It is illegal to discharge Trade Wastewater into the Sydney Water sewerage system without permission.

The permit application should be emailed to Sydney Water's [Business Customer Services](mailto:businesscustomers@sydneywater.com.au) at businesscustomers@sydneywater.com.au

A Boundary Trap is required for all developments that discharge trade wastewater where arrestors and special units are installed for trade wastewater pre-treatment.

If the property development is for Industrial operations, the wastewater may discharge into a sewerage area that is subject to wastewater reuse. Find out from Business Customer Services if this is applicable to your development.

Backflow Prevention Requirements

Backflow is when there is unintentional flow of water in the wrong direction from a potentially polluted source into the drinking water supply.

All properties connected to Sydney Water's supply must install a testable Backflow Prevention Containment Device appropriate to the property's hazard rating. Property with a high or medium hazard rating must have the backflow prevention containment device tested annually. Properties identified as having a low hazard rating must install a non-testable device, as a minimum.

Separate hydrant and sprinkler fire services on non-residential properties, require the installation of a testable double check detector assembly. The device is to be located at the boundary of the property.

Before you install a backflow prevention device:

1. Get your hydraulic consultant or plumber to check the available water pressure versus the property's required pressure and flow requirements.
2. Conduct a site assessment to confirm the hazard rating of the property and its services. Contact PIAS at NSW Fair Trading on 1300 889 099.

For installation you will need to engage a licensed plumber with backflow accreditation who can be found on the Sydney Water website:

<http://www.sydneywater.com.au/Plumbing/BackflowPrevention/>

Water Efficiency Recommendations

Water is our most precious resource and every customer can play a role in its conservation. By working together with Sydney Water, business customers are able to reduce their water consumption. This will help your business save money, improve productivity and protect the environment.

Some water efficiency measures that can be easily implemented in your business are:

- Install water efficiency fixtures to help increase your water efficiency, refer to WELS (Water Efficiency Labelling and Standards (WELS) Scheme, <http://www.waterrating.gov.au/>
- Consider installing rainwater tanks to capture rainwater runoff, and reusing it, where cost effective. Refer to <http://www.sydneywater.com.au/Water4Life/InYourBusiness/RWTCalculator.cfm>
- Install water-monitoring devices on your meter to identify water usage patterns and leaks.
- Develop a water efficiency plan for your business.

It is cheaper to install water efficiency appliances while you are developing than retrofitting them later.

Contingency Plan Recommendations

Under Sydney Water's [customer contract](#) Sydney Water aims to provide Business Customers with a continuous supply of clean water at a minimum pressure of 15meters head at the main tap. This is equivalent to 146.8kpa or 21.29psi to meet reasonable business usage needs.

Sometimes Sydney Water may need to interrupt, postpone or limit the supply of water services to your property for maintenance or other reasons. These interruptions can be planned or unplanned.

Water supply is critical to some businesses and Sydney Water will treat vulnerable customers, such as hospitals, as a high priority.

Have you thought about a contingency plan for your business? Your Business Customer Representative will help you to develop a plan that is tailored to your business and minimises productivity losses in the event of a water service disruption.

For further information please visit the Sydney Water website at:

<http://www.sydneywater.com.au/OurSystemsandOperations/TradeWaste/> or contact Business Customer Services on 1300 985 227 or businesscustomers@sydneywater.com.au.