

DOC18/893887-2 19/12/18 SSD 9344

Mr Navdeep Shergill Department of Planning and Environment GPO BOX 39 SYDNEY NSW 2001

Dear Mr Shergill

## SSD 9344 - KENT ROAD PUBLIC SCHOOL RE-DEVELOPMENT - ENVIRONMENTAL IMPACT STATEMENT (EIS)

I am writing to you in reply to your invitation to the Environment Protection Authority (EPA) to make a submission concerning the above project EIS.

The EPA requests that this submission be read in conjunction with its letter dated 22 June 2018 in respect of the draft Secretary's environmental assessment requirements for the project.

The EPA emphasises that it does not review or endorse environmental management plans or the like for reasons of maintaining regulatory 'arm's length'. As such, the EPA has not reviewed any environmental management plan forming part of or referred to in the EIS.

Section 3.2 of the EIS describes the development site as the whole of the school campus. However, EIS architectural drawing SSDA-0400 indicates that the development site is proposed to be limited to northeast corner of the school campus which is referred to as the "... buildable area ..." shaded orange on Drawing SSDA-0201. The EPA notes that the overall school campus includes outdoor sports courts and the existing school hall (i.e. Block N) which adjoins the proposed new structures. The EPA considers that the project is an integral part of the overall campus and is unclear what practical distinction might be drawn between operational environmental impacts (e.g. noise, cumulative) from activities on the "... buildable area ..." and those from the overall school campus. Accordingly, the EPA has reviewed the impacts of the proposed works as an integral part of the overall campus.

Section 4.0 of the EIS indicates that the project includes 'site preparation' but is unclear about whether site preparation includes demolition of existing structures (i.e. G, F K and L), infrastructure and underground services (and associated site disturbance) within the so-called "... buildable area ..." (viz drawing).

The EPA has identified the following site specific concerns based on the project information available on the Department of Planning and Environment major projects web site:

(a) the need for a detailed assessment of potential site contamination, including information about groundwater and a detailed assessment of the footprint and surrounds of existing buildings. infrastructure and underground services following their demolition;

Fax +61 2 9995 5999

- (b) demolition/construction phase noise and vibration impacts (including recommended standard construction hours and intra-day respite periods for highly intrusive noise generating work) on noise sensitive receivers such as surrounding residences;
- (c) demolition/construction phase dust control and management,
- (d) demolition/construction phase erosion and sediment control and management;
- (e) operational noise impacts on noise sensitive receivers (especially surrounding residences on adjoining holdings) arising from operational activities such as public address/school bell systems, community use of school facilities, waste collection services and mechanical services (especially air conditioning plant);
- (f) the need to assess feasible and reasonable noise mitigation and management measures (including time restrictions on the use of the facilities proposed to be available for community use) to minimise operational noise impacts on surrounding residences;
- (g) practical opportunities to implement water sensitive urban design principles, including stormwater re-use; and
- (h) practical opportunities to minimise consumption of energy generated from non-renewable sources and to implement effective energy efficiency measures.

Should you require clarification of any of the above please contact John Goodwin on 9995 6838.

Yours sincerely

SARAH THOMSON

food thoman

Unit Head, Metropolitan Infrastructure NSW Environment Protection Authority

Attachment A

Contact officer: JOHN GOODWIN

### **ATTACHMENT A**

### **ENVIRONMENT PROTECTION AUTHORITY COMMENTS**

### KENT ROAD PUBLIC SCHOOL RE-DEVELOPMENT

### 1. General

The EPA considers that the project comprises distinct phases of construction and operation and has set out its comments on that basis.

The EPA notes the proximity of surrounding residences which may be adversely affected by noise impacts during demolition, site preparation, construction and operation phases of the project.

## 2. Construction phase

The EPA anticipates that site establishment, demolition, bulk earthworks, construction and construction-related activities will be undertaken in an environmentally responsible manner with particular emphasis on:

- the site contamination remediation action plan accompanying the EIS,
- compliance with recommended standard construction hours,
- intra-day respite periods from high noise generating construction activities (including jack hammering, rock breaking, pile boring or driving, saw cutting),
- feasible and reasonable noise and vibration minimisation and mitigation,
- effective dust control and management,
- erosion and sediment control, and
- waste handling and management, particularly concrete waste and rinse water.

### 2.1 Site contamination (including hazardous building materials)

The EPA notes with concern that the soil and groundwater contamination assessment was limited to 5,500 square metres of the 40,000 square metre campus (i.e. development site). Accordingly, the proponent has not undertaken sampling at a sufficient number of locations required to properly characterise soil and groundwater contamination in accordance with the NSW Sampling Design Guidelines.

EIS Appendix P 'Preliminary Site Investigation' concluded that the site was a low risk of contamination despite acknowledging previous use as an orchard and market garden and limitation of the assessment to a visual inspection and desktop study. The EPA is not aware of supporting material to confirm the low risk assessment.

Section 1 to EIS Appendix Q reports that despite a subsequent due diligence soil contamination investigation confirmed the prior history of the campus as an orchard and market garden as well as identification of fill material of unknown origin, a fill mound at the eastern end of the site, asbestos containing building materials and lead-based paint.

The EPA anticipates that given the age of some of the structures on the development site, asbestos containing materials and lead-based paints are likely to be encountered during demolition. However, the EIS does not appear to be accompanied by a hazardous building materials survey.

Since late 2015, clause 79 of the Waste Regulation has required transporters of loads of asbestos waste to provide certain details of the loads to the EPA using the "WasteLocate" system. These details include details of the source site, date of proposed transport, details of the proposed destination site and the approximate weight of asbestos waste in the load. The information must be provided to the EPA before transportation of the load commences.

WasteLocate is an online tool that allows the EPA to track the transport of asbestos waste. Transporters are required to use WasteLocate to report the movement of more than 100 kilograms of asbestos waste or more than 10 square metres of asbestos sheeting within NSW. The details can be reported on WasteLocate by using an app on a mobile phone or tablet or by using a computer.

The EPA considers that there are too many data gaps to allow development to proceed without a detailed investigation of soil and groundwater contamination across the whole of the development site (including within and immediately surrounding the footprint of structures, infrastructure and underground services proposed to be demolished).

### Recommendations

- 1. The proponent be required, prior to commencing any demolition work, to undertake and report a hazardous building materials survey of all structures, infrastructure and underground services proposed for demolition.
- 2. The proponent be required (prior to commencing any work on the development site) to prepare and implement a procedure for identifying and dealing with unexpected finds of site contamination (including asbestos containing materials, lead-based paint and PCBs) and to include in that procedure details of who will be responsible for implementing the unexpected finds procedure and the roles and responsibilities of all parties involved
- 3. The proponent be required to satisfy the requirements of the Protection of the Environment Operations (Waste) Regulation 2014 with particular reference to Part 7 'asbestos wastes'.

**Note:** The EPA provides additional guidance material at its web-site

http://www.environment.nsw.gov.au/waste/asbestos/index.htm.

- 4. The proponent be required to consult with Safework NSW concerning the handling of any asbestos waste that may be encountered during the course of the project.
- 5. The proponent be required to undertake further detailed site investigation at such number of additional sampling locations, consistent with the NSW Sampling Design Guidelines, sufficient to properly characterise soil and groundwater contamination of the development site.
- 6. The proponent be required to remove asbestos contaminated soil from the development site (i.e. school campus) for disposal at a waste facility legally able to accept that waste.
- 7. The proponent be required to:
  - (a) engage a site auditor accredited under the Contaminated Land Management Act 1997; and
  - (b) provide a Section A site audit statement (SAS) and accompanying site audit report (SAR) prepared following completion of remediation and validation certifying suitability of the development site for the proposed use prior to undertaking any construction.

- 8. The proponent be required to ensure that:
  - (a) additional investigation, including the footprint of relocated and demolished structures, infrastructure and underground services, is undertaken and the scope of that investigation detailed in a sampling and analysis quality plan to be provided to the site auditor for review;
  - (b) a data gap contamination assessment is undertaken that includes a Conceptual Site Model, assessment of risks to on-site and off-site arising from any on-site contamination and provides conclusions concerning the suitability of the development site for the proposed use;
  - (c) further details of the proposed remediation and validation strategy are provided to the site auditor in a Works Plan and a Validation Sampling and Analysis Quality Plan (VSAQP) for review by the site auditor prior to remediation commencing any remediation;
  - (d) an asbestos management plan (AMP) is prepared and submitted to the site auditor for review; and
  - (e) a long term Environmental Management Plan (LTEMP) is prepared following remediation of the development site to document -
    - (i) the expected limitations on the development site use,
    - (ii) relevant environmental and health and safety processes and procedures,
    - (iii) management processes, procedures and responsibilities to be adopted by future site users within the development site, and
    - (iv) details on the location and extent of placed or residual asbestos contaminated fill materials, capping layers and marker barriers within the development site.
- 9. That the proponent be required to implement the recommendations of the Remedial Action Plan as conditioned by the accredited site auditor.
- 10. The proponent be required consider the guidance material provided in the *National Environment Protection (Assessment of Site Contamination) Measure* as well as the following EPA documents when undertaking further site assessment -
  - Technical Note: Investigation of Service Station Sites, 2014,
  - NSW EPA Sampling Design Guidelines,
  - Guidelines for the NSW Site Auditor Scheme (3<sup>rd</sup> edition) 2017, and
  - Guidelines for Consultants Reporting on Contaminated Sites, 2011.
- 11. The proponent be required to ensure that the processes outlined in *State Environmental Planning Policy 55 Remediation of Land (SEPP55)* are followed in assessing the suitability of the land and any remediation required in relation to the proposed use.
- 12. The proponent be required to ensure that the proposed development does not result in a change of risk in relation to any pre-existing contamination on the site so as to result in significant contamination
- 13. The proponent be required to notify the EPA should any contamination of the development site be identified which meets the triggers in the *Guidelines for the Duty*

## 2.2 Noise and vibration

The EPA anticipates that demolition, site preparation (including tree clearing), bulk earthworks, construction and construction-related activities are likely to have significant noise and vibration impacts on surrounding residences, especially adjoining residences. EIS section 4.13 indicates proposed construction hours consistent with recommended standard construction hours.

### 2.2.1 general construction hours

The EPA emphasises that demolition, site preparation, bulk earthworks, construction and constructionrelated activities should be undertaken during the recommended standard construction hours.

### Recommendation

The proponent be required to ensure that as far as practicable all demolition, site preparation, bulk earthworks, construction and construction-related activities likely to be audible at any noise sensitive receivers such as surrounding residences are only undertaken during the standard construction hours, being -

- (a) 7.00 am to 6.00 pm Monday to Friday,
- (b) 8.00 am to 1.00 pm Saturday, and
- (c) no work on Sundays or gazetted public holidays.

## 2.2.2 intra-day respite periods

The EPA anticipates that those demolition, site preparation, bulk earthworks, construction and construction-related activities generating noise with particularly annoying or intrusive characteristics (such as those identified as particularly annoying in section 4.5 of the Interim Construction Noise Guideline) would be subject to a regime of intra-day respite periods where –

- (a) they are only undertaken after 8.00 am,
- (b) they are only undertaken over continuous periods not exceeding 3 hours with at least a 1 hour respite every three hours, and
- (c) 'continuous' means any period during which there is less than an uninterrupted 60 minute respite between temporarily halting and recommencing any of the intrusive and annoying work referred to in Interim Construction Noise Guideline section 4.5.

The EPA emphasises that intra-day respite periods are not proposed to apply to those demolition, site preparation, bulk earthworks, construction and construction-related activities that do not generate noise with particularly annoying or intrusive characteristics.

### Recommendation

The proponent be required to schedule intra-day 'respite periods' for construction activities identified in section 4.5 of the Interim Construction Noise Guideline as being particularly annoying to noise sensitive receivers, including surrounding residents.

### 2.2.3 idling and queuing construction vehicles

The EPA is aware from previous major infrastructure projects that community concerns are likely to arise from noise impacts associated with the early arrival and idling of construction vehicles (including concrete agitator trucks) at the development site and in the residential precincts surrounding that site.

### Recommendation

The proponent be required to ensure construction vehicles (including concrete agitator trucks) involved in demolition, site preparation, bulk earthworks, construction and construction-related activities do not arrive at the project site or in surrounding residential precincts outside approved construction hours.

## 2.2.4 reversing and movement alarms

The EPA has identified the noise from 'beeper' type plant movement alarms to be particularly intrusive and is aware of feasible and reasonable alternatives. Transport for NSW, Barangaroo Delivery Authority/Lend Lease and Leighton Contractors have undertaken safety risk assessments of alternatives to the traditional 'beeper' alarms. Each determined that adoption of 'quacker' type movement/reversing alarms instead of traditional beepers on all plant and vehicles would not only maintain a safe workplace but also deliver improved outcomes of reduced noise impacts on surrounding residents. The Interim Construction Noise Guideline Appendix C provides additional background material on this issue.

### Recommendation

The proponent be required to consider undertaking a safety risk assessment of site preparation, bulk earth works, construction and construction-related activities to determine whether it is practicable to use audible movement alarms of a type that would minimise the noise impact on surrounding noise sensitive receivers, without compromising safety.

## 2.3 Dust control and management

The EPA considers dust control and management to be an important air quality issue during demolition, site preparation, bulk earthworks and subsequent construction.

## Recommendation

The proponent be required to minimise dust emissions on the site, and prevent dust emissions from the site.

## 2.4 Sediment control

Managing Urban Stormwater Soils and Construction, 4<sup>th</sup> Edition published by Landcom (the so-called 'Blue Book') provides guidance material for achieving effective sediment control on construction sites. The proponent should implement all such feasible and reasonable measures as may be necessary to prevent water pollution in the course of developing the site.

The EPA emphasises the importance of –

- (a) not commencing demolition, site preparation, bulk earthworks, construction and constructionrelated activities until appropriate and effective sediment controls are in place, and
- (b) daily inspection of sediment controls which is fundamental to ensuring timely maintenance and repair of those controls.

## 2.5 <u>Waste control and management (general)</u>

The proponent should manage waste in accordance with the waste management hierarchy. The waste hierarchy, established under the <u>Waste Avoidance and Resource Recovery Act 2001</u>, is one that ensures that resource management options are considered against the following priorities:

**Avoidance** including action to reduce the amount of waste generated by households, industry and all levels of government

**Resource recovery** including reuse, recycling, reprocessing and energy recovery, consistent with the most efficient use of the recovered resources

**Disposal** including management of all disposal options in the most environmentally responsible manner.

All wastes generated during the project must be properly assessed, classified and managed in accordance with the EPA's guidelines to ensure proper treatment, transport and disposal at a landfill legally able to accept those wastes.

The EPA further anticipates that, without proper site controls and management, mud and waste may be tracked off the site during the course of the project.

### Recommendation

The proponent be required to ensure that:

- (1) all waste generated during the project is assessed, classified and managed in accordance with the EPA "Waste Classification Guidelines Part 1: Classifying Waste", November 2014 and the 2016 Addendum thereto;
- (2) the body of any vehicle or trailer, used to transport waste or excavation spoil from the premises, is covered before leaving the premises to prevent any spill or escape of any dust, waste, or spoil from the vehicle or trailer; and
- (3) mud, splatter, dust and other material likely to fall from or be cast off the wheels, underside or body of any vehicle, trailer or motorised plant leaving the site, is removed before the vehicle, trailer or motorised plant leaves the premises.
- 2.6 <u>Waste control and management (concrete and concrete rinse water)</u>

The EPA anticipates that during the course of the project concrete deliveries and pumping are likely to generate significant volumes of concrete waste and rinse water. The proponent should ensure that concrete waste and rinse water is not disposed of on the project site and instead that –

- (a) waste concrete is either returned in the agitator trucks to the supplier or directed to a dedicated watertight skip protected from the entry of precipitation, and
- (b) concrete rinse water is directed to a dedicated watertight skip protected from the entry of precipitation or a suitable water treatment plant.

### Recommendation

The proponent be required to ensure that concrete waste and rinse water are

- (a) not disposed of on the development site, and
- (b) prevented from entering waters, including any natural or artificial watercourse.

### 3. Operational phase

The EPA considers that environmental impacts that arise once the development is operational should be able to be largely averted by responsible environmental management practices, particularly with regard to:

(a) feasible and reasonable noise mitigation measures;

- (b) waste management in accordance with the waste management hierarchy;
- (c) water sensitive urban design; and
- (d) energy conservation and efficiency.

### 3.1 Noise and vibration impacts

The EPA anticipates the proposed development (especially out of hours use of school facilities by external parties) may have significant operational noise impacts on nearby sensitive receivers, especially adjoining residences.

The EPA notes with concern the proximity of the surrounding residences and is aware from long experience of the need for appropriate operational noise mitigation and management measures, particularly in regard to:

- (a) the nature of and times during which school facilities are made available for community use;
- (b) the design and operation of the school public address/bell system;
- (c) the design and location of waste storage facilities;
- (d) time restrictions on waste collection services;
- (e) design, selection and operation of mechanical ventilation plant and equipment; and
- (f) time restrictions on grounds maintenance using powered equipment (e.g. leaf blowers, brush cutters and lawn mowers).

## Out of hours' community use of school facilities

The EPA is aware of government policy to encourage out of hours community use of school facilities provided that use does not cause noise emissions that interfere unreasonably with the comfort or repose of persons not on the premises.

The EPA considers that, in relation to the school hall, noise from normal school activities in class hours would not be acoustically significant. However, the use of the hall for other events, particularly outside school hours, has the potential to adversely impact on residences. The EPA notes that whilst section 6.2 to EIS Appendix O is headed 'Noise from Internal Areas (Classrooms and School Hall)' the discussion appears to be limited to noise from classrooms.

The EPA considers the proposed community use of school facilities (especially the hall and outdoor sports courts) outside normal school hours needs to be carefully managed to ensure noise impacts on nearby residences are minimised.

### Recommendations

- The proponent be required to ensure that the outdoor sports courts are not made available for community use –
  - (i) during week day mornings,
  - (ii) later than 6.00 pm on week nights,
  - (iii) other than between the hours of 8.00 am and 6.00 pm on Saturdays, and
  - (iv) during Sundays and public holidays.

- 2. The proponent be required to -
  - (a) undertake comprehensive noise compliance monitoring of representative uses of the school hall and outdoor sports courts and associated facilities (e.g. parking) outside school hours to demonstrate that the level, nature, quality and character of noise emitted by those uses and the time at which and frequency of those uses would not interfere unreasonably with or be likely to interfere unreasonably with the comfort or repose of persons not on the development site, especially the occupants of nearby residences.
  - (b) submit a detailed noise compliance monitoring report with noise measurements reported against relevant noise criteria and the outcomes of appropriate community consultation together with detailed recommendations concerning any additional feasible and reasonable noise mitigation and management measures, including further or more relaxed restrictions on the times at which and the frequency of each type of use of the school hall and outdoor sports courts and associated facilities (e.g. parking) outside school hours.
  - (c) ensure that noise compliance monitoring referred to in paragraph (a) above, would include quantitative noise impact assessment to address noise emissions arising from amongst other things
    - audience/spectator noise,
    - referee whistle noise,
    - training sessions as well as sporting events,
    - any amplified sound during sporting events and any associated training sessions, and
    - post-event audience/spectator noise, including vehicle door slamming and departure noise.

## Mechanical plant and equipment

Section 6.4 to EIS Appendix O states that in regard to mechanical services, plant and equipment "... plant selections and locations are not finalised."

## Recommendation

The proponent be required to:

- (a) provide a comprehensive quantitative assessment of operational noise impacts of mechanical plant and equipment (especially ventilation and air conditioning plant and equipment) on surrounding noise sensitive receivers, especially adjoining residences;
- (b) ensure mechanical plant and equipment installed on the development site does not generate—
  - (i) noise that exceeds the project noise trigger levels (day, evening and night) measured at the boundary of the development site, and
  - (ii) noise that exhibits tonal or other annoying characteristics.

## Public address and school bell system

The EPA notes numerous reports of community concern arising from inadequate design and installation as well as inappropriate use of school public address and bell systems and considers that appropriate design, installation and operation of those systems can both –

- meet the proponent's objectives of proper administration of the school and ensuring the safety
  of students, staff and visitors, and
- avoid interfering unreasonably with the comfort and repose of occupants of nearby residences.

### Recommendation

The proponent be required to design, install and operate the school public address/bell system to implement all such other measures as may be necessary to ensure use of that system does not interfere unreasonably with the comfort and repose of occupants of nearby residences.

## Waste collection services

The EPA notes numerous reports of community concern arising from waste collection services undertaken at schools and especially during evening and night times.

#### Recommendation

The proponent be required ensure waste collection services are not undertaken outside the hours of 7.30 am to 6.00 pm Monday to Friday.

## Grounds maintenance using powered equipment

The EPA notes numerous reports of community concern arising from grounds maintenance involving the use of powered equipment (example: leaf blowers, lawn mowers, brush cutters) at schools during early morning and evening periods as well as on weekends and public holidays.

### Recommendation

The proponent be required ensure grounds maintenance involving the use of powered equipment is not undertaken outside the hours of 7.30 am to 6.00 pm Monday to Friday.

## 3.2 Waste management

The proponent should manage waste in accordance with the waste management hierarchy outlined above.

#### Recommendation

The proponent be required to identify and implement feasible and reasonable opportunities for the reuse and recycling of waste, including food waste.

# 3.3 Water sensitive urban design and energy conservation and efficiency

The EPA acknowledges that EIS Appendix X comprises an environmentally sustainable development report that proposes –

- (a) a range of water sensitive urban design measures, including
  - (i) rainwater harvesting and re-use, and
  - (ii) water efficient fixtures; and
- (b) a range of measures to maximise energy efficiency and minimise energy consumption, including installation of rooftop solar photovoltaic arrays (see Drawing SSDA-1300)

.....