

| | | | | | | | |
|----------------------|-------------------------------------|------------------|---|--------------------------|--|-------------------------|---|
| Plan of: | Metford Rehabilitation Domain Areas | Location: | Metford Clay Mine Metford Rd, Metford NSW 2320 | Source: | Contours updated by GPS 22/5/07 Boundaries Monteath & Powys | Our Ref: | V:\Jobs_MT\2013\ClosurePlan\Figs\CPMOPMT.cdr |
| Figure: | Nine (MT13A) | Council: | Maitland City Council | Survey: | AAM Hatch 27/2/06 | Plan By: | LGT |
| Sheet: | 1 of 1 | Tenures: | ML 1523, 4589, 875, 2843, 5848, 4865, 5090 | Projection: | MGA | Project Manager: | GVT |
| Version/Date: | A 26/03/2014 | Client: | CSR Building Products Ltd | Contour Interval: | 1m | Office: | Thornton |
| | | | | | | Scale: | |



| Legend | | | | | | | |
|-----------------|---|-----------------|---|-----------------|---|-----------------|--|
| Domain A | Disturbed floor and stockpiles. <u>Action:</u> Fill in low lying areas with stockpile materials, shape to self-drain and apply grasses. | Domain C | Natural steep face with good vegetation. <u>Action:</u> Risk assess to potentially leave | Domain E | The Hill- mix of natural and carbonaceous shale stockpiles, vegetated. <u>Action:</u> None | Domain G | Mixed revegetated land and shallow water bodies. <u>Action:</u> Build access tracks for potential pedestrian use. |
| Domain B | Construction & Demolition batter with some vegetation and some steep slopes. <u>Action:</u> Survey, batter back slopes to 3:1 with available material, apply grasses to disturbed faces. | Domain D | Vegetated bund wall atop steep natural slope. <u>Action:</u> Use existing stockpiles, batter face to 3:1, apply grasses. | Domain F | Mostly revegetated with some aggregate stockpiles. <u>Action:</u> Pick out aggregates and apply grasses to disturbed areas | Domain H | Natural <u>Action:</u> None |
| | | | | | | Lime | Lime stockpile <u>Action:</u> Lime will be mixed with soil to assist with revegetation. |