

12 September 2016

Our Ref: 156784

Mr David Gibson
Team Leader
Social Infrastructure Assessments
Department of Planning & Environment
GPO Box 39, Sydney NSW 2001

**RE: Westmead Hospital Central Acute Services Building
SSD 7642**

Dear Mr Gibson,

Thank you for notifying Sydney Water of the development application listed above. We have reviewed the application and provide the following comments for your consideration.

Water and Wastewater


- The proposed development is located within the Greater Parramatta to Olympic Peninsula Urban Renewal area. Sydney Water is progressing strategic planning for this corridor, with a target completion date of September 2016. The outcome of this project will be an integrated long-term servicing strategy for the corridor that includes drinking water, wastewater, recycled water and stormwater services.
- Initial assessment indicates that there are trunk drinking water and wastewater constraints to service the Westmead Precinct, with system amplifications likely to be required within the next 5 years. Further detailed planning is required to confirm the timeframe and extent of system amplifications for both drinking water and wastewater services, taking into account any additional growth within the corridor. There is currently no recycled water service to the Precinct.
- Servicing strategy for the development will be consistent with strategic servicing plan for the Greater Parramatta. An appropriate connection point and extension of service line and its impact to the existing system downstream will also be assessed when further details are available during Section 73 application.

Sydney Water E-Planning

Sydney Water has an email address for planning authorities to submit statutory or strategic planning documents for review. This email address is urbangrowth@sydneywater.com.au.

Further advice and requirements for this proposal are at attachments 1 and 2 (overleaf). If you require any further information, please contact Manwella Hawell of Urban Growth Strategy on 02 8849 4354 or e-mail manwella.hawell@sydneywater.com.au.

Yours sincerely,

A handwritten signature in blue ink, consisting of a large, stylized 'G' followed by a horizontal stroke.

Greg Joblin
Manager, Growth Strategy

Attachment 1

Sydney Water Servicing

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water.

The proponent is advised to make an early application for the certificate, as there may be water and wastewater pipes to be built that can take some time. This can also impact on other services and buildings, driveways or landscape designs.

Applications must be made through an authorised Water Servicing Coordinator. For help either visit www.sydneywater.com.au > Plumbing, building and developing > Developing > Land development or telephone 13 20 92.

Building Plan Approval

The developer must have the building plans stamped and approved before any construction is commenced. Approval is needed because construction/building works may affect Sydney Water's assets (e.g. Water, sewer and stormwater mains).

For further assistance please telephone 13 20 92 or refer to the Building over or next to assets page on the Sydney Water website (see Plumbing, building and developing then Building over or next to assets).

Attachment 2

Requirements for Business Customers for Commercial and Industrial Property Developments

If this property is to be developed for Industrial or Commercial operations, it may need to meet the following requirements:

Trade Wastewater Requirements

If this development is going to generate trade wastewater, the property owner must submit an application requesting permission to discharge trade wastewater to Sydney Water's sewerage system. You must wait for approval of this permit before any business activities can commence.

The permit application should be emailed to Sydney Water's Business Customer Services at businesscustomers@sydneywater.com.au

It is illegal to discharge Trade Wastewater into the Sydney Water sewerage system without permission.

A Boundary Trap is required for all developments that discharge trade wastewater where arrestors and special units are installed for trade wastewater pre-treatment.

If the property development is for Industrial operations, the wastewater may discharge into a sewerage area that is subject to wastewater reuse. Find out from Business Customer Services if this is applicable to your development.

Backflow Prevention Requirements

Backflow is when there is unintentional flow of water in the wrong direction from a potentially polluted source into the drinking water supply.

All properties connected to Sydney Water's supply must install a testable Backflow Prevention Containment Device appropriate to the property's hazard rating. Property with a high or medium hazard rating must have the backflow prevention containment device tested annually. Properties identified as having a low hazard rating must install a non-testable device, as a minimum.

Separate hydrant and sprinkler fire services on non-residential properties, require the installation of a testable double check detector assembly. The device is to be located at the boundary of the property.

Before you install a backflow prevention device:

1. Get your hydraulic consultant or plumber to check the available water pressure versus the property's required pressure and flow requirements.
2. Conduct a site assessment to confirm the hazard rating of the property and its services. Contact PIAS at NSW Fair Trading on 1300 889 099.

For installation you will need to engage a licensed plumber with backflow accreditation who can be found on the Sydney Water website:

<http://www.sydneywater.com.au/Plumbing/BackflowPrevention/>

Water Efficiency Recommendations

Water is our most precious resource and every customer can play a role in its conservation. By working together with Sydney Water, business customers are able to reduce their water consumption. This will help your business save money, improve productivity and protect the environment.

Some water efficiency measures that can be easily implemented in your business are:

- Install water efficiency fixtures to help increase your water efficiency, refer to WELS (Water Efficiency Labelling and Standards) Scheme, <http://www.waterrating.gov.au/>
- Consider installing rainwater tanks to capture rainwater runoff, and reusing it, where cost effective. Refer to <http://www.sydneywater.com.au/Water4Life/InYourBusiness/RWTCalculator.cfm>
- Install water-monitoring devices on your meter to identify water usage patterns and leaks.
- Develop a water efficiency plan for your business.

It is cheaper to install water efficiency appliances while you are developing than retrofitting them later.

Contingency Plan Recommendations

Under Sydney Water's [customer contract](#) Sydney Water aims to provide Business Customers with a continuous supply of clean water at a minimum pressure of 15meters head at the main tap. This is equivalent to 146.8kpa or 21.29psi to meet reasonable business usage needs.

Sometimes Sydney Water may need to interrupt, postpone or limit the supply of water services to your property for maintenance or other reasons. These interruptions can be planned or unplanned.

Water supply is critical to some businesses and Sydney Water will treat vulnerable customers, such as hospitals, as a high priority.

Have you thought about a contingency plan for your business? Your Business Customer Representative will help you to develop a plan that is tailored to your business and minimises productivity losses in the event of a water service disruption.

For further information please visit the Sydney Water website at:

<http://www.sydneywater.com.au/OurSystemsandOperations/TradeWaste/> or contact Business Customer Services on 1300 985 227 or businesscustomers@sydneywater.com.au

