LEGEND

0000 - General
- Site Boundary
- Easement

1000 - Preparation, Groundworks & Drainage
- Native Garden Soil - 2,347 sqm
- Lawn Soil - 837 sqm

2000 - Walls & Edges
- 150mm concrete edge - 142 lm
- H350mm x W150mm concrete wall - 45 lm
- H450mm x W500mm stone block seat wall - 22 lm
- Steel edge - 124 lm
- Dia. 150~200mm sandstone boulder strip - 320 sqm

3000 - Pavements
- Rubber Softfall - 515 sqm
- Decomposed granite - 179 sqm
- Concrete in-situ - 277 sqm

4000 - Site Structures - N/A

5000 - Rails & Fencing
- Steel Handrail - 116 lm

6000 - Pools & Water Elements - N/A

7000 - Furniture & Fittings
- Arc seat - 9 no.
- Sandstone boulder (dia. 750-850mm) - 6 no.

NOTE : All proposed playground equipment & shading sail are not part of this SSD

8000 - Planting
- Existing tree to be retained
- Proposed trees - native (100L) - 38 no.
- Proposed trees - exotic (100L) - 1 no.
- Native grass mix 01 (140mm, 6p/sqm) - 1,482 sqm
- Native grass mix 02 (140mm, 6p/sqm)- 567 sqm
- Native grass mix 03 (140mm, 6p/sqm)- 190 sqm
- Dry Creekbed mix (140mm, 5p/sqm)- 108 sqm
- Lawn - Turf Sod 837 sqm

NOTES :

- Potential mobile kiosk and amenities may be provided
- Number of trees are subject to future design process and regulatory agencies review

MCGREGOR COXALL

© Copyright McGregor Coxall
AUS ACN 082 334 290
UK 10199853
PRC ID NO. 06000022016070800008
Sydney Melbourne Shenzhen Bristol
www.mcgregorcoxall.com

Client
Billard Leece Partnership

Project Team
BLP WGE ARUP STEENSEN VARMING

Project Name
CHW Stage02 Redevelopment-MSCP

Project No.
0785SYD

Address
Hawkesbury Road, Westmead NSW 2145

Key Plan

Issue Log

Rev	Revision Description	By / Checked	Date
6	For SSDA submission	MK	31/3/2021
7	For SDA RtS	MK/MR	15/06/2021

Scale
1: 250 @ A1

0 10 15 20 m

All dimensions are in millimetres unless otherwise noted.
Do not scale from this drawing.

North

Phase
Schematic Design

Sheet Title
MSCP Plan

Sheet No.
CHW-LD-DG-MSCP-SD101

Rev
7