

- "Provide further explanation as to how the forecast parking demand of 147 public spaces is calculated (Table 6 of the Traffic and Parking Report)."

Find below an extract of the parking demand study which shows how the 147 public spaces is arrived at:

Base Estimate	People	% Cars	People per car (a)	Total cars per day	Turnover	Peak spaces required
WEEKDAYS						
PUBLIC						
OUTPATIENTS	468	80%	1.00	375	3.07	122
VISITORS	149	87%	1.68	77	3.07	
<i>Visitors during peak hours (65%)</i>	97	87%	1.68	50	3.07	16
EMERGENCY DEPARTMENT PRESENTATIONS	58	80%	1.00	47	3.07	
<i>Emergency Dept presentations during peak hours 8am - 6pm (59%)</i>	34	80%	1.00	27	3.07	9
						147