

13 December 2021

Our Ref: 189673, 185077, 190067

Ferdinando Macri

Planning Officer

Social and Infrastructure Assessments

Department of Planning, Industry and Environment

Ferdinando.Macri@dpie.nsw.gov.au

**RE: SSD-9835-Mod-7 Sydney Football Stadium (design and construction) – Modification 7
– Precinct Village and Carpark**

Thank you for notifying Sydney Water of SSD-9835-Mod-77 at 40-44 Driver Avenue, Moore Park, which proposes a modification to seek approval for a Precinct Village and construction of a 1,500 space multi-level carpark adjacent to the new stadium, incorporating a single storey retail pavilion, four tennis courts, ancillary landscaping and the reconfiguration of stadium pedestrian and vehicular access. Sydney Water notes that a Sydney Water heritage listing, Busby's Bore, is located within the development site. Sydney Water has reviewed the application based on the information supplied and provides the following comments.

Heritage

The works cannot, without approval from the NSW Heritage Council, adversely impact Busby's Bore in any way. As per the archaeological report, no impacts to the bore or its spur are proposed. Based on the information supplied, Sydney Water has no heritage related concerns. Sydney Water supports the recommendations outlined in the Heritage Impact Assessment report (page v.) prepared by Artefact (September 2021).

Stormwater

The proposed development will impact Sydney Water's 600mm stormwater main which is located within the development site. In its current form, the development does not comply with Sydney Water's building over and adjacent to stormwater requirements.

Sydney Water notes that the proponent intends to deviate this existing Sydney Water's 600mm pipe to facilitate the proposal. However, no further details are available for the deviation of the 600mm stormwater pipe for Sydney Water to comment any further.

Sydney Water **will object** to the proposal, unless the proposed 600mm stormwater deviation pipe complies with the following requirements:

- No buildings or permanent structures are to be proposed over the new deviated 600mm stormwater pipe or within **1m** from the outside wall of the new stormwater pipe. Permanent structures include (but are not limited to) basement car parks, hanging balcony, roof eaves, hanging stairs, stormwater pits, stormwater pipes, elevated driveway, basement access or similar structures. This clearance requirement would apply for unlimited depth and height.
- The Proponent is required to submit the elevation drawings with the new deviated stormwater pipe, to ensure that the proposed buildings and permanent structures are 1m away from the outside face of the new deviated stormwater pipe.

- The proposed new 600mm stormwater deviation pipe is to be designed and constructed according to Sydney Water's deviation of stormwater asset requirements.

Water and Wastewater Servicing

Water and wastewater servicing is available to the site. Amplifications, adjustments and/or minor extensions to the networks may be required complying with the Water Services Association of Austral (WSAA) code – Sydney Water edition. Further servicing requirements will be provided at the Section 73 application phase.

This advice is not formal approval of our servicing requirements. Detailed requirements, including any potential extensions or amplifications, will be provided once the development is referred to Sydney Water for a Section 73 application. More information about the Section 73 application process is available on our web page in the [Land Development Manual](#).

Further advice and requirements for this proposal are in Attachments 1 & 2. If you require any further information, please contact the Growth Planning Team at urbangrowth@sydneywater.com.au.

Yours sincerely,

A handwritten signature in black ink, appearing to read "K. Leitch", with a stylized flourish extending to the right.

Kristine Leitch

Commercial Growth Manager

City Growth and Development, Business Development Group

Sydney Water, 1 Smith Street, Parramatta NSW 2150

Attachment 1

Section 73 Compliance Certificate

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water.

The proponent is advised to make an early application for the certificate, as there may be water and wastewater pipes to be built that can take some time. This can also impact on other services and buildings, driveways or landscape designs.

Applications must be made through an authorised Water Servicing Coordinator. For help either visit www.sydneywater.com.au > Plumbing, building and developing > Developing > Land development or telephone 13 20 92.

Building Plan Approval

The approved plans must be submitted to the Sydney Water [Tap in™](#) online service to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met.

The [Tap in™](#) service provides 24/7 access to a range of services, including:

- building plan approvals
- connection and disconnection approvals
- diagrams
- trade waste approvals
- pressure information
- water meter installations
- pressure boosting and pump approvals
- changes to an existing service or asset, e.g. relocating or moving an asset.

Sydney Water's [Tap in™](#) online service is available at:
<https://www.sydneywater.com.au/SW/plumbing-building-developing/building/sydney-water-tap-in/index.htm>

Sydney Water recommends developers apply for Building Plan approval early as in some instances the initial assessment will identify that an Out of Scope Building Plan Approval will be required.

Out of Scope Building Plan Approval

Sydney Water will need to undertake a detailed review of building plans:

1. That affect or are likely to affect any of the following:
 - Wastewater pipes larger than 300mm in size
 - Pressure wastewater pipes
 - Drinking water or recycled water pipes
 - Our property boundary
 - An easement in our favour
 - Stormwater infrastructure within 10m of the property boundary.
2. Where the building plan includes:
 - Construction of a retaining wall over, or within the zone of influence of our assets
 - Excavation of a basement or building over, or adjacent to, one of our assets
 - Dewatering – removing water from solid material or soil.

The detailed review is to ensure that:

- our assets will not be damaged during, or because of the construction of the development
- we can access our assets for operation and maintenance
- your building will be protected if we need to work on our assets in the future.

The developer will be required to pay Sydney Water for the costs associated with the detailed review.

Tree Planting

Certain tree species placed in close proximity to Sydney Water's underground assets have the potential to inflict damage through invasive root penetration and soil destabilisation. Sydney Water requires that all proposed or removed trees and vegetation included within the proposal adhere to the specifications and requirements within Section 46 of the Sydney Water Act (1994) and *Diagram 5 – Planting Trees* within our [Technical guidelines – Building over and adjacent to pipe assets](#). Please note these guidelines include more examples of potential activities impacting our assets which may also apply to your development.

If any tree planting proposed breaches our policy, Sydney Water may need to issue an order to remove every tree breaching the act, or directly remove every tree breaching the Act and bill the developer or Council for their removal.

Attachment 2

Requirements for **Business Customers for Commercial and Industrial Property Developments.**

Trade Wastewater Requirements

If this development is going to generate trade wastewater, the property owner must submit an application requesting permission to discharge trade wastewater to Sydney Water's sewerage system. You must obtain Sydney Water approval for this permit before any business activities can commence. It is illegal to discharge Trade Wastewater into the Sydney Water sewerage system without permission.

The permit application should be emailed to Sydney Water's [Business Customer Services](mailto:businesscustomers@sydneywater.com.au) at businesscustomers@sydneywater.com.au

A Boundary Trap is required for all developments that discharge trade wastewater where arrestors and special units are installed for trade wastewater pre-treatment.

If the property development is for Industrial operations, the wastewater may discharge into a sewerage area that is subject to wastewater reuse. Find out from Business Customer Services if this is applicable to your development.

Backflow Prevention Requirements

Backflow is when there is unintentional flow of water in the wrong direction from a potentially polluted source into the drinking water supply.

All properties connected to Sydney Water's supply must install a testable Backflow Prevention Containment Device appropriate to the property's hazard rating. Property with a high or medium hazard rating must have the backflow prevention containment device tested annually. Properties identified as having a low hazard rating must install a non-testable device, as a minimum.

Separate hydrant and sprinkler fire services on non-residential properties, require the installation of a testable double check detector assembly. The device is to be located at the boundary of the property.

Before you install a backflow prevention device:

1. Get your hydraulic consultant or plumber to check the available water pressure versus the property's required pressure and flow requirements.
2. Conduct a site assessment to confirm the hazard rating of the property and its services. Contact PIAS at NSW Fair Trading on 1300 889 099.

For installation you will need to engage a licensed plumber with backflow accreditation who can be found on the Sydney Water website:

<https://www.sydneywater.com.au/plumbing-building-developing/plumbing/backflow-prevention.html>

Water Efficiency Recommendations

Water is our most precious resource and every customer can play a role in its conservation. By working together with Sydney Water, business customers are able to reduce their water consumption. This will help your business save money, improve productivity and protect the environment.

Some water efficiency measures that can be easily implemented in your business are:

- Install water efficiency fixtures to help increase your water efficiency, refer to WELS (Water Efficiency Labelling and Standards (WELS) Scheme, <http://www.waterrating.gov.au/>
- Consider installing rainwater tanks to capture rainwater runoff, and reusing it, where cost effective. Refer to <https://www.sydneywater.com.au/your-business/managing-your-water-use/water-efficiency-tips.html>
- Install water-monitoring devices on your meter to identify water usage patterns and leaks.
- Develop a water efficiency plan for your business.

It is cheaper to install water efficiency appliances while you are developing than retrofitting them later.

Contingency Plan Recommendations

Under Sydney Water's [customer contract](#) Sydney Water aims to provide Business Customers with a continuous supply of clean water at a minimum pressure of 15meters head at the main tap. This is equivalent to 146.8kpa or 21.29psi to meet reasonable business usage needs.

Sometimes Sydney Water may need to interrupt, postpone or limit the supply of water services to your property for maintenance or other reasons. These interruptions can be planned or unplanned.

Water supply is critical to some businesses and Sydney Water will treat vulnerable customers, such as hospitals, as a high priority.

Have you thought about a contingency plan for your business? Your Business Customer Representative will help you to develop a plan that is tailored to your business and minimises productivity losses in the event of a water service disruption.

For further information please visit the Sydney Water website at:

<https://www.sydneywater.com.au/your-business/managing-trade-wastewater/commercial-trade-wastewater.html> or contact Business Customer Services on 1300 985 227 or businesscustomers@sydneywater.com.au.