



Warren Smith & Partners

CIVIL ENGINEERING SERVICES

University of New South Wales (UNSW) University Hall Precinct Site Redevelopment

Stormwater Management Report

Prepared for UNSW







DOCUMENT CONTROL

Rev #	Date	Description of Change	Status
04	3 rd April 2019	SSDA Resubmission RtS	Current
03	8 th November 2018	SSDA Resubmission	Superseded
02	6 th November 2018	SSDA Submission	Superseded
01	25 th October 2018	Draft SSDA Issue	Superseded

APPROVALS

Rev #	Author	Approver
04	Lovdeep Singh Graduate Engineer – Civil & Water Engineering	Michael Cahalane Director – Civil & Water Engineering
03	Lovdeep Singh Graduate Engineer – Civil & Water Engineering	Michael Cahalane Director – Civil & Water Engineering
02	Lovdeep Singh Graduate Engineer – Civil & Water Engineering	Michael Cahalane Director – Civil & Water Engineering
01	Lovdeep Singh Graduate Engineer – Civil & Water Engineering	Michael Cahalane Director – Civil & Water Engineering

PREPARED BY:

WARREN SMITH & PARTNERS PTY LTD

Consulting Engineers

ACN 002 197 088 ABN 36 300 430 126 Level 9, 233 Castlereagh Street Sydney 2000 NSW Australia T 02 9299 1312

Warren Smith & Partners

PREPARED FOR:

UNIVERSITY OF NEW SOUTH WALES (UNSW)

Educational and Research University

University of New South Wales Sydney 2052 NSW Australia T 02 9385 1000



D & C PARTNER: LENDLEASE





CONTENTS

1.	INTRODUCTION	2
2.	ABBREVIATIONS AND DEFINITIONS	3
3.	EXISTING STORMWATER DRAINAGE	4
4.	AUTHORITY AND REGULATORY REQUIREMENTS	5
5.	CIVIL SERVICES GENERAL	7
6.	STORMWATER DRAINAGE WORKS	9
7.	WATER QUALITY REQUIREMENTS AND PROPOSED TREATMENT SYSTEM	12
8.	SEDIMENT AND EROSION CONTROL	16





CIVIL ENGINEERING SERVICES

1. INTRODUCTION

Warren Smith and Partners (WS+P) has been engaged by Lendlease Group to prepare a Stormwater Management Report for the University of New South Wales (UNSW) University Hall Precinct site redevelopment.

1.1 BACKGROUND

The existing site is located within the University of New South Wales, Kensington, NSW, approximately 5km south of the Sydney CBD, and directly south of Randwick Racecourse. The development site is bound by the University Village and the Whitehouse to the north, Goldstein Hall to the east, UNSW Business School and the Quadrangle to the south and the Alumni lawn to the west. The existing site accommodates the University Hall (D14), which is a three (3) storey building and provides student accommodation. Please refer to Figure 1.1 below which shows the extent of the development site area in which the proposed works are to be undertaken.




Figure 1.1: Aerial View of Property Boundary (Source: Google Maps)

Hydraulic Services Fire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx





2. ABBREVIATIONS AND DEFINITIONS

AEP	Annual Exceedance Probability
AHD	Australian Height Datum
ARI	Average Recurrence Interval
ARR	Australian Rainfall and Runoff
DN	Diameter Nominal (mm)
EY	Exceedances per Year
GBCA	Green Building Council of Australia
GPT	Gross Pollutant Trap
IFD	Intensity-Frequency-Duration
IL	Invert Level
L/s	Litres per second
m/s	Metres per second
MUSIC	Model for Urban Stormwater Improvement Conceptualisation
OSD	On-Site Detention
PSD	Permissible Site Discharge
RCC	Randwick City Council
RCP	Reinforced Concrete Pipe
RL	Reduced Level
RWT	Rainwater Reuse Tank
SID	Safety In Design
SSR	Site Storage Requirement
UNSW	University of New South Wales
WSC	Water Services Coordinator
WS+P	Warren Smith and Partners
WSUD	Water Sensitive Urban Design

The Use of Must, Shall & Should:

In accordance with the International Organization for Standardisation (ISO) Directives, the word "shall" is used to state that a requirement is strictly to be followed in order to conform to a Performance Requirement. Consequently, there can be no deviation from that requirement, other than a specific tolerance.

It is noted that in legislation and specifications it is common to use the word "must" to express a requirement. The word "shall" in this document should be considered as equivalent to "must" in the legislation.

The word "should" introduces a suggestion or recommendation that is not a requirement. It is not necessary that such recommendations or suggestions be followed in order to comply with the Performance Requirement.

Hydraulic Services Hire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





3. EXISTING STORMWATER DRAINAGE

A desktop review was undertaken to determine the existing drainage infrastructure within the site and development area. The desktop review revealed the following:-

- There are three (3) primary catchments within UNSW, the largest of which discharges to a grassed detention/percolation system below the Village Green;
- There are a number of stormwater lines which traverse the development site, the majority of which shall be disused and removed to cater for the proposed development, and;
- Two (2) existing stormwater lines, one (1) of which is in the north-western corner of the site and another in the south-eastern corner, shall be deviated around the proposed building footprint.

Please refer to Figure 3.1 for an illustration of the existing stormwater infrastructure located within the development site.




Figure 3.1: Existing UNSW Stormwater Infrastructure

UNSW has maintained extensive and up to date documentation of the stormwater network throughout the Campus, with Ove Arup & Partners having undertaken a stormwater management study in 1997, which was updated by ANA Technical Services having updated this study in 2005 to form the 'Campus 2020 Master Plan – Stormwater Strategy'. This study was reviewed and approved by Randwick City Council.

Kustom Engineering Pty Ltd were engaged in 2015 to undertake a review of the stormwater network within UNSW and determine the capacity, and any deficiencies, of the existing system. The review incorporated the 2005 Masterplan and was updated to include all developments that occurred between 2005 and 2016. The outcomes of this investigation were amalgamated with the existing 2020 Masterplan to form the 2025 Stormwater Strategy Management Plan.

Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





4. AUTHORITY AND REGULATORY REQUIREMENTS

4.1 STORMWATER DRAINAGE REQUIREMENTS

While the UNSW Kensington Campus resides within the Randwick City Council LGA, UNSW has prepared a 2025 Stormwater Strategy Management Plan (July 2017) which shall serve as the basis for all future developments within the Campus. As stated in the 2025 Management Plan, "Kensington campus stormwater drainage is to be managed in accordance with this strategy masterplan document, as agreed by UNSW and Randwick City Council".

UNSW has split the campus into a number of catchments, each of which have their own stormwater management requirements due to the varying properties of the land. Refer to Figure 4.1 for an illustration of the existing catchment breakdown.




Figure 4.1: Existing UNSW Catchments (Source: UNSW 2025 Stormwater Strategy Management Plan)

The proposed development forms part of catchment 'B1'.

As specified in the UNSW 2025 Stormwater Strategy Management Plan, the site requirements for Catchment B1 are as follows:-

- Flows up to the 5yr ARI (20% AEP) storm event shall be piped to the Village Green Detention Basin;
- Flows between the 5yr ARI (20% AEP) and the 20yr ARI (5% AEP) storm event shall be piped to Council kerb;
- Flows exceeding the 20yr ARI (5% AEP) storm event shall overflow into the Anzac Parade North Catchment;
- Existing overland flow paths shall not be disturbed or altered in any way;
- Where practical, percolation/infiltration systems or detention tanks are to be designed to reduce stormwater discharge from the site, and;
- Diversion structures within the site are to be retained or suitable replacement management strategies are to be engineered to take their place.

📕 Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





The UNSW Management Plan is to be read in conjunction with the Randwick City Council DCP for the design of detention/percolation systems.

As specified in the RCC Private Stormwater Code 2013 and the UNSW 2025 Stormwater Strategy Management Plan, the following are the minimum requirements for the design of infiltration/percolation systems:-

- Should stormwater be discharged to an infiltration system, the infiltration area shall be sized for all storm events up to, and including, the 5% AEP storm event with provision for a formal overland flow path;
- Should no formal overland escape route be provided for storms greater than the 5% AEP storm event, the infiltration system shall be sized for the 1% AEP storm event, and;
- Sediment/silt arrestor pits are to be provided within the site prior to stormwater being discharged from the site or into any infiltration areas. The sediment/silt arrestor pits are to be constructed in accordance with RCC requirements.

4.2 WATER SENSITIVE URBAN DESIGN (WSUD) REQUIREMENTS

As Randwick City Council does not specify minimum pollutant reduction targets, the Green Building Council of Australia requirements for water quality that have been adopted. Refer to Table 4.1 for the pollutant reduction targets.

Pollutant Type	Column A Target Reduction Percentage (%)	Column B Target Reduction Percentage (%)	Column C Target Reduction Percentage (%)	
Gross Pollutants (GP)	85 90		95	
Total Suspended Solids (TSS)	80	80	90	
Total Phosphorus (TP)	30	60	70	
Total Nitrogen (TN)	30	45	60	

Table 4.1: WSUD Pollutant Reduction Targets (Source: GBCA)

For the purpose of this development, Column B targets shall be adopted for the design.

Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





5. CIVIL SERVICES GENERAL

5.1 PURPOSE OF THIS DOCUMENT

The purpose of this document is to describe the Civil stormwater services in relation to the UNSW University Hall building redevelopment.

5.1.1 REFERENCE DOCUMENTS

This report is based on the following reference documents:-

- Survey Plan;
- Tzannes Architectural Documentation;
- UNSW 2025 Stormwater Strategy Management Plan, and;
- Coffey Geotechnical Report (for adjacent site).

5.1.2 SCOPE OF WORK

The Civil Services scope consists of the following services:-

- Stormwater Drainage works and Infiltration System;
- Existing and proposed connections to UNSW drainage system;
- WSUD requirements, and;
- Sediment and erosion control.

The Civil scope for stormwater drainage will comprise of the infiltration system, located beneath the stairs on the western boundary of the site, and below ground pipework external to the building. For drainage associated with suspended slabs and pump systems, refer to the Hydraulic Engineer's documentation.

5.1.3 LIMITATIONS

This report is based on information provided by the Architects, Design Team, survey drawings, site inspections, and information communicated during the design development process. Any assumptions made in the design process have been communicated in this report.

In particular, it should be noted that the survey information provided was incomplete, with few ILs being provided for the existing stormwater drainage system. However, a partial DRAINS model was provided which confirmed ILs of the majority of the piped system within the vicinity of the development area, with some levels yet to be confirmed upon further investigation.

WS+P have based this report on the assumption that the information provided throughout the design development stage can be taken at face value and in general terms accurately reflects the installation on site. WS+P does not accept any liability in regard to the accuracy of the existing documentation.

Hydraulic Services Hire Protection Kinil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





5.1.4 DESIGN CRITERIA

Table 5.1: Design Critera

Item	Design Criteria
Stormwater Drainage Works	AS/NZS 3500.3 – 2015 – Stormwater Drainage AS 2865 – 2009 Safe Working in a Confined Space Randwick City Council Development Control Plan (DCP) UNSW Kensington Campus 2025 Stormwater Strategy Management Plan Randwick City Council Private Stormwater Code 2013
Detention/Infiltration System	AS/NZS 3500.3 – 2015 – Stormwater Drainage AS 2865 – 2009 Safe Working in a Confined Space Randwick City Council Development Control Plan (DCP) UNSW Kensington Campus 2025 Stormwater Strategy Management Plan Randwick City Council Private Stormwater Code 2013
Water Quality Requirements and Proposed Treatment System	Draft NSW MUSIC Modelling Guidelines 2010 Green Building Council of Australia
Sediment and Erosion Control	Landcom 'Blue Book' – Managing Urban Stormwater Soils and Construction Guideline Edition 4 Randwick City Council Sediment and Erosion Control <i>'Do It Right On Site</i> ' Guides

Hydraulic Services Hire Protection Kirle Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





6. STORMWATER DRAINAGE WORKS

The stormwater drainage system shall be designed in accordance with the UNSW Stormwater Strategy Management Plan and the RCC Private Stormwater Code 2013.

6.1 PROPOSED DRAINAGE INFRASTRUCTURE

The total site development area is 0.5555 Ha. Stormwater runoff from the majority of the site shall be captured via a pit and pipe network and shall reticulate to an infiltration located along the western boundary of the site. A small portion of the site shall bypass the piped network; refer to Table 6.1 for a catchment breakdown. Refer to Figure 6.1 for a stormwater drainage plan.

Table 6.1: Catchment Breakdown

Catchment	Impervious Area (Ha)	Pervious Area (Ha)	Total Area (Ha)	
To OSD Tank				
Roof (incl. terrace/balcony)	0.2558	0.0087	0.2645	
Ground Area	0.1430	0.0561	0.1991	
Bypass				
Roof	0.0090	-	0.0090	
Ground Area	0.0523	0.0306	0.0829	
Total Area (Ha)	0.4601	0.0954	0.5555	




Figure 6.1: Proposed Stormwater Drainage Reticulation

To reduce the stormwater discharge from the site, it is proposed that an infiltration system, constructed from Rocla Plastream slotted pipes, be installed beneath the stairs along the western boundary of the site, with the system encroaching approximately 4m into the Alumni Lawn. Stormwater shall infiltrate to the Botany Sands Aquifer, from where it will be drawn for irrigation and other non-potable uses within the Campus. The

Hydraulic Services Hire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





The Plastream pipes shall provide detention, while allowing stormwater to infiltrate into the ground. The pipes shall also be wrapped and sealed in one (1) layer of geotextile material to prevent the ingress of fine backfill material into the pipes. The piped infiltration system has been designed to cater for the 5% AEP storm event, with orifice plates being installed over the outlet pipes to limit the discharge into the Village Green to pre-development flows for the 5% AEP storm event. Any overflows from the system shall be safely conveyed west across College Road.

Access to the infiltration system shall be provided via large pits located at both the upstream and downstream ends of the pipes. These pits shall provide human access to allow for maintenance of the system, with a high-pressure hose being applied from either the upstream or downstream ends of the piped system. The stormwater pit immediately upstream of the infiltration system shall be a silt arrestor pit, in accordance with RCC requirements.

The design infiltration rate of 750mm/hr ($k = 0.2L/m^2/sec$) has been adopted in accordance with the 2025 Stormwater Strategy Management Plan. The discharges from the infiltration/detention system have been calculated using a DRAINS model. Refer to Section 6.2.2 for details of the infiltration system.

6.1.1 DRAINS INPUT PARAMETERS

The site discharges have been calculated using a DRAINS model, which is a stormwater drainage system design and analysis program. DRAINS performs hydraulic grade line analysis and generates flows that occur in a drainage system for a particular AEP storm event.

As previously mentioned, Kustom Engineering Pty Ltd were engaged in 2015 to undertake a review of the existing stormwater system. As part of this review, a DRAINS model was undertaken utilising ARR 1987 methods and ILSAX hydrology.

The catchment characteristic factor values for UNSW and used in the DRAINS model are listed below:-

•	Soil Type – Normal	3.0
•	Paved (Impervious) Area Depression Storage	1mm
•	Supplementary Area Depression Storage	1mm
•	Grassed (Pervious) Area Depression Storage	5mm
•	Antecedent Moisture Condition	3.5
•	Minimum Pit Blockage (Sag Pits)	50%
•	Minimum Pit Blockage (On-Grade Pits)	0%
•	Minimum Pit Freeboard	150mm
•	Minimum Fall Across Pits	30mm

The rainfall data has been taken from the Bureau of Meteorology Rainfall IFD Data System using local coordinates, and ARR 2016 procedures have been adopted for modelling purposes.

Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals



6.1.2 INFILTRATION SYSTEM PROPERTIES

The proposed infiltration system details are presented in Table 6.2 below.

Table 6.2: Infiltration System Details

Item	Value
Total catchment area reticulating to Infiltration System (Ha)	0.4636
Area within development site bypassing Infiltration System (Ha)	0.0919
Percentage of development site bypassing Infiltration System	16.5%
Infiltration System Volume (m ³)	185.70
Outlet Pipe Diameter (mm)	6 x 1050mm
Outlet Pipe Orifice Diameter (mm)	6 x 95mm

6.2 SITE DISCHARGE RESULTS

As discussed previously, the piped discharge from the developed site has been limited to the predevelopment discharge rate for all storm events to avoid overloading the Village Green detention and infiltration system. Refer to Table 6.3 for the site discharge results for both the piped systems and the total site discharge.

Table 6.3: Site Discharge Results

	20% AEP Storm Event (L/s)	5% AEP Storm Event (L/s)	1% AEP Storm Event (L/s)						
Piped System (To Village Green)									
Pre-Development	68	96	129						
Post Development	68	81	113						
Total Site Discharge									
Pre-Development	105	152	211						
Post Development 90		113	197						

Any overflows from the system shall be safely conveyed along the existing flow path route on College Road.

Hydraulic Services Hire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





7. WATER QUALITY REQUIREMENTS AND PROPOSED TREATMENT SYSTEM

In order to comply with the Green Star requirements for the adequate treatment of stormwater runoff, treatment solutions have been provided to remove suspended solids, hydrocarbons, and nutrients prior to being discharged from site.

The pollutants that could potentially be generated as a result of the development are as follows:-

- Litter;
- Sediments, and;
- Nutrients (Phosphorus and Nitrogen).

The development has been modelled to demonstrate the performance of the stormwater treatment system utilising a program called MUSIC. MUSIC models the proposed stormwater treatment devices and estimates their respective performance against the performance targets of the project. The pollutants modelled in MUSIC are Gross Pollutants (GP), Total Suspended Solids (TSS), Total Phosphorus (TP) and Total Nitrogen (TN).

7.1 RAINFALL

A continuous simulation of ten (10) years was run with a six (6) minute time step, in accordance with the Green Star minimum requirements. The time period for which the model was run is 1st January 1970 to 31st December 1979. The rainfall station utilised was 066062 Sydney Observatory.

The average potential evapotranspiration (PET) data used in the MUSIC model was based on the average Sydney PET and is presented in Table 7.1 below.

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
PET (mm)	180	135	128	85	58	43	43	58	88	127	152	163

Table 7.1: Evapotranspiration Data for MUSIC Modelling

7.2 RAINFALL RUNOFF PROPERTIES

In accordance with the Draft NSW MUSIC Modelling Guidelines, dated August 2010, the following Table 7.2 and Table 7.3 presents the rainfall runoff properties which have been used in the MUSIC model.

[📕] Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





Table 7.2: MUSIC Rainfall Runoff Properties

Parameter	Unit	Value					
Impervious Area Parameters							
Rainfall Threshold	mm	1.0 (for roads/paths etc.) 0.3 (for roofs)					
Pervious Area Parameters							
Soil Storage Capacity	mm	120					
Initial Storage Capacity	%	25					
Field Capacity	mm	80					
Infiltration Capacity co-efficient a		200					
Infiltration Capacity co-efficient b		1.0					
Groundwater Properties	- -						
Initial depth	mm	10					
Daily recharge rate	%	25					
Daily base seepage rate	%	5					
Daily seepage rate (%)	%	0					

Table 7.3: Pollutant Concentration Parameters for MUSIC Source Nodes

		Concentration (mg/L-log ₁₀)							
Land Use Category		Total Suspended Solids		Total Phosphorus		Total Nitrogen			
		Storm Flow	Base Flow	Storm Flow	Base Flow	Storm Flow	Base Flow		
General Urban (incl	Mean	2.43	1.20	-0.30	-0.85	0.34	0.11		
public open space)	Standard Deviation	0.32	0.17	0.25	0.19	0.19	0.12		
Poofo	Mean	1.30	*	-0.89	*	0.30	*		
Roofs	Standard Deviation	0.32	*	0.25	*	0.19	*		

*Base flows are only generated from pervious areas; therefore these parameters are not relevant to impervious areas.

Hydraulic Services Hire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





7.3 STORMWATER TREATMENT PLAN

The MUSIC model's total catchment area to be treated is 0.4913 Ha which shall ultimately reticulate to the infiltration system. The infiltration system shall provide filtration treatment, significantly reducing the stormwater suspended solid and nutrient content prior to infiltrating into the Botany Sands Aguifer.

Additionally, it is proposed that an Enviropod, supplied by Ocean Protect, be installed within Pit 1/2, which shall intercept surface runoff at the pit grates and filter the runoff prior to entering the piped stormwater system. The Enviropod is fitted with a monofilament 200 micron pore size filter bag that removes gross pollutants such as sediment, trash and debris, as well as suspended solids; please refer to Figure 7.1 for an illustration of a typical Enviropod.



Figure 7.1: Typical Enviropod

7.4 MUSIC MODEL TREATMENT RESULTS

The stormwater quality treatment system has been modelled using the MUSIC software. Please refer to Figure 7.2 for the treatment plan and Table 7.4 for the treatment results.




Figure 7.2: MUSIC Model Treatment Plan

Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx





Pollutant Type	Source (kg/yr)	Residual Load (kg/yr)	Reduction % Achieved	Column B Green Star Target Reduction (%)
Gross Pollutants (GP)	149	14.4	90.3	90
Total Suspended Solids (TSS)	714	121	83.0	80
Total Phosphorus (TP)	1.73	0.314	81.8	60
Total Nitrogen (TN)	15.1	2.42	84.0	45

Table 7.4: Percentage Based Load Reduction in Pollutant Results

As is demonstrated by the results, the development is achieving the Green Star Column B targets for pollutant load reduction.

7.5 MAINTENANCE

The infiltration system shall be inspected regularly to prevent any blockages of the system, with flushing out of the modules through the access pits, located on the upstream and downstream ends of the chamber, and standpipes every six months and after major storm events. A major storm event constitutes storm events equivalent to, and greater than, the 5% AEP storm event. The Enviropod too shall be inspected six-monthly and after major storm events.

Hydraulic Services Fire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx





8. SEDIMENT AND EROSION CONTROL

The Contractor for the works is required to provide Sedimentation and Erosion Control in accordance with the guidelines set out in Landcom's Managing Urban Stormwater Soils & Construction Guidelines, Randwick City Council's 'Do It Right On Site' Sediment and Erosion Control guides, and the general requirements outlined below.

8.1 SITE PROTECTION MEASURES

The Contractor for the works is required to provide Sedimentation and Erosion Control in accordance with the requirements outlined below to inhibit the movement of sediment off the site during demolition and construction phases.

8.1.1 SITE ACCESS

Site access shall be established from Third Avenue. Construction vehicles leaving the site shall be required to pass over a Temporary Construction Vehicle Entry consisting of a 1.5m long by 3m wide 'cattle rack'.

8.1.2 SEDIMENT CONTROL

All exposed earth areas where it may be possible for runoff to transport silt down slope shall be protected with a sediment and erosion control silt fence generally installed along the boundaries of the site.

The fence will be constructed in accordance with details provided by the Department of Conservation and Land Management incorporating geotextile fabric which will not allow suspended particles greater than 50mg/L non-filterable solids to pass through, and as such comply with the appropriate provisions of the Clean Waters Act 1970.

The construction of the silt fence will include the following: -


- Geotextile fabric buried to a maximum of 150mm below the surface. Refer to Figure 8.1 for details;
- Overlapping any joins in the fabric;
- Turning up on the ends for a length of 1 metre in order to prevent volumes of suspended solids escaping in a storm event;
- Any Council owned road kerb entry and or gully pits will be protected by Atlantis Filter Bales and EcoSock. Additional protection will be provided by inserting Water Clean Filter Cartridges into the gully opening, and;
- Internal site drainage pits shall be protected by Sediment Traps consisting of hay bales.

Refer to Figure 8.1, Figure 8.2, Figure 8.3 and Figure 8.4 for details.



Report [04].docx










Figure 8.2: Stormwater Pit Sediment Trap Detail

■ Hydraulic Services ■ Fire Protection ■ Civil Engineering ■ Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management








Figure 8.3: Geotextile Filter Fabric Drop Inlet Sediment Trap Detail

Hydraulic Services Fire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx







What are FilterBales?

Water Clean FilterBales are a unique new patented 7 stage sediment filter device developed to substantially reduce the migration of sediment and contaminants into drainage systems while allowing filtered water to easily pass through. FilterBales reduce customers' time and money by providing solutions to comply witht environmental and regulatory requirements. Durable, Dependable, Reusable. Replacing hay bales and other inadequate attempts to stop sediment run-off, FilterBales are durable and reuseable, effectively stopping your money from "pouring down the drain". They are also lightweight and easy to handle. Replaceable Water Clean Filter Cartridges guarantee peak performance is maintained.



Ask your local FilterBales stockist about replacement frequencies in your area. Cartridges and filter covers should be changed when the infiltration rate decreases. Water Clean FilterBales are suitable for a wide range of sediment and water management situations and can be easily secured in place for long term use. The unique multi-directional filter system allows you to position Water Clean FilterBales in any direction without reducing performance.

Water Clean FilterBales can be fixed to concrete or bitumen surfaces using an epoxy mortar-binder or fixed to earth surfaces using 6-10 mm pegs or stakes. When positioning, the side with the red reflective marker should be facing traffic.

www.atlantiscorp.com.au 🌐

Hydraulic Services Fire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx





1. FilterBales frames are a perforated plastic structure made from recycled wheelie bins, battery cases, milk bottles etc.

2. Filter medium (bio engineered soil media) used in the filter cartridges is made from a special blend of recycled organic (RO) materials from kerbside and vegetation drop off centres. The RO hosts enhanced naturally occurring micro-organisms. The blend also contains natural minerals to capture nutrients. The filter medium is as safe as normal soil.

3. FilterBales have a seven (7) stage filtration system:

- In through the filter bag
 Through the perforated plastic structure wall
 In through the filter cartridge bag
 Through the bio engineered filter medium
 Out through the filter cartridge bag
 Out through the perforated plastic structure wall
 Out through the filter bag

4. The filter bag is made from 300-micron (one third of a millimetre) pore size geotextile. This is the first stage that filters much of the sediment and other suspended solids from the run-off water. The geotextile is designed to stop sediment and reduce clogging but allow water to pass through easily. The filter cartridge bags are made from a similar geotextile.

5. FilterBales work effectively up to "a one-in-one-year 48 hours, 100 mm "storm events". This is the largest storm event experienced since the commercialisation of FilterBales. Having handled this easily, Filter Bales are considered capable of handling much greater "storm events". During these storm events FilterBales were used inside gully pits in one application and on the ground surrounding the gully pit in another application

6. EcoSocks are made from a similar geotextile to the filter cartridge bags and contain the same bio engineered soil media as the FilterBales. They appear able to stand up to as much wear and tear as a sandbag.

7. FilterBales are much lighter (at around 15 kgs dry weight) than hay bales. This reduces exposure to Occupational Health and Safety

Product Range

Item No.	Description						
HFB001	High FilterBale, suitable for high flow situations and higher retention time applications. Contains two standard size WaterClean Filter Cartridges in upright formation to treat contaminated waters. (605mm x 485mm x 460mm)						
LFB002	Low FilterBale, suitable for low flow situations and kerb & gutter applications. Multi-directional module containing two standard size WaterClean Filter Cartridges. (605mm x 485mm x 220mm)						
ESF004	Directional EcoSock, can be used in conjunction with FilterBales to direct water. Will also provide some sediment filtration from seepage through bio-remediating media contained within the EcoSock (1135mm x 160mm x 30mm)	-					

Accessories

Item No.	Description	
FCR004	WaterClean Filter Cartridges contain a unique blend of fixaling and bio- remediating products that treat common pollutants. To achieve maximum performance, each FilterBale uses two WaterClean Filter Cartridges. (440mm x 400mm x 100mm)	*
HBC005 (High bale)	Replaceable FilterBale covers, made from specially designed geotextile. FilterBale covers have a standard aperture of 300 microns.	
HBC006 (Low bale)	Replaceable FilterBale covers, made from specially designed geolexlile. FilterBale covers have a standard aperture of 300 microns.	

Atlantis Water Management Rebirth Pty Ltd trading as Atlantis Water Management Suite 402/781 Pacific Highway Chatswood NSW, 2067 Australia Phone • + 61 2 9419 6000 Fax • + 61 2 9419 6710 Email · info@atlantiscorp.com.au Web Site · www.atlantiscorp.com.au



Figure 8.4: Atlantis Sediment Control Filter Bale Detail

📕 Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





8.1.3 TEMPORARY STORMWATER SYSTEM (WHERE REQUIRED)

Site runoff within the zones of the excavation will be drained into a central holding well within the excavation. Runoff will be allowed to settle out suspended particles and debris, and an acceptable water of 50mg per litre of Non Filterable Residues (NFR) is required to be achieved prior to discharge.

8.1.4 DUST CONTROL

The following dust control procedures will be adhered to:

- Loose loads entering or leaving the site will be securely covered by a tarpaulin or like material in accordance with RMS and local Council Guidelines;
- Soil transport vehicles will use the single main access to the site (via the stabilised site access);
- There will be no burning of any materials on site;
- Vegetation shall be maintained on site where possible;
- Materials and stockpiles shall be covered;
- Water sprays will be used across the site to suppress dust. The water will be applied either by water sprinklers or water carts across ground surfaces whenever the surface has dried out and has the potential to generate visible levels of dust either by the operation of equipment over the surface or by wind. The watercraft will be equipped with a pump and sprays;
- Spraying water at the rate of not less than three (3) L/s and not less than 700kPa pressure. The area covered will be small enough that surfaces are maintained in a damp condition and large enough that runoff is not generated. The water spray equipment will be kept on site during the construction of the works;
- During excavation all trucks/machinery leaving the site will have their wheels washed and/or agitated prior to travelling on Council Roads, and;
- Fences will have shade cloth or similar fabric fixed to the inside of the fence.

Generally, if wind conditions are unsuitable, reasonable care shall be taken to ensure dust is controlled within the site. If it is unfeasible, work should be ceased until wind conditions are suitable.

8.1.5 SEDIMENT PUMP OUT PITS

Sediment pump out pits shall be installed where lift pits are to be excavated. A perforated riser outlet pipe shall be installed to pump any rainwater collected in these pits and shall discharge into a grated inlet pit as documented on the Soil and Water Management Plan. Refer to Figure 8.5 and Figure 8.6 for details of a perforated riser outlet pipe.

Hydraulic Services 📕 Fire Protection 📕 Civil Engineering 📕 Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals








Figure 8.5: Pump Out Pit Outlet Pipe Detail




Figure 8.6: Pump Out Pit Outlet Pipe Plan Arrangement

Hydraulic Services Hire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals





8.1.6 MAINTENANCE


Generally, the following maintenance measures shall be adhered to during construction:-

- It will be the responsibility of the site foreman for the building contractor to ensure sediment and erosion control devices on site are maintained. The devices shall be checked daily and the appropriate maintenance undertaken as necessary;
- Prior to the closing of the site each day, the road shall be swept and materials deposited back onto the site;
- Gutters and roadways will be kept clean regularly to maintain them free of sediment;
- Appropriate covering techniques, such as the use of plastic sheeting will be used to cover excavation faces, stockpiles and any unsealed surfaces;
- If dust is being generated from a given surface, and water sprays fail;
- If fugitive emissions have the potential to cause the ambient as quality to foul the ambient air quality;
- The area of soils exposed at any one time will be minimised wherever possible by excavating in a localised progressive manner over the site,;
- Materials processing equipment suitable comply with regulatory requirements. The protection will include the covering of feed openings with rubber curtains or socks, and;
- Suitable and approved bins shall be utilised for the containment of hard waste, including concrete slurries, building waste and litter. In the case of accidental spills, particularly within the public reserve, the material shall be swept and contained, and not washed into a gutter or waterway.


It is considered that by complying with the above, appropriate levels of protection are afforded to the site and the adjacent public roads, footpaths and environment.

Hydraulic Services Fire Protection Civil Engineering Sydney Water Accredited Water Servicing Co-ordinator - Design Project Management - Building Plan Approvals T:\5867012\Documents\Civil\Reports, Briefs, Letters & Registers\Design Reports\SSDA\5867012-WS+P-CV-RP-01 - UNSW D14 SSDA Stormwater Management Report [04].docx

UNIVERSITY HALL PRECINCT SITE REDEVELOPMENT STATE SIGNIFICANT DEVELOPMENT APPLICATION



LOCALITY AERIAL NOT TO SCALE





Warren Smith & Partners Pty Ltd

Level 9, 233 Castlereagh Street, Sydney 02 9299 1312 wsp@warrensmith.com. www.warrensmith.com.au ABN 36 30

ey 2000 NSW Australia
.au
00 430 126

CONSULTING ENGINEERS

Hydraulic Services Fire Services Civil Services Sydney Water Accredited Water Servicing Co-ordinator and Designer



DRAWING SCHEDULE						
DRG No.	DRAWING TITLE	REV.				
D14-CV-D-200-00-01	Cover Sheet	04				
D14-CV-D-200-00-02	Specification Notes	04				
D14-CV-D-200-00-03	Soil & Water Management Plan	04				
D14-CV-D-200-00-04	Soil & Water Management Details	04				
D14-CV-D-200-00-05	Stormwater Layout Plan	04				
D14-CV-D-200-00-06	Stormwater Pit Schedule	04				
D14-CV-D-200-00-07	Stormwater Catchment Plan	04				
D14-CV-D-200-00-09	Stormwater Drainage Details	04				

SOURCE : SIX MAPS

Serving the Construction	COVER SHEET								
	SCALE	DRAWN	DESIGNED	CHECKED	APPROVED				
Industry	AS SHOWN	M.Cz.	L.S.	M.C.	M.C.				
	JOB No.		DRAWING No.		ISSUE				
since 1981.	5867	012	D14-CV-D	-200-00-01	04				
	DATE SEP 2018	STATUS	SDA SUBI	MISSION					
	Plot Date								

GENEF	RAL		STW12.	BED ALL PIPES FIRM BEDDING FILL MATE		VENLY ONTO IMPORTED
G1.	DESIGN HEREIN HAS BEEN PREPARED WARREN SMITH AND PARTNERS PTY L CONSULTING CIVIL ENGINEERS, LEVEL 9, 233 CASTLEREAGH ST, SYDN TEL:- (02) 9299 1312	LTD	STW13.	MANUFACTURERS R AS 3725-1989 BURIEI AS 2566-1998 LOADS	ECOMME D FLEXIBL S ON BURI	
G2.	THE DRAWINGS HEREIN SHALL BE REA REQUIRED IN CONJUNCTION WITH ARC DRAWINGS BY: TZANNES SUITE 2, LEVEL 5, 2-12 FOVEAUX ST, S NSW 2010.	CHITECT		CULVERTS. AS 3500-1990 NATIOI PART 2, SANITARY P SYDNEY WATER REC	NAL PLUM LUMBING QUIREMEN	IBING & DRAINAGE CODE. AND SANITARY DRAINAGE. NTS.
G3.	TEL: (02) 9319 3744 ALL DIMENSIONS IN MILLIMETRES UNG		STW14.	ALLOW TO TEST ALL MANUFACTURERS R		
63.	LEVELS AND CHAINAGES ARE IN METE SCALE DRAWINGS. USE FIGURED DIM	RES. DO NOT	CONC	RETE WORKS		
G4.	THE PROPOSED WORKS DETAILED HE CONSTRUCTED TO THE REQUIREMEN GENERALLY AS DETAILED HEREUNDE	TS OF COUNCIL	C1.	ALL WORKMANSHIP ACCORDANCE WITH ASSOCIATION AUSTI THE DRAWINGS AND	I AS3600, RALIA, ST	THE STANDARDS ANDARDS CITED IN AS3600,
G5. G6.	ALL EXISTING SERVICES SHALL BE VE DEPTH AND HORIZONTAL POSITION BY MEANS PRIOR TO EXCAVATION. ANY E SHALL BE BROUGHT FORTHWITH TO T MANAGER'S ATTENTION. REFERENCE SHALL BE MADE TO THE O	Y PHYSICAL DISCREPANCIES THE PROJECT	C2.	MAXIMUM AGGREGA ASH, UNLESS OTHE WORK IN CONTACT PORTLAND CEMENT BRIDGE WORKS, A M	NTE WITH RWISE AF WITH SEW , OTHERW 1AXIMUM (nm NOMINAL SLUMP, 20mm NO ADMIXTURES OR FLY PROVED. ALL CONCRETE /ER TO HAVE TYPE SL /ISE TYPE A CEMENT FOR 56 DAYS SHRINKAGE OF 600 MENT CONTENT 350kg/m3
00.	MANAGEMENT PLAN FOR ALL SITE WO HEREIN.			AND MAXIMUM WAT	ER:CEMEN	NT RATIO OF 0.40.
STORM MATERIA	MWATER & SUB-SOIL DRAINA	GE	C3.	(KERBS, EDGE STRIF 32 MPa ELSEWHERE	PS & CON	RETE SHALL BE : 25 MPa CRETE ENCASEMENT) AND
STW1. A. B. C.	PIPES AND FITTINGS FOR STORMWAT DRAINAGE SHALL BE AS FOLLOWS UN DRAWINGS: SEWER GRADE uPVC (SN8) WITH SOLV JOINTS FOR BELOW GROUND DRAINA FIBRE REINFORCED CEMENT WITH RU CLASS 3, FOR PIPE DIA'S GREATER TH REINFORCED CONCRETE WHERE REG 3500 FOR EXCESSIVE DEPTH. INSTALL IN ACCORDANCE WITH AUSTF STANDARD AS3500 EXCEPT WHERE VA THE CONTRACT DOCUMENTS.	O ON THE /ENT WELDED GE UP TO 225mm. /BBER RINGS, /AN 225mm. UNO. ?UIRED BY AS RALIAN	C4.	AND USED ONLY WH GENERALLY FOR HA THICK APPROVED BI MATERIAL SHALL BE EXCEEDING 6m. FOR 6mm THICK APPROV MATERIAL SHALL BE EXCEEDING 12m & G JOINTS, 25mm IN DE OF GUTTER. JOINTS	HERE SHC ND PLACE ITUMINOU PROVIDE MACHINE D BITUM PROVIDE GUILLOTIN PTH, SHAI ARE ALSO NG AND G	ED KERB & GUTTER 6mm IS MASTIC JOINTING ED AT INTERVALS NOT E PLACED KERB & GUTTER IOUS MASTIC JOINTING ED AT INTERVALS NOT ED DUMMY GROOVED LL BE FORMED EVERY 3m D REQUIRED AT EACH END GULLY PITS. JOINTS SHALL
STW2.	PIPES & FITTINGS FOR SUBSOIL DRAIN SLOTTED POLYVINYL CHLORIDE (PVC) WELDED JOINTS, MIN. 150mm DIAMETE	WITH SOLVENT	C5.	REINFORCEMENT IS	REPRESE	ENTED DIAGRAMMATICALLY OWN IN TRUE PROJECTION
STW3.	IN GROUND DRAINAGE PIPEWORK SEF SHALL BE MINIMUM 150mm DIA. UNO.	RVING DP's	C6.			ORCEMENT SHALL BE USED
STW4.	GRATED DRAINS SHALL BE 150mm NO A. 150mm NOM. WIDTH IN NON TRAFFI B. 225mm NOM. WIDTH IN TRAFFICABL	CABLE AREAS. E AREAS.	C7.	CONCRETE CURING AS3600. CURING SHA HOURS OF FINISHING CONTINUED FOR A M	SHALL BE ALL BE CC G OPERAT	E IN ACCORDANCE WITH DMMENCED WITHIN TWO FIONS AND SHALL BE DF SEVEN DAYS BY AN
STW5.	STORMWATER PITS ARE AS SHOWN & THE PLANS . PRECAST TYPE ACCEPTA IRONS FOR DEPTH GREATER THAN 12 PITS MIN. 30mm & FORM SMOOTH TRA INLET TO OUTLET.	ABLE WITH STEP 00. BENCH ALL	C8.	CONTINUOUSLY WE FORMWORK SHALL E ACCORDANCE WITH	T. BE DESIGI AS3610. F	MPOUND OR BY KEEPING NED AND CONSTRUCTED IN FORMWORK SHALL NOT BE VED WITHOUT APPROVAL.
STW6.	SELECT FILL SHALL BE MATERIAL OBT EXCAVATION OF THE PIPE TRENCH OF WITH A PARTICLE SIZE FOR ROCK NO THAN 75mm OR FOR OTHER THAN ROC	R IMPORTED T GREATER	C9. C10.	FIG.13.2.4 OF AS3600).	E IN ACCORDANCE WITH
STW7.	GREATER THAN 150mm. IMPORTED FILL SHALL BE EITHER, ANI) GENERALLY	610.	WITH AS3600 UNO.	ENDS SH	ALL DE IN ACCORDANCE
	CONSIST OF SINGLE SIZED AGGREGA PARTICLE SIZE NOT GREATER THAN 5 ALL ROUND WITH GEOTEXTILE FILTER APPROVED HIGH COMPACTION SAND CRUSHED ROAD GRAVEL CONFORMIN 3051 OR SIMILAR.	TE WITH mm WRAPPED R FABRIC OR OR APPROVED IG TO RTA FORM	C11.	BY "RAMSET" WITH T INSTALLED IN STRIC	THE GLASS T ACCORINSTRUCTI WITH FOIL T ACCORI	DANCE WITH ONS %%uOR HILTI HVU L CAPSULE SYSTEM DANCE WITH
STW8.	STORMWATER PITS AND GRATES TO (STANDARD COUNCIL REQUIREMENTS PUBLIC LAND. GRATES TO BE SUPPLIE SHOWN ON THE DRAWINGS.	, WHERE ON	C12.	ALL CHEMICAL ANCH GALVANIZED AND BE		
INSTALLA	TION REQUIREMENTS:		GENER FILLING:	RAL EARTHWOR	KS, SIT	EWORKS & FILLING
STW9.	PIPES SHALL BE TRUE TO GRADES SH ALIGNED SO THAT THE CENTRES OF T INTERSECT WITH THE CENTRE OF THE	THE INLET PIPES	SGE1.	THESE CLAUSES SH GEOTECHNICAL INVI		EAD IN CONJUNCTION WITH
STW10.	THE DOWNSTREAM FACE OF THE PIT.		SGE2.			NTAINED IN THE GEOTECH E CLAUSES PRESENTED
S1W10.	DRAINAGE SHALL CONFORM TO AS350 FOLLOWS, UNO: 1% FOR 100 AND 150 mm DIA.		SGE3.	HEREIN. STRIP ALL TOPSOIL STOCKPILE TOPSOIL LANDSCAPING PURF	AND UNDI _ FOR LAT	ERLYING FILL AND
	0.5% FOR 225 mm DIA 0.5% FOR 300 mm DIA 0.4% FOR 375 mm DIA		SGE4.	NEW FILL REQUIRED PROPOSED BENCHIN FROM OTHER PARTS) TO REIN NG LEVEL S OF THE I	STATE CUT LEVELS TO S SHALL BE SOURCED EXCAVATION AS SELECT
STW11.	MINIMUM DEPTH OF COVER SHALL BE - 300mm IN PRIVATE PROPERTY (NON TRAFFIC). - 450mm IN PUBLIC AREAS. - 600mm IN VEHICULAR TRAFFICABLE / (FOOTWAY/ROADWAY)	VEHICULAR	SGE5. SGE6.	AND SGE 5. SELECT FILL SHALL CUT NATURAL CLAY IMPORTED FILL SHAL OR SHALE OR SIMIL	CONSIST S. LL CONSIS AR MATEF	PECIFIED BELOW IN SGE 4 OF LOCALLY DERIVED OR ST OF RIPPED SANDSTONE RIAL WITH MAXIMUM & THAN 120mm AND A
DO NOT SCALE FROM DRAWINGS, CHECK & VERIFY ALL DIMENSIONS & LEVELS BEFORE COMMENCEMENT OF ANY WORK. THIS DRAWING IS NOT TO BE COPIED IN PART					REVISION 01 02 03 04	AMENDMENT DRAFT SSDA SUBMISSION SSDA SUBMISSION SSDA RESUBMISSION RTS

OR WHOLE WITHOUT WRITTEN PERMISSION FROM WARREN SMITH AND PARTNERS.

> 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 A 4

MOISTURE CONTENT WITHIN 2-3% OF STANDARD OPTIMUM.

SGE7.	ALL FILL (COHESIVE SOIL) SHALL BE PLACED IN LAYERS
	OF 200mm MAXIMUM THICKNESS, COMPACTED BY
	MACHINE ROLLING TO ACHIEVE A DRY DENSITY RATIO
	OF NOT LESS THAN 98% STANDARD MAXIMUM AT A
	CORRESPONDING MOISTURE CONTENT WITHIN 2-3% OF
	STANDARD OPTIMUM.
SGE8.	IN AREAS WHERE HIGH IMPACT ROLLING IS USED TEST
	EACH FINAL LAYER OF NOT GREATER THAN 300mm TO
	400mm TO ACHIEVE A DRY DENSITY SGE8. RATIO OF NOT
	Ι ΕΩΩ ΤΗΛΝΙ 08%, ΩΤΛΝΙΠΛΟΠ ΜΛΥΙΜΙ ΙΜ ΛΤ Λ

LESS THAN 98% STANDARD MAXIMUM AT A CORRESPONDING MOISTURE CONTENT WITHIN 2-3% OF STANDARD OPTIMUM.

EXCAVATION BATTERS:

- SGE9. ALL TEMPORARY BATTERS CUT IN CLAY SUBSTRATE SHALL BE 1 HORIZ : 1 VERT. ALL LONG TERM EXPOSED BATTERS CUT IN CLAY SUBSTRATE SHALL BE 2 HORIZ : 1 VERT. ALL DETENTION BASIN BATTERS IN CLAY SUBSTRATE SHALL BE 3 HORIZ : 1 VERT. ALL DETENTION BASIN BATTERS IN ROCK SUBSTRATE SHALL BE NEAR VERTICAL.
- SGE10. GEOTECHNICAL TESTING IS TO BE UNDERTAKEN TO AT LEAST LEVEL 2 CONTROL OF FILL COMPACTION STANDARD, AS DEFINED IN AS. 3738 AS FOLLOWS:
- FOR GENERAL FILL OR CUT AREAS OVER THE AREA -PROVIDE ONE (1) TEST PER 200mm LAYER, OVER AN AREA NOT GREATER THAN 500 m²
- FOR GENERAL FILL AREAS IN CONCENTRATED AREAS -ADJACENT TO AND BEHIND THE STRUCTURE AND ADJACENT TO AND BEHIND RETAINING WALLS PROVIDE ONE (1) TEST PER 200mm LAYER, OVER AN AREA NOT GREATER THAN 50m²
- SGE11. SUBMIT ALL GEOTECHNICAL TEST RESULTS TO WARREN SMITH & PARTNERS FOR REVIEW PRIOR TO CONTINUATION WITH SUBSEQUENT SECTION OF WORK.

EARTH WORKS FOR SERVICES

- E1. EXCAVATE TRENCHES AND STOCKPILE ALL MATERIAL FOR INSPECTION WITH REGARD TO RE-USE FOR TRENCH BACKFILL. REMAINING MATERIAL TO BE REMOVED FROM SITE.
- E2. BEDDING MATERIAL SHALL CONSIST OF IMPORTED FILL ONLY. THICKNESS OF BEDDING LAYER SHALL BE 75mm IN O.T.R. AND 200mm IN ROCK.
- E3. EMBED ALL PIPES WITH IMPORTED FILL. PROVIDE 200mm SIDE SUPPORT AND 150mm OVERLAY ABOVE PIPE CROWN.
- E4. TRENCH FILL ABOVE THE EMBEDMENT ZONE TO THE UNDERSIDE OF THE ROAD PAVEMENT OR FOOTWAY FILL MATERIAL SHALL BE AS FOLLOWS :

UNDER ROADWAY

TRENCH FILL MATERIAL SHALL CONSIST OF IMPORTED FILL AS SPECIFIED HEREIN OF EITHER HIGH GRADE COMPACTION SAND OR APPROVED CRUSHED ROAD GRAVEL CONFORMING TO RTA FORM 3051 OR SIMILAR.

OTHER THAN ROADWAY

TRENCH FILL MATERIAL EXCAVATED SHALL CONSIST OF SELECT FILL AS SPECIFIED HEREIN AND SHALL NOT CONTAIN MORE THAN 20% OF STONES OF SIZE BETWEEN 75mm & 150mm AND NONE LARGER THAN 150mm. PRIOR TO THE USE OF THE EXCAVATED MATERIAL IT SHALL BE INSPECTED AND APPROVED BY THE CONSULTANT.

E5. COMPACT BEDDING, EMBEDMENT AND TRENCH FILL MATERIALS AS FOLLOWS:

EMBEDMENT:-

FOR GRANULAR FILL MATERIAL (NON-COHESIVE SOILS) EG. COARSE AGGREGATE FILL, HIGH GRADE COMPACTION SAND, THE DENSITY INDEX (ID) SHALL BE NOT LESS THAN 70%.

TRENCH FILL:-

E6.

FOR GRANULAR MATERIAL (NON-COHESIVE SOILS), THE DENSITY INDEX (ID) SHALL BE NOT LESS THAN 70%.

FOR NON-GRANULAR FILL MATERIAL (COHESIVE SOILS), THE DRY DENSITY RATIO (RD) SHALL BE NOT LESS THAN 95%.

MEASURE OF COMPACTION:-THE DEGREE OF COMPACTION SHALL BE MEASURED BY ONE OF THE FOLLOWING PARAMETERS :-

GRANULAR FILL (NON-COHESIVE SOILS). THE DENSITY INDEX (ID) DETERMINED IN ACCORDANCE WITH AS 1289.E6.1 BASED ON THE MAXIMUM AND MINIMUM DRY DENSITIES IN ACCORDANCE WITH AS 1289.E5.1 AND THE FIELD DRY DENSITY IN ACCORDANCE WITH AS 1289.5.3.2, AS 1289.E3.5 OR AS 1289.E8.1.

NON-GRANULAR FILL (COHESIVE SOILS). THE DRY DENSITY RATION (RD) DETERMINED IN ACCORDANCE WITH AS 1289.5.4.1 BASED ON THE FIELD DRY DENSITY IN ACCORDANCE WITH AS 1289.5.3.2 AND THE MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289.5.1.1

E7.	GEOTECHNICAL TESTING IS TO BE UNDERTAKEN TO AT LEAST LEVEL 2 CONTROL OF FILL COMPACTION STANDARD, AS DEFINED IN AS. 3738 AS FOLLOWS:
- -	TEST EACH 300mm LAYER ABOVE PIPE CROWN. TEST BASE & SUB-BASE LAYERS WHERE APPLICABLE. TESTS SHALL BE REQUIRED AT EACH 50m CENTRES WHERE THE LENGTH OF TRENCH IS WITHIN THE 50m REQUIREMENT.
E8.	SUBMIT ALL GEOTECHNICAL TEST RESULTS TO WARREN SMITH & PARTNERS FOR REVIEW PRIOR TO CONTINUATION WITH SUBSEQUENT SECTION OF WORK.
REST	ORATION:
RES1.	RESTORE ALL TRAFFIC AREAS TO PRE EXISTING CONDITION.
RES2.	FOR ALL SURFACES OTHER THAN IN TRAFFIC AREAS RESTORE DISTURBED SURFACES TO PRE-EXISTING CONDITIONS AND COMPACT AS SPECIFIED.
RES3.	RESTORE ALL AUTHORITY OWNED AREAS TO COUNCIL STANDARDS.
ROAD) WORKS, DRIVEWAYS & CARPARKS
R1.	ALLOW FOR LEVEL 2 TESTING AND SUB-GRADE CONDITIONS & PAVEMENT THICKNESS TO BE VERIFIED BY GEOTECHNICAL CONSULTANT AFTER INSPECTION OF PRELIMINARY BOXING.
R2.	ALLOW FOR ANY SUB-GRADE REPLACEMENT WORK TO BE DETERMINED AS REQUIRED BY GEOTECHNICAL CONSULTANT AT THE TIME OF PAVEMENT
R3.	CONSTRUCTION. MINIMUM DRY DENSITY RATIOS (AS 1289 3.4.1-1993) TO BE:
	BASE COURSE: 98% MODIFIED SUB-BASE: 95% MODIFIED SUB-GRADE: 100% STANDARD SUB-GRADE REPLACEMENT: 100% STANDARD
R4.	PAVEMENT MATERIALS TO COMPLY WITH RMS SPECIFICATION No. 3051 OR SIMILAR AS APPROVED BY GEOTECHNICAL CONSULTANT.
R5.	PROVIDE (1) TEST FOR EACH LAYER NOT EXCEEDING

- 250mm THICK BEING BASECOURSE, SUB-BASE & SUB-GRADE OVER AN AREA NOT GREATER THAN 500m². R6
- SUBMIT ALL GEOTECHNICAL TEST RESULTS TO WARREN SMITH & PARTNERS FOR REVIEW PRIOR TO CONTINUATION WITH SUBSEQUENT SECTION OF WORK.

APPROVALS

- THE AS CONSTRUCTED WORKS SHALL BE INSPECTED A1. BY DESIGN CONSULTANT. MINIMUM 48 HOURS NOTICE
- SHALL APPLY TO ALL INSPECTIONS. THE DESIGN PLANS HEREIN ARE SUBJECT TO COUNCIL A2. APPROVAL PRIOR TO CONSTRUCTION. OBTAIN EXPRESS (WRITTEN) ADVICE TO PROCEED FROM PROJECT MANAGER PRIOR TO COMMENCEMENT.
- A3. SUBMIT WORK-AS-EXECUTED DRAWINGS IN CIVILCAD OR DXF DIGITAL FORMAT AND HARD COPY FORMAT. VERIFY ALL CONSTRUCTION WORKS SHOWN HEREON.
- CERTIFY THAT THE AS CONSTRUCTED SYSTEM HAS A4. BEEN BUILT IN ACCORDANCE WITH THE APPROVED PLANS ISSUED FOR CONSTRUCTION.

SERVICES UNDER ROAD SURFACES

ALL OTHER SERVICES INCLUDING BUT NOT LIMITED TO S1. WATER, HYDRANT, GAS, SEWER, ELECTRICAL AND COMMUNICATIONS CONDUITS OR CABLES SHALL BE LAID WITH MINIMUM 600mm U.N.O. COVER BELOW PROPOSED ROAD SURFACE OR APPROVED OTHER MEANS TO PROTECT DURING CONSTRUCTION.

ROAD SIGNS & LINE MARKING

- RS1. ALL SIGNS AND LINEMARKING SHALL BE TO RMS STANDARDS AND SPECIFICATIONS AND AS.1742, MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- RS2. ALL LINEMARKING SHALL BE AUGMENTED BY RETROREFLECTIVE RAISED PAVEMENT MARKERS (RRPMs) AND ALL SHALL BE TO AS 1742.2 - 1994 AND AS 1742.2 /AMDT 1/1997-10-05
- RS3. ALL ROAD SIGNS AND POSTS SHALL BE TO AS 1742.2 -1994 AND AS 1742.2 /AMDT 1/1997-10-05

PROTECTION OF FLORA - REFER SPECIFICATION

- ANY TRENCHES WITHIN 3m OF TREES SHALL BE HAND 1. DUG TO AVOID DAMAGE TO TREE ROOTS.
- THE SEWERAGE WORKS HAVE BEEN LOCATED TO 2. MINIMISE CLEARING AND DAMAGE TO THE EXISTING FLORA ENVIRONMENT. NO TREES ARE PERMITTED TO BE REMOVED OR DAMAGED UNO. CONSTRUCTION OF THE SEWER GRAVITY OR RISING MAIN IN THE VICINITY OF EXISTING TREES SHALL BE HAND EXCAVATED ONLY,

DATE	REVISION	AMENDMENT	DATE	CLIENT	PREPARED BY	
25/10/18 06/11/18 08/11/18					Warren Smith &	Warren Smith & Partners Pty Ltd Level 9, 233 Castlereagh St, Sydney 2000 NSW Australi 02 9299 1312 wsp@warrensmith.com.au
03/04/19					Partners	www.warrensmith.com.au ABN 36 300 430 126
				PROJECT		CONSULTING ENGINEERS
				UNIVERSITY HALL	N.CONPLIANCE GL	 Hydraulic Services Fire Services Civil Services Sydney Water Accredited Water
					C1/04	Servicing Co-ordinator and Designer
				PRECINCT SITE		SERVING THE CONSTRUCTION INDUSTRY
				REDEVELOPMENT	ISO 9001 Certified	SINCE 1981.

ENSURING IRREVERSIBLE DAMAGE OF THE ROOT SYSTEM DOES NOT OCCUR.

- IF IT IS CONSIDERED NECESSARY TO PERFORM ANY WORK ON TREES, INCLUDING TRIMMING, LOPPING, ROOT CUTTING, REPAIR AND REMOVAL, APPLICATION IN WRITING SHALL BE MADE BY THE CONTRACTOR TO THE SUPERINTENDENT. ANY WORK PERMITTED TO BE DONE ON TREES TO BE RETAINED SHALL BE PERFORMED BY AN APPROVED TREE SURGEON.
- NO MATURE TREES OR SHRUBS ARE TO BE REMOVED 4 FOR THE PURPOSES OF THE WORKS WITHOUT PRIOR APPROVAL OF RANDWICK CITY COUNCIL.

AUTHORITY STANDARDS


LGA 1. THE DRAWINGS HEREIN SHALL BE READ IN CONJUNCTION WITH LOCAL AUTHORITY'S STANDARDS & SPECIFICATIONS WHICH SHALL OVERRIDE SPECIAL DETAILS SHOWN ON THE DRAWINGS.

CLOSED CIRCUIT COLOUR TV (CCTV)


- CCTV1. UNDERTAKE A CCTV INSPECTION OF ALL THE COMPLETED DRAINAGE IN ACCORDANCE WITH THE GUIDELINES OF THE THE AUSTRALIAN CONDUIT CONDITION EVALUATION MANUAL (ACCEM).
- CCTV2. APPLY THE FOLLOWING REQUIREMENTS TO THE CCTV **INSPECTION:-**
 - A. USE DATA CAPTURE SOFTWARE APPROVED BY SYDNEY WATER
 - B. USE CERTIFIED CCTV OPERATORS
 - C. THE CCTV VIDEOTAPE SHALL BE OF QUALITY TO ALLOW ACCURATE ASSESSMENT OF THE INTERNAL CONDITION OF THE PIPE.
- CCTV3. FURNISH TO THE DESIGN OF THE CONSULTANT:-A. VIDEOS IN MPG FORMAT FOR REVIEW B. CCTV REPORT AND SURVEY DATA IN PDF FORMAT


SPECIFICATION NOTES

SCALE	DRAWN	DESIGNED	CHECKED	APPROVED
AS SHOWN	M.Cz.	L.S.	M.C.	M.C.
JOB No.		DRAWING No.		ISSUE
5867	D14-CV-D-	-200-00-02	04	
DATE	STATUS			
SEP 2018	S	SDA SUBI	MISSION	



10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 A 4






A 4

g Co-ordinator and Desi	gner		5867	012		-200-00-04	04
LTING ENGINEERS aulic Services E Fire Se Services Sydney Wat		SCALE AS S JOB No.	HOWN	DRAWN M.Cz.	DESIGNED L.S. DRAWING No.	CHECKED M.C.	APPROVED M.C. ISSUE
1312 wsp@warrensmi arrensmith.com.au AB	lney 2000 NSW Australia th.com.au	S	OIL &		FAILS		
ST	ABILIZED WHEN T	HE CONS					D
A 5. SH TION	NSTRUCTION OPE MANNER THAT S ALL BE MINIMIZE E SEDIMENT TRA	EDIMENT, D.	EROSION	& WATER P	OLLUTION	<u>_</u>	REL
BED RE FURBED GO AREA 4.	E SEDIMENT FEN GULARLY INSPEC OD REPAIR AND	TED, ESPE FUNCTION	ECIALLY A IING CON	AFTER RAIN DITION AT A	AND KEPT LL TIMES.		IMI
2. SIL TO EED IT 3.	T & SEDIMENT N A COUNCIL APF WILL NOT ERODE	ROVED LC	DCATION	WITHIN THE	SITE, WHER		MINARY
1. AC	CUMULATED SILT GULAR INTERVAL	& SEDIM	ENT MUS	T BE REMOV	/ED AT		
	NTENANC						NOT
- PF	ART IS SITTING O TWEEN THE GRIE ROVIDE RAMPS A CCUR IN THE RAI	S TO WITH T ENDS A	HIN 50m ND SIDE	m OF THE T OF GRIDS. II	⁻ op. F depress	IONS	FO
	HERE GRIDS ARE /ER GEOTEXTILE WER GRID ON TO	USED FIR FABRIC. LI) THE PRE	ST CONS EVEL THI EPARED E	TRUCT A 15 S IN BOTH [BASE AND E	DIRECTIONS	At no	R
	ONSTRUCT 200mr DAD BASE OR 30 ETRES OR TO BU DNSTRUCT 300mr DIVERT WATER	–40mm A LDING ALI n HIGH HI	AGGREGA IGNMENT. UMP IMMI	TE. MINIMUM MINIMUM W EDIATELY WI	LENGTH 1 IDTH 3 ME	5 TRES.	CONSTR
MAX. 3. CC NE	OVER AREA WITH EDLE PUNCHED RENGTH (AS370)	PRODUCT	WITH A	MINIMUM CB		N OR	TRU
) WITH TC	RIP TOP SOIL & DIRECT RUNOFF MPACT SUBGRAI	WATER 1	to sedim	ENT TRAPS.		SIDES	CTION
							NO
DAILY.	SPACED 200mm APART (3000-3500mm LONG)	SHAKI	GEOTEX FABRIC				
- 1/3	100mm SQ HARDWOOD BI	CTED SUBGR AMS,					
REVENT							
TO EAC 1000mm	NIZED HEAVY STEEL STRA H HARDWOOD BEAM, STRA APART & FROM EDGE.		75mm STEE (PRE-DRILI				
C NOT COM	CES SHOULD BE BYPASS THE ST ING FROM A STA NIZED HEAVY STEEL STRA	ABILIZED BILIZED A	ACCESS REA.				
5. SEDI VEHI	LIC ROADS MUST MENT TRACKED CLES LEAVING TI PT UP IMMEDIATE	ONTO THE HE CONST	PUBLIC	ROADWAY B	Y		
4. COUI	UNSEALED ROAI NCILS ROADWAY K, 40mm NOMIN	IS TO BE	TOPPED	WITH 100mr	n		
CLE /	VEHICLE EXIT AF N & SERVICEAB OF USAGE.						
SITE SOUI ARE STEE	VEHICLE ENTRAN MUST BE STABI RCE OF SEDIMEN A. THIS MAY CON L SHAKER GRID	LIZED TO T, BY PRO ISIST OF	PREVENT DVIDING A A TIMBER	THEM BECC VEHICLE S R, CONCRETE	DMING A HAKE		
^{TE 4} <u>SITE E</u>	NTRY/EXIT	NTS		-			
DIRECT	F FROM PAD ED TO SEDIMENT TRA BILIZED CO VEHICLE	NSTRU		ISITE			
ERFLOW GEO FAB			MIN WI	DTH 3m			
CO	NSTRUCTION SITE	100mm	n HIGH SPA(R METAL GRILLE CED 200mm APAI BERM 0.3m MIN H	RT		

SSDA SUBMISSION


SEP 2018




10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

NAME	SURFACE ELEV. (m)	PIT DEPTH (m)	PIT SIZE AND TYPE	FROM	то	LENGTH (m)	U/S IL (m)	D/S IL (m)	SLOPE (%)	PIPE TYPE	DIA (mm)	NO. PIPES
PIT 1/1	33.58	0.83	600SQ PIT, CLASS B GRATE	PIT 1/1	PIT 2/1	16.52	32.75	31.91	5.08	uPVC(SN8)	225	1
PIT 2/1	32.74	0.94	900SQ PIT, CLASS B GRATE	PIT 2/1	PIT 3/1	16.9	31.8	31.2	3.55	RCP (CLASS 3)	300	1
PIT 3/1	32.1	1.01	900SQ PIT, CLASS B GRATE	PIT 3/1	PIT 4/1	14.5	31.09	30.52	3.93	RCP (CLASS 3)	375	1
PIT 4/1	31.5	1.01	900SQ PIT, CLASS B GRATE	PIT 4/1	PIT 5/1	18.7	30.49	30.12	1.98	RCP (CLASS 3)	375	1
PIT 5/1	31.1	1.01	900SQ PIT, CLASS D COVER	PIT 5/1	PIT 6/1	2.15	30.09	29.97	5.58	RCP (CLASS 3)	375	1
PIT 6/1	30.95	2.25	9m x 0.9m PIT, CLASS D COVER	PIT 6/1	PIT 7/1	35.74	28.7	28.5	0.56	ROCLA PLASTREAM SLOTTED PIPE	1050	6
PIT 7/1	30	1.59	9m x 0.9m PIT, CLASS B COVER	PIT 7/1	PIT 8/1	4.78	28.41	28.39	0.42	RCP (CLASS 3)	525	1
PIT 8/1	30	1.64	900SQ PIT, CLASS D COVER	PIT 8/1	EXISTING PIT	24.51	28.36	28.24	0.49	RCP (CLASS 3)	525	1
PIT 1/2	34.05	0.83	600SQ PIT, CLASS B GRATE	PIT 1/2	PIT 2/2	44.09	33.22	31.47	3.97	RCP (CLASS 3)	225	1
PIT 2/2	32.3	0.86	600SQ PIT, CLASS D COVER	PIT 2/2	PIT 3/2	32.23	31.44	30.57	2.7	RCP (CLASS 3)	225	1
PIT 3/2	31.4	0.86	600SQ PIT, CLASS D COVER	PIT 3/2	PIT 8/1	15.25	30.54	29.17	8.98	RCP (CLASS 3)	225	1


DO NOT SCALE FROM	REVISION	AMENDMENT	DATE	REVISION	AMENDMENT	DATE	CLIENT		PREPARED BY		TITLE				
DRAWINGS, CHECK &	01	DRAFT SSDA SUBMISSION	25/10/18							Warren Smith & Partners Pty Ltd					
VERIFY ALL DIMENSIONS	02	SSDA SUBMISSION	06/11/18					Warren Siniti a Partiers Pty Ltu Level 9, 233 Castlereagh St, Sydney 2000 NSW Australia		STORMWATER PIT SCHEDULE					
	03	SSDA RESUBMISSION	08/11/18					S Y D N E Y	Smith &	02 9299 1312 wsp@warrensmith.com.au					ULE
DRAWINGS, CHECK & VERIFY ALL DIMENSIONS & LEVELS BEFORE COMMENCEMENT OF ANY WORK.	04	SSDA RESUBMISSION RTS	03/04/19					~	Partners	www.warrensmith.com.au ABN 36 300 430 126					
							PROJECT	UNIVERSITY HALL	CONPLIANCE	CONSULTING ENGINEERS Hydraulic Services Fire Services Civil Services Sydney Water Accredited Water	SCALE AS SHOWN	DRAWN M.CZ.	DESIGNED L.S.	CHECKED M.C.	APPROVED M.C.
THIS DRAWING IS NOT TO BE COPIED IN PART OR WHOLE WITHOUT WRITTEN PERMISSION FROM WARREN SMITH AND PARTNERS.								PRECINCT SITE	GCCC	Servicing Co-ordinator and Designer	5867	012	DRAWING No.	0-200-00-0	¹⁶ 04
AND PARTNERS. 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150							_	REDEVELOPMENT	ISO 9001 Certified	SINCE 1981.	DATE SEP 2018	STATUS	SSDA SUB	MISSION	<u>. </u>



c-867012-TB_SSDA; X-5867012-AR_Property Boundary; X-5867012-DE-Design Surface; X-5867012-SU_Ground; X-5867012-AR_Lands te: 03.04.2019@14.21:42 Login Name: MCzarnota Cat File: T;\5867012\Drawings\utoCAD\CivilDesign\CivilDesign\Civil 2D\SSDAID14-CV-D-200-00-07 Stormwater Cc







REVISION	AMENDMENT	DATE	REVISION	AMENDMENT	DATE	CLIENT	PREPARED BY		TITLE				
01	DRAFT SSDA SUBMISSION	25/10/18						Warren Smith & Partners Pty Ltd					
02	SSDA SUBMISSION	06/11/18						Level 9, 233 Castlereagh St, Sydney 2000 NSW Australia 02 9299 1312 wsp@warrensmith.com.au	510	AINAG			
03	SSDA RESUBMISSION	08/11/18				S Y D N E Y	Smith &		DETAILS				
04	SSDA RESUBMISSION RTS	03/04/19				~	Partners	www.warrensmith.com.au ABN 36 300 430 126					
						PROJECT		CONSULTING ENGINEERS	SCALE	DRAWN		CHECKED	APPROVED
						UNIVERSITY HALL		 Hydraulic Services Fire Services Civil Services Sydney Water Accredited Water Servicing Co-ordinator and Designer 	AS SHOWN JOB No.	M.CZ.	L.S.	M.C.	M.C.
													ISSUE
						PRECINCT SITE	NION		5867	012	D14-CV-D-	-200-00-09	04 I
						REDEVELOPMENT	ISO 9001 Certified	SERVING THE CONSTRUCTION INDUSTRY SINCE 1981.		STATUS			
									SEP 2018		SDA SUBN	MISSION	


FROM WARREN SMITH AND PARTNERS.

10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

A 4

TYPICAL TRENCH DETAIL

NOT TO SCALE



NOT TO SCALE

	NOTES:							
	1. TRENCH WIDTH MAY NEED TO BE INCREASED							
	SUBJECT TO ACHIEVING ADEQUATE COMPACTION. 2. MINIMUM PIPE COVER NOT UNDER ROADS = 300mm							
— BACKFILL.	3. THE CONTRACTOR SHALL ENSURE THAT THE SHOREING OF TRENCHES IS INSTALLED AS							
	REQUIRED BY STATUTORY REQUIREMENTS. 4. ENSURE BACKFILLING COMPACTION MEETS THE							
	4. ENSORE BACKFILLING COMPACTION MEETS THE FOLLOWING STANDARDS;							
	 A) TRENCHES UNDER PAVED AREAS & BUILDINGS - 100% SMDD. 							
	B) TRENCHES NOT UNDER PAVEMENTS - 90% SMDD.							
FILL (MAX. 75mm).	ΥΥ							
	TE PIPE							
(OUTSIDE DIAMETER =								
	ACTED							
SELECTED FILL (NOMI								
10mm AGGREGATE).								
BED ZONE. SELECT FILL								
(NOMINAL 10mm AGGF	REGATE).							

