

27 July 2017

Lismore City Council
PO Box 1138
Lismore NSW 2480

Attention: Greg Buckler

Dear Greg,

Re: Proposed quarrying of cap rock in southern pit, and potential effect on groundwater

Further to our recent correspondence, Gilbert and Sutherland (G&S) has reviewed the proposed quarrying of cap rock from the southern pit and the potential for that extraction to effect groundwater.

Summary

G&S understand that due to increased demand, Blakebrook Quarry have identified a target for additional extraction to the north of the southern pit and submitted an application for that work. That target is presented below in **Drawing 001**. The target area approaches as close as 85 m to the southern groundwater monitoring cluster, and as such that cluster provides relevant data for the target. The elevation of the target varies from approximately 127.5 mAHD to 132 mAHD, and G&S understand that the top four to six metres of rock are expected to be removed.

Southern groundwater monitoring cluster

Within the southern cluster are three bores (BQS1S, S1I and S1L), each targeting a different water bearing zones. The water bearing zones interflow and are formed of vesicular and fractured basalt and sediments between successive basalt flows which form the ridge on which Blakebrook Quarry is situated. Groundwater has been recorded using down-hole loggers, and that data is retrieved regularly for download by Mat Baker of GDCS.

To analyse the level data and any potential effects, all heights and depths have been converted to mAHD.

The groundwater levels in the southern monitoring cluster can be tabulated as follows:

Monitoring Bore	Target water bearing zone	Minimum groundwater level (mAHD)	Maximum groundwater level (mAHD)
BQS1S	shallow	101.55	105.64
BQS1I	intermediate	84.00	84.83
BQS1D	deep	53.59	53.97

Table 1: minimum and maximum groundwater levels for the period 6 September 2016 to 6 June 2017

Conceptual model

A conceptual model has been produced showing three different water bearing zones (shallow, intermediate and deep) and relative pressure head levels. The depths of these water bearing zones were obtained from G&S drilling borelogs whilst the pressure head levels were the maximum groundwater levels shown in Table 1. The location of the conceptual model cross section is shown in Drawing 001 and the model itself presented in Drawing 002.

Conclusions and recommendations


The highest groundwater level in the southern area is that of the shallow water bearing zone at a maximum of 105.64 mAHD, recorded in the period between 6 September 2016 and 6 June 2017. It is understood that extraction will be to a depth of approximately 122mAHD. As such the water bearing zones will not be interfered with by the proposed extraction. Indeed a buffer of greater than 15m will be maintained. The current regime of groundwater monitoring should continue.

We trust this is acceptable. Please do not hesitate to contact this office if you require any further details or elaboration.

Yours faithfully,



Chris Anderson
Director/Principal Environmental
Engineer/Scientist
BEngEnv BScLan&Wat Man
MEIANZ MIEAust





for David Winterbotham
Senior Geoscientist
BSc(Hons)

Attachment 1: Drawings

Author Chris Anderson and David Winterbotham
Our Reference 11737_GWA_WSDW4D_072017.DOCX
Your Reference
By ☐ Courier ☒ Email ☐ Facsimile ☐ Post
Enclosures 2






ORIENTATION


SCALE 1:1 600

metres

ROBINA
PO Box 4115 Robina QLD4230 07 5578 9944
Email robina@access.gs www.access.gs

LEGEND

 Proposed Southern Extraction Pit (ERM 2011)

 Proposed Rock Extraction Area

 Cross Section A-A'


SOURCES

Image & Proposed Southern Extraction Pit boundary : Groundwork Plus - 2011 Proposed Extraction Limits drawing (1043.037)

Proposed Rock Extraction Area: Lismore City Council - Received by CMA from Greg Buckler via email (19/07/2017)

PROJECT		CLIENT		DRAWING			
BLAKEBROOK QUARRY GROUNDWATER ASSESSMENTS		LISMORE CITY COUNCIL		PROPOSED ROCK EXTRACTION AREA			
SCALE 1:1 600@A3	DATE 26/07/2017	DRAWN WPS	CHECKED CMA	PROJECT 11737	DRAWING 001	REVISION -	





ORIENTATION

SCALE
AS SHOWN

ROBINA

PO Box 4115 Robina QLD4230
Email robina@access.gs

07 5578 9944
www.access.gs

LEGEND

- Existing Ground Surface
- 4 - 6m Proposed Rock Extraction
- Basalt
- Shallow Water Bearing Zone
- Intermediate Water Bearing Zone
- Deep Water Bearing Zone

SOURCES

Surface elevations: ELVIS - Geoscience Australia.
Lismore City Council - monitoring well survey data received by CMA from Greg Buckler via email (24/07/2017)

Geology and water bearing zones: G&S borelogs. Drilling dates: 23/08/2016 - 25/08/2016

Groundwater levels: GDSC data package 05/07/2017

PROJECT

BLAKEBROOK
QUARRY
GROUNDWATER
ASSESSMENTS

CLIENT

LISMORE CITY
COUNCIL

DRAWING

PROPOSED ROCK
EXTRACTION
CROSS SECTION A - A'

SCALE	DATE	DRAWN	CHECKED	PROJECT	DRAWING	REVISION
AS SHOWN	26/07/2017	WPS	CMA	11737	002	-

**GILBERT
SUTHERLAND**

Attachment 2: Borelogs

Driller's Licence No:	DL2364	1
Class of Licence:		4
Driller's Name:	Cameron Sharp	
Assistant Driller:	Darryl Hunt	
Contractor:	Gilbert and Sutherland	
New bore	<input checked="" type="checkbox"/>	Replacement bore <input type="checkbox"/>
Deepened	<input type="checkbox"/>	Enlarged <input type="checkbox"/>
Reconditioned	<input type="checkbox"/>	Other (specify) <input type="checkbox"/>
Final Depth	55 m	

Work Licence No:	30BL207399	2	
Name of Licensee:	Lismore City Council		
Intended Use:	Monitoring		
Completion Date:	25/8/16		
DRILLING DETAILS 3			
From (m)	To (m)	Hole Diameter (mm)	Drilling Method
0	55	120	See Code 3 9

WATER BEARING ZONES 4											
From (m)	To (m)	Thickness (m)	S W L (m)	Estimated Yield (L/s)		Test method	D D L at end of test (m)	Duration		Salinity (Conductivity or TDS)	
				Individual Aquifer	Cumulative			Hrs	min	Cond (µS/cm)	TDS (mg/L)
38	43	5	30	0.195	0.195	See Code 4 1 H	30		15	300	

CASING / LINER DETAILS 5											
Material	OD (mm)	Wall Thickness (mm)	From (m)	To (m)	Method Fixing	Casing support method		See Code 5 2			
Code 5					Code 5	Type of casing bottom		See Code 5 1			
13	50		0	55	5	Centralisers installed {Yes/No}		No	(indicate on sketch)		
						Sump installed {Yes/No}		Yes	From	52 m	To 55 m
						Pressure cemented {Yes/No}		No	From	m	To m
Casing Protector cemented in place											

WATER ENTRY DESIGN 6											
General							Screen	Slot Details			
Material	OD (mm)	Wall Thickness (mm)	From (m)	To (m)	Opening type	Fixing	Aperture (mm)	Length (mm)	Width (mm)	Alignment	
Code 5					See Code 6	See Code 5				See Code 6	
8	50		40	52	5	5			0.5	H	

GRAVEL PACK 7									
Type	Grade	Grain size (mm)		Depth (m)		Quantity			
		From	To	From	To	Litres	m ³		
Rounded	X	Graded	X	2	3	35	55	190	0.19
Crushed		Ungraded							
Bentonite/Grout seal (Yes/No)		Yes				29	35	60	0.01
Method of placement of Gravel Pack				See Code 7		1			
For Departmental use only: GW <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>									



Work Licence No: 30BL207399

BORE DEVELOPMENT 8

Chemical used for breaking down drilling mud (Yes/No) <input checked="" type="checkbox"/> No		Name: _____				
Method	Bailing/Surging <input type="checkbox"/>	Jetting <input type="checkbox"/>	Airlifting <input type="checkbox"/>	Backwashing <input type="checkbox"/>	Pumping <input type="checkbox"/>	Other: _____
Duration	_____ hrs	_____ hrs	1 hrs	_____ hrs	_____ hrs	_____ hrs

DISINFECTION ON COMPLETION 9

Chemical(s) used	Quantity applied (Litres)	Method of application

PUMPING TESTS ON COMPLETION 10

Test type	Date	Pump intake depth (m)	Initial Water Level (SWL) (m)	Pumping rate (L/s)	Water Level at end of pumping (DDL) (m)	Duration of Test (hrs)	Recovery	
							Water level (m)	Time taken (hrs) (mins)
Multi stage (stepped drawdown)	Stage 1							
	Stage 2							
	Stage 3							
	Stage 4							
Single stage (constant rate)								
Height of measuring point above ground level		_____ m	Test Method		_____	See Code 4		

WORK PARTLY BACKFILLED OR ABANDONED 11

Original depth of work: _____ m	Is work partly backfilled: (Yes/No) <input type="checkbox"/>				
Is work abandoned: (Yes/No) <input type="checkbox"/>	Method of abandonment: Backfilled <input type="checkbox"/> Plugged <input type="checkbox"/> Capped <input type="checkbox"/>				
Has any casing been left in the work (Yes/No) <input type="checkbox"/>	From _____ m	To _____ m			
Sealing / fill type	From depth (m)	To depth (m)	Sealing / fill type	From depth (m)	To depth (m)
See Code 11	0	35	See Code 11		
1					

Site chosen by: Hydrogeologist ☐ Geologist ☒ Driller ☐ Diviner ☐ Client ☒ Other ☐ 12

Lot No _____ **DP No** _____ 13

Work Location Co ordinates		Easting	524670	Northing	6817819	Zone	54
GPS: (Yes/No) <input checked="" type="checkbox"/>	>>	AMG/AGD	<input type="checkbox"/>	or	MGA/GDA	<input checked="" type="checkbox"/>	(See explanation)
Longitude		_____	_____	Latitude		_____	_____

Please mark the work site with "X" on the CLID provided map.
Indicate also the distances in metres from two (2) adjacent boundaries, and attach the map to this Form A package.


Signatures:

Driller: _____

Licensee: _____

Date: 4/9/16

Date: _____

DRILLER'S ROCK/STRATA DESCRIPTION (LITHOLOGY)			15
Depth		Description <div>See Code 15</div>	WORK CONSTRUCTION SKETCH
From (m)	To (m)		
0	5	clay red	
5	8	clay firm brown	
8	55	bassalt firm blue	

WORK NOT CONSTRUCTED BY DRILLING RIG

16

Method of excavation: Hand dug <input type="checkbox"/> Back hoe <input type="checkbox"/> Dragline <input type="checkbox"/> Dozer <input type="checkbox"/> Other <input type="text"/>							
Depth (m)	Length (m)	Width (m)	Diameter (m)	Lining material	Dimensions of liner (m)	From Depth (m)	To Depth (m)

Please attach copies of the following if available

17

Geologist log	(Yes/No) <input type="checkbox"/>	Laboratory analysis of water Sample	(Yes/No) <input checked="" type="checkbox"/> Yes	Pumping test(s)	(Yes/No) <input type="checkbox"/>
Geophysical log	(Yes/No) <input type="checkbox"/>	Sieve analysis of aquifer material	(Yes/No) <input type="checkbox"/>	Installed Pump details	(Yes/No) <input type="checkbox"/>



Driller's Licence No:	DL2364	1
Class of Licence:		4
Driller's Name:	Cameron Sharp	
Assistant Driller:	Darryl Hunt	
Contractor:	Gilbert and Sutherland	
New bore	<input checked="" type="checkbox"/>	Replacement bore <input type="checkbox"/>
Deepened	<input type="checkbox"/>	Enlarged <input type="checkbox"/>
Reconditioned	<input type="checkbox"/>	Other (specify) <input type="checkbox"/>
Final Depth	73	m

Work Licence No:	30BL207399	2	
Name of Licensee:	Lismore City Council		
Intended Use:	Monitoring		
Completion Date:	24/8/16		
DRILLING DETAILS 3			
From (m)	To (m)	Hole Diameter (mm)	Drilling Method
0	73	120	See Code 3 9

WATER BEARING ZONES												4
From (m)	To (m)	Thickness (m)	S W L (m)	Estimated Yield (L/s)		Test method		D D L at end of test (m)	Duration		Salinity (Conductivity or TDS)	
				Individual Aquifer	Cumulative	See Code 4			Hrs	min	Cond (µS/cm)	TDS (mg/L)
34	39	5	30	0.195	0.195	1	H	30		15	300	
64	70	8	30	0.29	0.485	1	H	30		15	300	

CASING / LINER DETAILS												5
Material	OD	Wall Thickness	From	To	Method Fixing	Casing support method		See Code 5 2				
Code 5	(mm)	(mm)	(m)	(m)	Code 5	Type of casing bottom		See Code 5 1				
13	50		0	73	5	Centralisers installed (Yes/No)		No	(indicate on sketch)			
						Sump installed (Yes/No)		Yes	From	70	m	To 73 m
						Pressure cemented (Yes/No)		No	From		m	To m
						Casing Protector cemented in place						

WATER ENTRY DESIGN												6
General							Screen	Slot Details				
Material	OD	Wall Thickness	From	To	Opening type	Fixing	Aperture	Length	Width	Alignment		
Code 5	(mm)	(mm)	(m)	(m)	See Code 6	See Code 5	(mm)	(mm)	(mm)	See Code 6		
8	50		58	70	5	5			0.5	H		

GRAVEL PACK												7
Type	Grade	Grain size (mm)		Depth (m)		Quantity						
		From	To	From	To	Litres	m ³					
Rounded	<input checked="" type="checkbox"/>	Graded	<input checked="" type="checkbox"/>	2	3	53	73	190	0.19			
Crushed	<input type="checkbox"/>	Ungraded	<input type="checkbox"/>									
Bentonite/Grout seal (Yes/No)		Yes				47	53	60	0.01			
Method of placement of Gravel Pack				See Code 7	1							

For Departmental use only:	G W	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
----------------------------	------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

Work Licence No: 30BL207399

BORE DEVELOPMENT

8

Chemical used for breaking down drilling mud		(Yes/No) <input type="checkbox"/> No	Name:		
Method	Bailing/Surging <input type="checkbox"/>	Jetting <input type="checkbox"/>	Airlifting <input type="checkbox"/>	Backwashing <input type="checkbox"/>	Pumping <input type="checkbox"/>
Duration	<input type="text"/> hrs	<input type="text"/> hrs	<input type="text"/> 1 hrs	<input type="text"/> hrs	<input type="text"/> hrs

DISINFECTION ON COMPLETION

9

Chemical(s) used	Quantity applied (Litres)	Method of application

PUMPING TESTS ON COMPLETION

10

Test type	Date	Pump intake depth (m)	Initial Water Level (SWL) (m)	Pumping rate (L/s)	Water Level at end of pumping (DDL) (m)	Duration of Test (hrs)	Recovery	
							Water level (m)	Time taken (hrs) (mins)
Multi stage (stepped drawdown)	Stage 1							
	Stage 2							
	Stage 3							
	Stage 4							
Single stage (constant rate)								
Height of measuring point above ground level		<input type="text"/> m	Test Method		<input type="text"/>	See Code 4		

WORK PARTLY BACKFILLED OR ABANDONED

11

Original depth of work:	<input type="text"/> m	Is work partly backfilled:	(Yes/No) <input type="checkbox"/>
Is work abandoned:	(Yes/No) <input type="checkbox"/>	Method of abandonment:	Backfilled <input type="checkbox"/> Plugged <input type="checkbox"/> Capped <input type="checkbox"/>
Has any casing been left in the work	(Yes/No) <input type="checkbox"/>	From	<input type="text"/> m To <input type="text"/> m
Sealing / fill type	From depth (m)	To depth (m)	Sealing / fill type
See Code 11	<input type="text"/>	<input type="text"/>	See Code 11
1	0	47	

Site chosen by:	Hydrogeologist <input type="checkbox"/>	Geologist <input checked="" type="checkbox"/>	Driller <input type="checkbox"/>	Diviner <input type="checkbox"/>	Client <input checked="" type="checkbox"/>	Other <input type="text"/>
-----------------	---	---	----------------------------------	----------------------------------	--	----------------------------

12

Lot No	<input type="text"/>	DP No	<input type="text"/>
Work Location Co ordinates		Easting	524670
GPS:	(Yes/No) <input checked="" type="checkbox"/>	or	MGA/GDA <input checked="" type="checkbox"/>
		Longitude	<input type="text"/>
		Latitude	<input type="text"/>
		Zone	54

13

Please mark the work site with "X" on the CLID provided map.

Indicate also the distances in metres from two (2) adjacent boundaries, and attach the map to this Form A package.

Signatures:

Driller: _____

Licensee: _____

Date: _____

Date: _____

Work Licence No: 30BL207399

[illegible]



Driller's Licence No:	DL2364	1
Class of Licence:		4
Driller's Name:	Cameron Sharp	
Assistant Driller:	Darryl Hunt	
Contractor:	Gilbert and Sutherland	
New bore	<input checked="" type="checkbox"/>	Replacement bore <input type="checkbox"/>
Deepened	<input type="checkbox"/>	Enlarged <input type="checkbox"/>
Reconditioned	<input type="checkbox"/>	Other (specify) <input type="checkbox"/>
Final Depth	102.7	m

Work Licence No:	30BL207399	2	
Name of Licensee:	Lismore City Council		
Intended Use:	Monitoring		
Completion Date:	23/8/16		
DRILLING DETAILS			
From (m)	To (m)	Hole Diameter (mm)	Drilling Method See Code 3
0	102.7	120	9

WATER BEARING ZONES												4
From (m)	To (m)	Thickness (m)	S W L (m)	Estimated Yield (L/s)		Test method		D D L at end of test (m)	Duration		Salinity (Conductivity or TDS)	
				Individual Aquifer	Cumulative	See Code 4			Hrs	min	Cond (µS/cm)	TDS (mg/L)
34	39	5	30	0.195	0.195	1	H	30		15	300	
64	72	8	30	0.29	0.485	1	H	30		15	300	
95	99	4	30	0.73	1.215	1	H	30		15	300	

CASING / LINER DETAILS												5
Material	OD	Wall Thickness	From	To	Method Fixing	Casing support method		See Code 5		2		
Code 5	(mm)	(mm)	(m)	(m)	Code 5	Type of casing bottom		See Code 5		1		
13	50		0	102.7	5	Centralisers installed {Yes/No}		No	(indicate on sketch)			
						Sump installed {Yes/No}		Yes	From	99	m To 103 m	
						Pressure cemented {Yes/No}		No	From		m To m	
						Casing Protector cemented in place						

WATER ENTRY DESIGN												6
General							Screen	Slot Details				
Material	OD	Wall Thickness	From	To	Opening type	Fixing	Aperture	Length	Width	Alignment		
Code 5	(mm)	(mm)	(m)	(m)	See Code 6	See Code 5	(mm)	(mm)	(mm)	See Code 6		
8	50		87.7	99.7	5	5			0.5	H		

GRAVEL PACK												7
Type		Grade	Grain size (mm)		Depth (m)		Quantity					
			From	To	From	To	Litres	m ³				
Rounded	<input checked="" type="checkbox"/>	Graded	<input checked="" type="checkbox"/>	2	3	82.7	102.7	190	0.19			
Crushed	<input type="checkbox"/>	Ungraded	<input type="checkbox"/>									
Bentonite/Grout seal (Yes/No)				Yes		76.7	82.7	60	0.01			
Method of placement of Gravel Pack				See Code 7	1							
For Departmental use only:												
G W												



Work Licence No: 30BL207399

BORE DEVELOPMENT 8

Chemical used for breaking down drilling mud (Yes/No) <input checked="" type="checkbox"/> No		Name: _____				
Method	Bailing/Surging <input type="checkbox"/>	Jetting <input type="checkbox"/>	Airlifting <input type="checkbox"/>	Backwashing <input type="checkbox"/>	Pumping <input type="checkbox"/>	Other: _____
Duration	_____ hrs	_____ hrs	1 hrs	_____ hrs	_____ hrs	_____ hrs

DISINFECTION ON COMPLETION 9		
Chemical(s) used	Quantity applied (Litres)	Method of application

PUMPING TESTS ON COMPLETION 10								
Test type	Date	Pump intake depth (m)	Initial Water Level (SWL) (m)	Pumping rate (L/s)	Water Level at end of pumping (DDL) (m)	Duration of Test (hrs)	Recovery	
							Water level (m)	Time taken (hrs) (mins)
Multi stage (stepped drawdown)	Stage 1							
	Stage 2							
	Stage 3							
	Stage 4							
Single stage (constant rate)								
Height of measuring point above ground level			m	Test Method			See Code 4	

WORK PARTLY BACKFILLED OR ABANDONED 11					
Original depth of work: _____ m		Is work partly backfilled: (Yes/No) <input type="checkbox"/>			
Is work abandoned: (Yes/No) <input type="checkbox"/>		Method of abandonment: Backfilled <input type="checkbox"/> Plugged <input type="checkbox"/> Capped <input type="checkbox"/>			
Has any casing been left in the work (Yes/No) <input type="checkbox"/>		From _____ m To _____ m			
Sealing / fill type	From depth (m)	To depth (m)	Sealing / fill type	From depth (m)	To depth (m)
See Code 11			See Code 11		
1	0	76.7			

Site chosen by:	Hydrogeologist <input type="checkbox"/>	Geologist <input checked="" type="checkbox"/>	Driller <input type="checkbox"/>	Diviner <input type="checkbox"/>	Client <input checked="" type="checkbox"/>	Other <input type="checkbox"/>	12
-----------------	---	---	----------------------------------	----------------------------------	--	--------------------------------	----

Lot No _____ DP No _____		13					
Work Location Co ordinates		Easting	524670	Northing	6817819	Zone	54
GPS: (Yes/No) <input checked="" type="checkbox"/>	>>	AMG/AGD	<input type="checkbox"/>	or	MGA/GDA	<input checked="" type="checkbox"/>	(See explanation)
Longitude				Latitude			
Please mark the work site with "X" on the CLID provided map.							
Indicate also the distances in metres from two (2) adjacent boundaries, and attach the map to this Form A package.							

Signatures:

Driller: _____

Licensee: _____

Date: _____

Date: _____

