

PRIOR TO ANY DEMOLITION OR BULK EARTHWORKS OCCURRING ON SITE, CONSTRUCT 1.8m HIGH IMPERFORATE ACOUSTIC BARRIER. BARRIER IS NOT TO BE CONSTRUCTED OF A HIGHLY REFLECTIVE MATERIAL. THE ACOUSTIC BARRIER IS TO EXTEND TO THE GROUND WITH DRAINAGE SLOTS AT MAXIMUM 400mm CENTRES. SUBMIT DETAILS OF PROPOSED ACOUSTIC BARRIER FOR APPROVAL BY THE SUPERINTENDENT PRIOR TO FABRICATION.

DEMOLITION PLAN  
SCALE 1:200 @ B1

AUSTRALIAN INSTITUTE OF POLICE MANAGEMENT  
for The Australian Federal Police




brewster horth  
ARCHITECTS

A03

DECEMBER 2008  
20816-10.DD03-06  
PRINT DATE: 11.12.08

© Copyright of Brewster Horth Pty Limited, 2008. ACN 002 513 153.  
All rights reserved.  
Figured dimensions shall be taken in preference to scaling.  
This drawing is a preliminary design and is not to be used for construction work.  
Brewster Horth Architects is a division of Brewster Horth Pty Limited.



0 2m 5m 10m

NOTES:

- NOTE 1: SANITARY DRAINAGE AND WATER SUPPLY PIPEWORK TO BE REMOVED AND CAPPED OFF AT GROUND LEVEL TO ALLOW FOR DEMOLITION OF BUILDINGS.
- NOTE 2: DISCONNECT, REMOVE, AND MAKE SAFE ALL ELECTRICAL, FIRE, AND COMMUNICATIONS CABLING TO AND WITHIN THE BUILDINGS TO BE DEMOLISHED.
- NOTE 3: NOT USED
- NOTE 4: NOT USED
- NOTE 5: STORMWATER PITS TO BE RETAINED AT GROUND LEVEL. COVER TO PREVENT RUBBISH/DEBRIS AND BANDICOTS ENTERING STORMWATER LINES.
- NOTE 6: EXISTING STAIR TO BE DEMOLISHED AND REMOVED.
- NOTE 7: EXISTING WALL/DECKING/SLAB TO BE DEMOLISHED AND REMOVED.
- NOTE 8: REMOVE EXISTING SHADE STRUCTURE & SUPPORTS. MAKE GOOD ADJOINING SURFACE.
- NOTE 9: REMOVE EXISTING POWER POLE. DISCONNECT, REMOVE AND MAKE SAFE OVERHEAD POWER/TELEPHONE/DATA CABLING.

LEGEND:

- EXISTING BUILDING, BALCONY, STAIRS, FOOTINGS AND ALL ASSOCIATED STRUCTURE TO BE DEMOLISHED AND REMOVED. ALL EXISTING SERVICES TO BE CAPPED OFF AT GROUND LEVEL.
- EXISTING RETAINING WALL TO BE DEMOLISHED.
- EXTENT OF EXISTING CONCRETE SLAB OR PATH TO BE DEMOLISHED.
- DEMOLISH AND REMOVE EXISTING ROADWAY AND ALL ASSOCIATED KERBING.
- EXISTING BUILDING TO BE RETAINED.
- EXISTING CONCRETE RAMP OR PATH AND ABUTMENT BOUNDARY. ASSOCIATED KERBING AND FOOTINGS TO BE DEMOLISHED AND REMOVED.
- EXISTING TIMBER DECK AND ALL ASSOCIATED STRUCTURE AND FOOTINGS TO BE DEMOLISHED AND REMOVED.
- EXISTING STORMWATER SERVICES. REFER TO CIVIL ENGINEERS DRAWINGS.
- TELECOMMUNICATIONS PIT TO BE RETAINED
- EXISTING POWER POLE TO BE REMOVED
- EXISTING OVERHEAD ELECTRICAL CABLING TO BE REMOVED. REFER ELECTRICAL SPECIFICATION FOR WHERE TEMPORARY POWER NEEDS TO BE MAINTAINED.
- SITE BOUNDARY