



SHARVAIN PROJECTS

www.sharvainprojects.com

SHARVAIN FACADES PTY. LTD.
T/A SHARVAIN PROJECTS
ABN 45 116 437 462

HEAD OFFICE:
UNIT 7
119 ~ 133 McEVOY STREET
ALEXANDRIA NSW 2015

PH: (02) 9698 3411
FAX: (02) 9690 1006

FACTORY:
No. 16 MIDDLETON ROAD
DEE WHY NSW 2099

E-mail:
Kostura@sharvainprojects.com

24th October 2011

Brookfield Multiplex Pty Limited
GPO Box 172
Sydney NSW 2000

ATTENTION: **MR. TINO UCCINO**

RE: 11.14mm TRANSLUCENT LOW IRON GLASS REFLECTIVITY

Dear Tino,

We are referring to your enquiry about the external light reflectivity of the Low Iron translucent glass selected for the glass cladding to the MUEF project.

We would like to confirm that the external light reflectivity of the selected, 11.14mm thick Low Iron laminated glass with translucent PVB interlayer is appx. 10%.

The technical data sheet is attached. We have yellow highlighted the selected glass.

Please do not hesitate to contact me should you require any further information or clarification.

Yours Sincerely,
Sharvain Facades Pty. Ltd.



BORIS KOSTURA BEng, MIEAust No. 593803
Director



CHINA SOUTHERN GLASS(AUST) PTY LTD
SUITE 2 LEVEL 2 186-190 CHURCH ST PARRAMATTA NSW 2150

PERFORMANCE DATA OF GLASS PRODUCTS

Calculated programme: W5.2

External condition: ASHRAE

No.		试样规格、型号及结构 DESCRIPTION OF SAMPLE	可见光/Visible Light(%)				太阳能/Solar Energy(%)		U-值/U-value(W/m ² ·K)		遮阳系数 SC
			透过率 Trans	反射率 Refl	室外/Out	室内/In	透过率 Trans	反射率 Refl (out)	冬季晚上 Winter night	夏季白天 Summer day	
1		5C-0.38 white translucent+0.76 clear-5C(YGA1108067M)	74	10	10	64	9	5.81	5.26	0.82	
2		5C-0.38 soft white+0.76 clear-5C(YGA1108067M)	58	8	8	53	10	5.81	5.25	0.74	
3		5 low iron-0.38soft white+0.76 clear-5 low iron(YGA1108067M)	83	8	8	76	12	5.80	5.25	0.9	
4		5 low iron-0.38 white translucent+0.76 clear-5 low iron(YGA1108067M)	59	10	10	58	10	5.81	5.25	0.77	

Remark:

- 1 The data is based on calculation by Window 5.2 under ASHRAE standard conditions.
- 2 The actual performance data of products may slightly differ from the data listed.