BUNGARRIBEE INDUSTRIAL LOT 5B

PROPOSED CIVIL WORKS - BULK EARTHWORKS PACKAGE

DRAWING LIST

| C200 | COVER SHEET, NOTES, LEGENDS AND LOCALITY PLAN |
|------|---|
| C202 | GENERAL ARRANGEMENT PLAN |
| C205 | BULK EARTHWORKS PLAN SHEET 1 |
| C206 | BULK EARTHWORKS PLAN SHEET 2 |
| C207 | BULK EARTHWORKS PLAN SHEET 3 |
| C208 | BULK EARTHWORKS PLAN SHEET 4 |
| C210 | SEDIMENTATION AND EROSION CONTROL PLAN |
| C211 | SEDIMENTATION AND EROSION CONTROL DETAILS |
| | |

BULK EARTHWORKS NOTES

- 1. ORIGIN OF LEVELS: REFER SURVEY NOTES
- 2. STRIP ALL TOPSOIL/ORGANIC MATERIAL FROM CONSTRUCTION AREA AND REMOVE FROM SITE OR STOCK PILE AS DIRECTED BY SUPERINTENDENT.
- 3. EXCAVATED MATERIAL TO BE USED AS STRUCTURAL FILL PROVIDED THE PLACEMENT MOISTURE CONTENT OF THE MATERIAL IS */- 2% OF THE OPTIMUM MOISTURE CONTENT.

| 4. COMPACT FILL AREAS | AND SUBGRADE TO NOT LESS THAN: |
|-----------------------|--|
| LOCATION | CTANDARD RRY DENETTY |
| LOCATION | STANDARD DRY DENSITY (AS 1289 E 5.1.1.) |
| UNDER BUILDING SLABS | |

| IA3 1207 L 3.1. | 1.1 | |
|---|-----|--|
| | | |
| UNDER BUILDING SLABS | | |
| ON GROUND | 98% | |
| UNDER ROADS AND | | |
| CARPARKS | 98% | |
| LANDSCAPED AREAS UNLESS NOTED OTHERWISE | 98% | |
| | | |

- 5. FOR NON COHESIVE MATERIAL, COMPACT TO 75% DENSITY INDEX. 6. BEFORE PLACING FILL, PROOF ROLL EXPOSED SUBGRADE WITH AN 8 TONNE (MINI) DEADWEIGHT SMOOTH DRUM VIBRATORY ROLLER TO DETECT THEN REMOVE SOTT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER).
- TO STEEL OF COMPACTION TESTING SHALL BE NOT LESS THAN:

 [A] 1 TEST PER 200m OF FILL PLACED PER 300 LAYER OF FILL.

 [B] 3 TESTS PER 191517

 [C] 1 TEST PER 1000m OF EXPOSED SUBGRADE
 TESTING SHALL BE "LEVEL 1" TESTING IN ACCORDANCE WITH AS 3798
 (1996).
- 8. FILLING TO BE PLACED AND COMPACTED IN MAXIMUM 150mm LAYERS 9. NO FILLING SHALL TAKE PLACE TO EXPOSE SUBGRADE UNTIL THE AREA HAS BEEN PROOF ROLLED IN THE PRESENCE OF AT & L
 AND APPROVAL GIVEN IN WRITING THAT FILLING CAN PROCEED.

EROSION AND SEDIMENT CONTROL

NOTES

GENERAL INSTRUCTIONS

- THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH
 A. LOCAL AUTHORITY REQUIREMENTS
 B. EPA REQUIREMENTS O. CFA REQUIREMENTS
 C. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN
 STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH
 2004.
- 4. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.
- 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY, REPAIRS AND OR MAINTENANCE SHALL BE DEUDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- (A) INSTALL A BARRIER FENCE ALONG THE BOUNDARIES
- (B) INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES
- AS SHOWN ON PLAN.
- (C) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER.
- (D) INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN
- (E) INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- (F) UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.


SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH
 VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL
 MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION
 TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT
- 10. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11 WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED
- TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER
- 14 ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY
- (A) PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- (B) ENSURING THAT NOTHING IS NAILED TO THEM
- (C) PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS.
- (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

SITEWORKS LEGEND EXISTING BOUNDARY TO BE REMOVED ● BE56.00 BUIK FARTHWORKS LEVEL 54.0 PROPOSED BULK EARTHWORKS CONTOUR BENCH MARK TELSTRA PIT TEL TELSTRA PILLAR **⊠** TP ELECTRIC LIGHT POLE O ELP POWER POLE O PP SERVICE PIT (METAL LID) ☐ MPIT STREET SIGN ⊠ SS GRATED INLET PIT 目 GIP KERB INLET PIT KIP DRAINAGE PIT D DP STOP VALVE HYDRANT MD HYD GAS VALVE GAS TELSTRA OPTIC FIBRE ELECTRICITY (OVERHEAD) WATER STORMWATER SEWER HNKNOWN









CONTRACTOR SHALL CALL; DIAL BEFORE YOU DIG 1100 PRIOR TO COMMENCEMENT OF WORK TO OBTAIN ALL CURRENT SERVICE AUTHORITY PLANS



BUNGARRIBEE

Suite 702, 154 Pacific Hwy St Leonards NSW 2065 ABN 96 130 882 405

Tel: 02 9439 1777 Fax: 02 9460 8413

C200-COVER-SHEET-&-LOCALITY-PLAN.dwg

22-04-1 12-04-1

Date

A1

INDUSTRIAL LOT 5B


Civil Engineers and Project Managers


AHD


COVER SHEET, NOTES. LEGENDS AND LOCALITY PLAN


C200 12-106


C - S75W\C200-COVER-SHEET-&-LOCALITY-PLAN.dwg Date Plotted: 6 May 2013 - 10:25AM File Name: F:\12-106 BOC Gases\Drgs\Civil\Final\Earthworks Pac






















100mm on Original


MESH AND GRAVEL INLET FILTER



GEOTEXTILE INLET FILTER



TEMPORARY CATCH DRAIN
(MIN FALL 1%)
SCALE 1:10



| | B RE-ISSUED FOR S75W APPROVAL 22-04-13 | Issue | Description | Date |
|--|---|-------|-----------------------------|----------|
| | | A | ISSUED FOR S75W APPROVAL | 12-04-13 |
| C RE-ISSUED FOR S75W APPROVAL 06-05-13 | C RE-ISSUED FOR \$75W APPROVAL 06-05-13 | В | RE-ISSUED FOR S75W APPROVAL | 22-04-13 |
| | | С | RE-ISSUED FOR S75W APPROVAL | 06-05-13 |

THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

| Scales | 1 | I | |
|-----------------|----------|----------------|--|
| | AS SHOWN | Drawn GB | |
| | | Designed GB | |
| Height Datum | AHD | Checked AMc | |
| Grid | | Approved | |

File: C211-SEDIMENT-AND-EROSION-CONTROL-DETAILS.owg



Civil Engineers and Project Managers



Suite 702, 154 Pacific Hwy St Leonards NSW 2065 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9460 8413

BUNGARRIBEE INDUSTRIAL LOT 5B

SEDIMENTATION AND **EROSION CONTROL DETAILS** Issue

C211 12-106

Date Plotted: 6 May 2013 - 10:25AM File Name: F:\12-106 BOC Gases\Drgs\Civil\Final\Earthworks Package - \$75W\C211-\$EDIMENT-AND-EROSION-CONTROL-DETAILS dwg

1:10

0 100 200