

The conditions of consent are as follows:

Deferred commencement terms:

Conditions that identify approved plans:

Approved architectural plans and documentation (new development)

The development must be carried out in accordance with the following plans and documentation listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Plan no.	Drawn by	Dated
#	#	#
#	#	#

Document(s)	Dated
Colours and finishes schedule	#
Basix certificate No. (ADD NO.)	#
Bush fire risk assessment and certification, (CONSULTANTS NAME)	#
#	#

Reason: To ensure that the development is in accordance with the determination.

Agreed

Inconsistency between documents

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent prevail.

Reason: To ensure that the development is in accordance with the determination.

Agreed

Approved landscape plans

Landscape works shall be carried out in accordance with the following landscape plan(s), listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Plan no.	Drawn by	Dated
#	#	#

Reason: To ensure that the development is in accordance with the determination.

Agreed

Conditions to be satisfied prior to demolition, excavation or construction:**Road opening permit**

The opening of any footway, roadway, road shoulder or any part of the road reserve shall not be carried out without a road opening permit being obtained from Council (upon payment of the required fee) beforehand.

Reason: Statutory requirement (Roads Act 1993 Section 138) and to maintain the integrity of Council's infrastructure.

Agreed

Notice of commencement

At least 48 hours prior to the commencement of any development (including demolition, excavation, shoring or underpinning works), a notice of commencement of building or subdivision work form and appointment of the principal certifying authority form shall be submitted to Council.

Reason: Statutory requirement.

Agreed

Notification of builder's details

Prior to the commencement of any development or excavation works, the Principal Certifying Authority shall be notified in writing of the name and contractor licence number of the owner/builder intending to carry out the approved works.

Reason: Statutory requirement.

Agreed

Notice of proposed work (contaminated land)

A notice of proposed work form must be given to Council's Development Assessment Officer, in accordance with SEPP 55, Clause 16. Note: At least 30 days notice is required, except in the case of work required to be carried out immediately under the terms of remediation order (in which case, at least 1 days notice is required).

SEPP 55, Clause 16 requires that the notice must:

- be in writing
- provide the name, address and telephone number of the person who has the duty of ensuring that the notice is given
- briefly describe the remediation work
- show why the person considers that the work is category 2 remediation work by reference to Clause 9, 14 and (if it applies) 15(1)
- specify, by reference to its property description and street address (if any), the land on which the work is to be carried out
- provide a map of the location of the land
- provide estimates of the dates for the commencement and completion of the work

The following additional information must be submitted with the notice to Council:

- copies of any preliminary investigation, detailed investigation and remediation action plan for the site
- contact details for the remediation contractor and any other party responsible for ensuring compliance of remediation work with regulatory requirements

Reason: Protection of the environment and compliance with SEPP 55.

Not Agreed - The Contamination Assessment didn't conclude that remediation works were necessary - it is considered that the Statement of Commitment in regard to contamination in the EAR is adequate.

Dilapidation survey and report (public infrastructure)

Prior to the commencement of any development or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures of the following public infrastructure, has been completed and submitted to Council:

Public infrastructure

- Full road pavement width, including kerb and gutter, of Lindfield Avenue, Havilah Lane and Kochia Lane over the site frontage, including the full intersections.
- All driveway crossings and laybacks opposite the subject site.

The report must be completed by a consulting structural/civil engineer. Particular attention must be paid to accurately recording (both written and photographic) existing damaged areas on the aforementioned infrastructure so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development.

The developer may be held liable to any recent damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded by the requirements of this condition prior to the commencement of works.

Note: A written acknowledgment from Council must be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any excavation works.

Reason: To record the structural condition of public infrastructure before works commence.

Agreed

Dilapidation survey and report (private property)

Prior to the commencement of any demolition or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures upon the following lands, has been completed and submitted to Council:

Address

- 2 Kochia Lane
- ~~43 Lindfield Avenue~~
- 39-41 Lindfield Avenue
- ~~2-6 Milray Street, buildings fronting Havilah Lane.~~

The dilapidation report must include a photographic survey of adjoining properties detailing their physical condition, both internally and externally, including such items as walls ceilings, roof and structural members. The report must be completed by a consulting structural/geotechnical engineer as determined necessary by that professional based on the excavations for the proposal and the recommendations of the submitted geotechnical report.

In the event that access for undertaking the dilapidation survey is denied by a property owner, the applicant must demonstrate in writing to the satisfaction of the Principal Certifying Authority that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed.

Note: A copy of the dilapidation report is to be provided to Council prior to any excavation works been undertaken. The dilapidation report is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any civil action required to resolve any dispute over damage to adjoining properties arising from works.

Reason: To record the structural condition of likely affected properties before works commence.

Agreed - **subject to amendments.** Anka are happy to undertake dilapidation reports for public infrastructure and the adjoining buildings, being 2 Kochia Lane and 39-41 Lindfield Avenue, however 43 Lindfield Avenue and 2-6 Milray Street are not adjoining properties and will not be affected by any development works, therefore Anka **do not agree** to the preparation of dilapidation reports for these two properties.

Geotechnical report

Prior to the commencement of any bulk excavation works on site, the applicant shall submit to the Principal Certifying Authority, the results of the detailed geotechnical investigation comprising a minimum of five cored boreholes and 2 piezometer standpipes, as recommended in Jeffery and Katauskas Report on Desktop Assessment Ref. 24013SP dated 31 March 2011. The report is to address such matters as:

- appropriate excavation methods and techniques
- vibration management and monitoring
- dilapidation survey
- support and retention of excavated faces
- hydrogeological considerations

The recommendations of the report are to be implemented during the course of the works.

Reason: To ensure the safety and protection of property.

Agreed

Construction and traffic management plan

The applicant must submit to ~~Council~~ DoPI a Construction Traffic Management Plan (CTMP), which is to be approved prior to the commencement of any works on site.

The plan is to consist of a report with Traffic Control Plans attached.

The report is to contain commitments which must be followed by the demolition and excavation contractor, builder, owner and subcontractors. The CTMP applies to all persons associated with demolition, excavation and construction of the development.

The report is to contain construction vehicle routes for approach and departure to and from all directions.

The report is to contain a site plan showing entry and exit points. Swept paths are to be shown on the site plan showing access and egress for an 11 metre long heavy rigid vehicle.

The Traffic Control Plans are to be prepared by a qualified person (red card holder). One must be provided for each of the following stages of the works:

- Demolition
- Excavation
- Concrete pour
- Construction of vehicular crossing and reinstatement of footpath
- Traffic control for vehicles reversing into or out of the site.

Traffic controllers must be in place at the site entry and exit points to control heavy vehicle movements in order to maintain the safety of pedestrians and other road users.

When a satisfactory CTMP is received, a letter of approval will be issued with conditions attached. Traffic management at the site must comply with the approved CTMP as well as any conditions in the letter issued by Council. Council's Rangers will be patrolling the site regularly and fines may be issued for any non-compliance with this condition.

Reason: To ensure that appropriate measures have been considered during all phases of the construction process in a manner that maintains the environmental amenity and ensures the ongoing safety and protection of people.

Agreed – subject to the CTMP being submitted and approved by DoPI

Work zone

A Works Zone is to be provided in Lindfield Avenue and/or Havilah Lane subject to the approval of the Ku-ring-gai Local Traffic Committee.

No loading or unloading must be undertaken from the public road or nature strip unless within a Works Zone which has been approved and paid for.

In the event the work zone is required for a period beyond that initially approved by the Traffic Committee, the applicant shall make a payment to Council for the extended period in accordance with Council's schedule of fees and charges for work zones prior to the extended period commencing.

Reason: To ensure that appropriate measures have been made for the operation of the site during the construction phase.

Agreed

Temporary construction exit

A temporary construction exit, together with necessary associated temporary fencing, shall be provided prior to commencement of any work on the site and shall be maintained throughout the duration and progress of construction.

Reason: To reduce or eliminate the transport of sediment from the construction site onto public roads.

Agreed

Erosion and drainage management

Earthworks and/or demolition of any existing buildings shall not commence until an erosion and sediment control plan is submitted to and approved by the Principal Certifying Authority. The plan shall comply with the guidelines set out in the NSW Department of Housing manual "Managing Urban Stormwater: Soils and Construction" certificate. Erosion and sediment control works shall be implemented in accordance with the erosion and sediment control plan.

The plan may be based on Drawing 21-19509-C001 Rev. C by GHD but must be amended to show the sediment basin and a supplementary note regarding treatment of collected water prior to discharge into the stormwater system.

Reason: To preserve and enhance the natural environment.

Agreed

Construction waste management plan

Prior to the commencement of any works, the Principal Certifying Authority shall be satisfied that a waste management plan, prepared by a suitably qualified person, has been prepared in accordance with Council's DCP 40 – Construction and Demolition Waste Management.

The plan shall address all issues identified in DCP 40, including but not limited to: the estimated volume of waste and method for disposal for the construction and operation phases of the development.

Note: The plan shall be provided to the Certifying Authority.

Reason: To ensure appropriate management of construction waste.

Agreed

Noise and vibration management plan

Prior to the commencement of any works, a noise and vibration management plan is to be prepared by a suitably qualified expert addressing the likely noise and vibration from demolition, excavation and construction of the proposed development and provided to the Principal Certifying Authority. The management plan is to identify amelioration measures to ensure the noise and vibration levels will be compliant with the relevant Australian Standards and Ku-ring-gai Council's Code for the Control and Regulation of Noise on Building Sites. The report shall be prepared in consultation with any geotechnical report that itemises equipment to be used for excavation works.

The management plan shall address, but not be limited to, the following matters:

- identification of the specific activities that will be carried out and associated noise sources
- identification of all potentially affected sensitive receivers, including residences, churches, commercial premises, schools and properties containing noise sensitive equipment
- the construction noise objective specified in the conditions of this consent
- the construction vibration criteria specified in the conditions of this consent
- determination of appropriate noise and vibration objectives for each identified sensitive receiver
- noise and vibration monitoring, reporting and response procedures
- assessment of potential noise and vibration from the proposed demolition, excavation and construction activities, including noise from construction vehicles and any traffic diversions
- description of specific mitigation treatments, management methods and procedures that will be implemented to control noise and vibration during construction
- construction timetabling to minimise noise impacts including time and duration restrictions, respite periods and frequency
- construction timetabling to minimise noise impacts including time and duration restrictions, respite periods and frequency
- procedures for notifying residents of construction activities that are likely to affect their amenity through noise and vibration
- contingency plans to be implemented in the event of non-compliances and/or noise complaints
- compliance with Council's Code for the Control and Regulation of Noise on Building Sites

Reason: To protect the amenity afforded to surrounding residents during the construction process.

Agreed

Conditions to be satisfied prior to the issue of the construction certificate:

Development Contributions Consent Condition – Lindfield Town Centre

This development is subject to a development contribution calculated in accordance with *Ku-ring-gai Contributions Plan 2010*, being a s94 Contributions Plan in effect under the Environmental Planning and Assessment Act, as follows:

Key Community Infrastructure	Amount
Local parks and Local sporting facilities	\$844,001.94
Local recreational and cultural, Local social facilities	\$150,610.74
Local Roads, Local Bus Facilities & Local Drainage Facilities (New Roads and Road Modifications)	\$374,705.44
Local roads, Local bus facilities & Local drainage facilities (Townscape, Transport & Pedestrian facilities)	<u>\$591,324.07</u>
TOTAL CONTRIBUTIONS	<u>\$1,960,642.19</u>

The contribution shall be paid to Council prior to the issue of any Construction Certificate, ~~Linen Plan, Certificate of Subdivision or the final Occupation Certificate~~ whichever comes first in accordance with Ku-ring-gai Contributions Plan 2010.

The contributions specified above are as at the June 2011 quarter and are subject to indexation and will continue to be indexed to reflect changes in the consumer price index and housing price index until they are paid in accordance with Ku-ring-gai Contributions Plan 2010. Prior to payment, please contact Council directly to verify the current payable contributions.

[Ku-ring-gai Contributions Plan 2010 may be viewed at www.kmc.nsw.gov.au and at the Council Chambers.](http://www.kmc.nsw.gov.au)

Reason: To ensure the provision, extension or augmentation of the Key Community Infrastructure identified in Ku-ring-gai Contributions Plan 2010 that will, or is likely to be, required as a consequence of the development.

Wording Agreed – subject to proposed amendments. Anka is happy to pay contributions in accordance with the 2010 Contributions Plan however there is **concern** that there is no explanation as to how Council calculated the sum, as we can't tell how they came up with their floorspace figures.

Landscape plans

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that detailed landscape plans for the central level 1 podium are provided which include or address the following considerations:

The design is to provide

Soil depths and volumes are to be consistent as a minimum with the Residential Flat Design Code, DIPNR (Part 02 Site design page 53).

Specifically :

The proposed depth of soil 300 – 700mm is not sufficient for the establishment of small to medium size trees, nor in some cases are the trees planted in areas of soil of sufficient area.

The Residential Flat Design Code (Part 02 Site design page 53), recommends minimum provisions for small trees (4 metre canopy diameter at maturity) of Minimum soil depth of 800mm, volume 9 cubic metres and approximate soil area of 3.5m x 3.5m or equivalent, and 1 metre depth for medium trees (8 metre mature canopy diameter at maturity). Trees proposed are of a size capable of growing to the medium size category.

Tree selection also is not considered satisfactory with both Dragon Blood Tree (Draceana) and Frangipani (Plumeria) being very slow grow species, and Koelreutaria also relatively slow growing and not considered to be a reliable in the area. It is suggested faster growing medium sized species which will provide such as Crepe Myrtle may be more appropriate.

Reason : To ensure adequate landscaping of the site.

Not agreed - the RFDC is only a guide and is not mandatory. The proposed soil depths are considered to be sufficient for the proposed landscaping design.

Landscape plan

Prior to the issue of the Construction Certificate, the Principal Certifying Authority shall be satisfied that a landscape plan has been completed in accordance with Council's DA Guide, relevant development control plans and the conditions of consent by a landscape architect or qualified landscape designer.

Note: The landscape plan must be submitted to the Principal Certifying Authority.

Reason: To ensure adequate landscaping of the site.

Not agreed, the landscape plan as submitted is considered to be appropriate.

Excavation for services

Prior to the issue of the Construction Certificate, the Principal Certifying shall be satisfied that no proposed underground services (ie. water, sewerage, drainage, gas or other service) unless previously approved by conditions of consent, are located beneath the canopy of any tree protected under Council's Tree Preservation Order, located on the subject allotment and adjoining allotments.

Note: A plan detailing the routes of these services and trees protected under the Tree Preservation Order, shall be submitted to the Principal Certifying Authority.

Agreed

Extinguishment of right of way

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that the right of way 6.5 width and 5.105 wide which benefits Lot 4 DP713505, and which is to be built over, has been extinguished. Evidence in the form of registered title documents is to be submitted to and approved by the Principal Certifying Authority prior to issue of the Construction Certificate.

If the relocation of the drainage easement which benefits 39 and 41 Lindfield Avenue is required, then evidence of the relocation of the easement in the form of registered title documents is to be submitted to and approved by the Principal Certifying Authority prior to issue of the Construction Certificate.

Reason: To maintain the rights of benefitting owners to use the easements or rights of way on their titles.

Not agreed - please refer to proposed condition of consent as submitted in letter dated 19 August 2011 by Robert Moses of Holding Redlich.

Amendments to approved engineering plans

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that the approved engineering plan(s), listed below ~~and endorsed with Council's stamp~~, have been amended in accordance with the requirements of this condition as well as other conditions of this consent:

Plan no.	Drawn by	Dated
21-19509-C002 Rev. B	GHD	13 April 2011

The above engineering plan(s) shall be amended as follows:

- The 100 cubic metre rainwater retention tank is not required and should be deleted, as the BASIX commitments are for a recycled water supply, which is separately shown on the architectural plans in Basement 1. The retained rainwater would not be used.
- The on site detention volume is to be calculated using 100% of the site area, as given in Appendix A5.1g)(iv) of Council's DCP 47 *Water management*. The required volume is **104 cubic metres**.

- A design shall be included for the upgrading or relocation of the interallotment drainage pipe which services 39-41 Lindfield Avenue, consistent with the existing or a new easement location.
- Water quality measures are to be provided to achieve the targets given in Chapter 8 of Council's DCP 47 *Water management*.

The above amendments are required to ensure compliance with the following:

- BASIX Certificate 309478M_05.
- Ku-ring-gai Council Water Management Development Control Plan 47.

Note: An amended engineering plan, prepared by a qualified engineer shall be submitted to the Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

Agreed - subject to minor amendment

Long service levy

In accordance with Section 109F(i) of the Environmental Planning and Assessment Act a Construction Certificate shall not be issued until any long service levy payable under Section 34 of the Building and Construction Industry Long Service Payments Act 1986 (or where such levy is payable by instalments, the first instalment of the levy) has been paid. Council is authorised to accept payment. Where payment has been made elsewhere, proof of payment is to be provided to Council.

Reason: Statutory requirement.

Agreed

Builder's indemnity insurance

The applicant, builder, developer or person who does the work on this development, must arrange builder's indemnity insurance and submit the certificate of insurance in accordance with the requirements of Part 6 of the Home Building Act 1989 to the Certifying Authority for endorsement of the plans accompanying the Construction Certificate.

It is the responsibility of the applicant, builder or developer to arrange the builder's indemnity insurance for residential building work over the value of \$12,000. The builder's indemnity

insurance does not apply to commercial or industrial building work or to residential work valued at less than \$12,000, nor to work undertaken by persons holding an owner/builder's permit issued by the Department of Fair Trading (unless the owner/builder's property is sold within 7 years of the commencement of the work).

Reason: Statutory requirement.

Agreed

Outdoor lighting

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that all outdoor lighting will comply with AS/NZ1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Note: Details demonstrating compliance with these requirements are to be submitted prior to the issue of a Construction Certificate.

Reason: To provide high quality external lighting for security without adverse affects on public amenity from excessive illumination levels.

Agreed

External service pipes and the like prohibited

Proposed water pipes, waste pipes, stack work, duct work, mechanical ventilation plant and the like must be located within the building. Details confirming compliance with this condition must be shown on construction certificate plans and detailed with construction certificate specifications. Required external vents or vent pipes on the roof or above the eaves must be shown on construction certificate plans and detailed with construction certificate specifications. External vents or roof vent pipes must not be visible from any place unless detailed upon development consent plans. Where there is any proposal to fit external service pipes or the like this must be detailed in an amended development (S96) application and submitted to Council for determination.

Vent pipes required by Sydney Water must not be placed on the front elevation of the building or front roof elevation. The applicant, owner and builder must protect the appearance of the building from the public place and the appearance of the streetscape by elimination of all external services excluding vent pipes required by Sydney Water and those detailed upon development consent plans.

Reason: To protect the streetscape and the integrity of the approved development.

Agreed

Access for people with disabilities (commercial)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that access for people with disabilities from the public domain and all car parking areas on site to all tenancies within the building is provided. Consideration must be given to the means of dignified and equitable access.

Compliant access provisions for people with disabilities shall be clearly shown on the plans submitted with the Construction Certificate. All details shall be provided to the Principal Certifying Authority prior to the issue of the Construction Certificate. All details shall be prepared in consideration of the Disability Discrimination Act and the relevant provisions of AS1428.1, AS1428.2, AS1428.4 and AS 1735.12.

Reason: To ensure the provision of equitable and dignified access for all people in accordance with disability discrimination legislation and relevant Australian standards.

Agreed

Adaptable units

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that the nominated adaptable units within the development application, [enter unit nos.], are designed as adaptable housing in accordance with the provisions of Australian Standard AS4299-1995: Adaptable Housing.

Note: Evidence from an appropriately qualified professional demonstrating compliance with this control is to be submitted to and approved by the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Disabled access & amenity.

Agreed

Stormwater management plan

Prior to issue of the Construction Certificate, the applicant must submit, for approval by the Principal Certifying Authority, scale construction plans and specifications in relation to the stormwater management and disposal system for the development. The plan(s) may be based on Drawings 21-19509-C002 Rev. B by GHD, dated 13 April 2011, and must include the following detail:

- exact location and reduced level of discharge point to the public drainage system
- Layout of the property drainage system components, including but not limited to (as required) gutters, downpipes, spreaders, pits, swales, kerbs, cut-off and intercepting drainage structures, subsoil drainage, flushing facilities and all ancillary stormwater plumbing - all designed for a 235mm/hour rainfall intensity for a duration of five (5) minutes (1:50 year storm recurrence)
- details of the required on-site detention tanks required by Ku-ring-gai Water Management DCP 47, including dimensions, materials, locations, orifice and discharge control pit details as required (refer Chapter 6 and Appendices 2, 3 and 5 of DCP 47 for volume, PSD and design requirements)
- the required basement stormwater pump-out system is to cater for driveway runoff and subsoil drainage (refer appendix 7.1.1 of Development Control Plan 47 for design)

The above construction drawings and specifications are to be prepared by a qualified and experienced civil/hydraulic engineer in accordance with Council's Water Management Development Control Plan 47, Australian Standards 3500.2 and 3500.3 - Plumbing and Drainage Code and the Building Code of Australia.

Reason: To protect the environment.

Agreed

Recycling and waste management

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that the development provides a common garbage collection/separation area sufficient in size to store all wheelie garbage bins and recycling bins provided by Council for the number of units in the development ~~in accordance with DCP-40~~. The garbage collection point is to be accessible by Council's Waste Collection Services.

The responsibility for:

- the cleaning of waste rooms and waste service compartments; and
- the transfer of bins within the property, and to the collection point once the development is in use;

shall be determined when designing the system and clearly stated in the Waste Management Plan.

Note: The architectural plans are to be amended and provided to the Certifying Authority.

Reason: Environmental protection.

Agreed - with suggested amendment

Noise from road and rail (residential only)

Prior to the issue of the Construction Certificate, the Certifying Authority shall submit evidence to Council demonstrating that the development will be acoustically designed and constructed to ensure that the following LAeq levels are not exceeded:

- (a) in any bedroom in the building—35 dB(A) at any time between 10 pm and 7 am,
- (b) anywhere else in the building (other than a garage, kitchen, bathroom or hallway)—40 dB(A) at any time.

Plans and specifications of the required acoustic design shall be prepared by a practicing acoustic engineer and shall be submitted to the Principal Certifying Authority.

Reason: To minimise the impact of noise from the adjoining road or rail corridor on the occupants of the development.

Agreed

Noise from plant in residential zone

Where any form of mechanical ventilation equipment or other noise generating plant is proposed as part of the development, prior to the issue of the Construction Certificate the Certifying Authority, shall be satisfied that the operation of an individual piece of equipment or operation of equipment in combination will not exceed more than 5dB(A) above the background level during the day when measured at the site's boundaries and shall not exceed the background level at night (10.00pm –6.00 am) when measured at the boundary of the site.

C1. Note: A certificate from an appropriately qualified acoustic engineer is to be submitted with the Construction Certificate, certifying that all mechanical ventilation equipment or other noise generating plant in isolation or in combination with other plant will comply with the above requirements.

Reason: To comply with best practice standards for residential acoustic amenity.

Agreed

Location of plant (residential flat buildings)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that all plant and equipment (including but not limited to air conditioning equipment) is located within the basement.

C1. Note: Architectural plans identifying the location of all plant and equipment shall be provided to the Certifying Authority.

Reason: To minimise impact on surrounding properties, improved visual appearance and amenity for locality.

Not agreed - the plant is to be on the roof, as shown on the plans - it will not be seen from surrounding properties and will not impact upon the visual appearance of the locality.

Number of bicycle spaces

~~The basement car park shall be adapted to provide the number of bicycle spaces in accordance with DCP 55.~~ The bicycle parking spaces shall be designed in accordance with AS2890.3. Details shall be submitted to the satisfaction of the Certifying Authority prior to the issue of a Construction Certificate.

Reason: To provide alternative modes of transport to and from the site.

Agreed - with suggested amendment

Energy Australia requirements

Prior to issue of the Construction Certificate, the applicant must contact Energy Australia regarding power supply for the subject development. A written response detailing the full requirements of Energy Australia (including any need for underground cabling, substations or similar within or in the vicinity the development) shall be submitted to the Principal Certifying Authority for approval prior to issue of the Construction Certificate.

Any structures or other requirements of Energy Australia shall be indicated on the plans issued with the Construction Certificate, to the satisfaction of the Principal Certifying Authority and Energy Australia. The requirements of Energy Australia must be met in full prior to issue of the Occupation Certificate.

Reason: To ensure compliance with the requirements of Energy Australia.

Agreed

Utility provider requirements

Prior to issue of the Construction Certificate, the applicant must make contact with all relevant utility providers whose services will be impacted upon by the development. A written copy of the requirements of each provider, as determined necessary by the Certifying Authority, must be obtained. All utility services or appropriate conduits for the same must be provided by the developer in accordance with the specifications of the utility providers.

Reason: To ensure compliance with the requirements of relevant utility providers.

Agreed

Driveway grades – basement car parks

Prior to the issue of the Construction Certificate, longitudinal driveway sections are to be prepared by a qualified civil/traffic engineer and be submitted for to and approved by the Certifying Authority. These profiles are to be at 1:100 scale along both edges of the proposed driveway, starting from the centreline of the frontage street carriageway to the proposed basement floor level. The traffic engineer shall provide specific written certification on the plans that:

- vehicular access can be obtained using grades of 25% (1 in 4) maximum (20% where access for Council's small waste collection vehicle is required) and where access for Council's small waste collection vehicle is required) and
- all changes in grade (transitions) comply with Australian Standard 2890.1 –“Off- street car parking” (refer clause 2.5.3) to prevent the scraping of the underside of vehicles.

If a new driveway crossing is proposed, the longitudinal sections must incorporate the driveway crossing levels as issued by Council upon prior application.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

Agreed

Basement car parking details

Prior to issue of the Construction Certificate, certified parking layout plan(s) to scale showing all aspects of the vehicle access and accommodation arrangements must be submitted to and approved by the Certifying Authority. A qualified civil/traffic engineer must review the proposed vehicle access and accommodation layout and provide written certification on the plans that:

- all parking space dimensions, driveway and aisle widths, driveway grades, transitions, circulation ramps, blind aisle situations and other trafficked areas comply with Australian Standard 2890.1 – 2004 “Off-street car parking”
- a clear height clearance of **2.6 metres** (~~required under DCP40 for waste collection trucks~~) is provided over the designated garbage collection truck manoeuvring areas within the basement
- no doors or gates are provided in the access driveways to the basement carpark which would prevent unrestricted access for internal garbage collection at any time from the basement garbage storage and collection area
- the vehicle access and accommodation arrangements are to be constructed and marked in accordance with the certified plans

Reason: To ensure that parking spaces are in accordance with the approved development.

Agreed - with suggested amendments

Design of works in public road (Roads Act approval)

Prior to issue of the Construction Certificate, the Certifying Authority shall be satisfied that engineering plans and specifications prepared by a qualified consulting engineer ~~have been approved by Council's Development Engineer~~. The plans to be assessed must be to a detail suitable for construction issue purposes and must detail the following infrastructure works required in Lindfield Avenue, Kochia Lane and Havilah Lane:

- reconstruct the footpath, and road pavement where applicable, to meet Council's strategies for the public domain (see Council's Public Domain Plan at the following link: http://www.kmc.nsw.gov.au/resources/documents/0016_Part2E3-3_Lindfield.pdf). Street furniture and/or street tree planting are also to be included where required.

Development consent does not give approval to these works in the road reserve. The applicant must obtain a separate approval under sections 138 and 139 of The Roads Act 1993 for the works in the road reserve required as part of the development. The Construction Certificate must not be issued, and these works must not proceed until Council has issued a formal written approval under the Roads Act 1993.

The required plans and specifications are to be designed in accordance with the General Specification for the Construction of Road and Drainage Works in Ku-ring-gai Council, dated November 2004. The drawings must detail existing utility services and trees affected by the works, erosion control requirements and traffic management requirements during the course of works. Survey must be undertaken as required. Traffic management is to be certified on the drawings as being in accordance with the documents SAA HB81.1 – 1996 – Field Guide for Traffic Control at Works on Roads – Part 1 and RTA Traffic Control at Work Sites (1998). Construction of the works must proceed only in accordance with any conditions attached to the Roads Act approval issued by Council.

A minimum of three (3) weeks will be required for Council to assess the Roads Act application. Early submission of the Roads Act application is recommended to avoid delays in obtaining a Construction Certificate. An engineering assessment and inspection fee (set out in Council's adopted fees and charges) is payable and Council will withhold any consent and approved plans until full payment of the correct fees. Plans and specifications must be marked to the attention of Council's Development Engineers. In addition, a copy of this condition must be provided, together with a covering letter stating the full address of the property and the accompanying DA number.

Reason: To ensure that the plans are suitable for construction purposes.

Agreed – with suggested amendment

Conditions to be satisfied prior to the issue of the construction certificate or prior to demolition, excavation or construction (whichever comes first):

Infrastructure restorations fee

To ensure that damage to Council Property as a result of construction activity is rectified in a timely matter:

- a) All work or activity taken in furtherance of the development the subject of this approval must be undertaken in a manner to avoid damage to Council Property and must not jeopardise the safety of any person using or occupying the adjacent public areas.
- b) The applicant, builder, developer or any person acting in reliance on this approval shall be responsible for making good any damage to Council Property, and for the removal from Council Property of any waste bin, building materials, sediment, silt, or any other material or article.
- c) The Infrastructure Restoration Fee must be paid to the Council by the applicant prior to both the issue of the Construction Certificate and the commencement of any earthworks or construction.
- d) In consideration of payment of the Infrastructure Restorations Fee, Council will undertake such inspections of Council Property as Council considers necessary and also undertake, on behalf of the applicant, such restoration work to Council Property, if any, that Council considers necessary as a consequence of the development. The provision of such restoration work by the Council does not absolve any person of the responsibilities contained in (a) to (b) above. Restoration work to be undertaken by the Council referred to in this condition is limited to work that can be undertaken by Council at a cost of not more than the Infrastructure Restorations Fee payable pursuant to this condition.
- e) In this condition:

“Council Property” includes any road, footway, footpath paving, kerbing, guttering, crossings, street furniture, seats, letter bins, trees, shrubs, lawns, mounds, bushland, and similar structures or features on any road or public road within the meaning of the Local Government Act 1993 (NSW) or any public place; and

“Infrastructure Restoration Fee” means the Infrastructure Restorations Fee calculated in accordance with the Schedule of Fees & Charges adopted by Council as at the date of payment and the cost of any inspections required by the Council of Council Property associated with this condition.

Reason: To maintain public infrastructure.

Agreed

Conditions to be satisfied during the demolition, excavation and construction phases:

Prescribed conditions

The applicant shall comply with any relevant prescribed conditions of development consent under clause 98 of the Environmental Planning and Assessment Regulation. For the purposes of section 80A (11) of the Environmental Planning and Assessment Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- The work must be carried out in accordance with the requirements of the Building Code of Australia
- In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any works commence.

Reason: Statutory requirement.

Agreed

Hours of work

Demolition, excavation, construction work and deliveries of building material and equipment must not take place outside the hours of 7.00am to 5.00pm Monday to Friday and 8.00am to 12 noon Saturday. No work and no deliveries are to take place on Sundays and public holidays.

Excavation or removal of any materials using machinery of any kind, including compressors and jack hammers, must be limited to between 7.30am and 5.00pm Monday to Friday, with a respite break of 45 minutes between 12 noon 1.00pm.

Where it is necessary for works to occur outside of these hours (ie) placement of concrete for large floor areas on large residential/commercial developments or where building processes require the use of oversized trucks and/or cranes that are restricted by the RTA from travelling during daylight hours to deliver, erect or remove machinery, tower cranes, pre-cast panels, beams, tanks or service equipment to or from the site, approval for such activities will be subject to the issue of an "outside of hours works permit" from Council as well as notification of the surrounding properties likely to be affected by the proposed works.

Note: Failure to obtain a permit to work outside of the approved hours will result in on the spot fines being issued.

Reason: To ensure reasonable standards of amenity for occupants of neighbouring properties.

Agreed

Construction noise

During excavation, demolition and construction phases, noise generated from the site shall be controlled in accordance with the recommendations of the approved noise and vibration management plan.

Reason: To ensure reasonable standards of amenity to neighbouring properties.

Agreed

Site notice

A site notice shall be erected on the site prior to any work commencing and shall be displayed throughout the works period.

The site notice must:

- be prominently displayed at the boundaries of the site for the purposes of informing the public that unauthorised entry to the site is not permitted
- display project details including, but not limited to the details of the builder, Principal Certifying Authority and structural engineer
- be durable and weatherproof
- display the approved hours of work, the name of the site/project manager, the responsible managing company (if any), its address and 24 hour contact phone number for any inquiries, including construction/noise complaint are to be displayed on the site notice
- be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted

Reason: To ensure public safety and public information.

Agreed

Dust control

During excavation, demolition and construction, adequate measures shall be taken to prevent dust from affecting the amenity of the neighbourhood. The following measures must be adopted:

- physical barriers shall be erected at right angles to the prevailing wind direction or shall be placed around or over dust sources to prevent wind or activity from generating dust
- earthworks and scheduling activities shall be managed to coincide with the next stage of development to minimise the amount of time the site is left cut or exposed
- all materials shall be stored or stockpiled at the best locations
- the ground surface should be dampened slightly to prevent dust from becoming airborne but should not be wet to the extent that run-off occurs
- all vehicles carrying spoil or rubble to or from the site shall at all times be covered to prevent the escape of dust
- all equipment wheels shall be washed before exiting the site using manual or automated sprayers and drive-through washing bays
- gates shall be closed between vehicle movements and shall be fitted with shade cloth
- cleaning of footpaths and roadways shall be carried out daily

Reason: To protect the environment and amenity of surrounding properties.

Agreed

Post-construction dilapidation report

The applicant shall engage a suitably qualified person to prepare a post construction dilapidation report at the completion of the construction works. This report is to ascertain whether the construction works created any structural damage to adjoining buildings, infrastructure and roads. The report is to be submitted to the Principal Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings, infrastructure and roads, the Principal Certifying Authority must:

- compare the post-construction dilapidation report with the pre-construction dilapidation report
- have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.

A copy of this report is to be forwarded to Council at the completion of the construction works.

Reason: Management of records.

Agreed

Approval for recycled water supply system

During the course of the construction works, the applicant must obtain a separate approval from Ku-ring-gai Council under Section 68 of the Local Government Act 1993 to install and operate the recycled water supply system which is required under the BASIX water commitments.

Reason: Statutory requirement.

Agreed

Further geotechnical input

The geotechnical and hydro-geological works implementation, inspection, testing and monitoring program for the excavation and construction works must be in accordance with the report by Jeffery and Katauskas dated 31 March 2011 and the report prepared prior to commencement of bulk earthworks. Over the course of the works, a qualified geotechnical/hydro-geological engineer must complete the following:

- further geotechnical investigations and testing recommended in the above report(s) and as determined necessary
- further monitoring and inspection at the hold points recommended in the above report(s) and as determined necessary
- written report(s) including certification(s) of the geotechnical inspection, testing and monitoring programs

Reason: To ensure the safety and protection of property.

Agreed

Compliance with submitted geotechnical report

A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee excavation.

Geotechnical aspects of the development work, namely:

- appropriate excavation method and vibration control
- support and retention of excavated faces
- hydro-geological considerations

must be undertaken in accordance with the recommendations of the geotechnical report prepared by Jeffery and Katauskas dated 31 March 2011 and the report prepared prior to commencement of bulk earthworks. Approval must be obtained from all affected property owners, including Ku-ring-gai Council, where rock anchors (both temporary and permanent) are proposed below adjoining property(ies).

Reason: To ensure the safety and protection of property.

Agreed

Use of road or footpath

During excavation, demolition and construction phases, no building materials, plant or the like are to be stored on the road or footpath without written approval being obtained from Council beforehand. The pathway shall be kept in a clean, tidy and safe condition during building operations. Council reserves the right, without notice, to rectify any such breach and to charge the cost against the applicant/owner/builder, as the case may be.

Reason: To ensure safety and amenity of the area.

Agreed

Guarding excavations

All excavation, demolition and construction works shall be properly guarded and protected with hoardings or fencing to prevent them from being dangerous to life and property.

Reason: To ensure public safety.

Agreed

Toilet facilities

During excavation, demolition and construction phases, toilet facilities are to be provided, on the work site, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Reason: Statutory requirement.

Agreed

Protection of public places

If the work involved in the erection, demolition or construction of the development is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or building involves the enclosure of a public place, a hoarding or fence must be erected between the work site and the public place.

If necessary, a hoarding is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

Any hoarding, fence or awning is to be removed when the work has been completed.

Reason: To protect public places.

Agreed

Recycling of building material (general)

During demolition and construction, the Principal Certifying Authority shall be satisfied that building materials suitable for recycling have been forwarded to an appropriate registered business dealing in recycling of materials. Materials to be recycled must be kept in good order.

Reason: To facilitate recycling of materials.

Agreed

Construction signage

All construction signs must comply with the following requirements:

- are not to cover any mechanical ventilation inlet or outlet vent
- are not illuminated, self-illuminated or flashing at any time
- are located wholly within a property where construction is being undertaken
- refer only to the business(es) undertaking the construction and/or the site at which the construction is being undertaken
- are restricted to one such sign per property
- do not exceed 2.5m²
- are removed within 14 days of the completion of all construction works

Reason: To ensure compliance with Council's controls regarding signage.

Agreed

Approval for rock anchors

Approval is to be obtained from the property owner for any anchors proposed beneath adjoining private property. If such approval cannot be obtained, then the excavated faces are to be shored or propped in accordance with the recommendations of the geotechnical and structural engineers.

Reason: To ensure the ongoing safety and protection of property.

Agreed

Maintenance period for works in public road

A maintenance period of six (6) months applies to all work in the public road reserve carried out by the applicant - after the works have been completed to the satisfaction of Ku-ring-gai Council. In that maintenance period, the applicant shall be liable for any section of the public infrastructure work which fails to perform in the designed manner, or as would reasonably be expected under the operating conditions. The maintenance period shall commence once the applicant receives a formal letter from Council stating that the works involving public infrastructure have been completed satisfactorily.

Reason: To protect public infrastructure.

Agreed

Road reserve safety

All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works. Construction materials must not be stored in the road reserve. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site. Where public infrastructure is damaged, repair works must be carried out when and as directed by Council officers. Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

Reason: To ensure safe public footways and roadways during construction.

Agreed

Services

Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the applicant and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the applicants' full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services (including water, phone, gas and the like). Council accepts no responsibility for any matter arising from its approval to this application involving any influence upon utility services provided by another authority.

Reason: Provision of utility services.

Agreed

Road repairs necessitated by excavation and construction works

It is highly likely that damage will be caused to the roadway at or near the subject site as a result of the construction (or demolition or excavation) works. The applicant, owner and builder (and demolition or excavation contractor as appropriate) will be held responsible for repair of such damage, regardless of the Infrastructure Restorations Fee paid (this fee is to cover wear and tear on Council's wider road network due to heavy vehicle traffic, not actual major damage).

Section 102(1) of the Roads Act states "A person who causes damage to a public road is liable to pay to the appropriate roads authority the cost incurred by that authority in making good the damage."

Council will notify when road repairs are needed, and if they are not carried out within 48 hours, then Council will proceed with the repairs, and will invoice the applicant, owner and relevant contractor for the balance.

Reason: To protect public infrastructure.

Agreed

Temporary rock anchors

If the use of temporary rock anchors extending into the road reserve is proposed, then approval must be obtained from Council and/or the Roads and Traffic Authority in accordance with Section 138 of the Roads Act 1993. The Applicant is to submit details of all the work that is to be

considered, and the works are not to commence until approval has been granted. The designs are to include details of the following:

- How the temporary rock anchors will be left in a way that they will not harm or interfere with any future excavation in the public road
- That the locations of the rock anchors are registered with Dial Before You Dig
- That approval of all utility authorities likely to use the public road has been obtained.
- All temporary rock anchors are located outside the allocations for the various utilities as adopted by the Streets Opening Conference.
- That any remaining de-stressed rock anchors are sufficiently isolated from the structure that they cannot damage the structure if pulled during future excavations or work in the public road.
- That signs will be placed and maintained on the building stating that de-stressed rock anchors remain in the public road and include a contact number for the building manager. The signs are to be at least 600mm x 450mm with lettering on the signs is to be no less than 75mm high. The signs are to be at not more than 60m spacing. At least one sign must be visible from all locations on the footpath outside the property. The wording on the signs is to be submitted to Council's Director Technical Services for approval before any signs are installed.

Permanent rock anchors are not to be used where any part of the anchor extends outside the development site into public areas or road reserves.

All works in the public road are to be carried out in accordance with the Conditions of Construction issued with any approval of works granted under Section 138 of the Roads Act 1993.

Reason: To ensure the ongoing safety and protection of property.

Agreed

Drainage to street

Stormwater runoff from all new impervious areas and subsoil drainage systems shall be piped to the street drainage system. New drainage line connections to the street drainage system shall conform and comply with the requirements of Sections 5.3 and 5.4 of Ku-ring- gai Water Management Development Control Plan No. 47.

Reason: To protect the environment.

Agreed

Sydney Water Section 73 Compliance Certificate

The applicant must obtain a **Section 73 Compliance Certificate** under the *Sydney Water Act 1994*. An application must be made through an authorised Water Servicing CoOrdinator. The applicant is to refer to "Your Business" section of Sydney Water's web site at www.sydneywater.com.au then the "e-develop" icon or telephone 13 20 92. Following application a "Notice of Requirements" will detail water and sewer extensions to be built and charges to be paid. Please make early contact with the CoOrdinator, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Reason: Statutory requirement.

Agreed

No storage of materials beneath trees

No activities, storage or disposal of materials shall take place beneath the canopy of any tree protected under Council's Tree Preservation Order at any time.

Reason: To protect existing trees.

Agreed

Removal of refuse

All builders' refuse, spoil and/or material unsuitable for use in landscape areas shall be removed from the site on completion of the building works.

Reason: To protect the environment.

Agreed

Survey and inspection of waste collection clearance and path of travel

At the stage when formwork for the ground floor slab is in place and prior to concrete being poured, a registered surveyor is to:

- ascertain the reduced level of the underside of the slab at the driveway entry,
- certify that the level is not lower than the level shown on the approved DA plans; and certify that the minimum headroom of 2.6 metres will be available for the full path of travel of the small waste collection vehicle from the street to the collection area.
- This certification is to be provided to Council's Development Engineer prior to any concrete being poured for the ground floor slab.
- No work is to proceed until Council has undertaken an inspection to determine clearance and path of travel.

At the stage when formwork for the ground floor slab is in place and prior to concrete being poured, Council's Development Engineer and Manager Waste Services are to carry out an inspection of the site to confirm the clearance available for the full path of travel of the small waste collection vehicle from the street to the collection area. This inspection may not be carried out by a private certifier because waste management is not a matter listed in Clause 161 of the Environmental Planning and Assessment Regulation 2000.

Reason: To ensure access will be available for Council's contractors to collect waste from the collection point.

Agreed

On site retention of waste dockets

All demolition, excavation and construction waste dockets are to be retained on site, or at suitable location, in order to confirm which facility received materials generated from the site for recycling or disposal.

- Each docket is to be an official receipt from a facility authorised to accept the material type, for disposal or processing.
- This information is to be made available at the request of an Authorised Officer of Council.

Reason: To protect the environment.

Agreed

Conditions to be satisfied prior to the issue of an Occupation Certificate:**Compliance with BASIX Certificate**

Prior to the issue of an Occupation Certificate, the Principal Certifying Authority shall be satisfied that all commitments listed in BASIX Certificate No. 309478M_05 have been complied with. **Ku-ring-gai Council's approval must be obtained for the operation of the recycled water supply system.** A copy of the approval must be provided to the Principal Certifying Authority.

Reason: Statutory requirement.

Agreed

Easement for waste collection

Prior to issue of the Occupation Certificate, an easement for waste collection is to be created under Section 88B of the Conveyancing Act 1919. This is to permit legal access for Council, Council's contractors and their vehicles over the subject property for the purpose of collecting waste from the property. The terms of the easement are to be generally in accordance with Council's draft terms for an easement for waste collection and shall be to the satisfaction of Council's Development Engineer.

Reason: To permit legal access for Council, Council's contractors and their vehicles over the subject site for waste collection.

Agreed

OSD positive covenant/restriction

Prior to issue of the Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the owner with the requirement to maintain the on-site stormwater detention facilities on the lot.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instrument for protection of on-site detention facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Council Water Management DCP 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the on-site detention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents, showing the covenants and restrictions, must be submitted and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

Agreed

Mechanical ventilation

Following completion, installation and testing of all the mechanical ventilation systems, the Principal Certifying Authority shall be satisfied of the following prior to the issue of any Occupation Certificate:

1. The installation and performance of the mechanical systems complies with:
 - The Building Code of Australia
 - Australian Standard AS1668
 - Australian Standard AS3666 where applicable
2. The mechanical ventilation system in isolation and in association with other mechanical ventilation equipment, when in operation will not be audible within a habitable room in any other residential premises before 7am and after 10pm Monday to Friday and before 8am and after 10pm Saturday, Sunday and public holidays. The operation of the unit outside these restricted hours shall emit a noise level of not greater than 5dbA above the background when measured at the nearest adjoining boundary.

Note: Written confirmation from an acoustic engineer that the development achieves the above requirements is to be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To protect the amenity of surrounding properties.

Agreed

Provision of copy of OSD designs if Council is not the PCA

Prior to issue of the Occupation Certificate, the following must be provided to Council's Development Engineer:

- a copy of the approved Construction Certificate stormwater detention/retention design for the site
- A copy of any works-as-executed drawings required by this consent
- The Engineer's certification of the as-built system.

Reason: For Council to maintain its database of as-constructed on-site stormwater detention systems.

Agreed

Certification of drainage works (dual occupancies and above)

Prior to issue of the Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the stormwater drainage works have been satisfactorily completed in accordance with the approved Construction Certificate drainage plans
- the minimum retention and on-site detention storage volume requirements of BASIX and Ku-ring-gai Water Management Development Control Plan No. 47 respectively, have been achieved
- basement and subsoil areas are able to drain via a pump/sump system installed in accordance with AS3500.3 and Appendix 7.1.1 of Ku-ring-gai Water Management Development Control Plan No. 47

- all grates potentially accessible by children are secured
- components of the new drainage system have been installed by a licensed plumbing contractor in accordance with the Plumbing and Drainage Code AS3500.3 2003 and the Building Code of Australia
- all enclosed floor areas, including habitable and garage floor levels, are safeguarded from outside stormwater runoff ingress by suitable differences in finished levels, gradings and provision of stormwater collection devices

The on-site detention certification sheet contained in Appendix 4 of DCP 47 must be completed and attached to the certification.

Note: Evidence from a qualified and experienced consulting civil/hydraulic engineer documenting compliance with the above is to be provided to Council prior to the issue of an Occupation Certificate.

Reason: To protect the environment.

Agreed

WAE plans for stormwater management and disposal (dual occupancy and above)

Prior to issue of the Occupation Certificate, a registered surveyor must provide a works as executed survey of the completed stormwater drainage and management systems. The survey must be submitted to and approved by the Principal Certifying Authority prior to issue of the Occupation Certificate. The survey must indicate:

- as built (reduced) surface and invert levels for all drainage pits
- gradients of drainage lines, materials and dimensions
- as built (reduced) level(s) at the approved point of discharge to the public drainage system
- as built location and internal dimensions of all detention and retention structures on the property (in plan view) and horizontal distances to nearest adjacent boundaries and structures on site
- the achieved storage volumes of the installed retention and detention storages and derivative calculations as built locations of all access pits and grates in the detention and retention system(s), including dimensions
- the size of the orifice or control fitted to any on-site detention system
- dimensions of the discharge control pit and access grates
- the maximum depth of storage possible over the outlet control
- top water levels of storage areas and indicative RL's through the overland flow path in the event of blockage of the on-site detention system

The works as executed plan(s) must show the as built details above in comparison to those shown on the drainage plans approved with the Construction Certificate prior to commencement of works. All relevant levels and details indicated must be marked in red on a copy of the Principal Certifying Authority stamped construction certificate stormwater plans.

Reason: To protect the environment.

Agreed

Basement pump-out maintenance

Prior to issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that a maintenance regime has been prepared for the basement stormwater pump- out system.

Note: A maintenance regime specifying that the system is to be regularly inspected and checked by qualified practitioners is to be prepared by a suitable qualified professional and provided to the Principal Certifying Authority.

Reason: To protect the environment.

Agreed

Mechanical ventilation

Prior to the issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that all mechanical ventilation systems are installed in accordance with Part F4.5 of the Building Code of Australia and comply with Australian Standards AS1668.2 and AS3666 Microbial Control of Air Handling and Water Systems of Building.

Reason: To ensure adequate levels of health and amenity to the occupants of the building.

Agreed

Fire safety certificate

Prior to the issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that a Fire Safety Certificate for all the essential fire or other safety measures forming part of this consent has been completed and provided to Council.

Note: A copy of the Fire Safety Certificate must be submitted to Council.

Reason: To ensure suitable fire safety measures are in place.

Agreed

Sydney Water Section 73 Compliance Certificate

Prior to issue of an Occupation Certificate the Section 73 Sydney water Compliance Certificate must be obtained and submitted to the Principal Certifying Authority

Reason: Statutory requirement.

Agreed

Construction of works in public road – approved plans

Prior to issue of the Occupation Certificate, the Principal Certifying Authority must be satisfied that all approved road, footpath and/or drainage works have been completed in the road reserve in accordance with the Council Roads Act approval and accompanying drawings, conditions and specifications.

The works must be supervised by the applicant's designing engineer and completed and approved to the satisfaction of Ku-ring-gai Council.

The supervising consulting engineer is to provide certification upon completion that the works were constructed in accordance with the Council approved stamped drawings. The works must be subject to inspections by Council at the hold points noted on the Roads Act approval. All conditions attached to the approved drawings for these works must be met prior to the Occupation Certificate being issued.

Reason: To ensure that works undertaken in the road reserve are to the satisfaction of Council.

Agreed

Conditions to be satisfied at all times:

Outdoor lighting

At all times for the life of the approved development, all outdoor lighting shall not detrimentally impact upon the amenity of other premises and adjacent dwellings and shall comply with, where relevant, AS/NZ1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Reason: To protect the amenity of surrounding properties.

Agreed

No door restricting internal waste collection in basement

At all times, the basement garbage storage and collection area is to be accessible by

Council's Waste Collection Services. No doors, grilles, gates or other devices shall be provided in any location which would prevent this service. Where a gate, door or the like is to be erected, unimpeded access to the garbage collection point is to be provided by other means through written agreement with Council's Waste Collection Services.

Reason: To facilitate access to the garbage collection point.

Agreed

Noise control – plant and machinery

All noise generating equipment associated with any proposed mechanical ventilation system/s shall be located and/or soundproofed so the equipment is not audible within a habitable room in any other residential premises before 7am and after 10pm Monday to Friday and before 8am and after 10pm Saturday, Sunday and public holidays. The operation of the unit outside these restricted hours shall emit a noise level of not greater than 5dbA above the background when measured at the nearest boundary.

Reason: To protect the amenity of surrounding residents.

Agreed

Loading dock management plan

The loading dock management, capacity and operating procedures for all deliveries (including hours of deliveries) to the development must comply with the Loading Dock Management Plan, which is to include details in regard to:

- Hours of operation
- Noise management
- Light spill management
- Vehicular and pedestrian access management
- Safety and security management
- Maintenance
- Ongoing review requirements.

Reason: To protect the amenity of surrounding residents and motorists.

Agreed