



Check all dimensions and site conditions prior to commencement of any work, the purchase or ordering of any materials, fittings, plant, services or equipment and the preparation of shop drawings and/or the fabrication of any components.

Do not scale drawings - refer to figured dimensions only. Any discrepancies shall immediately be referred to the architect for clarification.

All drawings may not be reproduced or distributed without prior permission from the architect.

Legend

Materials

- CP-01 Textured Granosite sandbased render - white
- CP-02 Sandblasted pre-cast concrete panels- green pigment added to mix
- CP-03 Sandblasted pre-cast concrete panels- pink pigment added to mix
- CP-04 Sandblasted pre-cast concrete panels- yellow pigment added to mix
- CP-05 Sandblasted pre-cast concrete panels- blue pigment added to mix
- CP-06 Sandblasted pre-cast concrete panels- orange pigment added to mix
- GL-01 Glass - clear to BASIX spec below
- GL-02 Glass - colourbacked
- GC-01 Glass canopy - clear glass with stainless steel fittings on powdercoated steel frame
- BH-01 Balustrade - clear glass
- BH-02 Balustrade - sandblasted glass
- RD-01 Rollerdoor - anodised aluminium
- LV-01 Louvre - clear glass on anodised aluminium frame
- LV-02 Louvre - anodised aluminium

1. BASIX Thermal Comfort Comment
2. All external walls to have R1.5 insulation.
3. Floorboard Bragg to all internal walls within the units.
4. All walls between units to be plastered masonry.
5. All roofs and exposed ceilings to have mixed GRC R1.0 insulation (not exposed blanket, unventilated 50mm air space, R2.5 insulation and plasterboard (downwards)).
6. Concrete like to form of kitchen, bathroom, ensuite, study, hallway and laundry.
7. Carpet to the floor of bathroom.
8. All bathroom external windows to have single clear glazing (System=35, SHGC=0.77).
9. Units 3.04, 3.05, 3.06, 4.01, 4.02, 4.03, 4.04 and 7.01 to have double clear glazing (System=46, SHGC=0.69), Unit 1.19 to have double Low-E glazing (System=26, SHGC=0.41, View=0.68, 5.08 and 6.08 to have single Low E glazing. All other units to have single clear glazing (System=35, SHGC=0.77).

Rev.	Date	Description	Initial	Checked
3	26/03/10	PPR Submission	JL	KP

61 Hall Street, Bondi

General Arrangement
Level 04

Status: PREFERRED PROJECT SUBMISSION

Scale: 1/200 @ A2

Drawn: JL

Project no.: 10788

Date:

Plot file: S:\10788-10788\10788_T004_HALLSTREET\01_MAIN\CAD\PL01\PPRA2.205.DWG

Drawing no.: A2.209

Revision: 3

Melbourne 1 Nicholson Street
Melbourne VIC 3000 Australia
T 03 8664 6200 F 03 8664 6300
email melb@batesmart.com.au
http://www.batesmart.com.au

Sydney 1/243 Liverpool Street
East Sydney NSW 2010 Australia
T 02 8354 5100 F 02 8354 5199
email syd@batesmart.com.au
http://www.batesmart.com.au

Bates Smart Pty Ltd ABN 70 004 999 400

BATESSMART