APPENDIX 2: CAPITAL INVESTMENT VALUE

BIAT & ASSOC QUANTITY SURVEYORS



a perspective on the past



a solution for the present



a vision for the future

Preliminary Cost Plan

Project Contact: Martin Sadlier
Director Responsible: Tom Plenty
Direct Contact Number: (02) 9261 1107

Client:

Property Address:

Date:

Mr Sung Ki Lee

6-16 Atchison Street, ST LEONARDS, NSW

2065

June 18, 2010



QUANTITY SURVEYORS
Property Depreciation and Construction Cost Consultants
ABN 84 079 247 751

Friday, 18 June 2010

Mr Sung Ki Lee
Bancor Developments Pty Limited
C/- Southern Cross Asset, Suite 501, 460 Pacific Hwy
ST LEONARDS, NSW 2065

Level 20, 201 Sussex Street Sydney NSW 2000 PO Box N314 Grosvenor Place NSW 1220

t 02 9261 1107 f 02 9261 1142

e info@bmtqs.com.auw www.bmtqs.com.au

BMT & ASSOC payeds in Australia with Sevice with others a Systrey. Metalvania, Status of Hewards of Chapag. Automolyn (1995).

RE - 6-16 Atchison Street, ST LEONARDS, NSW 2065

Dear Sung Ki,

Please find attached our Preliminary Cost Plan for the above-mentioned development.

BMT & ASSOC Pty Ltd note that in accordance with the definition of Capital Investment Value, our estimated development cost includes for all costs necessary to establish and operate the development, including the design and construction of buildings, structures, associated infrastructure and fixed or mobile plant and equipment.

Please refer to the attached indicative elemental trade breakup for an indication of the respective costs of the projects elements. Please note the following indicative elemental trade breakup has been derived from the total project costs, and only illustrates a very broad indication of the percentage of the total cost that can be allocated to the projects trade elements.

These figures have been derived from previous projects of a similar nature and do not necessarily reflect this project directly and as such can only be treated as a very broad indication.

We draw your attention to the lists of "Exclusions" and "Finishes" appended.

Yours Sincerely,

BMT & ASSOC Pty Ltd



QUALITY SURVEYORS

Preliminary Cost Plan For

6-16 Atchison Street, ST LEONARDS, NSW 2065

Prepared for: Mr Sung Ki Lee

Prepared by:

BMT & ASSOC Pty Ltd

Sydney

PO Box N314

Grosvenor Place NSW 1220 Level 20, 201 Sussex Street SYDNEY, NSW 2000 P: (02) 9261 1107

F: (02) 9261 1142

Brisbane

GPO Box 3229 BRISBANE, QLD 4001

Level 7, 320 Adelaide Street

BRISBANE, QLD 4001 P: (07) 3221 6990 F: (07) 3221 2565

Adelaide

GPO 80x 1588 ADELAIDE, \$A 5001

Level 10, 60 Waymouth Street

ADELAIDE, SA 5000 P: (08) 8231 1133 F: (08) 8231 6600

Gold Coast

PO Box 810 SOUTHPORT, QLD 4215 Level 9, 12 Marine Parade SOUTHPORT, QLD 4215 P: (07) 5226 3520

F: (07) 5526 3521

Perth

GPO Box 2572 PERTH, WA 6001

Level 28, 140 St Georges Terrace,

PERTH, WA 6000 P: (08) 9485 2111 F: (08) 9485 2133

Melbourne

GPO Box 4260 MELBOURNE, VIC 3001 Level 50, 120 Collins Street MELBOURNE, VIC 3000 P: (03) 9650 4848 F: (03) 9650 8389

Newcastle

PO Box 340 NEWCASTLE, NSW 2300 19 Brunker Road BROADMEADOW, NSW 2292 P: (02) 4978 6477 F: (02) 4978 6499

Canberra

GPO Box 2526 CANBERRA, ACT 2601 Level 6, 39 London Circuit CANBERRA, ACT 2600 P: (02) 6257 4800 F: (02) 6257 4811

Cairns

PO Box 1720 CAIRNS, QLD 4870 181 Mulgrave Road CAIRNS, QLD 4870 P: (07) 4031 5699 F: (07) 4031 5799

Australia Wide

P: 1300 728 726 F: 1300 728 721 E: info@bmtqs.com.au W: www.bmtqs.com.au

Disclaimer

The information provided in this report has been prepared by BMT & ASSOC Pty Ltd (Quantity Surveyors), as Construction Cost Consultants and not in any other capacity, on the basis of estimated costs and information provided to us by the client, it is intended for use by the parties to whom directed. The contents should thus be treated as odvice on construction costs and like motters, and not as legal or accounting advice.



1.0 Financial Summary

Based on our professional opinion and the material provided to BMT & ASSOC Pty Ltd, we believe the attached development cost summary reflects a fair and competitive indication of the cost to complete the development.

The BMT & ASSOC Pty Ltd Preliminary Cost Plan for construction cost totals \$111,934,150 exclusive of GST or \$123,127,565 inclusive of GST, with a further \$24,625,513 payable in consultants fees.

When a contingency allowance of \$5,596,708 is factored in the total development cost totals \$142,156,371 exclusive of GST or \$156,372,008 inclusive of GST.

Item	Total Cost		Cost Per Unit	
	GST Exclusive	GST Inclusive	GST Exclusive	
BMT Estimate				
Construction Cost	\$111,934,150	\$123,127,565	\$419,229	
Council / Authority Fees	EXCL	EXCL	EXCL	
Consultants Fees	\$24,625,513	\$27,088,064	\$92,230	
Development Contingency	\$5,596,708	\$6,156,378	\$20,961	
Total Development Cost	\$142,156,371	\$156,372,008	\$532,421	
Program				
Anticipated Construction Period		156	Weeks	

The development consists of a total gross floor area (fully enclosed and unenclosed covered area) of 36,010 square metres.

2.0 Construction Program

BMT & ASSOC Pty Ltd anticipate a period of 156 weeks to be appropriate for the construction of a development of this nature.

3.0 Descriptive Summary

The development involves the construction of a Mixed Use development containing 228 residential units, 38 serviced apartments and 1 restaurant, located at 6-16 Atchison Street, ST LEONARDS, NSW 2065.

An appropriate quality level of finishes has been allocated to the development.

Please refer to the Schedule of Finishes which have been allowed for within our estimate.


The development cost per square metre of gross floor area (fully enclosed covered area and unenclosed covered area) is \$3,948 exclusive of GST or \$4,342 inclusive of GST.



4.0 Limit of Accuracy

As with any development, the limit of accuracy for any level of cost and risk control is dictated by the level, and quality of documentation associated with its construction.

Figure 1. Below illustrates the effect of cost planning on a client's perception of the final cost of the proposed development.



For any given stage, anticipation of actual final cost can only improve as the design itself becomes more refined. Estimates can fall anywhere between the two curves. The vertical red line illustrates the current level of documentation available for the completion of the BMT & ASSOC Pty Ltd budget estimate, and the limit of accuracy that can be achieved given this.

5.0 Cash Flow Analysis

Please refer to the attached cash flow diagram for the development. The forecast cash flow for this development has been derived using the CSIRO - Bromilow 20/20 curve that generates a mean cashflow for developments of this nature.

For a further detailed explanation of the scope of works, please refer to the attached trade break up estimate.



6.0 Disclaimer

BMT & ASSOC Pty Ltd have prepared this report in part on the basis of information supplied in the ordinary course of business by Mr Sung Ki Lee of Boncor Developments Pty Limited.

Whilst all professional care and skill have been exercised to validate its accuracy and authenticity, BMT & ASSOC Pty Ltd is unable to provide ony guarantee in that regord, and will not be liable to any porty for any loss arising as o result of any such information subsequently being found to be inaccurate or lacking authenticity.

7.0 Conclusion

Should you have any queries or require any further clarification, please do not hesitate to contact our office.

Yours Sincerely,

BMT & ASSOC Pty Ltd



Project Information

Project Number 115636.2

Project Description Mixed Use Development

Project Address 6-16 Atchison Street, ST LEONARDS, NSW 2065

Version Number 1

Version Description Preliminary Cost Plan

Rates Current June 18, 2010

Gross Floor Area 36,010m2

Total Cost (GST Exclusive) \$142,156,371

Cost/m2 (GST Exclusive) \$3,948

Total Cost (GST Inclusive) \$156,372,008

Cost/m2 (GST Inclusive) \$4,342



Schedule of Exclusions

- Land cost
- Rise and fall
- Holding costs and interest charges
- Delay costs
- \succ Unknown ground conditions allowance
- Leasing costs
- Finance costs
- Staging, phasing or delay costs
- Removal of contaminated soil/materials
- Cost increases beyond June 2010



Schedule of Information

Following is a schedule of information used in the preparation of the Preliminary Cost Plan.

- Written and verbal information as provided by Peter Zervos of Southern Cross Asset
- Architectural Drawings: Project No: EA Submission Drawing No's: SK100-01 to SK100-17, dated 19 May 2010; SK20-01, dated 19 May 2010; SK210-01 to SK210-04, dated 19 May 2010; SK300-01 to SK300-04, dated 19 May 2010, as prepared by Francis-Jones Morehen Thorp
- Draft Pre EA Design Report: prepared by FJMT Architects, dated September 2009



Schedule of Finishes

Following is a schedule of assumed finishes used in the preparation of the Preliminary Cost Plan.

- Curtain glazed walls to façade
- Frameless glass façade to lobby and café with stone clad cores
- High quality fitout to apartments
- Community level core shell only tennant to fitout
- Polished cancrete paving to ground floor



Schedule of Areas

The costs within this report are calculated based on a Gross Floor Area (GFA) rate. Typically GFA can be determined as the sum of the Fully Enclosed Covered Floor Area (FECA) and the Unenclosed Covered Floor Area (UCA) of the building at all floor levels, measured in a square metre rate.

Fully Enclosed Covered Areas Include

- Basements
- Attics
- Garages
- Penthouses
- Lift Shafts
- Staircases
- Columns and Piers
- Equipment rooms

Unenclosed Covered Areas Include

- Roofed Balconies
- Open Verandahs
- Porches and Porticos
- Attached Covered Walkways
- Useable Space Under Buildings



Preliminary Cost Plan



Indicative Trade Summary

Mixed Use Development - 6-16 Atchison Street, ST LEONARDS, NSW 2065

Number Of Units - 266


Trade	\$/sqm	%	Total Cost	Cost/Unit
Preliminaries & Margin	361	11.6%	\$12,992,357	\$48,843
Demolition	5	0.2%	\$181,711	\$683
Excavation	103	3.3%	\$3,725,081	\$14,004
Substructure	134	4.3%	\$4,815,349	\$18,103
Columns	28	0.9%	\$999,412	\$3,757
Upper Floors	449	14.4%	\$16,172,304	\$60,798
Staircases	48	1.5%	\$1,726,257	\$6,490
Roof	66	2.1%	\$2,362,247	\$8,881
External Walls	192	6.2%	\$6,905,029	\$25,959
Windows & Glazing	106	3.4%	\$3,815,937	\$14,346
Internal Walls	341	11.0%	\$12,265,512	\$46,111
External Doors	35	1.1%	\$1,271,979	\$4,782
Internal Doors	45	1.5%	\$1,635,402	\$6,148
Wall Finishes	53	1.7%	\$1,907,968	\$7,173
Floor Finishes	114	3.7%	\$4,088,504	\$15,370
Ceiling Finishes	81	2.6%	\$2,907,381	\$10,930
Fixtures (PC Items)	187	6.0%	\$6,723,317	\$25,276
Fitments	91	2.9%	\$3,270,803	\$12,296
Electrical Services	146	4.7%	\$5,269,627	\$19,811
Hydraulic Services	154	5.0%	\$5,542,194	\$20,835
Mechanical Services	86	2.8%	\$3,089,092	\$11,613
Fire Services	53	1.7%	\$1,907,968	\$7,173
Transportation Services	93	3.0%	\$3,361,659	\$12,638
Site Works	103	3.3%	\$3,725,081	\$14,004
External Services	35	1.1%	\$1,271,979	\$4,782
Sub Total	3,108	100%	\$111,934,150	\$420,805
Contingency Allowance	155	3.9%	\$5,596,708	\$21,040
Consultants Fees	684	17.3%	\$24,625,513	\$92,577
Council Fees		÷	-	-
Total	3,948		\$142,156,371	\$534,422

Please note the above trade costs have been derived from previous project of similar nature and do not necessarily reflect this project directly and as such can only be treated as a very broad indication.




Cashflow Forecast












Original Vs Revised Cash Flow Comparison





Cash Flow Calculations

otal Work	cs To D	ate	\$0				
Month		nticipated penditure	Actual Expenditure	Variance	Forecast Cumulative	Actual Cumulative	Cumulativ Variance
0	\$	-	\$ -	\$.	\$ -	\$ -	\$
1	\$	697,779			\$ 697,779		
2	\$	1,333,536			\$ 2,031,315		
3	\$	1,680,870			\$ 3,712,185		
4	\$	2,006,492			\$ 5,718,677		
5	\$	2,310,403			\$ 8,029,080		
6	\$	2,592,602			\$ 10,621,682		
7	\$	2,853,091			\$ 13,474,773		
8	\$	3,091,867			\$ 16,566,640		
9	\$	3,308,933			\$ 19,875,573		
10	\$	3,504,287			\$ 23,379,860		
11	\$	3,677,929			\$ 27,057,789		
12	\$	3,829,861			\$ 30,887,650		
13	\$	3,960,081			\$ 34,847,730		
14	\$	4,068,589			\$ 38,916,320		
15	\$	4,155,386			\$ 43,071,706		
16	\$	4,220,472			\$ 47,292,178		
17	\$	4,263,847			\$ 51,556,025		
18	\$	4,285,510			\$ 55,841,535		
19	\$	4,285,462			\$ 60,126,997		
20	\$	4,263,702			\$ 64,390,699		
21	\$	4,220,231			\$ 68,610,930		
22	\$	4,155,049			\$ 72,765,979		
23	\$	4,068,155			\$ 76,834,134		
24	\$	3,959,550		7	\$ 80,793,683		
25	\$	3,829,233	1 11		\$ 84,622,917		
26	\$	3,677,206			\$ 88,300,123		
27	\$	3,503,467			\$ 91,803,589		
28	\$	3,308,016			\$ 95,111,605		
29	\$	3,090,854			\$ 98,202,459		
30	\$	2,851,981			\$ 101,054,440		
31	\$	2,591,396			\$ 103,645,836		
32	\$	2,309,100			\$ 105,954,936		
33	\$	2,005,093			\$ 107,960,029		
34	\$	1,679,374			\$ 109,639,403		
35	\$	1,331,944			\$ 110,971,347		
36	\$	962,803			\$ 111,934,150		