

Woodlawn Bioreactor

Addendum to modification application

Modification of DA 31-02-99 and MP 10_0012 for the construction of a leachate treatment plant and associated infrastructure, and changes to regional waste limits and operating hours



Prepared for Veolia Environmental Services (Australia) Pty Ltd

June 2017



Contents

1 Introduction

2 Leachate Management

- 2.1 Short Term Storage solution*
- 2.2 Long Term Storage solution*
- 2.3 Need for interim storage solution*
- 2.4 The Proposal*

3 Consideration

- 3.1 Odour*
- 3.2 Water*
- 3.3 Other*

4 Conclusion

Attachments

- Appendix 1 – Woodlawn Bioreactor Facility Odour Modelling Study – Proposed Addition of ED3S to Leachate Management System (May 2016).*
- Appendix 2 – Updated Water Balance*

1 Background

This addendum is submitted in support of Veolia Environmental Services (Australia) Pty Ltd modification application recently submitted to the Department of Planning and Environment (DPE). The modification application to amend DA 31-02-99 and MP 10_0012 seeks to enable the construction of a leachate treatment plant (LTP) and associated infrastructure. The addendum should be read in conjunction with the environmental assessment (EA) supporting that application.

Veolia owns and operates the Woodlawn Bioreactor, Mechanical Biological Treatment (MBT) plant and Crisps Creek Intermodal Facility (IMF). Along with the Woodlawn Wind Farm, Woodlawn Farm and Woodlawn Fish Farm, they are collectively referred to as the Woodlawn Eco Precinct located approximately 40 km south of Goulburn and 50 km north of Canberra.

The Bioreactor is a major putrescible landfill and the MBT a resource recovery facility which extracts metals and produces compost. Together, they service a significant proportion of Sydney's metropolitan waste disposal needs. Containers of compressed waste are railed from Sydney to the IMF where they are transferred a short distance by road for disposal at the Bioreactor or for processing at the MBT.

2 Leachate Management

Veolia is in the process of implementing a long term leachate management strategy (LTLMS) for the Eco Precinct. Leachate generated within the Bioreactor is now beyond the capacity of the existing leachate management system to deal with effectively. This has reduced the efficiency of gas extraction and increased the potential for odour impacts within the Eco Precinct. To maintain operational and environmental performance Veolia has been extracting more leachate from the Bioreactor resulting in existing leachate storage approaching capacity.

2.1 Short Term Storage solution

On 9 September 2016 DPE approved a modification to Veolia's planning approvals to convert storm water storage to leachate storage to temporarily address the shortfall in leachate capacity. The additional storage volume was to be achieved by:

- transferring stormwater currently stored in Evaporation Dam 3 South (EDS3) to Evaporation Dam (ED2);
- using ED3S South (once emptied of stormwater) to store treated leachate collected from the mine void; and
- enabling the storage of up to 111 megalitres (ML) of additional treated leachate in ED3S-S.

In approving the short term storage solution, the DPE imposed a condition that required Veolia to implement and have operational a long term leachate management strategy by no later than 20 December 2017, or as otherwise agreed by the Secretary.

2.2 Long Term Storage solution

In late 2016, Veolia reached agreement with the EPA on the principal elements of the LTLMS which are now reflected in its Environment Protection Licence (EPL 11436). The modification application recently submitted to the Department seeks to implement key elements of the LTLM Strategy as follows:

- The construction of a leachate treatment plant to process leachate from the Bioreactor, Evaporation Dam 3 North (ED3N) and Evaporation Dam 3 South (ED3S) to an agreed standard;
- The discharge of all treated leachate into Evaporation Dam 1 (ED1) which will become the primary leachate storage facility;
- The use of mechanical evaporation (and possibly heating) equipment (up to 4) when necessary; and
- To ensure the integrity of Evaporation Dam 1 (ED1) against leakage prior to the discharge of treated effluent into ED1.

It is proposed that overland pipelines will transfer raw leachate from the Bioreactor directly to the leachate treatment plant. The LTP will be capable of treating leachate at a rate of up to 4 litres per second including up to 1 litre per second from ED3 to reduce leachate volumes in this dam. The modification application predicts that it will take up to 8 years to reprocess the 271 ML of stored leachate within the ED3 system through the LTP.

2.3 Need for interim storage solution

While construction of the LTP is expected to be complete by the middle of 2018, it will not be fully operational until late 2018 due to delays in the:

- detailed design of the LTP;
- need to clarify the interactions between Veolia and Heron operations on site;
- need to finalise investigations into dam integrity; and
- late delivery of equipment.

The delay means that at current pumping rates Veolia will not have sufficient storage during the construction and commissioning of the LTP. While the water balance submitted with the modification request did envisage some transfer of leachate into ED1 in the event that ED3N became full, it did not envisage the quantum as recently identified. The current leachate management system has a total capacity of 271ML. It is now predicted that the storage shortfall will be approximately 140ML or nearly 50% of the capacity of the leachate management system (refer to Appendix 2).

There are two options to address the shortfall.

Option 1 – Reduce leachate extraction

In the interim Veolia could reduce leachate pump out rates from the Bioreactor until such time as the LTP was operational. This would however, have a number of adverse outcomes. It would facilitate the buildup of leachate in the void which would compromise the efficiency of the Bioreactor by reducing gas extraction and increasing the risk of adverse odour outcomes. This is not desirable from an environmental, amenity and regulatory viewpoint.

Option 2 – Temporary Additional Storage

Alternatively Veolia could provide temporary additional storage capacity within the leachate management system to enable:


- the pumping of the additional leachate into the system until such time as the LTP is commissioned. Under this scenario pumping rates would remain consistent with the pumping rates identified in the short term leachate management solution; and
- the temporary use of the additional storage capacity to enable the additional leachate to be progressively processed through the LTP consistent with the objectives of the long term leachate management strategy.

2.4 The Proposal

The modification application nominates ED1 as the primary storage facility for treated leachate consistent with the long term leachate management strategy approved by the EPA. As outlined in the modification, and in agreement with Heron, Veolia will manage ED1 in the long term to ensure the successful the implementation of the LTLMS.

To accommodate the temporary additional storage needs, Veolia proposes to utilise an area within the footprint of ED1 as identified in Figure 1. This are will have a capacity of 150 ML providing sufficient freeboard for the estimated additional 140,576m³ or 140 ML of leachate. The temporary storage facility will be approximately 4.5 ha in area and about 3 m in height and will be situated about 2m above the water table. It will be a standalone storage facility within ED1 and immediately adjacent to the existing leachate storage in ED3.

Figure 1 – Location of proposed additional storage capacity



Given it is located within ED1, minimal excavation is required to create the temporary additional storage capacity. The area will be de-silted before being lined consistent with EPA standards. It will have a clay liner which will be approximately 0.7 to 1 m thick, comprising 2 impervious layers (i.e. insitu clays at $K= 1 \times 10^{-09}$ to 1×10^{-10} m/sec and, imported clays from Holcim site at $K=$ approx 1×10^{-10} m/sec). Final design details including the precise thickness and mix of insitu/exsitu clay materials will be based on the results of site testing, survey and design considerations.

Given that the area will be appropriately lined consistent with contemporary standards, the findings of the recent seepage investigations are not considered specifically relevant.

In summary, this addendum report updates the modification application by seeking approval to pump the additional 140 ML of leachate into the area within ED1, and further to store that leachate in this area and progressively reprocess it through the LTP over a 12 year period. This timeframe reflects an approximate 50% increase in temporary storage capacity and therefore an approximate 50% increase in the time required to process this leachate through the LTP from 8 to 12 years. Beyond this point in time, this area would be utilised for the storage of treated leachate consistent with the long term use of ED1 in the LTLMS.

While unlikely, any winning of material required to establish the additional storage will be undertaken in agreement with Heron and under its mine operations plan (MOP) attached to Special Mining Lease (SML20) applying to the site.

Consideration

3.1 Odour

An odour assessment (refer to Appendix 1) including odour dispersion modelling was undertaken to assess the potential for odour impacts arising from the storage of leachate within the ED3S system. This has subsequently been updated to include an odour assessment of the temporary storage of leachate within ED1 as outlined in this addendum. The full report as attached and includes the relevant assessment criteria adopted in the assessment of both ED3 and the temporary storage capacity in ED1.

The aim of the updated study was to determine the contribution of odour emissions from the temporary additional storage compared to previous overall projected impacts from the ED3 system. As identified in Appendix 1, updates were made to the model, and the results compared with previous modelling results as ground level concentrations at nearby receptors which are also identified in Attachment 1.

The odour assessment found that there would be a small incremental increase to the overall projected ground level concentrations at nearby receptors and the overall extent of impact area. The findings are similar to the findings and conclusions relevant to the commissioning of the ED3SS system. The assessment, as updated, found that it was unlikely that the small identified increases would be perceivable within the community and that the existing amenity of nearby sensitive receivers would not be affected by the temporary storage of leachate within ED1.

3.2 Water

The water balance accompanying the modification request identified that once the LTP became operational it would take approximately 8 years to progressively reprocess the 271 ML of stored leachate in ED3 under a dry climate. This was based on the ability of the LTP to process leachate from ED3 at a rate of approximately 1 litre per second.

The updated water balance (refer to Appendix 2) now estimates that by the end of 2018, an additional 140 ML (nearly 50% of 271 ML which represents current peak storage load) of leachate would need to be stored on site to maintain current pumping rates. Based on the ability of the LTP to progressively process stored leachate at a rate of approximately 1 litre per second, it is estimated that it will take an additional 4 years to remove the total of 411 ML stored on site. Subsequently, it is now estimated that it will take approximately 12 years (up from 8 years) to reprocess all stored leachate through the LTP.

Veolia is committed to reducing the amount of stored leachate on site as quickly as possible without compromising the environmental performance of the Bioreactor. Subsequently, once the LTP is

operational Veolia will investigate all feasible and reasonable measures aimed at increasing the performance of both the LTP and leachate storage system to increase the rate of progressive reprocessing.

The temporary additional storage will not compromise the long term leachate management strategy as the area in ED1 will ultimately be used for the storage of treated leachate, as per the LTLMS. While adding an additional 4 years to process all stored leachate at the site, the Bioreactor will continue to be a nil discharge site.

3.3 Other

The proposed changes in the addendum will not involve any transport to and from the site. The location is within the existing ED1 footprint and as such is highly disturbed and devoid of any flora and fauna, and flora and fauna habitat. Subsequently, there will be no impacts on biodiversity. There are no heritage items and any unforeseen finds will be dealt with under existing heritage related conditions as applicable. As the location is within the existing ED1 footprint, it will have minimal or no impact on visual amenity.

Veolia is committed to implementing all environmental management plans applicable under the approvals to the operation of the new dam including:

- Landfill Environmental Management Plan
- Stormwater Management Plan
- Management Plans for ED1 and ED2
- Soil and Water Management Plan
- Leachate Management Plan

3 Conclusion

Given the delay in delivering the LTP and associated infrastructure, Veolia now needs to pump and temporarily store up to an additional 140 ML of leachate within the next 12-18 months. While the pumping of leachate will cease once the LTP is commissioned, the time required to progressively reprocess the stored leachate back through the LTP will increase by 4 years to a total of 12 years, which reflects the 50% increase in storage volume.

The temporary storage area will be located within the footprint of ED1. Minimal excavation is required and the area will be de-silted before being lined consistent with EPA standards, similar to the lining of ED3S.

The current modification before the Department seeks approval for key elements of the long term leachate management strategy. This addendum seeks to update the modification to enable Veolia to pump leachate from the Bioreactor into temporary storage capacity within ED1. Once the LTP is operational, the pumping of leachate will cease and the stored leachate progressively reprocessed through the LTP.

The potential odour and water issues have been considered. The odour assessment found that the increase in stored leachate would not affect the amenity of nearby sensitive receivers. A new water balance estimates that the additional 140,576m³ of stored leachate would add about 4 years to the current estimate of 8 years to re process stored leachate through the LTP. The additional water storage will not compromise the ability of the site to accommodate and safely dispose of treated effluent with the site remaining a nil discharge site.



THE ODOUR UNIT PTY LTD

Bay 4 Suite 3011
Australian Technology Park
2 Locomotive St
EVELEIGH NSW, 2015
Phone (+61 2) 9209 4420
Fax (+61 2) 9209 4421
www.odourunit.com.au

A C N 091 165 061
A B N 53 091 165 061

27/06/17

David Figueiredo,
Operations Manager – Woodlawn
Veolia Australia and New Zealand
Woodlawn Bioreactor,
619 Collector Road,
TARAGO, NSW 2580

By email: david.figueiredo@veolia.com

RE: PRELIMINARY ODOUR MODELLING RESULTS – ADDITIONAL TREATED EFFLUENT DAM

Dear David,

Thank you for your instructions to reconfigure the Woodlawn Bioreactor odour model to assess the proposed additional dam to be constructed next to the ED3N system to store excess treated effluent from the ED3S system. The location of the proposed dam is illustrated in **Figure 1**.



Figure 1 – Proposed location of excess treated effluent dam.

I have modelled the impact of the new dam (“ED3N-5”) alone and collectively with the sources modelled in the previous study:

Woodlawn Bioreactor Facility Odour Modelling Study – Proposed Addition of ED3S to Leachate Management System (May 2016).

Please refer to the previous report regarding the methodology used to complete this study. The aim of this study is to assess the contribution of odour emissions from the additional dam to the previous projected impacts overall. This letter documents the changes made to the model, and the results and findings of the updated odour impact projection.

Odour Model Updates

The following updates were made to the odour model:

- ED3S
 - Increased surface area from 6.8ha to 8.9ha
 - Updated SOER from 0.159 ou.m³/m².s to 0.277ou.m³/m².s as measured during Odour Audit #5
- ED3S-S
 - Updated SOER from 0.159 ou.m³/m².s to 0.437ou.m³/m².s as measured during Odour Audit #5
- ED3N-5
 - New source with an assumed surface area of 1.5ha and SOER of 0.437ou.m³/m².s (representative of excess treated effluent from ED3S-S).

Odour Model Results


The results of the odour modelling are compared with the previous modelling results as ground level odour concentrations (99%ile, 1s avg) at nearby receptors in **Table 1**. The odour contour plot depicted in **Figure 2**, illustrates the **adopted Impact Assessment Criterion of 6ou (99%ile, 1s avg)** for the proposed ED3N-5 dam individually, and cumulatively compared with the result modelled in the previous study.

Table 1 – Projected ground level concentrations at nearby receptors.

Name	X (km)	Y (km)	Previous Conc. (ou)	New Conc. (ou)	Change	Odour IAC (99%,1s)
R1	734.581	6118.144	8.1	8.7	+0.6	6.0
R2	736.674	6117.689	3.9	4.2	+0.3	
R3	737.492	6114.374	1.3	1.4	+0.1	
R4	731.286	6114.654	1.4	1.6	+0.2	



Updated odour plot - new treated effluent dam



- - - ED3N-5 ONLY (6ou)
 - - - Previous Cumulative (6ou)
 - - - New Cumulative (6ou)

Figure 2 – Odour contour plot of proposed ED3N-5 individually and cumulatively.

Findings and conclusion

The odour dispersion modelling has shown that the increase to the overall projected ground level concentration at nearby receptors and overall extent of impact area would occur as a small increment. This is a similar finding to what was expected in the conclusions for the commissioning of the ED3S system in the previous study. It is very unlikely that this small increase would be perceivable by the nearby community. It is therefore concluded that the existing amenity of nearby sensitive places would remain unaffected as the result of the commissioning of a new treated effluent dam constructed with properties similar to what is described by this letter.

Yours sincerely,



Steven Hayes BSc, CAQP
 Atmospheric Scientist & Senior Consultant
 The Odour Unit Pty Ltd

Updated source and emission rate configuration (Highlighted Yellow)

AREA SOURCE																	
Source Name (12 chars.)	Lower Left X Coord. (km)	Lower Left Y Coord. (km)	Upper Left X Coord. (km)	Upper Left Y Coord. (km)	Upper Right X Coord. (km)	Upper Right Y Coord. (km)	Lower Right X Coord. (km)	Lower Right Y Coord. (km)	Effect. Height (m)	Base Elev. (m)	Init. Sigma Z (m)	Previous Area (m2)	Updated Area (m2)	Previous ODOR (ou/m**2/s)	Updated ODOR (ou/m**2/s)	Previous OER (ou/s)	Updated OER (ou/s)
LDAM	734.1	6117.183	734.166	6117.287	734.184	6117.268	734.129	6117.163	0	797.19	0.1	3641	3641	3.6	3.6	13108	13108
GW	733.455	6117.624	733.399	6117.421	733.552	6117.39	733.652	6117.541	0	791.39	0.1	35410	35410	0.3	0.3	10623	10623
TL1	733.559	6117.387	733.658	6117.54	733.707	6117.508	733.725	6117.46	0	791.56	0.1	9961	9961	3.6	3.6	35860	35860
UTL	733.661	6117.366	733.788	6117.346	733.73	6117.455	733.662	6117.37	0	791.55	0.1	6425	6425	5	5	32125	32125
COVW	734.128	6116.962	734.37	6117.189	734.463	6117.157	734.735	6117.023	0	731.67	0.1	63452	63452	0.3	0.3	19036	19036
AGEDW	734.156	6116.944	734.649	6116.721	734.498	6116.646	734.099	6116.859	0	687.56	0.1	58363	58363	3.6	3.6	210107	210107
FW	734.099	6116.858	734.098	6116.793	734.359	6116.638	734.493	6116.644	0	753.02	0.1	24030	24030	0.7	0.7	16821	16821
WR3	733.132	6117.509	733.185	6117.628	732.905	6117.753	732.852	6117.634	0	793.74	2	39985	39985	0.253	0.253	10116	10116
WR2	733.163	6117.495	733.216	6117.614	733.185	6117.628	733.132	6117.509	0	792.15	2	4424	4424	13	13	57512	57512
WR4	733.193	6117.482	733.246	6117.6	733.216	6117.614	733.163	6117.495	0	791.81	2	4260	4260	11.3	11.3	48138	48138
WR4_2	732.816	6117.65	732.869	6117.769	732.857	6117.775	732.803	6117.656	0	796.36	2	1804	1804	11.3	11.3	20385	20385
WR5	732.803	6117.656	732.857	6117.775	732.843	6117.781	732.79	6117.662	0	796.38	2	1930	1930	5.45	5.45	10519	10519
WR5_2	732.79	6117.662	732.843	6117.781	732.778	6117.81	732.725	6117.691	0	796.74	2	9269	9269	0.253	0.253	2345	2345
ED3S-5	733.529	6116.967	733.523	6117.122	733.739	6117.044	733.641	6116.904	0	794	0.1	27471	27471	0.159	0.437	4368	12005
ED3S1	733.413	6117.195	733.426	6117.323	733.583	6117.362	733.533	6117.15	0	793	0.1	19722	23666	0.159	0.277	3136	6555
ED3S2	733.533	6117.15	733.583	6117.362	733.867	6117.322	733.775	6117.07	0	793	0.1	48384	65261	0.159	0.277	7693	18077
ED3N5	733.841	6117.345	733.841	6117.471	733.922	6117.534	733.953	6117.473	0	791	0.1	0	15377	0	0.437	0	6720
VOLUME SOURCE																	
Source Name (12 chars.)	X Coord. (km)	Y Coord. (km)	Effect. Height (m)	Base Elev. (m)	Init. Sigma Y (m)	Init. Sigma Z (m)	Previous ODOR (ou/s)	Updated ODOR (ou/s)									
SRC_1	732.95	6117.695	0	0	20	2	5.65	5.65									
SRC_2	733.066	6117.623	0	0	10	2	2.37	2.37									



Veolia Australia & New Zealand

**Woodlawn Bioreactor Facility Odour
Modelling Study**

**Proposed Addition of ED3S to Leachate
Management System**

May 2016

Final Report

THE ODOUR UNIT PTY LTD

ABN 5309 116 5061
ACN 091 165 061

Bay 4 Suite 3011
Australian Technology Park
2 Locomotive St
EVELEIGH, NSW 2015
E: info@odourunit.com.au
W: www.odourunit.com.au

This document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. This document should not be used or copied without written authorisation from **THE ODOUR UNIT PTY LTD** or **VEOLIA AUSTRALIA & NEW ZEALAND**.

Project Number: N1806L.02

Report Revision		
Revision Number	Date	Description
Draft Report	26.05.2016	Draft report for internal review
Final Draft Report	30.05.2016	Final draft report issued to client for review
Final Report	30.05.2016	Final report issued
Report Preparation		
Report Prepared By: M. Assal & S. Hayes		Approved By: T. Schulz
Report Title: Veolia Australia & New Zealand Woodlawn Bioreactor Facility Odour Modelling Study – Proposed Addition of ED3S to Leachate Management System		

CONTENTS

1	INTRODUCTION	5
1.1	Scope of Works	5
2	STUDY METHODOLOGY	6
2.1	Previous Odour Assessment Study	6
2.2	Proposed Addition of ED3S To LMS	6
2.3	Representative Odour Emissions Data for the ED3S System	7
3	ODOUR DISPERSION MODELLING METHODOLOGY	9
3.1	NSW Odour Criteria and Dispersion Model Guidelines	9
3.2	Odour Dispersion Model Selection.....	11
3.3	Geophysical and Meteorological Configuration.....	12
3.3.1	Terrain configuration	12
3.3.2	Land use configuration.....	13
3.3.3	Geophysical configuration.....	13
3.3.4	Meteorological configuration	14
3.4	CALPUFF Dispersion Model Configuration.....	23
3.4.1	Computational domain	23
3.4.2	Receptor configuration	23
3.4.3	Source Configuration and Emission Rates	23
3.4.4	CALPUFF Model Options.....	23
3.5	Modelling Scenarios	23
4	ODOUR DISPERSION MODELLING RESULTS.....	24
5	MODELLING STUDY FINDINGS & CONCLUSION.....	30
	BIBLIOGRAPHY.....	31
6	REPORT SIGNATURE PAGE	32

LIST OF FIGURES & TABLES

FIGURES

Figure 3.1 - Terrain map of Woodlawn and surrounds	13
Figure 3.2 - Land use map of Woodlawn and surrounds	14
Figure 3.3 - Annual windroses for Goulburn Airport 5 years and 2015 only	17
Figure 3.4 - Annual and seasonal windroses for Woodlawn 2015 (modelled).....	18
Figure 3.5 - Monthly average temperatures for Goulburn Airport 5 years and 2015 only	19
Figure 3.6 - Annual diurnal temperature for Goulburn Airport 5 years and 2015 only ..	20
Figure 3.7 - Annual X-Y scatter plot diurnal mixing height for Woodlawn 2015 (modelled)	21
Figure 3.8 - Annual stability class frequency for Woodlawn 2015 (modelled)	22

Figure 4.1 – Projected ground level odour concentration contour plots for the baseline EA model (updated meteorology)	25
Figure 4.2 – Projected ground level odour concentration contour plots for ED3S-S only	26
Figure 4.3 – Projected ground level odour concentration contour plots for ED3S only	27
Figure 4.4 – Projected ground level odour concentration contour plots for ED3S-S & ED3S.....	28
Figure 4.5 – Projected ground level odour concentration contour plots for Baseline, ED3S-S and ED3S.....	29

TABLES

Table 2.1 - Projected Odour Emission Rates for ED3S	8
Table 3.1 - EPA peak-to-mean factors.....	10
Table 3.2 - Odour Performance Criteria under Various Population Densities	11
Table 3.3 - CALMET key variable fields.....	16

APPENDICES

Appendix A: Woodlawn Bioreactor Facility Odour Assessment Study – Addition of ED3S to Leachate Management System (30 October 2015)

Appendix B: Bureau of Meteorology Basic Climatological Station Metadata – Goulburn Airport (Compiled 26 November 2015)

Appendix C: CALPUFF Source and Emission Modelling Configurations

1 INTRODUCTION

In April 2016, Veolia Australia & New Zealand (Veolia) engaged The Odour Unit Pty Ltd (TOU) to carry out an odour dispersion model study to evaluate the odour profile contribution and assess compliance against the New South Wales Environment Protection Authority (NSW EPA) odour performance criteria of the addition of the proposed Evaporation Dam 3 South (ED3S) System to the Leachate Management System (LMS) at the Woodlawn Bioreactor Facility located at Collector Road, Tarago, NSW (the Site). The basis for this additional pond system is to create the necessary supplementary reserve capacity for the storage of treated leachate from the LMS.

1.1 SCOPE OF WORKS

The scope of works for the odour dispersion model study consisted of:

- Sourcing and setting up the original odour dispersion model used in the *Environmental Assessment Woodlawn Expansion Report* dated August 2010 (EA). Some meteorology-based revisions to this model were necessary given the year that the model was completed (see **Section 3** for details);
- Inclusion of the proposed ED3S System into the EA odour dispersion model; and
- Odour dispersion modelling projection of the individual off-site odour impact from the inclusion of the proposed ED3S System. In addition, the cumulative off-site odour impact with the other modelled emission sources in the EA were undertaken to assess site-wide compliance with the relevant NSW EPA odour performance criterion.

The following report summarises the methodologies and results from the odour dispersion model of the proposed ED3S System addition to the LMS at the Site. Moreover, this modelling study report should be read in the context of the previously issued TOU letter report issued to Veolia on 30 October 2015 titled *Woodlawn Bioreactor Facility Odour Assessment Study – Addition of ED3S to Leachate Management System* (see **Appendix A**).

2 STUDY METHODOLOGY

2.1 PREVIOUS ODOUR ASSESSMENT STUDY

TOU's understanding of the proposed addition to the LMS is that Veolia intends to pump the stormwater currently in ED3S to Evaporation Dam 2 (ED2), thereby freeing up storage volume and natural evaporation capacity for treated leachate in ED3S System. In 2015, NSW EPA had requested an odour assessment of the proposed change to operation based on the odour emissions data from the 2015 Independent Odour Audit. Specifically, NSW EPA had confirmed at the time with Veolia that the following odour assessment methodology would be suitable (email dated 28 September 2015 from Veolia to TOU):

- *“Utilising data from existing treated leachate dams and extrapolate this to the new dam in order to quantify odour emission rates from ED3S;*
- *Comparing the data against the current odour emissions inventory developed for the site (as part of the annual odour audits); and*
- *Quantifying the impact as a percentile increase in comparison to the overall site emissions as well as the leachate pond system.”*

Following that odour assessment study report, odour dispersion modelling was further requested by the NSW EPA to determine its compliance with the relevant NSW EPA odour performance criterion. This resulted in the need to source, setup, and carry out new modelling runs of the original EA odour dispersion model, developed by the former Heggies Pty Ltd, now operating as SLR Consulting, to evaluate the contribution and assess compliance of the proposed addition of ED3S to the LMS and other modelled emissions.

The previously issued odour assessment report from October 2015 is attached as **Appendix A** for reference purposes.

2.2 PROPOSED ADDITION OF ED3S TO LMS

TOU's understanding is that due to time constraints, Veolia is proposing to construct the leachate storage dam in two parts. Firstly, the ED3S-Southern partition (ED3S-S) liner will be constructed, which is separated via a breakwall from the main ED3S system. Survey data from Veolia, undertaken by LandTeam Australia Pty Ltd (LandTeam), indicate that the new ED3S-S partition pond will have a surface area between 2.30 ha at low water level, and 2.83 ha when full. (see **Appendix A - Attachment 1 - LandTeam Drawing No. 16800-437**).

The second part will involve pumping water from the ED3S to ED2 and then constructing the liner for the main ED3S system. Survey data for this dam indicates that it will have a maximum surface area of 8.94 ha see (**Appendix A - Attachment 2 - Woodlawn Bioreactor ED3S Information** for projected volumes and surface areas). The combined surface area of both dams (i.e. ED3S & ED3S-S) have been added for the purposes of this assessment, as will be shown later in **Table 2.1**). The details for the surveying work are contained in **Appendix A**.

2.3 REPRESENTATIVE ODOUR EMISSIONS DATA FOR THE ED3S SYSTEM

Previous odour audits in 2012 and 2013 conducted at the Site found elevated odour emissions from pond ED3N-1 (2012) and ED3N-2 (2013) due to insufficient treatment in the Leachate Aeration Dam system, a critical process component of the LMS. Improvements to this system saw a large decrease in odour emissions from all four ED3N ponds in 2014, following re-treatment of these liquids, to extremely low levels. These results, together with the 2015 audit results, are shown in **Appendix A - Attachment 3 - Odour Emissions Inventory Comparison Inventory & Odour Emissions Inventory 2015 Audit Excel Sheets**. It should be noted that the Specific Odour Emission Rate (SOER) values represent the measured rates of odour emission per square metre of exposed pond area ($\text{ou.m}^3/\text{m}^2/\text{s}$), while the Odour Emission Rate results represent the total odour emission rate determined for each source ($\text{ou.m}^3/\text{s}$).

The 2015 audit results show a slightly higher rate of odour emission from all four ED3N ponds, when compared with 2014, but still very low rates of odour emission for treated wastewater pond systems and well within the EA performance targets for the Site. These latest results, considered to be the expected quality of treated leachate generated by the current LMS, have been used to project emissions from pond ED3S, as shown in the **Table 2.1**. Note that the mean SOER result for the four ponds has been used in the modelling projections.

Table 2.1 - Projected Odour Emission Rates for ED3S

ED3N System 2015			
Source ID	Dam Surface Area (m²)	SOER (ou.m³/m²/s)	OER (ou.m³/s)
ED3N-1	6,000	0.132	794
ED3N-2	5,500	0.145	797
ED3N-3	5,500	0.091	500
ED3N-4	25,000	0.269	6,720
ED3N Total	42,000	0.159 (mean)	8,810
Projected ED3S System			
ED3S	89,435	0.159	14,200
ED3S-S	28,330		4,510
ED3S Total	118,000		18,700

As per the previous TOU odour assessment report issued in October 2015, from a comparative analysis viewpoint, it can be seen that the projected odour emission increase from the conversion of ED3S-S to leachate storage and evaporation duties would increase the pond systems odour emission rate by 4,510 ou.m³/s (51%). If the combined ED3S system projected surface areas, the overall odour emission rate would increase by 18,700 ou.m³/s, equivalent to a two-fold increase in odour emissions from the evaporation dam system. TOU considers this increase to be insignificant in the context of the distance of this odour source from potential receptors. This is consistent with the project modelling results (see **Section 4**). The relatively neutral odour character in the pond emissions (described as earthy/mildly ammoniacal) further supports our view that this source is benign and will not cause problems off-site. TOU would expect this state of affairs to continue provided that the LMS continues to be managed and operated effectively.

3 ODOUR DISPERSION MODELLING METHODOLOGY

3.1 NSW ODOUR CRITERIA AND DISPERSION MODEL GUIDELINES

Regulatory authority guidelines for odorous impacts of gaseous process emissions are not designed to satisfy a 'zero odour impact criteria', but rather to minimise the nuisance effect to acceptable levels of these emissions to a large range of odour sensitive receptors within the local community.

The odour impact assessment for this project has been carried out in accordance with the methods outlined by the documents:

- Environment Protection Authority, 2005, *Approved Methods for the Modelling and Assessment of Air Pollutants in New South Wales*;
- Environment Protection Authority, 2006, *Technical Framework (and Notes): Assessment and Management of Odour from Stationary Sources in NSW*; and
- Barclay & Scire, 2011. *Generic Guidance and Optimum Model Settings for the CALPUFF Modeling System for Inclusion into the 'Approved Methods for the Modeling and Assessments of Air Pollutants in NSW, Australia'*.

The documents specify that the odour modelling for Level 3 impact assessments, upon which this study has been conducted, be based on the use of:

- The 99.0th percentile dispersion model predictions;
- 1-hour averaging times with built-in peak-to-mean ratios to adjust the averaging time to a 1-second nose-response-time;
- Odour emission rates multiplied by the peak-to-mean ratios as outlined in **Table 3.1**;
- The near field distance, defined typically as 10 times the largest source dimension, either height or width; and
- The appropriate odour unit performance criterion, based on the population of the affected community in the vicinity of the development.

Table 3.1 - EPA peak-to-mean factors

Source type	Pasquill-Gifford stability class	Near-field P/M60*	Far-field P/M60*
Area	A, B, C, D	2.5	2.3
	E, F	2.3	1.9
Line	A-F	6	6
Surface wake-free point	A, B, C	12	4
	D, E, F	25	7
Tall wake-free point	A, B, C	17	3
	D, E, F	35	6
Wake-affected point	A-F	2.3	2.3
Volume	A-F	2.3	2.3

* Ratio of peak 1-second average concentrations to mean 1-hour average concentrations

Source: Environment Protection Authority, 2005 – Table 6.1

The impact assessment criteria (IAC) for complex mixtures of odours are designed to include receptors with a range of sensitivities. Therefore a statistical approach is used to determine the acceptable ground level concentration of odour at the nearest sensitive receptor. This criterion is determined by the following equation (Environment Protection Authority, 2005, p. 37):

$$IAC = \frac{\log_{10}(p) - 4.5}{-0.6} \quad \text{Equation 3.1}$$

where,

IAC = Impact Assessment Criteria (ou)

p = population

Based on **Equation 3.1**, **Table 3.2** outlines the odour performance criteria for six different affected population density categories. It states that higher odour concentrations are permitted in lower population density applications.

Table 3.2 - Odour Performance Criteria under Various Population Densities

Population of affected community	Odour performance criterion (ou)
Urban Area ($\geq \sim 2000$)	2.0
~ 500	3.0
~ 125	4.0
~ 30	5.0
~ 10	6.0
Single rural residence ($\leq \sim 2$)	7.0

Source: Environment Protection Authority, 2005 – Table 7.5

The original odour impact assessment (Heggies, 2010) had adopted the IAC of **6 ou** “given the low number of sensitive receptor locations in the vicinity of the Woodlawn site” (PAE Holmes, 2010). TOU has maintained consistency with this approach as conditions have not significantly changed.

3.2 ODOUR DISPERSION MODEL SELECTION

The odour dispersion modelling assessment was carried out using the CALPUFF System (Version 6.42). CALPUFF is a puff dispersion model that is able to simulate the effects of time- and three dimensional space-varying meteorological conditions on pollutant transport (Environment Protection Authority, 2005). CALMET is a meteorological model that produces three dimensional gridded wind and temperature fields to be fed into CALPUFF (Atmospheric Studies Group, 2011). The primary output from CALPUFF is hourly pollutant concentrations evaluated at gridded and/or discrete receptor locations. CALPOST processes the hourly pollutant concentration output to produce tables at each receptor and contour plots across the modelling domain. For further technical information about the CALPUFF modelling system refer to the document *CALPUFF Modeling System Version 6 User Instructions* (Atmospheric Studies Group, 2011).

The CALPUFF system can account for a variety of effects such as non-steady-state meteorological conditions, complex terrain, varying land uses, plume fumigation and low wind speed dispersion (Environment Protection Authority, 2005). CALPUFF is considered an appropriate dispersion model for impact assessment by EPA in their document - *Approved Methods and Guidance for the Modelling and Assessment of Air Pollutants in New South Wales* in one or more of the following applications:

- complex terrain, non-steady-state conditions,
- buoyant line plumes,
- coastal effects such as fumigation,

- high frequency of stable calm night-time conditions,
- high frequency of calm conditions, and
- inversion break-up fumigation conditions.

In the case of the this odour impact assessment, CALPUFF was required in order to handle the complexity of surrounding terrain features. Under calm and very light winds, non-steady-state conditions such as accumulation of odour and/or downslope movement with drainage air flow would almost certainly occur.

For this study, the air contaminant was odour and ground level concentrations in odour units (ou) have been projected.

3.3 GEOPHYSICAL AND METEOROLOGICAL CONFIGURATION

A CALMET hybrid three-dimensional meteorological data file for Tarago, NSW was produced that incorporated of gridded numerical meteorological data supplemented by surface observation data, topography and land use over the domain area.

3.3.1 Terrain configuration

Terrain elevations were sourced from 1 Second Shuttle Radar Topography Mission (SRTM) Derived Smoothed Digital Elevation Model (DEM-S). The SRTM data was treated with several processes including but not limited to removal of stripes, void filling, tree offset removal and adaptive smoothing (Gallant, et al., 2011). The DEM-S was used as input into TERREL processor to produce a 400 km² grid at 0.15 km resolution. A map of the terrain is illustrated in **Figure 3.1**.




Figure 3.1 - Terrain map of Woodlawn and surrounds

3.3.2 Land use configuration

Land use was sourced from the United States Geological Survey (USGS) Global Land Cover Characteristics Data Base for the Australia-Pacific Region (USGS, 1997). The data was used as input into CTGPROC processor to produce a 400 km² grid at 0.15 km resolution. A map of the land use is illustrated in **Figure 3.2**.

3.3.3 Geophysical configuration

The geophysical data file was created using the MAKEGEO processor. Land use data from CTGPROC and terrain data from TERREL was used as input to produce a 20 km² geophysical grid at 0.15 km resolution.




Figure 3.2 - Land use map of Woodlawn and surrounds

3.3.4 Meteorological configuration

3.3.4.1 Input data

One-hour average observed meteorological surface data for the latest representative year (2015) was sourced from Goulburn Airport maintained by Bureau of Meteorology (BOM). The location of Goulburn Airport surface station and other metadata are available in **Appendix B**. The BOM data was formatted into generic format and was processed with SMERGE to produce a surface meteorological data file.

Numerical meteorological data was produced as a 3D data tile from The Air Pollution Model (v4.0.5) and processed it with CALTAPM (v7.0.0) into a suitable format. TAPM was run using multiple nested grids, at least three nests and 35 vertical levels centred over the Woodlawn site. TAPM innermost nest was 33 km by 33 km at 1 km resolution. The nested grid resolutions were close to a ratio of three as possible.

3.3.4.2 CALMET meteorological model configuration

CALMET was run using the hybrid option that uses geophysical data, surface station data from Bundaberg Airport and upper air data from the TAPM 3D data tile. The data was used to initialise the diagnostic functions of the CALMET module to produce a full 3D meteorology data for input into CALPUFF. **Table 3.3** shows key variable fields selected.

3.3.4.3 Meteorological data analysis

Observed 2015 BOM surface data was compared with longer term climate (2011 – 2015) from Goulburn Airport to gauge how representative and suitable the year is for the purpose of air quality dispersion modelling. For reference, meteorological data was also extracted from the CALMET model for the location directly nearby the Woodlawn site office. The annual windroses for Goulburn Airport show very good agreement with west to northwest winds dominating (**Figure 3.3**) The Woodlawn windroses (**Figure 3.4**) show bias to lighter winds and greater frequency of east to south-easterly winds, perhaps due influences from the nearby valley and ridgelines. A more conservative bias is expected relative to the observations at Goulburn Airport.

Both monthly average (**Figure 3.5**) and diurnal temperature (**Figure 3.6**) profiles for the long term and 2015 are in very good agreement. Diurnal mixing heights and stability class frequencies over the Woodlawn site are shown in **Figure 3.7** and **Figure 3.8** respectively.

Table 3.3 - CALMET key variable fields												
Grid Configuration (WGS-84 UTM Zone 55S)												
134						NX Cells						
134						NY Cells						
0.15						Cell Size (km)						
724.277			6106.107			SW Corner (km)						
11						Vertical Layers						
ZFACE (m)	0	20	40	80	160	320	640	1000	1500	2000	2500	3000
LAYER	1	2	3	4	5	6	7	8	9	10	11	
MID-PT (m)	10	30	60	120	240	480	820	1250	1750	2250	2750	
Critical Wind Field Settings												
Value	Found		Typical		Values							
TERRAD	4		None		Terrain scale (km) for terrain effects							
IEXTRP	-4		4,-4		Similarity extrap. of wind (-4 ignore upper stn sfc)							
ICALM	0		0		Do Not extrapolate calm winds							
RMAX1	6		None		MAX radius of influence over land in layer 1 (km)							
RMAX2	8		None		MAX radius of influence over land aloft (km)							
R1	3		None		Distance (km) where OBS wt = IGF wt in layer 1							
R2	4		None		Distance (km) where OBS wt = IGF wt aloft							




Figure 3.3 - Annual windroses for Goulburn Airport 5 years and 2015 only




Figure 3.4 - Annual and seasonal windroses for Woodlawn 2015 (modelled)




Figure 3.5 - Monthly average temperatures for Goulburn Airport 5 years and 2015 only




Figure 3.6 - Annual diurnal temperature for Goulburn Airport 5 years and 2015 only




Figure 3.7 - Annual X-Y scatter plot diurnal mixing height for Woodlawn 2015 (modelled)




Figure 3.8 - Annual stability class frequency for Woodlawn 2015 (modelled)

3.4 CALPUFF DISPERSION MODEL CONFIGURATION

3.4.1 Computational domain

The computational domain was set to the same parameters as the meteorological domain.

3.4.2 Receptor configuration

Three groups of arbitrary discrete receptors were configured over the modelling domain. Four sensitive discrete receptors were placed at ground level at the same locations identified by the previous EA modelling (Heggies, 2010). A receptor grid was created with a fine resolution inner nest of 9.6 km by 9.6 km by 0.15 km spacing; and an outer nest of 19.35 km by 19.35 km by 0.45 km spacing.

3.4.3 Source Configuration and Emission Rates

See **Appendix C** for full odour source and emission rate configurations.

3.4.4 CALPUFF Model Options

CALPUFF default model options were set except for the following as recommended in *Table A-4* contained and explained within *Barclay and Scire (2011)*:

- Dispersion coefficients (MDISP) = dispersion coefficients from internally calculated sigma v, sigma w using micrometeorological variables (2);
- Probability Density Function used for dispersion under convective conditions (MPDF) = Yes (1); and
- Minimum turbulence velocities sigma v for each stability class over land and water (SVMIN) = 0.2 m/s for A, B, C, D, E, F (0.200, 0.200, ... , 0.200).

3.5 MODELLING SCENARIOS

The following scenarios were simulated with CALPUFF:

1. Woodlawn EA 2010 emissions (Baseline) with updated meteorology.
2. ED3S-S only.
3. ED3S only.
4. ED3S-S and ED3S.
5. Baseline, ED3S-S and ED3S.

4 ODOUR DISPERSION MODELLING RESULTS

The odour dispersion modelling results are shown in the following plots that illustrate the isopleth of the projected ground level odour performance criterion:

- **Figure 4.1** – Projected ground level odour concentration contour plots for the baseline EA model (updated meteorology);
- **Figure 4.2** – Projected ground level odour concentration contour plots for ED3S-S only;
- **Figure 4.3** – Projected ground level odour concentration contour plots for ED3S only;
- **Figure 4.4** – Projected ground level odour concentration contour plots for ED3S-S & ED3S; and
- **Figure 4.5** – Projected ground level odour concentration contour plots for Baseline, ED3S-S and ED3S.

All modelling scenarios show clear compliance with the 6 ou ground level criterion, 99.0%, 1-sec averaging at the nearest sensitive receptors. Each contour plot has a table that shows the individual projected ground level concentrations at the nearest sensitive receptors for the modelled scenarios.

Please note that the modelled receptor location shown immediately north of the Woodlawn Bioreactor Facility is within the site boundary and is owned by Veolia. Therefore, for the purposes of this odour assessment, it is not considered to be a sensitive receptor location.




Figure 4.1 – Projected ground level odour concentration contour plots for the baseline EA model (updated meteorology)




Figure 4.2 – Projected ground level odour concentration contour plots for ED3S-S only




Figure 4.3 – Projected ground level odour concentration contour plots for ED3S only




Figure 4.4 – Projected ground level odour concentration contour plots for ED3S-S & ED3S




Figure 4.5 – Projected ground level odour concentration contour plots for Baseline, ED3S-S and ED3S

5 MODELLING STUDY FINDINGS & CONCLUSION

The aim of the odour dispersion modelling study was to assess compliance of the proposed addition of ED3S System to the LMS at the Woodlawn Bioreactor Facility against the NSW EPA odour performance criterion ground level concentration of 6 ou based on 1-hour averaging at the 99.0th percentile frequency at the nearest sensitive receptor. The modelling projection results demonstrate compliance with this criterion at the nearest sensitive receptor, and is consistent with the previous odour assessment study findings in October 2015 where negligible change to existing projected impacts were anticipated.

On this basis, it can be safely concluded that the use of the ED3S system for the storage of treated leachate will not result in any significant increase to off-site odour impacts, have negligible change on the existing surrounding off-site amenity, and is in compliance with the relevant NSW EPA odour performance criterion.

BIBLIOGRAPHY

- The Odour Unit Pty Ltd, December 2015, Woodlawn Bioreactor Expansion Project – *Independent Odour Audit #4 – Final Report*
- Wessel, P. & Smith, W. H. F., 2015, *Global Self-consistent Hierarchical High-resolution Geography*, National Oceanic and Atmospheric Administration - National Centers for Environmental Information
- Environmental Assessment Woodlawn Expansion Project Volume 2 – Appendices, March 2011, *Appendix D – Air Quality and Odour Assessment*.
- Atmospheric Studies Group, 2011, *CALPUFF Modeling System Version 6 User Instructions, Lowell*: TRC Environmental Corporation.
- Gallant, J. C. et al, 2011, 1 second SRTM Derived Digital Elevation Models User Guide, Canberra: Geoscience Australia.
- Environmental Assessment Woodlawn Expansion Project Volume 1 – Main Report, August 2010, *Chapter 9 – Air Quality and Odour Assessment*.
- Environment Protection Authority, 2006, *Technical Framework: Assessment and management of odour from stationary sources*, Sydney, Department of Environment and Conservation.
- Environment Protection Authority, 2006, *Technical notes: assessment and management of odour from stationary sources in NSW*, Sydney, Department of Environment and Conservation.
- Environment Protection Authority, 2005, *Approved Methods for the Modelling and Assessment of Air Pollutants in New South Wales*, Sydney, Department of Environment and Conservation.
- United States Geological Survey, 1997, Global Land Cover Characteristics Database.

6 REPORT SIGNATURE PAGE


The Odour Unit Pty Ltd (NSW)

P: (02) 9209 4420

F: (02) 9209 4421

E: info@odourunit.com.au

ABN: 53 091 165 061



Terry Schulz
Managing Director



Michael Assal
Senior Engineer &
Consultant



Steven Hayes
Senior Atmospheric
Scientist & Consultant



THE ODOUR
UNIT



Veolia Australia & New Zealand

**Woodlawn Bioreactor Facility Odour
Modelling Study**

**Proposed Addition of ED3S to Leachate
Management System**

May 2016

Appendices



Veolia Australia & New Zealand

Appendix A:

**Woodlawn Bioreactor Facility Odour
Assessment Study – Addition of ED3S to
Leachate Management System**

(30 October 2015)



THE ODOUR UNIT PTY LTD

Bay 4 Suite 3011
Australian Technology Park
2 Locomotive St
EVELEIGH NSW, 2015
Phone (+61 2) 9209 4420
Fax (+61 2) 9209 4421
www.odourunit.com.au

ACN 091 165 061
ABN 53 091 165 061

Stephen Bernhart
Project Manager – Resource Recovery
Veolia Australia and New Zealand.
Cnr Unwin & Shirley Sts
Rosehill, NSW 2142

30 October 2015

by email: stephen.bernhart@veolia.com

**WOODLAWN BIOREACTOR FACILITY ODOUR ASSESSMENT STUDY –
ADDITION OF ED3S TO LEACHATE MANAGEMENT SYSTEM**

Dear Stephen,

As requested, The Odour Unit Pty Ltd (TOU) has reviewed the odour emissions data from the recent 2015 Odour Audit in the context of Veolia's proposal to incorporate the Evaporation Dam 3 South (ED3S) into the existing Woodlawn Leachate Management System, which is based on the storage and evaporation of treated leachate in the Evaporation Dam 3 North (ED3N) system. We have prepared this letter as a formal report on the findings of our investigation.

Our understanding of the proposed change is that Veolia proposes to pump the stormwater currently in ED3S to Evaporation Dam 2 (ED2), thereby freeing up storage volume and natural evaporation capacity for treated leachate in ED3S.

We also understand that the NSW Environment Protection Authority (NSW EPA) has requested an odour assessment of the proposed change to operation based on the odour emissions data from the October 2015 Odour Audit. Specifically, NSW EPA has confirmed with Veolia that the following odour assessment methodology would be suitable (emailed dated 28 September 2015 from Veolia to TOU):

- *Utilising data from existing treated leachate dams and extrapolate this to the new dam in order to quantify odour emission rates from ED3S;*
- *Comparing the data against the current odour emissions inventory developed for the site (as part of the annual odour audits); and*
- *Quantifying the impact as a percentile increase in comparison to the overall site emissions as well as the leachate pond system.*

The 2015 Odour Audit included ambient odour assessments immediately downwind of the Bioreactor and the ED3N system containing treated leachate, as well as far-field assessments

as distant as the Tarago Township. I personally carried out these field assessments. While the quantitative findings of the Odour Audit, with respect to the ED3N system, will be discussed later in this report, it was clearly evident that at no stage were the pond odours detectable beyond the site boundary. This is supported by the low odour emission rate results from the Odour Audit.

TOU's understanding is that due to time constraints, Veolia is proposing to construct the leachate storage dam in two parts. Firstly, the ED3S-Southern partition (ED3S-S) liner will be constructed, which is separated via a breakwall from the main ED3S system. Survey data from Veolia, undertaken by LandTeam Australia Pty Ltd (LandTeam), indicate that the new ED3S-S partition pond will have a surface area between 2.30 ha at low water level, and 2.83 ha when full (see **Attachment 1 - LandTeam Drawing No. 16800-437**).

The second part will involve pumping water from the ED3S to ED2 and then constructing the liner for the main ED3S system. Survey data for this dam indicates that it will have a maximum surface area of 8.94 ha (see **Attachment 2 - Woodlawn Bioreactor ED3S Information** for projected volumes and surface areas). The combined surface area of both dams (i.e. ED3S & ED3S-S) have been added for the purposes of this assessment, as will be shown later in **Table 1**).

Previous audits in 2012 and 2013 found elevated odour emissions from pond ED3N-1 (2012) and ED3N-2 (2013) due to insufficient treatment in the Leachate Aeration Dam system. Improvements to this system saw a large decrease in odour emissions from all four ED3N ponds in 2014, following re-treatment of these liquids, to extremely low levels. These results, together with the 2015 audit results, are shown in **Attachment 3 - Odour Emissions Inventory Comparison Inventory & Odour Emissions Inventory 2015 Audit Excel Sheets**. It should be noted that the Specific Odour Emission Rate (SOER) values represent the measured rates of odour emission per square metre of exposed pond area ($\text{ou.m}^3/\text{m}^2/\text{s}$), while the Odour Emission Rate results represent the total odour emission rate determined for each source ($\text{ou.m}^3/\text{s}$).

The 2015 audit results show a slightly higher rate of odour emission from all four ED3N ponds, when compared with 2014, but still very low rates of odour emission for treated wastewater pond systems. At the time of writing this report, Veolia was in the process of investigating this matter. The findings from that investigation will be reported in the 2015 Odour Audit Formal Report. The results have been used to project emissions from pond ED3S, as shown in the **Table 1**. Note that the mean SOER result for the four ponds has been used in the projection.

Table 1 - Projected Odour Emission Rates for ED3S

ED3N System 2015			
Source ID	Dam Surface Area (m ²)	SOER (ou.m ³ /m ² /s)	OER (ou.m ³ /s)
ED3N-1	6,000	0.132	794
ED3N-2	5,500	0.145	797
ED3N-3	5,500	0.091	500
ED3N-4	25,000	0.269	6,720
ED3N Total	42,000	0.159 (mean)	8,810
Projected ED3S System			
ED3S	89,435	0.159	14,200
ED3S-S	28,330		4,510
ED3S Total	118,000		18,700

It can be seen that the projected odour emission increase from the conversion of ED3S-S to leachate storage and evaporation duties would increase the pond systems odour emission rate by 4,510 ou.m³/s (51%). If the combined ED3S system projected surface areas, the overall odour emission rate would increase by 18,700 ou.m³/s, equivalent to a twofold increase in odour emissions from the evaporation dam system. TOU considers this increase to be insignificant in the context of the distance of this odour source from potential receptors. The relatively neutral odour character in the pond emissions (described as earthy/mildly ammoniacal) further supports our view that this source is benign and will not cause problems off-site. TOU would expect this state of affairs to continue provided that the Leachate Aeration Dam system continues to be managed and operated effectively.

The question of the relative magnitude of the proposed ED3S system emissions compared to overall site odour emissions is difficult to address quantitatively, given the disparate Bioreactor odour sources and the inherent difficulties in quantifying odour emissions using the odour sampling and testing techniques available to the audit team. The 2015 Odour Audit was able to determine that the odour emission rate from the active tipping face inside the Bioreactor was 45,100 ou.m³/s – well below the estimate in the original Environmental Assessment projection (292,000 ou.m³/s). This reduction is largely due to a decrease in the active tipping area – minimising the active tipping face is one of the key performance indicators at the Woodlawn site as addressed in previous audits. It is TOU's judgement at this stage that fugitive odour emissions are likely to be comparable to the active tipping face emissions to the overall Bioreactor emissions.

On this basis, and assuming a Bioreactor emission rate of at least 100,000 m³/s, it can be seen that the proposed utilisation of the ED3S system will add a maximum of 17% to overall site odour emissions, at full dam capacity.

On the basis of this assessment, it can be safely concluded that the conversion of ED3S system to leachate management duties will not result in any increase in odour impacts from the Woodlawn site.

Yours sincerely,



Terry Schulz
Principal & Managing Director

Attachments:

Attachment 1 – LandTeam Drawing No. 16800-437


Attachment 2 – Woodlawn Bioreactor ED3S Information

Attachment 3 - Odour Emissions Inventory Comparison Inventory & Odour Emissions Inventory 2015 Audit Excel Sheets



Attachment 1 –

LandTeam Drawing No. 16800-437



VOLUME	ML
789.37	6.85
789.47	7.78
789.57	8.80
789.67	9.91
789.77	11.14
789.87	12.45
789.97	13.84
790.07	15.32
790.17	16.89
790.27	18.57
790.37	20.38
790.80	29.20 (0.50m FREEBOARD)
791.20	38.50 (FULL)

SURFACE AREA AT FULL CAPACITY: 2.833ha
 SURFACE AREA AT BASE OF WALL: 2.303ha

File Name: J:\Surveyors\Jobs\Veolia\16800 Engineering\CAD\16800-437 ED3S-SOUTH VOLUMES.dwg

ISSUE	AMENDMENT	DATE
A	INITIAL ISSUE	24/08/2015

SCALE 1:800

0 10 20 30 40 50
Metres

Liability limited by a scheme approved under Professional Standards Legislation. **A3 SHEET**

VEOLIA
ENVIRONMENTAL SERVICES

LandTeam Australia Pty Ltd
 ABN 35 300 283 592
 Goulburn Office p: (02) 4821 1033
 36 Montague Street f: (02) 4821 7238
 Postal: PO Box 1040 e: goulburn@landteam.com.au
 GOULBURN NSW 2580 w: www.landteam.com.au

Integrated Management System

VEOLIA ENVIRONMENTAL SERVICES		DATE: 24/08/2015
PLAN SHOWING STORAGE INFORMATION EVAPORATION DAM 3 - SOUTH (SOUTHERN PARTITION) WOODLAWN BIOREACTOR		SURVEYED: VAR
		ISSUE A
		DRAWN: MK
		CHECKED: JK
		DRAWING No. 16800-437
DATUM	AHD	CONTOUR INTERVAL 0.5m



Attachment 2 –

Woodlawn Bioreactor ED3S Information

WOODLAWN BIOREACTOR ED3S INFORMATION



DAM: ED3SOUTH

Minimum RL: 786.40

Minimum Wall Level: 791.00

Maximum Water Level: 790.50 (0.5m freeboard)

Water Level	Volume (m ³)	Area (m ²)		Filling rates			Annual filling rate
				Low 1L/s	Average 1.5L/s	High 2L/s	
786.40	0.0	0.0	Yr 1	31.6	47.3	63.1	
786.50	0.3	13.3	Yr 2	63.1	94.7	126.2	
786.60	4.9	89.4	Yr 3	94.7	142.0	189.3	
786.70	20.4	233.1	Yr 4	126.2	189.3	252.5	
786.80	54.0	454.0	Yr 5	157.8	236.7	315.6	
786.90	114.2	762.4	Yr 6	189.3	284.0	378.7	
787.00	209.0	1147.3	Yr 7	220.9	331.4	441.8	
787.10	346.1	1608.6	Yr 8	252.5	378.7	504.9	
787.20	533.3	2147.6	Yr 9	284.0	426.0	568.0	
787.30	778.4	2769.6	Yr 10	315.6	473.4	631.2	
787.40	1090.1	3477.4	Yr 11	347.1	520.7	694.3	
787.50	1476.8	4271.6	Yr 12	378.7	568.0	757.4	
787.60	1947.9	5175.5	Yr 13	410.2	615.4	820.5	
787.70	2515.2	6182.5	Yr 14	441.8	662.7	883.6	
787.80	3187.7	7302.1	Yr 15	473.4	710.0	946.7	
787.90	4000.4	9044.2	Yr 16	504.9	757.4	1009.8	
788.00	5020.0	11544.8	Yr 17	536.5	804.7	1073.0	
788.10	6329.9	14605.3	Yr 18	568.0	852.1	1136.1	
788.20	7928.4	17372.5	Yr 19	599.6	899.4	1199.2	
788.30	9812.0	20341.8	Yr 20	631.2	946.7	1262.3	
788.40	12000.8	23840.0	Yr 21	662.7	994.1	1325.4	
788.50	14493.3	26446.4	Yr 22	694.3	1041.4		
788.60	17266.1	29052.6	Yr 23	725.8	1088.7		
788.70	20304.1	31711.6	Yr 24	757.4	1136.1		
788.80	23618.9	34639.8	Yr 25	788.9	1183.4		
788.90	27232.4	37649.8	Yr 26	820.5	1230.7		
789.00	31149.5	40706.2	Yr 27	852.1	1278.1		
789.10	35381.0	43989.0	Yr 28	883.6	1325.4		
789.20	39958.1	47625.5	Yr 29	915.2			
789.30	44921.4	51714.8	Yr 30	946.7			
789.40	50315.7	56314.8	Yr 31	978.3			
789.50	56191.0	61757.4	Yr 32	1009.8			
789.60	62669.6	67889.9	Yr 33	1041.4			
789.70	69609.4	73133.4	Yr 34	1073.0			
789.80	76868.5	75406.4	Yr 35	1104.5			
789.90	84392.4	77377.4	Yr 36	1136.1			
790.00	92145.4	79343.5	Yr 37	1167.6			
790.10	100124.3	81359.7	Yr 38	1199.2			
790.20	108332.8	83408.3	Yr 39	1230.7			
790.30	116767.1	85617.2	Yr 40	1262.3			
790.40	125427.2	87739.4	Yr 41	1293.9			
790.50	134275.9	89434.7	Yr 42	1325.4			
				1357.0			



Attachment 3 –

Odour Emissions Inventory Comparison Inventory & Odour Emissions
Inventory 2015 Audit Excel Sheets



Location	2015			2014			2013				2012			Environmental Assessment		
	Current Area (m ²)	TOU SOER (ou.m ³ /m ² /s)	TOU OER - Current Area (ou.m ³ /s)	2014 Area (m ²)	TOU SOER (ou.m ³ /m ² /s)	TOU OER - 2014 Area (ou.m ³ /s)	2013 Area (m ²)	TOU SOER (ou.m ³ /m ² /s)	TOU OER 2012 Area (ou.m ³ /s)	TOU OER - Current Area (ou.m ³ /s)	2012 Area (m ²)	TOU SOER (ou.m ³ /m ² /s)	TOU OER (ou.m ³ /s)	SOER (ou.m ³ /m ² /s)	OER (ou.m ³ /s)	OER - 2015 Current Area (ou.m ³ /s)
ED3N-1	6,000	0.132	794	6,000	0.017	104	6,000	0.30	2,100	1,800	7,000	394	2,760,000	8.8	61,600	52,800
ED3N-2 & 3	11,000	0.118	1,300	11,000	0.049	543	11,000	11.6	150,000	127,000	13,000	0.29	3,800	7.4	96,200	81,400
ED3N-2	5,500	0.145	797	5,500	0.066	365	5,500	20.1	131,000	111,000	6,500	0.21	1,350	n/a		
ED3N-3	5,500	0.091	500	5,500	0.032	178	5,500	0.2	1,010	852	6,500	0.37	2,430	n/a		
ED3N-4	25,000	0.269	6,720	25,000	0.023	575	25,000	0.0603	965	1,510	16,000	0.41	6,600	0.7	11,200	17,500
Active Tipping Face	6,000	7.509	45,100	6,000	4.28	25,700	6,000	3.04	121,000	18,200	40,000	8.36	334,000	7.3	292,000	43,800
Leachate Aeration Dam	5,000	0.276	1,380	5,000	0.026	129	5,000	0.323	646	1,620	2,000	0.46	920	3.6	7,200	18,000
Construction and Demolition Tip Face	900	0.326	294	500	n/a^	n/a	500	0.293	264	147	900	n/a	n/a	n/a	n/a	n/a
Storage Pond 7	n/a	n/a	n/a	n/a	n/m^^	n/a	n/a	n/m	n/m	n/m	1,200	85	102,000	n/m	n/m	n/m

^ non-existent in this audit
 ^^ non-existent
 n/a = not applicable
 n/m = not measured

Veolia Woodlawn Audit #4

Odour Emissions Inventory 2015 Audit



Odour Emissions Inventory 2015 Audit

Client: Veolia (Australia & New Zealand)

Sampling Site: Woodlawn Bioreactor Facility

Project Number: N1806L.03 - Woodlawn Audit #4

Sample Location	TOU Sample Number	Odour Concentration (ou)	Specific Odour Emission Rate (ou.m ³ /m ² /s)	Odour character	H ₂ S concentraton measurement in bag (ppm)
Evaporation Dam 3 North (ED3N) System					
Sample #1 - ED3N-4	SC15494	362	0.269	ammonical, dirt, soil	0.000
Sample #2 - ED3N-2	SC15495	197	0.145	ammonical, dirt, soil	0.000
Sample #3 - ED3N-1	SC15496	181	0.132	muddy, dirt	0.000
Sample #4 - ED3N-3	SC15497	118	0.091	muddy, dirt	0.000
Leachate Aeration Dam					
Sample #5 - Leachate Aeration Dam	SC15498	362	0.276	ammonical, dirt, soil	0.000
Active Tipping Area					
Sample #12 - Active Tipping Face Area: Soil Covered Final Layer (Point #1A)	SC15505	256	0.19	dirt, garbage	0.011
Sample #13 - Active Tipping Face Area: ConCover Secondary Layer (Point #1B)	SC15506	6,320	4.45	ammonical, garbage	0.026
Sample #14 - Active Tipping Face Area: Soil Covered (Point #2A)	SC15507	724	0.50	vanilla, gassy	0.000
Sample #15 - Active Tipping Face Area: ConCover (Point #2B)	SC15508	4,470	2.83	dirt, garbage	0.045
Sample #16 - Active Tipping Face Area: No cover (Point #3A)	SC15509	23,200	14.05	lime, sour, ammonical, garbage	0.60
Sample #17 - Active Tipping Face Area: No cover (Point #3B)	SC15510	27,600	17.11	ammonical, garbage	0.11
Sample #18 - Active Tipping Face Area: Freshly Waste (< 1 day old, Point #1)	SC15511	17,900	11.79	garbage	0.140
Sample #19 - Active Tipping Face Area: Freshly Waste (< 1 day old, Point #2)	SC15512	15,000	9.15	garbage	0.020
Waste Covered Area					
Sample #6 - Waste Covered Area: Normal Capping (Zone A between LE85 & SM13)	SC15499	181	0.127	sweet, fermented	0.000
Sample #7 - Waste Covered Area: Normal Capping (Zone A and parallel to LE99)	SC15500	558	0.388	sweet, fermented, pineapple, rotten egg, landfill gas	0.01
Sample #10 - Waste Covered Area: Biocovered Material Area (LE41)	SC15503	256	0.176	garbage, dirt, ammonical	0.004
Sample #11 - Waste Covered Area: Biocovered Material Area (LE57)^	SC15504	2,520,000	1,692.871	landfill gas, rotten egg	840
Sample #20 - Waste Covered Area: Normal Capping (Zone D - LE65)	SC15513	101,000	58.43	garbage, landfill gas, rotten, pineapple	n/m
Sample #21 - Waste Covered Area: Biocovered Material Area (Zone D - LE65)	SC15514	3,120,000	1,765.44	landfill gas, rotten egg, pineapple, garbage	180
Construction and Demolition Area					
Sample #8 - Construction and Demolition Area: Active Tipping Face (Point #1)	SC15501	431	0.299	sweet, fermented, pineapple, rotten egg, landfill gas	0.025
Sample #9 - Construction and Demolition Area: Active Tipping Face (Point #2)	SC15502	512	0.353	garbage, pineapple	n/m

n/m = not measured

^ estimated at 3,000 ou per 1 ppm of H₂S (i.e. mean of 2,000 - 4,000 ou per 1 ppm of H₂S)



THE ODOUR
UNIT



Veolia Australia & New Zealand

Appendix B:

**Bureau of Meteorology Basic
Climatological Station Metadata –
Goulburn Airport**

(Complied 26 November 2015)



Basic Climatological Station Metadata

Current status

Metadata compiled: 26 NOV 2015

Station: GOULBURN AIRPORT AWS

Bureau of Meteorology station number: 070330

Bureau of Meteorology district name: Sthn Tablelands Gburn-Monaro

State: NSW

World Meteorological Organization number: 95716

Identification: YGLB

Network Classification: National Benchmark Network for Agrometeorology

Station purpose: Synoptic, Aeronautical

Automatic Weather Station: Almos



Current Station Location				
Latitude	Decimal	-34.8085	Hour Min Sec	34°48'31"S
Longitude	Decimal	149.7312	Hour Min Sec	149°43'52"E
Station Height	640 m	Barometer Height	640.8 m	
Method of station geographic positioning			GPS	

Year opened: 1988

Status: Open

Station summary

No summary for this site has been written as yet.

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Basic Climatological Station Metadata

Current status

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Observation summary

The table below indicates the approximate completeness of the record for individual element types within the Australian Data Archive for Meteorology. For elements not listed see the note below.



DAILY DATA HOLDINGS

OBSERVATION TYPE	FIRST MONTH	LAST MONTH	COMPLETENESS (% estimate)	SINGLE DAYS MISSED	FULL MONTHS MISSED
MAXIMUM AIR TEMPERATURE	JUL 1990	OCT 2015	95.9	372	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0
MAXIMUM WIND GUST SPEED	JUN 2003	OCT 2015	98.8	53	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0
WIND RUN ABOVE 10 FEET	JUN 2003	OCT 2015	98.7	57	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0
RAINFALL	JUN 1994	NOV 2015	94	N/A	N/A
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0

HOURLY DATA HOLDINGS - from 1 to 24 observations per day

OBSERVATION TYPE	FIRST MONTH	LAST MONTH	COMPLETENESS (% estimate)	FREQUENCY average daily	SINGLE DAYS MISSED	FULL MONTHS MISSED
AIR TEMPERATURE	AUG 1989	OCT 2015	97.7	8.6	61	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0	2 0 0 0
DEW POINT	AUG 1989	OCT 2015	97.4	8.6	64	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0	2 0 0 0
MEAN SEA LEVEL PRESSURE	SEP 1995	OCT 2015	98.4	8.9	42	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0	2 0 0 0
TOTAL CLOUD AMOUNT	AUG 1995	OCT 2015	8.3	5.4	111	217
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0	2 0 0 0
WIND SPEED	AUG 1989	OCT 2015	97.7	8.6	59	0
1 8 5 0	1 9 0 0	1 9 0 0	1 9 5 0	2 0 0 0	2 0 0 0	2 0 0 0

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Basic Climatological Station Metadata

Current status

Station:	GOULBURN AIRPORT AWS			Location:	GOULBURN AIRPORT AWS		State:	NSW	
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988	Current Status:	Still open
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m	Metadata compiled:	26 NOV 2015

THERE ARE NO RAINFALL INTENSITY DATA HOLDINGS

ONE-MINUTE DATA HOLDINGS

OBSERVATION TYPE	FIRST MONTH	LAST MONTH	COMPLETENESS (% estimate)	FREQUENCY average daily	SINGLE DAYS MISSED	FULL MONTHS MISSED
ALL ELEMENTS	SEP 2010	NOV 2015	99.1	1427.4	N/A	0

HALF-HOURLY DATA HOLDINGS

OBSERVATION TYPE	FIRST MONTH	LAST MONTH	COMPLETENESS (% estimate)	FREQUENCY average daily	SINGLE DAYS MISSED	FULL MONTHS MISSED
ALL ELEMENTS	JAN 1989	NOV 2015	72.1	34.6	N/A	2

THERE ARE NO UPPER-AIR EDT DATA HOLDINGS

Holdings calculated up to 01 Nov 2015

The % complete figure is the completeness of observations averaged over all months of record, for the given station and observation type, taking gaps into account. For hourly holdings, the completeness is relative to the maximum number of daily observations for the site each month, and is therefore an estimate. For daily holdings, the completeness figure shown is exact.

The single days missed figure is the total number of days for which no observation was received, not including full missed months. The full months missed figure is the total of full month gaps over the period of record. Where an element is not included assumptions can generally be made about availability, and the list to use has been suggested below.

Unlisted element

Minimum air temperature
Wet bulb temperature
Soil temperature at 20, 50 & 100cm
Relative humidity
Minimum temp. of water in evaporimeter
Visual observations eg. weather, visibility
Sea related observations

Listed element to use

Maximum air temperature
Dew point
10cm soil temperature
Dew point
Evaporimeter - max water temp
Total cloud amount
Sea state

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Instrument Location and Surrounding Features

17/11/2010(most recent)



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW	
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988	
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m	
							Current Status:	Still open
							Metadata compiled:	26 NOV 2015

Instrument Location and Surrounding Features

26/03/2007



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW	
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988	
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m	
							Current Status:	Still open
							Metadata compiled:	26 NOV 2015

Instrument Location and Surrounding Features

13/11/2002



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m
						Current Status:	Still open
						Metadata compiled:	26 NOV 2015

Instrument Location and Surrounding Features

27/03/2001



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Instrument Location and Surrounding Features

09/03/1998



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Skyline Diagram 11/02/2014(most recent)



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Skyline Diagram

06/09/2009



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.




Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Skyline Diagram

24/02/2004



Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW		
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988	Current Status:	Still open
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m	Metadata compiled:	26 NOV 2015

Station Observation Program Summary (Surface Observations) from 01/11/1988 to 13/09/2010

Current Observation	Continuous	Half Hourly	Hourly
Surface Observations	-	Y	Y

Current Observation	Program Type	12 AM	3 AM	6 AM	9 AM	12 PM	3 PM	6 AM	9 AM
Surface Observation	PERFORMED	Y	Y	Y	Y	Y	Y	Y	Y
Surface Observation	REPORTED	Y	Y	Y	Y	Y	Y	Y	Y
Surface Observation	SEASONAL	-	-	-	-	-	-	-	-

Station Observation Program Summary (Surface Observations) 26 NOV 2015 (most recent)

Current Observation	Continuous	Half Hourly	Hourly
Surface Observations	Y	Y	Y

Current Observation	Program Type	12 AM	3 AM	6 AM	9 AM	12 PM	3 PM	6 AM	9 AM
Surface Observation	PERFORMED	Y	Y	Y	Y	Y	Y	Y	Y
Surface Observation	REPORTED	Y	Y	Y	Y	Y	Y	Y	Y
Surface Observation	SEASONAL	-	-	-	-	-	-	-	-

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m
						Current Status:	Still open
						Metadata compiled:	26 NOV 2015

Station Equipment History

Equipment Install/Remove

Cloud Height

31/OCT/2013 INSTALL Ceilometer (Type Vaisala CL31 S/N - J3510003) Surface Observations

River Height (No Electronic History)

Wind Run (No Electronic History)

Spectral Radiation (No Electronic History)

Sea Surface Temperature (No Electronic History)

Sea Water Temperature (No Electronic History)

Evaporation (No Electronic History)

Minimum Temperature (No Electronic History)

Soil Temperature 50cm (No Electronic History)

Sub Surface Temperature (No Electronic History)

Electrical Conductivity (No Electronic History)

Maximum Temperature (No Electronic History)

Soil Temperature 20cm (No Electronic History)

Solar Radiation (No Electronic History)

Soil Temperature 5cm (No Electronic History)

Oxygen Content (No Electronic History)

Sea Water Level (No Electronic History)

Surface Inclination (No Electronic History)

Terrestrial Minimum Temperature (No Electronic History)

Visibility (No Electronic History)

Solar Radiation (Direct) (No Electronic History)

Magnetic Bearing (No Electronic History)

Wind Direction

10/SEP/2004 INSTALL Anemometer (Type Synchrotac Cups - Type 732 S/N - 80261) Surface Observations

01/NOV/1988 INSTALL Anemometer (Type Synchrotac Vane - Type 706 S/N - WS - 74105 WD - 74066) Surface Observations

01/NOV/1988 INSTALL Mast Anemometer (Type Pivot, Standard 8m S/N - NONE) Infrastructure

15/FEB/2005 REPLACE Anemometer (Now Synchrotac Cups - Type 732 S/N - D100) Surface Observations

10/SEP/2004 REPLACE Anemometer (Now Synchrotac Vane - Type 706 S/N - 80309) Surface Observations

15/FEB/2005 REPLACE Anemometer (Now Synchrotac Vane - Type 706 S/N - D100) Surface Observations

Air Temperature

01/NOV/1988 INSTALL Humidity Probe (Type Rotronics S/N - 713201/9) Surface Observations

23/FEB/2012 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 11666-005) Surface Observations

19/FEB/2010 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 39220-007) Surface Observations

03/APR/2012 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 49513-003) Surface Observations

25/NOV/2002 REPLACE Humidity Probe (Now Vaisala HMP45D S/N - X4150011) Surface Observations

01/NOV/1988 INSTALL Temperature Probe - Dry Bulb (Type Rosemount S/N - NONE) Surface Observations

23/FEB/2012 REPLACE Temperature Probe - Dry Bulb (Now WIKA TR40 S/N - 107822-1) Surface Observations

01/NOV/1988 INSTALL Thermometer, Mercury, Dry Bulb (Type Dobbie S/N - M1803) Surface Observations

Wet Bulb Temperature (No Electronic History)

Lightning (No Electronic History)

Turbidity (No Electronic History)

Total Column Ozone Amount (No Electronic History)

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Extended Climatological Station Metadata

All History

Station: GOULBURN AIRPORT AWS	Location: GOULBURN AIRPORT AWS			State: NSW
Bureau No.: 070330	WMO No.: 95716	Aviation ID: YGLB	Opened: 07 Nov 1988	Current Status: Still open
Latitude: -34.8085	Longitude: 149.7312	Elevation: 640 m	Barometer Elev: 640.8 m	Metadata compiled: 26 NOV 2015

Station Equipment History (continued)

Equipment Install/Remove(Continued)

Pressure

- 01/MAY/1995 INSTALL Barometer (Type Vaisala PA11A S/N - 601091) Surface Observations
- 23/SEP/2002 REPLACE Barometer (Now Vaisala PA11A S/N - 458199) Surface Observations
- 31/MAR/2011 REPLACE Barometer (Now Vaisala PTB220B S/N - D3540108) Surface Observations

Humidity

- 01/NOV/1988 INSTALL Humidity Probe (Type Rotronics S/N - 713201/9) Surface Observations
- 23/FEB/2012 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 11666-005) Surface Observations
- 19/FEB/2010 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 39220-007) Surface Observations
- 03/APR/2012 REPLACE Humidity Probe (Now Rotronics MP101A-T4-W4W S/N - 49513-003) Surface Observations
- 25/NOV/2002 REPLACE Humidity Probe (Now Vaisala HMP45D S/N - X4150011) Surface Observations

Sunshine Hours (No Electronic History)

Pressure Trend (No Electronic History)

Snow Height (No Electronic History)

Wind Speed

- 10/SEP/2004 INSTALL Anemometer (Type Synchrotac Cups - Type 732 S/N - 80261) Surface Observations
- 01/NOV/1988 INSTALL Anemometer (Type Synchrotac Vane - Type 706 S/N - WS - 74105 WD - 74066) Surface Observations
- 01/NOV/1988 INSTALL Mast Anemometer (Type Pivot, Standard 8m S/N - NONE) Infrastructure
- 15/FEB/2005 REPLACE Anemometer (Now Synchrotac Cups - Type 732 S/N - D100) Surface Observations
- 10/SEP/2004 REPLACE Anemometer (Now Synchrotac Vane - Type 706 S/N - 80309) Surface Observations
- 15/FEB/2005 REPLACE Anemometer (Now Synchrotac Vane - Type 706 S/N - D100) Surface Observations

Rainfall

- 01/NOV/1988 INSTALL Raingauge (Type Rimco 7499 TBRG S/N - 66837) Surface Observations
- 31/JUL/2006 REPLACE Raingauge (Now Rimco 7499 TBRG S/N - 84619) Surface Observations
- 01/AUG/2006 REPLACE Raingauge (Now Rimco 7499 TBRG S/N - 84625) Surface Observations

Soil Temperature 100cm (No Electronic History)

Soil Temperature 10cm (No Electronic History)

Solar Radiation (Long Wave) (No Electronic History)

RF Reflectivity (No Electronic History)

The following table summarises information on field performance checks available electronically over the period indicated. The number of instances an instrument was found to fail field performance checks should only be used as a guide. A system of data quality flags is implemented by the Bureau of Meteorology to indicate the data quality of an observation as determined by a multi-stage quality control process.

Available Date Range	Element	Fail Field Performance Check
14/NOV/2013 - 10/MAR/2015	Cloud Height	0
09/MAR/1998 - 18/NOV/2015	Wind Direction	6
09/MAR/1998 - 18/NOV/2015	Air Temperature	3
09/MAR/1998 - 10/MAR/2015	Pressure	0
09/MAR/1998 - 18/NOV/2015	Humidity	2
09/MAR/1998 - 18/NOV/2015	Wind Speed	6
09/MAR/1998 - 18/NOV/2015	Rainfall	4

Station Detail Changes

09/MAY/2006 CLASSIFICATION Category D (TAF D)

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Extended Climatological Station Metadata

All History

Station:	GOULBURN AIRPORT AWS		Location:	GOULBURN AIRPORT AWS		State:	NSW	
Bureau No.:	070330	WMO No.:	95716	Aviation ID:	YGLB	Opened:	07 Nov 1988	
Latitude:	-34.8085	Longitude:	149.7312	Elevation:	640 m	Barometer Elev:	640.8 m	
							Current Status:	Still open
							Metadata compiled:	26 NOV 2015

Station Equipment History (continued)

Station Detail Changes(Continued)

01/NOV/1988 CLASSIFICATION Mesonet (FME)
05/OCT/2001 CLASSIFICATION National Benchmark Network for Agrometeorology (NBNA)
10/JAN/2011 CLASSIFICATION Standard (ASOSSTD)
10/JUN/2014 CLASSIFICATION Standard Aviation or Defence (AVSTD)
28/JUN/2011 OBJECT Document/AWS SITE AUDIT
14/NOV/2013 OBJECT Document/CEILOMETER STATUS
24/FEB/2004 OBJECT Document/Goulburn APT AWS Skyline points
06/SEP/2009 OBJECT Document/SKYLINE DATA
11/FEB/2014 OBJECT Document/SKYLINE DATA
07/NOV/1988 STATION - (nondb seeding) Opened
07/NOV/1988 STATION - (nondb seeding) aero_ht Changed to 652.6
07/NOV/1988 STATION - (nondb seeding) bar_ht Changed to 640.8
07/NOV/1988 STATION - (nondb seeding) bar_ht_deriv Changed to MAP 1:25 000
07/NOV/1988 STATION - (nondb seeding) stn_ht Changed to 640
07/NOV/1988 STATION - (nondb seeding) stn_ht_deriv Changed to MAP 1:25 000
07/NOV/1988 STATION - (nondb seeding) wmo_num Changed to 95716
07/NOV/1988 STATION aviation_id Changed to YGLB
07/NOV/1988 STATION latitude Changed to -34.80854
07/NOV/1988 STATION latlon_deriv Changed to GPS
07/NOV/1988 STATION latlon_error Changed to 4
07/NOV/1988 STATION longitude Changed to 149.73118
09/MAR/1998 STATION lu_0_100m Changed to Airport
09/MAR/1998 STATION lu_100m_1km Changed to Airport
09/MAR/1998 STATION lu_1km_10km Changed to Open farmland, grassland or tundra
07/NOV/1988 STATION name Changed to GOULBURN AIRPORT AWS
09/MAR/1998 STATION soil_type Changed to red soil
09/MAR/1998 STATION surface_type Changed to fully covered by grass

System Changes

01/NOV/1988 SYSTEM Infrastructure Commenced
01/NOV/1988 SYSTEM Surface Observations Commenced

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.

Notes on these metadata

The following notes have been compiled to assist with interpreting the metadata provided in this document. These notes are subject to change as the network evolves. Changes in station-specific metadata occur more frequently, both as recent changes are recorded and historical information is transferred from paper file to electronic database.

Reliability of the metadata

The Commonwealth Bureau of Meteorology maintains information on more than 20,000 stations which have operated since observations began in the mid 1800s. The amount of information available for each of these sites and its associated uncertainty are influenced by a number of factors including the type and purpose of the station and the time over which it operated.

Early information about stations was held only on paper file. In 1998 a corporate electronic database was established to help maintain information about the network and its components. The number of parameters recorded about a station is now much greater than before this database was established. The national database has also helped improve consistency in the metadata through the implementation of predefined fields. As a result, and through the refinement of operating procedures, station metadata recorded since 1998 are of a higher overall standard than previously, although occasional omissions and errors are still possible.

The Bureau is part way through a task of entering historical information held on paper file into the corporate database. **Until this process is completed there will remain large gaps in the information contained in these metadata documents and considerable caution should be used when deriving conclusions from the metadata.** As an example, two consecutive entries about a rain gauge dated 50 years apart may appear in the equipment metadata. This may either mean that nothing happened to that instrument over the 50 years, or that information for the intervening period has yet to be entered into the database. Similarly, if no information was available about instruments at a site when it was first established, fields which were required to have a value present may have used the earliest information available as a best-guess estimate. Sometimes this was the metadata current when the database was established in 1998. In some instances there may be gaps in metadata relevant to the post 1998 period.

For the above reasons it is recommended that all metadata prior to 1998 be considered as indicative only, and used with caution, unless it has been quality controlled. The Bureau of Meteorology should be contacted if further information or confirmation of the data is required. Depending on the nature of the inquiry there may be a fee associated with this request. Contact details are provided in the telephone book for each capital city or the Bureau's web site at:
<http://www.bom.gov.au>

The following pages contain explanatory notes for selected terms found in this document.

Station Number

The Bureau of Meteorology station number uniquely specifies a station and is not intended to change over time, although on very rare occasions a station number may change or be deleted from the record (usually to correct an error). Generally a new station number is established if an existing station changes in a way that would affect the climate data record for that site (measured in terms of air temperature and precipitation). Significant station moves are an example of this.

Some stations also possess a World Meteorological Organization (WMO) station number. The WMO number is different to the Bureau of Meteorology number. It also uniquely specifies a station at any given time but can be reassigned to another station if the new station takes priority in the global reporting network. Only selected stations will have a WMO number. Significant stations may maintain their WMO number for many decades.

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Notes on these metadata

Network Classification

SUPPORTING the BASIC CLIMATE SERVICE
Global Climate Observing System (GCOS)
GCOS Upper Air Network (GUAN)
GCOS Surface Network (GSN)
National Climate Network {not yet assigned}
Reference Climate Stations (RCS)
Regional Basic Climatological Network (RBCN)
CLIMAT Stations (CLC)
CLIMAT TEMP Stations (CLT)
SUPPORTING the NATIONAL WEATHER WATCH SYSTEM
WMO Global Observing System (GOS)
GOS Upper Air Network
GOS Satellite Network
Global Atmospheric Watch
Background Atmospheric Pollution Monitoring Network (BAPMON)
Basic Ozone Network
Basic Solar and Terrestrial Radiation Network
Regional Basic Synoptic Network (RBSN)
WMO Global Oceanic Observing System (GOOS)
SUPPORTING the BASIC WEATHER SERVICE (BWS)
BWS Land Network
Significant Land Locations
Capital City Mesonets
National Benchmark Network for Agrometeorology (NBNA)
BWS Marine Network
Significant Coastal Locations
Open Ocean Network
BWS Upper Air Network
Major Significant Locations
BWS Remote Sensing Network
Weather Watch Radar Network
Fire Weather Wind Mesonets
High Resolution Satellite
SUPPORTING the BASIC HYDROLOGICAL SERVICE
Regional Flood Warning Network
Water Resources Assessment Network
Global Hydrological Network
Global Terrestrial Observing System (GTOS)
World Hydrological Cycle Observing System (WHYCOS)
National Hydrological Network

Networks of stations are defined for a variety of purposes (as defined in above table).

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.

Notes on these metadata

Network Classification Continued....

Stations may be included in several different networks, which may change over time. The table on the previous page lists current network classifications related to the scientific purpose of the network. Some of these networks - the GCOS network for instance - are components of a global network. Entries in the database for some networks may not be complete, thus not properly representing the status of the network. The composition of the network will usually change over time. While several of the networks have international significance, other network classifications have been developed to aid operational management.

Station Purpose

The station purpose can be classified according to the observation program listed below. Parameters in brackets list some of the various different configurations which occur.

- Synoptic [Seasonal, River Height, Climatological, Telegraphic Rain, Aeronautical, Upper Air]
- Climatological [Seasonal, Telegraphic Rain]
- Aeronautical
- Rainfall [River Height]
- River Height
- Telegraphic Rain [Non-Telegraphic River Height, Telegraphic River Height]
- Non-Telegraphic Rain [Telegraphic River Height]
- Evaporation [Rainfall, River Height, Telegraphic River Height, Non-Telegraphic River Height, Telegraphic Rain, Non-Telegraphic Rain]
- Pluviograph [Rainfall, Telegraphic Rain, Non-Telegraphic Rain, River Height, Telegraphic River Height, Non-Telegraphic River Height]
- Radiation
- Lightning Flash Counter
- Public Information
- Local Conditions
- Radar Site
- Unclassified
- No Routine Observations

Note: Telegraphic observations are those which are sent by some electronic means be it a phone or telegram to the responsible Bureau office. It is a term which is historically linked to analogue non automatic data transmission.

Station Observation Program Summary

Surface Observations

The following terms are used to describe the frequency of surface observations at a site. Historical observation programs will typically be missing for many sites until the database is backfilled with information.

Set a)

- Continuous Program
 - More than half hourly observations sent (eg an automatic weather station {AWS} which continuously transmits 10 minute observations). This will automatically include half hourly and hourly observations programs.
- Half hourly observations
 - Half hourly observations sent. This will automatically include hourly observations.
- Hourly observations
 - Hourly observations sent only. Stations report on non-synoptic hours (ie. 0100, 0200, 0400, 0500, etc)

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.

Notes on these metadata

Surface observations continued....

Set b)

- Performed
 - Observations performed, instruments read and observations recorded
- Reported
 - Observations performed, instruments read and reported real time
- Seasonal
 - The program may only be performed during a defined season (such as Fire Weather observations) or the routine program may increase in reporting frequency and/or parameters. The program dates are currently modified at the start and end of each season for stations performing seasonal observations. Historically this was not always the case.

Current Station Equipment Summary

Equipment listed in this metadata product is catalogued under one of systems listed below, appropriate to its application. The "Infrastructure" category has been included since it contains information about the mast height of an anemometer (if present).

- Flood Warning
- Infrastructure
- Radiation
- Rainfall Intensity
- Surface Observations
- Upper Air
- Weather Watch {RADAR}

Station Equipment History

Equipment Install/Remove

One of four types of actions can be performed on an instrument in this listing:

Install - A new instrument is installed at the site. This can be either a completely new addition (eg the first barometer at the site), or the replacement of an existing instrument with a different type (eg replacing mercury barometer with electronic barometer)

Remove - An instrument can be removed either when it is no longer necessary to measure a particular element, or when the element is to be measured by an instrument of a different type (see under "Install" above)

Replace - This occurs when one instrument is replaced with another of the same type (eg Kew pattern mercury barometer replacing another Kew pattern mercury barometer)

Share - The same instrument is used for observations under two (or more) systems (eg a rain gauge may be used within both Surface Observations and Rainfall Intensity systems)

Unshare - The instrument is no longer shared between systems

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.

Notes on these metadata

Calibration

During a site inspection an instrument will be calibrated as either being within or not within the specified tolerance in accuracy.

Where a quantitative calibration result can be achieved by comparison to a transfer standard (eg barometer comparisons and tipping bucket rain gauge calibrations), the instrument will be recorded as being within or outside the required tolerance. Instruments (such as 203mm rain gauges, screens and evaporation pans) where quantitative calibrations cannot be derived should be regarded as meeting specifications when the instrument is in 'good working order'.

This product provides a summary table of the number of times an instrument was found to be out of calibration

Station Detail Changes

This set of metadata indicates when some aspect of the general information about a station has changed.

- STATION

Metadata which are categorised as pertaining to STATION are items of (textual) information describing a specific attribute of the station. A reference to (nondB seeding) indicates initial information of this field has been sourced from a previous database.

Station position

- Latitude and longitude

Derivation of station latitude and longitude, defined by the location of the rain gauge when it is present, has changed over time. Current practice is to locate or verify open and operational station latitude and longitude based on Global Positioning System equipment. Methods used to locate a station as described in this product (latlon_deriv) are as follows: GPS, MAP 1:10000, MAP 1:12500, MAP 1:25000, MAP 1:50000, MAP 1:100000, MAP 1:250000, SURVEY, and Unknown (which is more commonly represented by a null value). The field latlon_error should be used with caution as the method of determining this value has been interpreted in different ways over time.

- Height

Determination of heights for observing sites is by survey where possible. Otherwise height may be determined using a Digital Aneroid Barometer and a known surveyed point, or derived from map contours. The source of height is provided in the corresponding parameter with a suffix of "_deriv".

Heights which may appear in these metadata are:

- aero_ht
 - The official elevation of the aerodrome which normally corresponds to the altitude of the highest threshold of the runways at that airport;
- bar_ht
 - this represents the height of the mercury barometer cistern or the digital aneroid barometer above mean sea level (MSL);
- stn_ht
 - this normally represents the height of the rain gauge above MSL

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



Notes on these metadata

- Land Use

To assist the long term understanding of climate change it is important to be able to determine the differences over time which are attributed to variations in the climate. Since land use has an effect on the micro climate around the site, and changes in land use will therefore affect the climate record, it is important that the characteristics of the site are monitored. Soil types are recorded as they affect the land use and also add to the knowledge of the site details.

Defined Land use Types.

- Non-vegetated (barren, desert)
- Coastal or Island
- Forest
- Open farmland, grassland or tundra
- Small town, less than 1000 population
- Town 1000 to 10,000 population
- City area with buildings less than 10 metres (3 stories)
- City area with buildings greater than 10 metres (3 stories)
- Airport

The land use code is entered on the station inspection form in the ranges 0 to 100 m, 100 to 1 km and 1km to 10 km; ie:

- lu_0_100m: Land Use 0 to 100 metres from the enclosure
- lu_100m_1km: Land Use 100 metres to 1 kilometre
- lu_1km_10km: Land Use 1 kilometre to 10 kilometres

Defined Soil Type (At Enclosure).

- unable to determine
- sand
- black soil
- clay
- rock
- red soil
- other

Surface Type (At Enclosure).

- unable to determine
- fully covered by grass
- mostly covered by grass
- partly covered by grass
- bare ground
- sand
- concrete
- asphalt
- rock
- other

Historical metadata for this site has not been quality controlled for accuracy and completeness. Data other than current station information, particularly earlier than 1998, should be considered accordingly. Information may not be complete, as backfilling of historical data is incomplete.

Prepared by the Bureau of Meteorology.

Contact us by phone on (03) 9669 4082, by fax on (03) 9669 4515, or by email on climatedata@bom.gov.au

Station metadata is compiled for a range of internal purposes and varies in quality and completeness. The Bureau cannot provide any warranty nor accept any liability for this information. © Copyright Commonwealth of Australia 2015, Bureau of Meteorology.



THE ODOUR
UNIT *m³*



Veolia Australia & New Zealand

Appendix C: CALPUFF Source and Emission Modelling Configurations

Appendix C - CALPUFF Source and Emission Modelling Configurations



AREA SOURCE

Source Name	Lower Left X Coord.	Lower Left Y Coord.	Upper Left X Coord.	Upper Left Y Coord.	Upper Right X Coord.	Upper Right Y Coord.	Lower Right X Coord.	Lower Right Y Coord.	Effect. Height	Base Elev.	Init. Sigma Z	ODOUR
(12 chars.)	(km)	(km)	(km)	(km)	(km)	(km)	(km)	(km)	(m)	(m)	(m)	(g/m**2/s)
LDAM	734.1	6117.183	734.166	6117.287	734.184	6117.268	734.129	6117.163	0	797.19	0.1	3.6
GW	733.455	6117.624	733.399	6117.421	733.552	6117.39	733.652	6117.541	0	791.39	0.1	0.3
TL1	733.559	6117.387	733.658	6117.54	733.707	6117.508	733.725	6117.46	0	791.56	0.1	3.6
UTL	733.661	6117.366	733.788	6117.346	733.73	6117.455	733.662	6117.37	0	791.55	0.1	5
COVW	734.128	6116.962	734.37	6117.189	734.463	6117.157	734.735	6117.023	0	731.67	0.1	0.3
AGEDW	734.156	6116.944	734.649	6116.721	734.498	6116.646	734.099	6116.859	0	687.56	0.1	3.6
FW	734.099	6116.858	734.098	6116.793	734.359	6116.638	734.493	6116.644	0	753.02	0.1	0.7
WR3	733.132	6117.509	733.185	6117.628	732.905	6117.753	732.852	6117.634	0	793.74	2	0.253
WR2	733.163	6117.495	733.216	6117.614	733.185	6117.628	733.132	6117.509	0	792.15	2	13
WR4	733.193	6117.482	733.246	6117.6	733.216	6117.614	733.163	6117.495	0	791.81	2	11.3
WR4_2	732.816	6117.65	732.869	6117.769	732.857	6117.775	732.803	6117.656	0	796.36	2	11.3
WR5	732.803	6117.656	732.857	6117.775	732.843	6117.781	732.79	6117.662	0	796.38	2	5.45
WR5_2	732.79	6117.662	732.843	6117.781	732.778	6117.81	732.725	6117.691	0	796.74	2	0.253
ED3S-S	733.529	6116.967	733.523	6117.122	733.739	6117.044	733.641	6116.904	0	794	0.1	0.159
ED3S1	733.449	6117.187	733.394	6117.285	733.579	6117.344	733.533	6117.15	0	793	0.1	0.159
ED3S2	733.533	6117.15	733.579	6117.344	733.805	6117.32	733.746	6117.093	0	793	0.1	0.159

VOLUME SOURCE

Source Name	X Coord.	Y Coord.	Effect. Height	Base Elev.	Init. Sigma Y	Init. Sigma Z	ODOUR
(12 chars.)	(km)	(km)	(m)	(m)	(m)	(m)	(g/s)
SRC_1	732.95	6117.695	0	0	20	2	5.65
SRC_2	733.066	6117.623	0	0	10	2	2.37

ATTACHMENT 2 - WATER BALANCE

	unit	ED3N1	ED3N2	ED3N3	ED3N4	ED3SS
Water level (RL survey at 28/04/2017)	m	790.79	790.86	790.80	790.73	791.51
Maximum level (RL with 0.5 m freeboard)	m	791.30	791.10	791.00	791.30	793.62
Maximum surface area (with 0.5 m freeboard)	m ²	8,572.60	7,103.60	6,304.20	39,719.50	21,781.70
Volume of leachate (survey at 28/04/2017)	m ³	18,349.00	16,400.00	13,553.00	82,077.00	69,523.00
Full capacity with 0.5 m freeboard	m ³	22,593.30	18,080.30	14,796.30	104,209.60	111,439.40
Residual Volume capacity	m ³	4,244.30	1,680.30	1,243.30	22,132.60	41,916.40
Total residual volume	m ³	71,216.90				
Flow rate into the evaporation dams	L/s	4.50				
Weekly volume of leachate to the evaporation dams	m ³	2,721.60				
Total maximum surface area of all the dam	m ²	83,481.60				
Annual rain drop (2016)	mm	818.00				
Average weekly rain drop	mm	15.73				
weekly volume of rain water into dam	m ³	1,313.23				
Total volume of liquid to evaporation dams (leachate + rain) each week with out evaporation	m ³	4,034.83				
Time to fully fill all the evaporation dams	weeks	17.65053393				
Estimated time for needing the new dam						Week 35 of 2017 (28/08/2017)
Average evaporation in year 2015 and year 2016	mm/day	3				
Equivalent of evaporation from Sep - March	mm/day	5.2				
Weekly volume of evaporation during 9/2017 - 3/2018	m ³	3,018				
Net inflow into the EDs from 09/2017 - 03/2018	m ³	1,016				
Extra volume need to be stored during 09/2017-03/2018	m ³	30,495				
Evaporation stops from 04/2018-08/2018	Weeks	23				
Inflow into EDs from 04/2018 - 08/2018	m ³	92,801				
Evaporation starts from 09/2018-12/2018	weeks	17				
Inflow into EDs from 09/2018 - 12/2018	m ³	17,280				
Total volume of leachate need to be stored till 12/2018	m³	140,576				