

Structural Report
Tweed Valley Hospital,
Kingscliff, NSW
Lot 11 DP1246853

Issue: 3 – SSD2

Prepared For: Health Infrastructure, NSW

Project No.: 19005

15th August 2019



Report Amendment Register

Issue	Section & Page No.	Issue/Amendment	Author/ Initials	Project Engineer	Reviewer/ Initials	Date
1	ALL	DRAFT - SSD2	VI		MH	11/06/2019
2	ALL	SSD2	SH		МН	02/08/2019
3	ALL	SSD2	SH	, v	MH	15/08/2019
-						
-						
					(3)	
					,	

ISSUE ACCEPTED BY:

AUTHOR:

SAM HAWDON

Signing for and on behalf of **Robert Bird Group Pty Ltd** Date: 15th August 2019

REVIEWER:

MATT HARDING Signing for and on behalf of Robert Bird Group Pty Ltd Date: 15th August 2019

Appendix D

Table of Contents

1.0	Over	view	
	1.1	Stage 2 Hospital Main Works and Operation	1
	1.2	Potential Future Expansions	
2.0	Introd	duction	
	2.1	Client Briefing Documentation and NSW Health Guidelines	2
	2.2	Geotechnical Reports	
3.0	Struc	tural Performance Brief	3
	3.1	Design Life	3
	3.2	Future Flexibility Design	
	3.3	Structural Importance Level	4
	3.4	Applicable Codes and Standards	4
	3.5	Vertical Design Loads	5
	3.6	Earthquake Loads	6
	3.7	Wind Loads	6
	3.8	Deflection Criteria	6
	3.9	Vibration Criteria	7
	3.10	Fire Resistance	9
	3.11	Crack Control in Concrete Elements	10
	3.12	Safety in Design	10
	3.13	Durability	10
	3.14	Sustainability	10
4.0	Struc	tural Concept Summary	10
	4.1	Excavation Methodology, Shoring and Retention Systems	10
	4.2	Foundations	11
	4.3	Vertical Support and Structural Grids	12
	4.4	Floor Systems	
	4.5	Lateral Load-Resisting System	13
	4.6	Steel structures	13
	4.7	Other	13
Appe	ndix A	A Structural drawings coordinated to 30-5-2019 Architectural	
Appe	ndix E	B Floor loading plans coordinated to 30-5-2019 Architectural	
Appe	ndix (Floor Vibration plans coordinated to 30-5-2019 Architectural	

This report has been prepared on behalf of and for the exclusive use of the Client, and is subject to and issued in accordance with the agreement between the Client and Robert Bird Group Pty Ltd. Robert Bird Group Pty Ltd accepts no liability or responsibility whatsoever for any use of or reliance upon this report by any third party. Any copying of this report to external parties requires the permission of the Client and Robert Bird Group Pty Ltd.

RBG-TN002 – Slab efficiency report

1.0 Overview

On the 11 June 2019 the Minister for Planning and Public Spaces granted approval for the Concept Proposal and Stage 1 Early and Enabling Works for the new Tweed Valley Hospital (SSD 9575) located at 771 Cudgen Road, Cudgen (Lot 11 DP1246853). All documents relating to this consent can be found on the major project website of DPIE at https://www.planningportal.nsw.gov.au/major-projects/project/10756.

The Environmental Impact Statement (EIS) has been prepared to assist in the State Significant Development (SSD) Stage 2 Application for the Tweed Valley Hospital which will be assessed under Part 4 Division 4.7 of the *Environmental Planning and Assessment Act 1979* (EP&A Act). This, along with supporting documentation, provides a clear outline of the Stage 2 Application.

The Tweed Valley Hospital Project broadly consists of:

- Construction of a new Level 5 major regional referral hospital to provide the health services required to meet the needs of the growing population of the Tweed-Byron region (in conjunction with the other hospitals and community health facilities across the region);
- Delivery of the supporting infrastructure required for the Tweed Valley Hospital, including green space and other amenities, roads and car parking, external road upgrades and connections, utilities connections, and other supporting infrastructure.

1.1 Stage 2 Hospital Main Works and Operation

The Stage 2 SSD component seeks consent for the Main Works and Operation of the Tweed Valley Hospital, including:

Construction of Main Hospital Building

- Main entry and retail area
- Administration
- Community health
- In-Patient units
- Outpatient clinics and day only units
- Child and Adolescent Services
- Intensive Care Unit
- Mental Health Unit
- Maternity Unit and Birthing Suites
- Renal Dialysis
- Pathology
- Pharmacy
- Radiation Oncology as part of integrated Cancer Care
- Emergency Department
- Perioperative Services
- Interventional Cardiology
- Medical Imaging
- Mortuary
- Education, Training, Research

- Back of House services
- Rooftop Helipad
- Construction of Support Buildings, referred to as the 'Health Hub', containing:
 - Oral Health
 - Community Health
 - Aboriginal Health
 - Administration
 - Education, Training and Research
- Internal Roads and carparking, including multi-deck parking for staff, patients and visitors:
- Construction of a temporary building for the 'Tweed Valley Skills Centre'
- External road infrastructure upgrades and main site access
- Environmental and wetland rehabilitation, including rehabilitation of existing farm dam as outlined in the Biodiversity Development Assessment Report (BDAR) prepared for the Concept Proposal and Stage 1 works
- Site landscaping
- Signage
- Utility and service works



Project No. 19005 Issue: 3 - SSD2 15th August 2019

The works outlined above comprise five key components, which are subject to various funding allocations and may be delivered independently to each other. Stage 2 has therefore been defined in the following sub-stages¹:

- Stage 2A Main Hospital Building complete with supporting roads, services infrastructure and landscaping
- Stage 2B Main Hospital Building incremental expansion areas
- Stage 2C Health Hub
- Stage 2D Tweed Valley Skills Centre
- Stage 2E Multi-deck car park.

Development consent is sought for the all 5 components of Stage 2 under this SSDA.

Plans for Stage 2 Main Works and Operation are attached in Appendix B of the EIS. Approval of Stage 2 will enable the new Tweed Valley Hospital to be built which will provide a much-needed contemporary health service facilities for the surrounding region.

1.2 Potential Future Expansions

Any subsequent stages or modifications to the proposal would be subject to separate applications as required including the potential future expansion of the facility.

2.0 Introduction

This structural report has been prepared by Robert Bird Group (RBG) for Health Infrastructure, to summarise the structural design works associated with the new Tweed Valley Hospital project.

A new multi-story concrete building is to be constructed centrally to the site located at Lot 11 DP1246853. The new building will feature one Basement level (B1), Lower Ground Floor, Ground level, and typical suspended floors to Level 6. The column grid to the new building is typically spaced at 8.4 metres in each direction, with columns supported on pile foundations socketed into medium strength basalt.

The suspended slabs are proposed to be post-tensioned flat slabs designed to accommodate the requirements in the HI guidelines with respect to vibration performance and future flexibility. Vertical expansion has been accommodated in the design of the Level 6 roofs. Lateral loads are resisted by in-situ concrete stair and lift cores, with the structure designed to Importance Level 4 design return period.

There will also be three new buildings to form an external Health Hub. One building will be single storey and the other two will be double storey.

The structural design will be developed to ensure the adequate functioning of the building structure consistent with the intended use of the project as described in the Engineering Services Guidelines by NSW Health (published on 26 August 2016), and will address the performance requirements of the structure in terms of strength, serviceability (deflection, vibration) and durability.

The RBG structural brief is compliant with the NSW Health guidelines.

2.1 Client Briefing Documentation and NSW Health Guidelines

The following documentation has been provided by Health Infrastructure for this project:

Date	Title	Author
Aug 2016	Engineering Services Guidelines	NSW Health
Oct 2018	Tweed Valley Hospital Project – Project Brief	NSW Health

Where additional briefing information is available or has been updated, the latest information shall be used.



¹ Stages are not listed in chronological order and may be delivered independently to each other

Tweed Valley Hospital, NSW Project No. 19005 Issue: 3 – SSD2 15th August 2019

2.2 Geotechnical Reports

The following existing geotechnical reports are available for reference for this project.

Date	Title	Author
Sep 2018	PRELIMINARY GEOTECHNICAL INVESTIGATION,	Morrison
	PROPOSED TWEED VALLEY HOSPITAL	Geotechnic
	Ref: GE18/144-Rev2	
Dec 2018	ADDITIONAL GEOTECH INVESTIGATION	Morrison
	PROPOSED TWEED VALLEY HOSPITAL	Geotechnic
	Ref: GE18/144-Rev2	

3.0 Structural Performance Brief

3.1 Design Life

General Requirements of Structural Engineering Design

All structure is to be designed to carry applied loads (vertical and horizontal loads) and to satisfy serviceability criteria, in particular:

- Strength;
- Vibration-performance criteria;
- · Deflection limits;
- Durability criteria
- Satisfy all Client user and other stated requirements;
- Architectural and building services requirements;
- Existing buildings and services adjacent to the project site.

The design life adopted for the project is -

Structural Durability - 50 years Structural Flexibility of Function - 50 years

In order to achieve 50 years design life, the following criteria must be met:

- · Concrete;
 - Covers and strengths to be in accordance with the AS/NZS 3600-2018: Concrete Structures & AS 2159-2009: Piling Code.
- · Steelwork;
 - A 50-year design life shall be achieved via selection of appropriate protection systems (applied paint systems or similar), coupled with a rigorous maintenance regime of scheduled repainting for structural elements.
- A 50-year functional design life is proposed to be achieved via adoption of:
 - Integral removable floor cover zone to allow additional or relocated set down areas.
 - Predetermined zones for future services risers.
 - Refer section 2.2 Future Flexibility Design for details.
- All new suspended slab areas shall be assessed for vibration as general ward space unless noted otherwise, to meet the future flexibility requirements of the functional brief.
 This has been achieved by assessing corridor vibration loading throughout the floors.

Maintenance of the Structural Elements

The continued satisfactory performance of the structures designed to the criteria outlined in this report assumes an appropriate and comprehensive maintenance regime specific to those structures will be developed and implemented by the building owner as part of the overall maintenance regime for the facility.



Tweed Valley Hospital, NSW
Project No. 19005
Issue: 3 – SSD2
Project No. 19005
15th August 2019

3.2 Future Flexibility Design

To ensure that a 50-year functional design life is achieved in the proposed hospital redevelopment, the structural design of the new clinical services building requires the inclusion of a number of 'future proofing' initiatives:

Sacrificial cover zone

Levels 1 to 5 have generally been designed with an increased cover over reinforcement to allow maximum flexibility with regards to future wet area set-downs. The design allows for 40mm to be removed from the top of the slab and maintain the minimum cover requirements for the reinforcement. (Refer structural drawings for locations).

Note: Any future set-downs will require a re-assessment of the vibration performance of the slab to determine if any additional measures, i.e. introduction steel posts, are required to meet the vibration criteria.

Future Services Risers

All suspended floor plates to be designed with predetermined future service risers (refer structural drawings for locations). The future risers will be identified on the drawings so that they can be cut in the future without the need for strengthening works.

Vibration Response Factors

Levels 2 to 5 have been designed to achieve a maximum response factor (Rf) of 2.0 in the IPUs and 4.0 in the work zones. This provides future flexibility that allows these floors to accommodate operating theatres and future vibration sensitive equipment without the need for any additional structural works. Additionally, operating theatres and other critical zones will be designed for a maximum response factor (Rf) of 1.0.

The level 5 floor plate will be designed to achieve the same vibration performance as the general ward space on levels 2-4. It will also be designed with a higher load capacity so that the floor plate can accommodate an additional level of ward space with a light framed steel roof above in the future, without the need for any strengthening works.

Vertical and Lateral Load Capacity

The vertical structural elements, i.e. foundations, columns and walls will be designed to support the loads created by the future works (refer above).

3.3 Structural Importance Level

The building has been classified as Importance Level 4 to AS 1170.0, for the purposes of wind and earthquake design.

3.4 Applicable Codes and Standards

The structural design of the project is to be completed in accordance with the relevant Australian Standard Codes of Practice including but not limited to the following:

- Building Code of Australia (BCA 2019)
- Engineering Services
- Guidelines NSW Health
- AS/NZS 1170.0 (2002)Structural Design Actions General Principles
- AS/NZS 1170.1 (2011)Structural Design Actions Permanent, Imposed & Other Actions
- AS/NZS 1170.2 (2011)Structural Design Actions Loading Code Wind
- AS 1170.4 (2007) Structural Design Actions Loading Code Earthquakes
- AS 2159 (2009) Piling Code



Tweed Valley Hospital, NSW
Project No. 19005
Issue: 3 – SSD2
15th August 2019

AS/NZS 3600 (2018) Concrete Structures

- AS/NZS 3700 (2018) Masonry Code
- AS/NZS 4100 (1998) Steel Structures

For standards relevant to vibration criteria, please refer Section 2.8.

In addition to the standards listed above, all local service authority requirements will be complied with, including but not limited to –

- Sydney Water Corporation
- Other gas, electricity, water and sewer authorities as relevant to the project

3.5 Vertical Design Loads

The following design loads shall be applied to floor areas on the project for various buildings and spatial usages.

Floor Usage	Uniform Live Load (kPa)	Point Live Load (kN)	Superimposed Dead Load (kPa)	40mm Sacrificial Topping (kPa)
Plant Rooms U.N.O	7.5	4.5	2.4	-
Fire Stairs / Stairs	4.0	4.5	0.5	-
Common Areas / Lobbies / Corridors / Circulation Spaces	5.0	1.8	1.8	1.0
Offices	3.0	4.5	1.8	1.0
General Ward Space	3.0	4.5	2.0	1.0
Storage Areas U.N.O	5.0	4.5	1.8	-
Retail	5.0	4.5	1.8	1.0
Cardiology Gym	5.0	3.6	1.8	1.0
Cool Rooms	15 kPa minimum	10.0, maximum	2.0	1.0
Façades (Typical)	N/A	N/A	As calculated in accordance with AS1170.1, refer structural loading plans	-
Balconies	4.0	1.8	2.0	-
Concrete Roof- Non-trafficable	1.0, (200mm ballast allowance)	L4	5.0	-
Shell space future expansion	4.0	4.5	3.0	-
Operating Theatre, X-ray room	3.0	4.5	2.0	1.0
Parking, Driveway & Ramp	2.5	13	0.5	-
Landscape	5		11 (600mm Soil fill)	-
Roof	0.5	1.4	2.5 (10mm screed)	-
Other	as calculated,	as calculated	as calculated	1.0

Superimposed Dead Load

Refer Appendix A for the superimposed dead loading diagrams which illustrate the superimposed dead loads applied to each area of the structure. The design of structure allows for the above listed permanent floor loads superimposed over (and in addition to) the self-weight of the structure (self-weight shall be calculated separately). Where an area is not defined in the above table or in the loading diagram, advice shall be sought from the project manager and reference made to AS/NZS 1170.1.

Live Loadings



Issue: 3 – SSD2

Refer Appendix B for the live loading diagrams which illustrate the relevant live loads for each area of the structure. Where an area is not defined in the above table or loading diagram, advice shall be sought from the project manager and reference made to AS/NZS 1170.1. Where loads in this table are in excess of the minimum loadings stated in the Australian Standard, the loadings rated in the

3.6 Earthquake Loads

The following earthquake design criteria in accordance with AS1170.4 (2007) and NCC (2016) are to be adopted: –

Factor	Adopted Value
Hazard Factor	0.09
Site Subsoil Class	Ce
Building Importance Level	4
Annual Probability of Exceedance	1:1500
Probability Factor k _p	1.5
Earthquake Design Category	EDC III

above table / loading diagrams shall be adopted.

3.7 Wind Loads

The building will be designed for wind loads in accordance with the relevant Australian Standards for the following parameters: -

Factor	Adopted Value
Region	В
Terrain Category	2
Building Importance Level	4
Annual Probabilities of	Ultimate 1:2000
Exceedance	Service 1:25
Basic Wind Velocities –	
V ₂₀₀₀	63m/s
V ₁₀₀	48m/s
V ₂₀	38m/s
Ms	1.0
Mt	1.0
Md	1.0

It is not considered necessary that a detailed structural wind study to be carried out. Studies of cladding pressures and wind environmental effects may be required.

Glazing shall be articulated as necessary to provide allowance for structural mullions and wind beams to support minor awnings and architectural louvres.

3.8 Deflection Criteria

Structural elements are to be designed to achieve deflection control in accordance with the criteria set out in the table below –

Project No. 19005 Issue: 3 - SSD2 15th August 2019

Structural Element	Deflection Type	Limit	
Overall building structure	Lateral sway due to permissible wind load	height/500	
Overall building structure	Lateral sway due to ultimate earthquake loads	interstorey drift limit of height/500	
Floor slabs – spans (no sensitive partitions)	Long-term incremental deflection	span/250 or 25mm whichever is less	
Floor slabs – spans (with sensitive partitions)	Long-term incremental deflection	span/500 or 25mm whichever is less	
Floor slabs – cantilevers (no sensitive partitions)	Long-term incremental deflection	cantilever/125 or 25mm whichever is less	
Floor slabs – cantilevers (with sensitive partitions)	Long-term incremental deflection	cantilever/250 or 25mm whichever is less	
Transfer beams	Long-term incremental deflection	span/1000 or 10mm, whichever is less	

3.9 Vibration Criteria

Vibration performance for the structural elements of the project has been selected to address the effects of vibration on: -

- Structural adequacy / durability
- Regenerated noise / acoustic performance
- Perception / comfort of building occupants
- Performance of sensitive equipment / processes

Relevant Codes and Standards

- SCI P354: Design of Floors for Vibration: A New Approach, Steel Construction Institute (2009, Revised)
- CCIP-016: A Design Guide for Footfall Induced Vibration of Structures, The Concrete Centre
- Comparison of Possible Hospital Floor Structures with Respect to NHS Vibration Criteria, The Concrete Centre (2004)
- BS 6472.1 Guideline to Evaluation of Human Exposure to Vibration in Buildings
- 130559-BON-CIV-RPT-006: Tweed Valley Hospital Development Design Report, Civil & Structural – Issued for 100% Concept Design (Revision D), Bonacci Group
- TN290: Vibration Design of Concrete Floors for Serviceability, AdaptSOFT, 2008
- Engineering Services Guidelines Health Infrastructure NSW

Application of Relevant Vibration Criteria

Refer Appendix C for floor vibration design response factor diagrams that identify the adopted response factor criteria for each floor plate. The vibration thickness for modelling purposes is considered to equal the total slab thickness (i.e. includes the sacrificial cover zones and architectural set-downs where necessary), refer figure 2.8.1 below.



Project No. 19005 Issue: 3 – SSD2 15th August 2019




Figure 2.8.1 Vibration Thickness Diagram

The critical considerations and/or factors in determining the criteria are:

- Identification of the vibration sources.
- The impact of the vibration on the vibration receiver.
- The required dynamic characteristics of the structure and the resultant design consequences and cost (i.e. the mass, stiffness and damping of the floor structure).

In most instances, the critical vibration source considered in the structural design of the Clinical Services Building is vibration induced by human walking. The definition of human walking adopted for the structural design is one, 76 kg person, walking at 132 steps per minute, corresponding to a foot fall frequency of 2.2 Hz.

Structural Element	Deflection Type	Limit	
Percentage of Damping	3%	For fully fitted out and furnished floors in normal use	
Applied Live Load	10% of nominal live load	-	
Dynamic Modulus of Elasticity	38,000 MPa	-	
Walking Pace Frequency	1.0 to 2.2 Hz	-	
Static Force Exerted by an 'Average Person'	746 N	76 kg x 9.81 m/s2	
Number of Modes to be Considered	All modes up to minimum 15 Hz	-	

The building floor system must be designed so that the vibration effects of human walking are kept to within an agreed set of criteria relevant to the usage of the floor area under consideration. These have been taken from CCIP-016 and are reproduced below:

Draft - Structural Performance Brief Tweed Valley Hospital, NSW Issue: 3 – SSD2

Project No. 19005 15th August 2019

Criterion curve	Max. velocity level* μm/sec (RMS)	Detail size** microns	Description of use
Workshop (ISO2631 and BS6472) R = 8, ASHRAE J	800	N/A	Distinctly perciptible vibration. Appropriate to workshops and non-sensitive areas.
Office (ISO2631 and BS6472) <i>R</i> = 4, ASHRAE I	400	N/A	Perceptible vibration. Appropriate to offices and non-sensitive areas.
Residential day (ISO2631 and BS6472) R = 2, ASHRAE H	200	75	Barely perceptible vibration. Appropriate to sleep areas in most instances. Probably adequate for computer equipment, probe test equipment and low-power (to 20X) microscopes.
Operating theatre (ISO2631 and BS6472) R = 1, ASHRAE F	100	25	Threshold of perception. Suitable for sensitive sleep areas. Suitable in most instances for microscopes to 100X and for other equipment of low sensitivity.
VC-A (BBN-A or ASHRAE E) <i>R</i> = 0.5	50	8	Adequate in most instances for optical microscopes to 100X, microbalances, optical balances, proximity and projection aligners, etc.
VC-B (BBN-B or ASHRAE D) <i>R</i> = 0.25	25	3	An appropriate standard for optical microscopes to 1000X, inspection and lithography equipment (including steppers) to 3 microfline widths.
VC-C (BBN-C or ASHRAE C) <i>R</i> = 0.125	12.5	1	A good standard for most lithography and inspection equipment to 1-micron detail size.
VC-D (BBN-D or ASHRAE B) <i>R</i> = 0.0625	6	0.3	Suitable in most instances for the most demanding equipment including electron microscopes (TEMs and SEMs) and E-Beam systems, operating to the limits of their capability.
VC-E (BBN-E or ASHRAE A) <i>R</i> = 0.03125	3	0.1	A difficult criterion to achieve in most instances. Assumed to be adequate for the most demanding of sensitive systems including long path, laser-based, small target systems and other systems requiring extraordinary dynamic stability.

The excitation points, e, and the response points, r, are chosen to produce the maximum response to the floor. This usually occurs when the excitation point, e, and the response point, r, will occur at the same point – a conservative assumption.

The precast and lightweight facade has been assumed to provide vertical restraint to the perimeter of internal and external floor slabs for the purposes of vibration analysis. Note, full height glazing (both articulated and non-articulated) has been assumed to not provide any restraint for the purposes of vibration analysis.

For vibration analysis, the mesh size used is considered sufficient if the elements can be doubled without significantly changing the frequency. RBG have adopted a 500x500mm mesh size for vibration assessment.

RBG have adopted a floor system using standard formwork for construction. This allows for the floor plate to be designed with consistent section properties in all directions for vibration analysis. If non-standard formwork is to be used for construction (i.e. bondek etc.), the floor plate section properties will vary in each direction and therefore will need to be reassessed.

3.10 Fire Resistance

Structural elements are to be designed in accordance with the Building Code of Australia and the



^{*} As measured in one-third octave bands of frequency over the frequency range 8 to 100 Hz.

^{**} The detail size refers to the line widths for microelectronics fabrication, the particle(cell) size for medical and pharmaceutical research, etc. the values given take into account the observation that the vibration requirements of many items depend upon the detail size of the process.

Tweed Valley Hospital, NSW
Project No. 19005
Issue: 3 – SSD2
Project No. 19005
15th August 2019

relevant Australian Standards to satisfy the required FRL levels for fire. These levels will be advised by the Principal Certifying Authority for the project.

3.11 Crack Control in Concrete Elements

The effects of thermal movement and shrinkage must be allowed for in the structural design. Structural concrete elements are to be designed to maintain serviceability and visual adequacy (i.e. generally a minor degree of crack control, moderate degree of crack control for areas with 'brittle' finishes as per AS3600) via movement controls including but not limited to –

- construction joints
- pour strips
- · grouted dowel joints
- · slip joints
- expansion joints
- · other detailing as deemed necessary

3.12 Safety in Design

Safety in Design reviews on all structural elements will be completed at the following milestones in the course of the project –

- prior to issue of structural trade packages for tender
- prior to issue of structural drawings "For Construction"

3.13 Durability

Concrete: -

Exposure Classifications:

Internal	General	A1
	Plant room and soffits of	B1
	slabs over plant rooms	
	Basements generally	A1
External	All external areas	B1

Steel: -

The surface treatments to exposed steelwork will be as per the required architectural finish and determined by the architect.

All external steelwork shall be hot dipped galvanised unless noted otherwise.

3.14 Sustainability

Sustainability is an important requirement for this building in particular and to developments in general undertaken by Health Infrastructure. Appian Group has issued sustainability guidelines which will be monitored in conjunction with the ESD Consultant.

4.0 Structural Concept Summary

4.1 Excavation Methodology, Shoring and Retention Systems

Site Information

The proposed development is located in Kingscliff and includes one Basement level (B1), Lower Ground Floor and Ground level. All the above floors are part suspended and part slab on grade and the verticals are supported by foundations starting at each of these levels.

Retention System and Basement Excavation



Based on the topography of the site earthworks should take account of the sloping terrain and be limited to cuts and fills. The option of temporary and permanent battered excavations is feasible but dependent on the excavation location in relation to the existing roads, boundary lines and other infrastructure. For Maximum safe batter angles for the different materials encountered on site are indicated in Table 7 of Geotechnical report.

It is expected that the clays and weathered basalt will not be self-supporting therefore retaining walls and permanent batters will to be utilised to avoid the potential issues with long term performance of waterproofing systems.

Where space constraints prevent the use of battered or benched excavations the use of temporary retention systems is likely to be required for excavations exceeding approximately 1.0m to 2.0m. The temporary lateral support will be designed prior to the commencement of excavation.

Refer to the Civil Infrastructure drawings (C-2 series) for the scope of works that is to be provided under that contract.

It is anticipated that due to the topography, the lower levels of the building are to be excavated into the northern slope of the site and the intent to utilise cut material as filling for building platforms.

All exposed permanent batters should have appropriate drainage and properly maintained vegetation to reduce the occurrence of surface erosion and scour by impingent rainfall. Upslope runoff should also be directed away from the batters limiting the ingress of water into the fill. The surface water should not be allowed to discharge directly across the batters and surface drains must be constructed and located behind the crests of all batters and benches.

Groundwater Control – During Construction

No significant groundwater issues are expected to be encountered in excavations under normal weather conditions in the slightly elevated cut areas of the site.

The bore log indicated that the groundwater was encountered in deep boreholes BH1, BH6, BH7, BH25, BH29, BH43 and BH45 to BH55 only at depths ranging between 6.5m and 14.9m below the existing ground surface. No groundwater was encountered in any of the shallow boreholes which extended to depths ranging up to 4.5m below the existing ground surface. On this basis, it is likely that groundwater would only be encountered below a level of approximately RL14.0m within the footprint of the proposed hospital building.

The Geotech report indicates that the seepages may be encountered at the natural soil/weathered rock interface, especially following rainfall events. The presence and depth to groundwater is dependent on rainfall, subsurface material and permeability, integrity of in-ground services, and the proximity to, type and density of vegetation.

For Groundwater Depths and Levels refer table 3 of Geotechnical report by Morrisons Geotechnic.

4.2 Foundations

Generally, the subsurface conditions comprised 3 different strata. The upper layer between 0.8m and 3.6m is formed of silty clays. This overlies a layer of material which is highly variable and comprises bands of low strength basalt, high to very high strength basalt and clays. Below this variable layer very high strength fresh basalt was encountered as per the bore logs. Having studied the option of providing both Raft and Pile foundation. It is noted that there is a lot of cut into the rock which could potentially increase construction time and will influence final construction methodology.

Based on section 14, Cl. 14.2 of Morrisons report indicates preference for deep foundations and suggest that dimensions for shallow foundations must be increased (doubled) to deal with inconsistent rock strength. Bored piles or CFA grout injected piles founding in the basalt rock is found to be suitable for reducing the differential settlement.



Issue: 3 - SSD2

Though the option of using pile foundation is suited, owing to the varying geology and significant difference in the strength of the material below the founding level possibility of using combination of piles and pad footings is considered.

Based on the borehole log and the ground profile, possibility of using pad footings at locations where Very High, High, Medium strength rock are encountered is considered and, in few cases, at locations where Low and medium strength rock are found refer Appendix D for details

It is observed that there are areas where corridors similar to the one connecting the lift core at level B1 are present, these areas present difficulty in getting the piling rig to the required location. Considering pad footings are these areas may be beneficial.

Due to varying Geology where interbedded layers of Extreme (EX), Distinctly (DW) and Slightly (SW) weathered rock is found, using date related to Medium strength rock will be considered. At locations where layers of the low and medium strength rock are encountered, Low strength rock sub grade modules will be considered.

Typically for Medium strength rock is found to have bearing capacities or 1250kPa and sub grade modules of 200kPa/mm; For low strength rock the bearing capacity of 500 kPa and subgrade modulus of 100kpa/mm may be considered based on Table 10, Section 14 of Geotechnical report.

Where the footings for the proposed structures found in different materials, consideration should be given to designing the structure to accommodate the possible differential settlements. The geotechnical report further specifies that when adopting the parameters for the encountered materials shown in the Tables 10 above, there must be a minimum 2B (where B is width of footing) of the design foundation material present below the design foundation level for the footings.

Preliminary piling layout and a combination of pile and pad footing layout at each level along with concept sizing of piles and pad foundations may be found in Appendix D.

4.3 Vertical Support and Structural Grids

Vertical support of the floor slabs is provided by a series of concrete columns, with reinforced concrete walls forming selected lift and stair cores, and major services risers.

The column grid has been selected to -

- · maximise floor slab spans
- integrate with the modular room layout of the hospital wards
- minimises the total number of columns required, giving maximum flexibility to the floor plate design for potential future "churn" or adaptive re-use

4.4 Floor Systems

Basement Level

The foundation at Basement level is pile foundations. The slab at these levels will be a reinforced concrete slab-on-grade.

Lower Ground Level

The suspended floor slab will be a post-tensioned concrete flat slab system (no drop caps), supported by concrete columns and walls.



Tweed Valley Hospital, NSW
Project No. 19005
Issue: 3 – SSD2
Project No. 19005
15th August 2019

Slab thicknesses will remain generally consistent across the floor plate with local heavier zones in some end spans. However, reinforcement & post-tensioning will vary depending on the usage of the slab area.

The foundation in the remaining area is to be pile footings with a reinforced slab-on-grade.

Levels 1-6

The suspended floor slabs will be a post-tensioned concrete flat slab system (no drop caps), supported by concrete columns and walls.

Slab thicknesses will remain generally consistent across the floor plate with local heavier zones in some end spans. However, reinforcement & post-tensioning will vary depending on the usage of the slab area.

Level 6-7 - Plant Areas and Roof

The roof will comprise of a post-tensioned concrete slab system (no drop caps), supported by concrete columns and walls.

Slab thicknesses, reinforcement and post-tensioning will vary depending on the usage of the slab area.

4.5 Lateral Load-Resisting System

The lateral load-resisting system for the building consists of -

- reinforced concrete lift cores
- · reinforced concrete stair cores
- reinforced concrete shear walls

Where required, ground anchors or tension piles will be utilised to ensure the overall lateral stability of the structure, and adequate transfer of wind, earthquake and robustness loads into the supporting foundation material.

4.6 Steel structures

Steel structures including plant, selected platforms and enclosures, roofs, hospital street roof, etc.

- · Allow to coordinate the various sub-contractors and their details
- Steelwork details (eg cast in bolts, shear keys etc) with the concrete details
- Façade cast-in elements with the concrete details (eg, post-tensioning anchorages)

4.7 Other

- Precast Concrete Elements:
 - Specification is by Architect and Façade Engineer
 - Allow for coordination with cast-in / drilled in fixings
- Façade Elements:
 - Specification is by Architect and Façade Engineer
 - Allow for coordination with cast-in / drilled in fixings
- Balustrade Elements:
 - Specification is by Architect and Façade Engineer
 - Allow for coordination with cast-in / drilled in fixings




Project No. 19005 15th August 2019

Appendix A

Structural drawings coordinated to 30-5-19 Architectural






BASEMENT 1 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1:350 SLAB TO BE 200 SOG UNO ALL CORE WALLS TO BE 250 THK UNO

NOTE:

ALLOW FOR 200 SOG TO BE POURED ON VAPOUR BARRIER OVER 80mm SAND BLINDED LAYER OF 20mm SINGLE SIZE GRANULAR FILL - IF ROCK STRATA NOT REACHED, THIS IS TO BE POURED OVER WELL COMPACTED ENGINEERED FILL.

> Rev Revision Description By App Date | Rev Revision Description Design Checker Client Scale at A1 Structural, Civil & Construction 1:350 K.PETROVSKI BASEMENT 1 - OVERALL S.HAWDON 01 ISSUED FOR INFORMATION KP SH 23.05.19 ingineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group R.RAMACHANDRA M.HARDING Feb 2019 Job Number Member of the Surbana Jurong Group 19005 RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE **NOT FOR CONSTRUCTION** Robert Bird Group Pty Ltd TWEED VALLEY HOSPITAL Fax: (02) 8246 3201 PO Box A2309 Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com RBG-ST-DWG-MHB-80B1000 REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000



REFER TO LOADING PLANS REFER TO VIBRATION PLANS


COLUMN SIZES : INTERNAL EXTERNAL			
COLUMNS	COLUMNS	COLUMNS	
BASEMENT TO U/S L02	600x600	500x500	
L02 TO U/S L05	500x500	400x400	
L05 TO ROOF	400x400	400x400	

CONCRETE NOTES: -REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

LOCATION	f'c
COLUMNS	
BASEMENT TO U/S L01	65
L01 TO U/S L04	50
L04 TO ROOF	40
RETAINING DINCEL WALLS	25

REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

LOCATION	RATE
CORE WALLS	ТВС
SHEAR WALLS	TBC
RETAINING WALLS	TBC
-BUILDING UNDER CROFT	TBC
-EXTERNAL	TBC
COLUMNS	TBC
SLAB	TBC
-REO	TBC
-PT	TBC



LOWER GROUND OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1:350 SLAB TO BE 200 SOG UNO ALL CORE WALLS TO BE 250 THK UNO

NOTE:

ALLOW FOR 200 SOG TO BE POURED ON VAPOUR BARRIER OVER 80mm SAND BLINDED LAYER OF 20mm SINGLE SIZE GRANULAR FILL - IF ROCK STRATA NOT REACHED, THIS IS TO BE POURED OVER WELL COMPACTED ENGINEERED FILL.

Rev Revision Description	By App Date Rev Revision Description	By App Date	SCALE 1 2 3 4 5 6 7 8 Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the Structural, Civil & Construction	Client	Title	Scale at A1	Drawn	Design Checker
01 ISSUED FOR INFORMATION	KP SH 23.05.19		accuracy, currency or completeness of any information or data they supply or transfer by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means		LOWER GROUND - OVERALL	1:350	K.PETROVSKI	S.HAWDON
			matches the information or data on the corresponding PDF or DWF version issued by Rig. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirectly suffer in connection with your access to or use of that information or data. RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for		GENERAL ARRANGEMENT PLAN	Pate Feb 2019	Designer R.RAMACHANDRA	Approved M.HARDING Job Number 19005
			any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE Robert Bird Group Pty Ltd Ph (02) 8246 3200 PO Box A2309 Fax: (02) 8246 3201		Project TWEED VALLEY HOSPITAL	NOT F	FOR CONSTRUCT	
			DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney South, NSW 1235 Level 11, 151 Castlereagh St Sydney NSW 2000 Email: sydney@robertbird.com.au Web: www.robertbird.com ACN 010 580 248			RBG-ST-DWG	-MHB-80LG000	Revision 01

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

TOP OF BATTER

COLUMNS

L05 TO ROOF

LOCATION

COLUMNS

BASEMENT TO U/S L01

RETAINING DINCEL WALLS

TMJ AND CJ LOCATIONS TBC

L01 TO U/S L04

L04 TO ROOF

LOCATION

HATCH DENOTES SLAB ON GROUND

ALL STEPS AND FALLS IN SLABS

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

COLUMNS COLUMNS

600x600

500x500

400x400

-REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

500x500

400x400

400x400

f'c


RATE

TBC

TBC

TBC TBC

TBC TBC TBC TBC TBC



GROUND OVERALL GENERAL ARRANGEMENT PLAN

SLAB TO BE 320 THICK UNO ALL CORE WALLS TO BE 250 THK UNO

NOTE:

ALLOW FOR 200 SOG TO BE POURED ON VAPOUR BARRIER OVER 80mm SAND BLINDED LAYER OF 20mm SINGLE SIZE GRANULAR FILL - IF ROCK STRATA NOT REACHED, THIS IS TO BE POURED OVER WELL COMPACTED ENGINEERED FILL.

Rev Revision Description	By App Date	Rev Revision Description	By App Date	SCALE 1 2 3 4 5 6 7 8 Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the	Structural, Civil & Construction
01 ISSUED FOR INFORMATION	KP SH 23.05.19			accuracy, currency or completeness of any information or data they supply or transfer by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means matches the information or data or the corresponding PDF or DWF version issued by RBG. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirectly suffer in connection with your access to or use of that information or data. RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document Unless	
				information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose.	Robert Bird Group Pty Ltd Ph (02) 8246 3200 PO Box A2309 Fax: (02) 8246 3201
				DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE	Sydney South, NSW 1235 Email: sydney@robertbird.com.au Level 11, 151 Castlereagh St Sydney NSW 2000 Email: sydney@robertbird.com Web: www.robertbird.com ACN 010 580 248



GROUND LEVEL - OVERALL GENERAL ARRANGEMENT PLAN

TWEED VALLEY HOSPITAL

Scale at A1 1:350 Feb 2019

Design Checker S.HAWDON R.RAMACHANDRA M.HARDING Job Number 19005

NOT FOR CONSTRUCTION Drawing Number

K.PETROVSKI

GENERAL ARRANGEMENT LEGEND:

DENOTES DINCEL WALL OVER

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

— TOP OF BATTER

DESIGN LOADS: REFER TO LOADING PLANS REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS

L02 TO U/S L05

L05 TO ROOF

CONCRETE NOTES:

BASEMENT TO U/S L01

RETAINING DINCEL WALLS

REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

L01 TO U/S L04 L04 TO ROOF

LOCATION

CORE WALLS SHEAR WALLS

-EXTERNAL

COLUMNS

SLAB -REO

NOTES:

RETAINING WALLS

-BUILDING UNDER CROFT

LOCATION

COLUMNS

-REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

BASEMENT TO U/S L02 600x600

NOTE: REFER ARCHITECTS DRAWINGS FOR

ALL STEPS AND FALLS IN SLABS

TOE OF BATTER

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

f'c

40

RATE

TBC TBC

TBC

TBC

TBC

TBC

TBC TBC TBC

1. SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY.
TMJ AND CJ LOCATIONS TBC

COLUMNS

500x500

400x400


400x400

COLUMNS

500x500

400x400

| RBG-ST-DWG-MHB-8000000



LEVEL 01 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1 : 350

SLAB TO BE 320 THICK UNO

ALL CORE WALLS TO BE 250 THK UNO

Rev Revision Description By App Date | Rev Revision Description Design Checker Client Scale at A1 Structural, Civil & Construction LEVEL 01 - OVERALL 1:350 K.PETROVSKI S.HAWDON 01 ISSUED FOR INFORMATION KP SH 23.05.19 ngineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group Feb 2019 R.RAMACHANDRA M.HARDING Job Number Member of the Surbana Jurong Group 19005 RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE **NOT FOR CONSTRUCTION** Robert Bird Group Pty Ltd Ph (02) 8246 3200 TWEED VALLEY HOSPITAL Fax: (02) 8246 3201 PO Box A2309 **Drawing Number** Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com RBG-ST-DWG-MHB-8001000 REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000

GENERAL ARRANGEMENT LEGEND:

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER
AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES DINCEL WALL OVER

THK DENOTES SLAB THICKNESS

DENOTES PENETRATION

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON BLOCK WALLS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

DESIGN LOADS:REFER TO LOADING PLANS
REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS	INTERNAL COLUMNS	EXTERNAL COLUMNS
BASEMENT TO U/S L02	600x600	500x500
L02 TO U/S L05	500x500	400x400
L05 TO ROOF	400x400	400x400

CONCRETE NOTES: -REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

f'c
65
50
40
25


REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

REFER HOTES ON COVERS	
LOCATION	RATE
CORE WALLS	ТВС
SHEAR WALLS	TBC
RETAINING WALLS	TBC
-BUILDING UNDER CROFT	TBC
-EXTERNAL	TBC
COLUMNS	TBC
SLAB	TBC
-REO	TBC
-PT	TBC

NOTES:

 SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION ANALYSIS

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY. TMJ AND CJ LOCATIONS TBC



LEVEL 02 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1 : 350

SLAB TO BE 320 THICK UNO

ALL CORE WALLS TO BE 250 THK UNO

By App Date | Rev Revision Description Design Checker S.HAWDON Rev Revision Description Client Scale at A1 Structural, Civil & Construction **LEVEL 02 - OVERALL** 1:350 K.PETROVSKI 01 ISSUED FOR INFORMATION KP SH 23.05.19 ngineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group Feb 2019 R.RAMACHANDRA M.HARDING Job Number RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. Member of the Surbana Jurong Group 19005 SYDNEY OFFICE **NOT FOR CONSTRUCTION** Robert Bird Group Pty Ltd Ph (02) 8246 3200 TWEED VALLEY HOSPITAL PO Box A2309 Fax: (02) 8246 3201 Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com RBG-ST-DWG-MHB-8002000 REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000

GENERAL ARRANGEMENT LEGEND:

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

AND INSITU CONCRETE ELEMENT O

DENOTES DINCEL WALL UNDER

DENOTES DINCEL WALL OVER

THK DENOTES SLAB THICKNESS

DENOTES PENETRATION

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON BLOCK WALLS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

DESIGN LOADS:

REFER TO LOADING PLANS REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS	INTERNAL COLUMNS	EXTERNAL COLUMNS
BASEMENT TO U/S L02	600x600	500x500
L02 TO U/S L05	500x500	400x400
L05 TO ROOF	400x400	400x400

CONCRETE NOTES: -REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

LOCATION	f'c
COLUMNS	
BASEMENT TO U/S L01	65
L01 TO U/S L04	50
L04 TO ROOF	40
RETAINING DINCEL WALLS	25


REINFORCEMENT RATES:

-REFER NOTES ON COVER SHEET			
LOCATION	RATE		
CORE WALLS	TBC		
SHEAR WALLS	TBC		
RETAINING WALLS	TBC		
-BUILDING UNDER CROFT	TBC		
-EXTERNAL	TBC		
COLUMNS	TBC		
SLAB	TBC		
-REO	TBC		
-PT	TBC		

NOTES:

 SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION ANALYSIS

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY.
TMJ AND CJ LOCATIONS TBC



LEVEL 03 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1:350 SLAB TO BE 280 THCIK UNO ALL CORE WALLS TO BE 250 THK UNO

> Rev Revision Description By App Date | Rev Revision Description Design Checker Client Scale at A1 Structural, Civil & Construction **LEVEL 03 - OVERALL** 1:350 K.PETROVSKI S.HAWDON 01 ISSUED FOR INFORMATION KP SH 23.05.19 ngineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group R.RAMACHANDRA M.HARDING Feb 2019 Job Number Member of the Surbana Jurong Group 19005 RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE **NOT FOR CONSTRUCTION** Robert Bird Group Pty Ltd Ph (02) 8246 3200 TWEED VALLEY HOSPITAL PO Box A2309 Fax: (02) 8246 3201 Drawing Number Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com | RBG-ST-DWG-MHB-8003000 REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000

GENERAL ARRANGEMENT LEGEND:

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES DINCEL WALL OVER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON **BLOCK WALLS**

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

REFER TO LOADING PLANS

DESIGN LOADS:

REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS	INTERNAL COLUMNS	EXTERNAL COLUMNS
BASEMENT TO U/S L02	600x600	500x500
L02 TO U/S L05	500x500	400×400
L05 TO ROOF	400x400	400x400

CONCRETE NOTES: -REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

LOCATION	f'c
COLUMNS	
BASEMENT TO U/S L01	65
L01 TO U/S L04	50
L04 TO ROOF	40
RETAINING DINCEL WALLS	25


REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

KEI EK HOTES OH COVER SHEET	
LOCATION	RATE
CORE WALLS	200kg/m³
SHEAR WALLS	180kg/ ³
RETAINING WALLS	
-BUILDING UNDER CROFT	100kg/³
-EXTERNAL	150kg/m³
COLUMNS	?
SLAB	
-REO	50kg/m³
-PT	5.4kg/m²

NOTES:

1. SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION 2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY.

TMJ AND CJ LOCATIONS TBC



LEVEL 04 OVERALL GENERAL ARRANGEMENT PLAN
SCALE 1: 350
SLAB TO BE 280 THICK UNO
ALL CORE WALLS TO BE 250 THK UNO



GENERAL ARRANGEMENT LEGEND:

DENOTES DINCEL WALL OVER

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

DESIGN LOADS:REFER TO LOADING PLANS
REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS

BASEMENT TO U/S L02

L02 TO U/S L05

L05 TO ROOF

LOCATION

COLUMNS

L04 TO ROOF

LOCATION

CORE WALLS
SHEAR WALLS

-EXTERNAL

COLUMNS

SLAB -REO

NOTES:

RETAINING WALLS

-BUILDING UNDER CROFT

TMJ AND CJ LOCATIONS TBC

CONCRETE NOTES:

BASEMENT TO U/S L01 L01 TO U/S L04

RETAINING DINCEL WALLS

REINFORCEMENT RATES:

-REFER NOTES ON COVER SHEET

1. SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY.

-REFER NOTES ON COVER SHEET

-MIN CONC. STRENGTH AT 28 DAYS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

COLUMNS

500x500

400x400

400x400

f'c

50

40

RATE


TBC
TBC
TBC
TBC
TBC
TBC
TBC
TBC
TBC

COLUMNS

600x600

500x500

400x400



LEVEL 05 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1:350 SLAB TO BE 280 THICK UNO ALL CORE WALLS TO BE 250 THK UNO

> Rev Revision Description By App Date | Rev Revision Description Client Structural, Civil & Construction **LEVEL 05 - OVERALL** 01 ISSUED FOR INFORMATION KP SH 23.05.19 ngineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group Member of the Surbana Jurong Group RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE Robert Bird Group Pty Ltd Ph (02) 8246 3200 TWEED VALLEY HOSPITAL PO Box A2309 Fax: (02) 8246 3201 Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000

GENERAL ARRANGEMENT LEGEND:

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES DINCEL WALL OVER

DENOTES SLAB THICKNESS

DENOTES PENETRATION T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

BLOCK WALLS

DESIGN LOADS:

REFER TO LOADING PLANS REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS	INTERNAL COLUMNS	EXTERNAL COLUMNS
BASEMENT TO U/S L02	600x600	500x500
L02 TO U/S L05	500x500	400x400
L05 TO ROOF	400x400	400x400

CONCRETE NOTES: -REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

LOCATION	f'c
COLUMNS	
BASEMENT TO U/S L01	65
L01 TO U/S L04	50
L04 TO ROOF	40
RETAINING DINCEL WALLS	25
I	

REINFORCEMENT RATES:

LOCATION	RATE
CORE WALLS	TBC
SHEAR WALLS	TBC
RETAINING WALLS	TBC
-BUILDING UNDER CROFT	TBC
-EXTERNAL	TBC
COLUMNS	TBC
SLAB	TBC
-REO	TBC
-PT	TBC

NOTES:

Scale at A1

May 2019

1:350

SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION

Design Checker

S.HAWDON

Job Number

19005


K.PETROVSKI

NOT FOR CONSTRUCTION

| RBG-ST-DWG-MHB-8005000

R.RAMACHANDRA M.HARDING

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY. TMJ AND CJ LOCATIONS TBC



LEVEL 06 OVERALL GENERAL ARRANGEMENT PLAN SCALE 1:350 SLAB TO BE 280 THICK UNO

ALL CORE WALLS TO BE 250 THK UNO

Rev Revision Description By App Date | Rev Revision Description 01 ISSUED FOR INFORMATION KP SH 23.05.19 RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE



Sydney NSW 2000

LEVEL 06 - OVERALL GENERAL ARRANGEMENT PLAN

TWEED VALLEY HOSPITAL

Design Checker Scale at A1 1:350 K.PETROVSKI S.HAWDON Feb 2019 R.RAMACHANDRA M.HARDING Job Number

GENERAL ARRANGEMENT LEGEND:

DENOTES DINCEL WALL OVER

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

DESIGN LOADS: REFER TO LOADING PLANS REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS

BASEMENT TO U/S L02

L02 TO U/S L05

L05 TO ROOF

LOCATION

COLUMNS

CONCRETE NOTES:

BASEMENT TO U/S L01

RETAINING DINCEL WALLS

REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

L01 TO U/S L04

L04 TO ROOF

CORE WALLS

SHEAR WALLS

-EXTERNAL

COLUMNS

SLAB -REO

NOTES:

RETAINING WALLS

-BUILDING UNDER CROFT

1. SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY. TMJ AND CJ LOCATIONS TBC

-REFER NOTES ON COVER SHEET

-MIN CONC. STRENGTH AT 28 DAYS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

COLUMNS

500x500

400x400

400x400

f'c

200kg/m³

180kg/³

100kg/³

150kg/m³

50kg/m³ $5.4 kg/m^2$

COLUMNS


600x600

500x500

400x400

19005 **NOT FOR CONSTRUCTION**

| RBG-ST-DWG-MHB-8006000



LEVEL 07 OVERALL GENERAL ARRANGEMENT PLAN

SCALE 1:350 SLAB TO BE 280 UNO ALL CORE WALLS TO BE 250 THK UNO

> Rev Revision Description By App Date | Rev Revision Description 01 ISSUED FOR INFORMATION KP SH 23.05.19 RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE



Sydney NSW 2000

LEVEL 07 - OVERALL GENERAL ARRANGEMENT PLAN

TWEED VALLEY HOSPITAL

Scale at A1 1:350 Feb 2019

Design Checker K.PETROVSKI S.HAWDON R.RAMACHANDRA M.HARDING Job Number 19005

NOT FOR CONSTRUCTION

| RBG-ST-DWG-MHB-8007000

GENERAL ARRANGEMENT LEGEND:

DENOTES DINCEL WALL OVER

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

DESIGN LOADS: REFER TO LOADING PLANS REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS

BASEMENT TO U/S L02

L02 TO U/S L05

L05 TO ROOF

LOCATION

COLUMNS

SHEAR WALLS **RETAINING WALLS** -BUILDING UNDER CROFT

-EXTERNAL

COLUMNS SLAB

-REO -PT

CONCRETE NOTES:

BASEMENT TO U/S L01 L01 TO U/S L04 L04 TO ROOF

RETAINING DINCEL WALLS

REINFORCEMENT RATES: -REFER NOTES ON COVER SHEET

-REFER NOTES ON COVER SHEET -MIN CONC. STRENGTH AT 28 DAYS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

500x500

400x400

400x400

f'c

TBC

TBC TBC

TBC TBC TBC TBC

COLUMNS COLUMNS

600x600


500x500

400x400

NOTES:

1. SLAB THICKNESSES ARE PRELIMINARY AND SUBJECT TO REVIEW, CONSULTANT DESIGN AND VIBRATION

2. TEMPORARY MOVEMENT JOINTS SHOWN NDICATIVELY.
TMJ AND CJ LOCATIONS TBC



LEVEL 08 OVERALL GENERAL ARRANGEMENT PLAN
SCALE 1: 350
SLAB TO BE 250 THICK UNO

Rev Revision Description By App Date | Rev Revision Description Design Checker Client Scale at A1 Structural, Civil & Construction **LEVEL 08 - OVERALL** 1:350 K.PETROVSKI S.HAWDON 01 ISSUED FOR INFORMATION KP SH 23.05.19 ingineering Consultant GENERAL ARRANGEMENT PLAN Robert **Bird** Group R.RAMACHANDRA M.HARDING May 2019 Job Number Member of the Surbana Jurong Group 19005 RBG provides this information for the express purpose contemplated by the RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferrable, fully revocable licence to use the intellectual property rights for the express purpose. SYDNEY OFFICE **NOT FOR CONSTRUCTION** Robert Bird Group Pty Ltd Ph (02) 8246 3200 TWEED VALLEY HOSPITAL PO Box A2309 Fax: (02) 8246 3201 **Drawing Number** Sydney South, NSW 1235 Email: sydney@robertbird.com.au DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS Level 11, 151 Castlereagh St Web: www.robertbird.com | RBG-ST-DWG-MHB-8008000 REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE Sydney NSW 2000

GENERAL ARRANGEMENT LEGEND:

DENOTES DINCEL WALL OVER

DENOTES INSITU CONCRETE ELEMENT OVER

DENOTES LOAD BEARING ELEMENT UNDER

DENOTES LOAD BEARING ELEMENT UNDER AND INSITU CONCRETE ELEMENT OVER

DENOTES DINCEL WALL UNDER

DENOTES SLAB THICKNESS

DENOTES PENETRATION

BLOCK WALLS

DESIGN LOADS:REFER TO LOADING PLANS
REFER TO VIBRATION PLANS

COLUMN SIZES:

COLUMNS

BASEMENT TO U/S L02

L02 TO U/S L05

L05 TO ROOF

LOCATION

COLUMNS

LOCATION

CORE WALLS SHEAR WALLS RETAINING WALLS -BUILDING UNDER CROFT

-EXTERNAL

COLUMNS SLAB -REO

-PT

CONCRETE NOTES:

BASEMENT TO U/S L01 L01 TO U/S L04 L04 TO ROOF

RETAINING DINCEL WALLS

REINFORCEMENT RATES:
-REFER NOTES ON COVER SHEET

-REFER NOTES ON COVER SHEET
-MIN CONC. STRENGTH AT 28 DAYS

NOTE: REFER ARCHITECTS DRAWINGS FOR ALL STEPS AND FALLS IN SLABS

T.M.J. - DENOTES TEMPORARY MOVEMENT JOINT

HATCH DENOTES SLAB ON GROUND

HATCH DENOTES 200 THK BONDEK SLAB ON

INTERNAL EXTERNAL

COLUMNS COLUMNS

600x600

500x500

400x400

500x500

400x400

400x400

f'c

RATE

TBC

TBC

TBC TBC TBC

TBC



Sydney Office

Robert Bird Group Pty Ltd ABN 67 010 580 248 ACN 010 580 248

Level 11, 151 Castlereagh Street Sydney NSW 2000 PO Box A2309 Sydney South NSW 1235 Australia

> P: +61 (0) 2 8246 3200 F: +61 (0) 2 8246 3201