



# **Douglas Partners**

*Geotechnics | Environment | Groundwater*

Report on  
Geotechnical Investigation of C4 Site

Stage 2 - Midtown  
Herring Road, Macquarie Park

Prepared for  
Frasers Property Ivanhoe Pty Ltd

Project 86043.06  
August 2021

Integrated Practical Solutions



## Document History

### Document details

Project No.	86043.06	Document No.	R.003.Rev2
Document title	Report on Geotechnical Investigation of C4 Site Stage 2 - Midtown		
Site address	Herring Road, Macquarie Park		
Report prepared for	Frasers Property Ivanhoe Pty Ltd		
File name	86043.06.R.003.Rev2.C4.docx		



### Document status and review

Status	Prepared by	Reviewed by	Date issued
Revision 0	Sally Peacock	Bruce McPherson	25 May 2021
Revision 1	Sally Peacock	Bruce McPherson	18 June 2021
Revision 2	Sally Peacock	Bruce McPherson	4 August 2021

### Distribution of copies

Status	Electronic	Paper	Issued to
Revision 0	1	0	Chris Koukoutaris, Frasers Property Ivanhoe Pty Ltd
Revision 1	1	0	Chris Koukoutaris, Frasers Property Ivanhoe Pty Ltd
Revision 2	1	0	Chris Koukoutaris, Frasers Property Ivanhoe Pty Ltd

The undersigned, on behalf of Douglas Partners Pty Ltd, confirm that this document and all attached drawings, logs and test results have been checked and reviewed for errors, omissions and inaccuracies.

	Signature	Date
Author		4 August 2021
Reviewer		4 August 2021



Douglas Partners Pty Ltd  
 ABN 75 053 980 117  
[www.douglaspartners.com.au](http://www.douglaspartners.com.au)  
 96 Hermitage Road  
 West Ryde NSW 2114  
 PO Box 472  
 West Ryde NSW 1685  
 Phone (02) 9809 0666

## Table of Contents

	Page
1. Introduction.....	1
2. Proposed Development.....	1
3. Background .....	2
4. Site Description .....	2
5. Published Data .....	3
6. Field Work .....	4
6.1 Field Work Methods .....	4
6.2 Field Work Results .....	5
7. Comments .....	6
7.1 Geotechnical and Hydrogeological Model .....	6
7.1.1 Geotechnical Model .....	6
7.1.2 Hydrogeological Model .....	8
7.2 Excavation .....	9
7.2.1 Vibrations .....	10
7.2.2 Batters .....	10
7.2.3 Waste Classification .....	11
7.3 Shoring/Retaining Walls.....	11
7.3.1 General .....	11
7.3.2 Shoring Design.....	12
7.3.3 Anchor Design.....	13
7.3.4 Shoring Wall and Excavation Movement .....	13
7.4 Groundwater and Dewatering .....	14
7.4.1 Groundwater Inflows .....	14
7.4.2 Management of Groundwater Seepage .....	15
7.5 Foundations .....	17
7.6 Further Investigation and Assessment .....	20
8. References .....	20
9. Limitations .....	20
 Appendix A: About This Report	
Appendix B: Drawings	
Appendix C: Results of Field Work	
Appendix D: Summary of Groundwater Measurements	
Appendix E: Selected Results of Previous Field Work	

## **Report on Geotechnical Investigation of C4 Site**

### **Stage 2 - Midtown**

### **Herring Road, Macquarie Park**

---

## **1. Introduction**

This revised report presents the results of a geotechnical investigation, undertaken by Douglas Partners Pty Ltd (DP) for the C4 site at the proposed Midtown development (Stage 2) at Herring Road, Macquarie Park. Midtown is located at the former Ivanhoe Estate Social Housing precinct. The investigation was commissioned by Chris Koukoutaris of Frasers Property Ivanhoe Pty Ltd (Frasers) and was undertaken in accordance with the Consulting Services Agreement dated 26 April 2021 and a subsequent variation. Revision 2 has been issued due to the update of Figure 1, only.

The C4 investigation was undertaken in conjunction with geotechnical investigation for the C2 and C3 sites, which together comprise the Stage 2 area, although the detailed results of those investigations will be reported separately. This revised report has been prepared following the completion of supplementary groundwater wells and permeability testing at the C3 and C4 sites in May and June 2021, the relevant results of which have been incorporated into this report.

The investigation also follows previous geotechnical investigation of the greater Midtown site in 2017 and groundwater monitoring from 2017 to 2018. The geotechnical investigation report for the greater Midtown site was updated in 2018 following the completion of that stage of groundwater monitoring.

A high-rise residential development is proposed at the C4 site. The aim of the investigation was to assess the subsurface soil, rock and groundwater conditions at the site, in order to provide geotechnical comment relevant to the proposed development on:

- Excavation conditions, including excavatability, excavation stability, shoring and batters;
- Groundwater conditions; and
- Foundations.

The investigation included the drilling of fourteen (14) boreholes in or near the C3 basement area and the installation of selected groundwater monitoring standpipes (or 'wells'). The details of the field work are presented in this report, together with comments and recommendations on the items listed above.

## **2. Proposed Development**

The proposed C4 development is for two residential high-rise buildings with a shared basement. Three basement levels are proposed, with a larger Basement 1 footprint (with floor level at RL 43.7), reducing to a smaller footprint for the lower basement floors, with the Basement 3 floor level at RL 37.9.

The location of the C4 development site and the proposed basement footprints is shown in Drawing 401 in Appendix B.



### 3. Background

In September 2015 the Ivanhoe Estate was rezoned by the Department of Planning and Environment as part of the Macquarie University Station (Herring Road) Priority Precinct, to transform the area into a vibrant centre that benefits from the available transport infrastructure and the precinct's proximity to jobs, retail and education opportunities within the Macquarie Park corridor. The new community will be known as Midtown MacPark, or "Midtown".

Douglas Partners Pty Ltd undertook investigation for the greater Ivanhoe Estate (now Midtown) site, in 2017, and undertook groundwater monitoring at 6 bores from November 2017 to June 2018. The detailed results were reported in the following DP Reports:

- 86043.01.R.001.Rev1, Preliminary Geotechnical Investigation of Ivanhoe Estate, dated 30 July 2018, including several boreholes drilled in the general vicinity, but outside of the C3 site in 2017 and revised in 2018 with summary data relating to groundwater monitoring; and
- 86043.01.R.005.Rev0, Groundwater Monitoring, dated 30 July 2018.

Relevant results from those previous investigations have been referenced or included in the current report, with selected field work results reproduced in Appendix E.


Since that time, demolition of the previous residences has been completed and earthworks have commenced for the development of infrastructure, roads and public areas at Midtown. These works have necessarily destroyed several of the previous groundwater monitoring standpipes or wells. While attempts were made during the current field work to locate possible remaining standpipes (at Bores 10, 12 and 13) near Shrimpton's Creek, these bores appear to have been either destroyed or obscured by overgrowth or temporary construction measures such as fencing and sedimentation controls.

The investigation for the C4 site was undertaken in conjunction with investigations for the C2 and C3 sites, which together comprise the Stage 2 works. Reference is made in this report to the relevant results of those investigations, particularly with respect to standpipes and groundwater levels. The detailed results of those investigations, however, will be separately reported in the following DP Reports:

- 86043.06.R.001, Geotechnical Investigation of the C2 site; and
- 86043.06.R.002, Geotechnical Investigation of the C3 site.

### 4. Site Description

The greater Midtown site is in Macquarie Park near the corner of Epping Road and Herring Road, within the Ryde Local Government Area. The site occupies an area of approximately 8.2 hectares. The approximate location of the proposed C4 development, with respect to other Stage 2 sites and the greater Midtown area, is shown in Figure 1.



**Figure 1: Location of the Stage 2 development areas (red), relative to the greater Midtown site (provided by Client).**

Topographically, the Midtown site is located on a sideslope, with ground surface levels falling from approximately RL 71 near Herring Road, to approximately RL 41 at Shrimpton's Creek, at the south-eastern boundary.

Ground surface levels at the C4 development area typically fall from approximately RL 50 to RL 44, towards the east and south-east, though from RL 50 to RL 45 in the proposed basement footprint. Notably, a sedimentation basin has been constructed in the north-western, central part of the site (see also Figure 1), to support the Midtown earthworks higher up the slope. The fill embankments for the sedimentation basin were constructed up to approximately RL 48.0, with a base at RL 47 and weir at RL 47.9. Ground surface levels drop off steeply at Shrimpton's Creek, where the creek level is understood to be at approximately RL 41.

## 5. Published Data

Reference to the regional mapping indicates the following at the C4 site:

- The Sydney Soils Landscape Series Sheet indicates that the site is underlain by the residual Lucas Heights soil landscape. These soils typically comprise sandy clay and clayey sand soils developed from Mittagong Formation and Hawkesbury Sandstone;
- The Sydney Geology Series Sheet indicates that the site is underlain by Hawkesbury Sandstone, near the boundary with Ashfield Shale; and
- The site is in an area of no known risk of coastal Acid Sulfate soils and is outside of the Salinity Potential in Western Sydney mapping.

The results of past and present field work indicate that ground conditions are generally consistent with the mapping of residual soils over Hawkesbury Sandstone, though a layer of fill is generally present, overlying the residual soil, and alluvial soils are apparently present locally towards Shrimpton's Creek.

Reference to the WaterNSW data on registered boreholes indicates that groundwater bores in the vicinity of the Midtown site are relatively distant from the site but that the results are broadly consistent with the previous groundwater monitoring at the greater Midtown site.

## **6. Field Work**

### **6.1 Field Work Methods**

The field work for the current investigation of the C4 site comprised fourteen (14) deep, small-diameter boreholes (Bore 103 to 116, and 118), drilled with a truck-mounted (Explora) drilling rig under the supervision of a geotechnical engineer. Two of these boreholes (Bores 103 and 106) were drilled significantly upslope of the site, with standpipes installed for the purpose of groundwater measurement.

The boreholes were drilled using auger or rotary drilling methods to the bedrock surfaces, then continued by NMLC (50 mm diameter) diamond core drilling methods into the underlying bedrock. Sampling and identification of strata was undertaken from the cuttings returned by the auger blade, supplemented by disturbed sampling of soils by Standard Penetration Tests, and by logging of the retrieved rock core. Point load strength index tests were also undertaken on the recovered rock core at typical intervals of 1.0 m. The bores were generally taken to depths of between 12.9 m and 14.2 m, though bores higher up the slope, including those into which standpipes were installed, were drilled to depths of 13.8 m to 17.1 m.

Groundwater monitoring wells or standpipes were installed in six of the boreholes within the C4 site footprint (Bores 107, 109, 111, 113, 114 and 115); and two bores were located upslope of the site (Bores 103 and 106). Three further, 'cluster wells' (109A, 111A and 114A) were installed in separate boreholes within 1 m of the standpipes in Bores 109, 111 and 114, respectively. These wells are installed in near identical locations, but with different screen depths. All wells were installed by drilling or reaming of the boreholes with a PCD bit, with screen lengths within the bedrock backfilled with a gravel pack, then with a bentonite seal above the screened length. Where the original cored borehole was taken to greater depth, any cored length (in rock) below the standpipe screen was sealed by bentonite, prior to installation of the standpipe. Spoil (ie cuttings) was used to backfill the standpipe above the bentonite 'seal' to near ground surface level, and the standpipe was 'finished' at ground surface with a Gatic cover, concreted in place. The bentonite seal is intended to isolate surface water inflow and shallow 'perched' groundwater flows or aquifers from the screened length of the borehole, generally within the underlying bedrock.

Following the installation of the standpipes, they were purged by pumping to remove drilling fluid from the standpipe. Follow-up visits were undertaken to obtain a groundwater level at each standpipe (following stabilisation of the water levels after purging) and to perform a falling or rising head permeability test, except at Bore 103 where the standpipe was destroyed by site operations after purging, but prior to measurements being taken. Details of standpipe construction in the Stage 2 area are included in Table D2, in Appendix D.

Further details on the methods and procedures employed in the investigation are presented in the notes in Appendices A and C of this report.

Test locations and ground surface levels at test locations were determined relative to Australian Height Datum (AHD) by high precision differential GPS equipment, as per the 2017 test locations.

The locations of the bores and standpipes are shown in Drawing 401, in Appendix B, together with other (rock) cored boreholes drilled nearby during the current and previous investigations.

## 6.2 Field Work Results

The detailed results of the field work for the C4 site are given in Appendix C of this report, together with relevant notes on classification terms, symbols and abbreviations, and rock core photographs. The results of point load strength index ( $I_{s(50)}$ ) tests are included at the relevant depths on the borehole logs.

The results of the *current* field work may be broadly summarised as follows:

- **Fill** – variable fill, including concrete, gravelly sand, clayey sand and re-worked natural clay, of apparently variable compaction, and including very loose fill (see Bore 112) to depths of 0.4 m to 1.9 m; underlain by
- **Sandy Clay and Clayey Sand** – residual soil, typically firm to stiff and very stiff, to depths of 1.5 m to 2.8 m; underlain by
- **Sandstone** – variable, fractured, very low to medium strength, including extremely low strength and high strength bands, to depths of 1.2 m to 6 m; then fractured to slightly fractured, medium strength, with some low strength bands, with variable weathering to depths of 3.4 m to 6.2 m, (absent in some locations); becoming slightly fractured to unbroken, high strength with occasional medium and very high strength bands, variably weathered to depths of 8.1 m to 14.7 m, then fresh.

No groundwater was observed whilst augering at the borehole locations.

The results of the groundwater measurements from the current investigation are summarised together with previous groundwater measurements in the vicinity of the Stage 2 development area of the Midtown site, in Table D1, in Appendix D. The results generally show that deep groundwater levels fall from approximately RL 42 at the upper, north-western side of the C4 site, to approximately RL 41 towards the south and south-east, to Shrimpton's Creek, though with some local variation. The higher-level standpipes at 109A, 111A and 114A indicated higher standing water levels, suggesting that a 'stacked' groundwater level may be present following periods of heavy rainfall, with higher standing water levels in some shallow wells compared to wells with a deeper screen interval. This is supported by falls in standing water levels measured during subsequent readings, and the results of previous shallow standpipes in the Stage 2 area (Bores 10, 12, 13).

Rising or falling head permeability tests were undertaken at the intact standpipes in the C3 and C4 areas. The results of the permeability tests are summarised in Appendix C, together with the base calculations associated with the rising or falling head permeability calculations. The results at Bore 114A could not be readily assessed due to the standing water level and well geometry. Hydraulic conductivities of  $1.9 \times 10^{-6}$  m/s to  $7.7 \times 10^{-8}$  m/s were estimated from the testing within the C4 area, which is relatively consistent with the results obtained in the broader Stage 2 area. The values are considered

to be consistent with expected permeabilities in Hawkesbury Sandstone, slightly higher than typical values, but within the range of values previously observed by DP in similar materials

The results of the field work were generally consistent with the results of previous investigations, although higher groundwater levels were generally indicated by the current investigation in the upper parts of the C4 site, when compared to levels from previous investigations.

## 7. Comments

### 7.1 Geotechnical and Hydrogeological Model

#### 7.1.1 Geotechnical Model

An interpreted geological model has been developed for the C4 site, based on the results of both current and previous field work. The model is summarised in Table 1.

**Table 1: Simplified Geotechnical Model**

Unit	Summary	Typical Description
1	Fill	Variable fill, including gravelly sand and apparently re-worked natural clay soils, to typical depths of 0.5 m to 1.5 m, but likely to be deeper at sedimentation basin embankments and potentially in any areas of stockpiles, other recent earthworks or past services.
2a	Alluvial Soil	Soft to firm, sandy clay, identified at Bore 10 only, to a depth of 2.1 m.
2b	Residual Soil	Firm to very stiff sandy clay and clayey sand, with trace iron-indurated bands, often grading to hard clay and dense clayey sand (extremely weathered sandstone), to depths of 0.2 m to 3.2 m at test locations, though absent at some locations.
3a	Sandstone – Variable	Typically very low to low strength, but with extremely low (soil strength), medium and high strength, iron-cemented bands, highly weathered, typically fractured to highly fractured sandstone
3b	Sandstone – Low and Medium Strength	Typically medium strength, but low strength or with thick beds of low strength sandstone at some bores (see Bores 103, 106, 110), and some high strength bands (see Bore 116), highly to slightly weathered, fractured and slightly fractured sandstone.
3c	Sandstone – Medium and High Strength	Typically high strength, but with some thick beds of medium or medium to high strength sandstone (see Bores 13, 110, 111), and some very high strength bands (see Bore 112), moderately weathered to fresh, slightly fractured to unbroken, with some fractured lengths. This unit is distinguished from Unit 3d by weathering.
3d	Sandstone – High Strength	Typically high strength with some very high strength bands (see Bore 103), fresh, slightly fractured to unbroken.



The above interpreted units are shown in relation to the C4 boreholes and site levels on the Interpreted Geotechnical Cross-Sections presented on Drawings 402 to 405, in Appendix B. It should be noted that the subsurface profile is accurate only at the borehole locations and that substantial variation can occur in between and away from the boreholes. The interpreted geotechnical boundaries are for illustrative purposes and should not be relied upon.

It is noted that while Unit 3b and 3c have similar summary descriptions to those used in the reports for the C2 and C3 sites, Unit 3b and 3c in the C4 site are typically of higher strength and often less fractured than those encountered upslope, at the C2 and C3 sites. This can be seen by contrasting the detailed descriptions and logs between these areas.

While not included in the above interpreted Cross-Sections, Bore 11 drilled east of (beyond) the proposed basement, encountered a significant band of lateritic sandstone in the upper 3.8 m (to RL 40.4), and some significant bands of core loss to 6 m depth (RL 37.2). These materials would generally be associated with high permeability. While these conditions have not been indicated by the other bores within the proposed C4 basement and may not affect the proposed excavation, such ground conditions would be significant to the works, if encountered. Accordingly, the logs and photographs for Bore 11 are included in Appendix E, for information.

Previous investigation by DP in the general vicinity of the site have also indicated the presence of dykes and thrust faults, which are considered likely to be encountered at the greater Midtown site, though investigations to date have not confirmed their presence. They are nonetheless considered a possible presence at the C4 area.

The following information also informs the geotechnical model for the site:

- **Dykes** – Dykes may be present on this site. Dykes have been identified by previous DP experience on sites to the north-east of the site and in the geological mapping north-west of the site. Both of these dykes may project to near the site, but given that dykes may “step” or “fork” in plan, they may potentially intersect the subject site.

Dykes in Sydney are typically near-vertical, planar features that may change in thickness, become discontinuous and/or step in plan. Common dyke widths in Sydney range from less than 1 m to approximately 6 m. They are typically completely weathered basalt or dolerite (clay) near surface and are usually weathered and weaker than the surrounding rock to significant depth. The rock adjacent to the dyke can also be highly fractured, variable or abnormally high strength due to the heat and pressure effects of the intrusion. Higher permeability and greater water seepage is also often observed within and on either side of the dyke material; and

- **Thrust Faults** – Thrust faulting, often associated with dykes, have been previously identified on nearby sites. A photograph showing the subsurface profile exposed by bulk excavation at a recently developed site to the north-west of the greater Midtown site, is included in Figure 2.



**Figure 2: Back thrusts in an excavation wall at a nearby site**

These features are of limited lateral extent and may be present but remain undetected by even significant geotechnical investigation. If encountered, the precise influence and treatment (if required) of dykes and thrust faults are often only determined at construction stage, when their presence, extent and orientation with respect to the works can be more reliably assessed.

### 7.1.2 Hydrogeological Model

The hydrogeology at the C4 site, in the depth of interest, can be characterised by the following:

- Ephemeral, 'perched' groundwater, or seepage, expected to occur within the upper fill and along the top of rock following periods of rainfall or due to human influences such as stormwater runoff and irrigation. Some ephemeral seepage may also migrate through defects within the rock;
- A transient, intermediate 'stacked' groundwater level, within the upper sandstone, as evidenced from the shallow cluster wells (Bores 109A, 111A, 114A), developing particularly after heavy rainfall and responsive to weather variations; and
- Long-term groundwater levels, at depth, within the deeper sandstone (Bores 106, 107, 109, 111, 113, 114, 115). These water levels are expected to respond to climatic and weather variations, which would be expected to be reflected by natural fluctuations in groundwater levels.

Within the bedrock, groundwater flows would be concentrated along defects within the rock such as joints and bedding planes. Iron-staining of the existing joints are suggestive of past groundwater passage, and greater water ingress would be expected through such joints.

The existing and previous standpipe monitoring wells were installed with bentonite seals to limit the influence of the 'perched' seepage through soil on the standpipe measurements. These measurements are therefore generally considered to reflect the groundwater levels within bedrock, and not ephemeral seepage and also to measure the water table at the screened depth.

Drawing 402 (Interpreted Geotechnical Cross-Section A-A') shows the difference in level between the recent intermediate groundwater levels obtained at wells 109A and 111A, and those from the deeper wells. Similarly, Drawing 404 (Interpreted Geotechnical Cross-Section C-C') towards Shrimpton's Creek shows the difference between the long-term groundwater levels at depth, groundwater levels measured

in 2017-2018 and during the recent (2021) field work. Screen depths for the wells are also shown in the relevant Cross-Sections. Both groundwater levels appear to fall towards Shrimpton's Creek.

The presence of the 'perched' intermediate groundwater table indicates a permeability contrast within the sandstone (ie a change to a lower permeability sandstone) with depth, likely due to a relatively thick bed of sandstone. Based on the screen levels for the intermediate levels, and deep groundwater tables, this change in permeability is likely to be near or slightly below the existing basement level.

Natural groundwater fluctuations in the order of 1.5 m to 3 m are suggested by comparison of previous water level monitoring at Bores 10, 12 and 13, and recent measurements in the standpipes of Bores 109A, 111A and 114A, for the intermediate groundwater level. Given that the previous 2017-2018 groundwater monitoring indicated no significant response to rainfall events, the prolonged wet weather that preceded the current field work and possibly higher levels at Shrimpton's Creek is likely to have been necessary to produce this increase in level.

## 7.2 Excavation

The proposed basement floor levels are at approximately RL 37.9 (Basement 3) or RL 43.7, for the larger area of Basement 1. Excavation of approximately 0.5 m below these levels is anticipated for bulk excavation levels, although this has not been confirmed.

Based on the existing information excavation of approximately 7.5 m to 12.5 m below existing ground surface levels is anticipated for the deeper basement (Basement 3) construction, reducing to approximately 3 m to 6.5 m within the extended Basement 1 footprint.

Reference to the results of the geotechnical investigation indicates that the excavation will extend through fill and natural soils (Units 1, 2a and 2b) and into sandstone bedrock. Within the sandstone, excavation is expected to proceed through variable strength (Unit 3a) rock, then through generally low and medium strength (Unit 3b) rock, into typically high strength sandstone, with some significant medium strength layers and some very high strength bands (Unit 3c). This may include excavation through significant beds of unbroken, high strength sandstone and very high strength bands within unbroken beds (see Bore 112).

Materials in Units 1, 2 and 3a are likely to be readily excavated using conventional earthmoving equipment (eg bulldozers and hydraulic excavators, with some rock hammering of stronger bands within the variable sandstone). The medium and high strength sandstone (Unit 3b, 3c and 3d) is likely to require excavation by ripping tynes mounted on large bulldozers (eg D12 or larger), large rock hammers, rock saws and milling heads. Productivity may be reduced by the relatively thick, often high strength beds and also by very high strength bands (eg Bore 112) within the depth of proposed excavation.

The excavatability of the medium and high strength (Unit 3b, 3c and 3d) bedrock will be governed by the defects within the rock mass. Based on the rock cores, the rock in this unit frequently includes bed spacings of more than 1 m. In general, the excavation of high strength sandstone, which is most of Unit 3c and 3d, is likely to be difficult and slow, with low productivity and high hammer/tyne wear expected.



### 7.2.1 Vibrations

Significant vibrations are anticipated during excavation within low to high strength (and very high strength) bedrock. Excavation methods may therefore be limited by acceptable vibration levels, particularly if the new services installed in the adjacent roads are sensitive to vibrations. At this stage, no buildings are within 50 m of the site, but depending on the staging of other site works, consideration may also need to be given to other structures, particularly if they are occupied at the time of the works. Acceptable vibration levels should therefore be confirmed with the asset owners prior to excavation.

The limit may need to be adjusted to reflect the asset requirements, response of neighbouring structures during excavation and vibration dosage once the neighbouring building is occupied.

A vibration trial may be required to size equipment at the commencement of excavation into rock. The trial may indicate that minimum offset distances are required from vibration-sensitive assets for the preferred plant, or that alternative excavation methods or equipment are required.

Where a vibration trial indicates that the equipment may potentially exceed vibration levels, or where buildings or occupants are otherwise sensitive to vibration levels, consideration could be given to continuous vibration monitoring during the works. These monitors may be set up to activate a flashing 'alarm' light, or send text messages, if pre-set vibration levels are exceeded during the work.

### 7.2.2 Batters

Batters or excavation support will be required for excavations through soil and extremely low to very low strength sandstone, and also for fractured low and medium strength rock (i.e. Units 1, 2a, 2b, 3a and 3b). While Unit 3b often includes medium strength rock, from a stability perspective the rock is still relatively fractured and includes more frequent steep joints.

Preliminary safe batter slopes are provided in Table 2, for batter slopes no greater than 3 m in height, with horizontal ground beyond the crest and below the toe, no deflection sensitive structures or services above the crest, no surcharges above the crest and no seepage from the face.

**Table 2: Preliminary Safe Batter Slopes for Batter Slopes  $\leq$  3 m Height**

Unit	Material	Maximum Temporary Safe Batter Slope (Horizontal:Vertical)
1	Fill	2:1
2a	Alluvial Soil (firm to stiff)	2:1
2b	Residual Soil (stiff to hard)	1.5:1
3a	Sandstone – Variable	1:1
3b	Sandstone – Low and Medium Strength	0.5:1
3c	Sandstone – Medium and High Strength	Vertical
3d	Sandstone – High Strength	Vertical

Batters higher than 3 m, steeper batters, batters in weaker materials, or batters subject to surcharges behind the crest (within an exclusion zone equal to the height of the batter, extending back from the crest), adjacent sloping ground or seepage would generally require more detailed geotechnical assessment. These conditions would require specific analysis.

All batter slopes should be subject to inspection by an experienced geotechnical professional at maximum 1.5 m drops. Flatter or steeper slopes may be required, depending on the results of assessment. Protection for the face of the batter slope may also be required to reduce the risk of loose materials falling into the excavation below.

Within the medium and high strength sandstone (Unit 3c and Unit 3d) the rock is likely to be able to be cut vertically and stand unsupported, even for cut depths greater than 3 m, but subject to regular defect and localised stability assessment by an experienced geotechnical professional, at drops no greater than 1.5 m. This may indicate that additional local support (eg bolts or anchors) and/or shotcrete is required due to adverse jointing or other defects.

### **7.2.3 Waste Classification**

All excavated materials will need to be disposed of in accordance with the provisions of the current legislation and guidelines including the Waste Classification Guidelines (EPA, 2014). This includes fill and natural materials that may be removed from the site.

## **7.3 Shoring/Retaining Walls**

### **7.3.1 General**

Shoring will be required where the rock strength or condition is unsuitable for vertical excavation, and conditions are unsuitable for batters (eg inadequate space). Shoring is therefore anticipated along all boundaries, except if and where acceptable batters may be formed in the adjacent (C3) site to the north-west. Shoring may still be required along part, or all, of the north-western boundary, depending on the adjoining ground and possibly groundwater levels.

From a stability perspective, soldier pile shoring walls are considered suitable for this site, with walls taken down through the Unit 1, 2, 3a and 3b material to socket in or bear on at least medium strength, slightly fractured sandstone (ie Unit 3c) with infill shotcrete panels constructed between the piles as excavation proceeds. Typical soldier pile spacings at 2 m to 2.5 m are likely to be suitable for the support of the natural clay soils and weathered rock above the groundwater table, but closer spacings are likely to be required where these materials extend below the groundwater table, particularly where the wall is required to manage groundwater inflows (refer Section 7.4).

Bored, concrete piles would generally be suitable for the construction of shoring piles at this site, although casing may be required for drilling through fill and possibly soil materials, to prevent side wall material falling into the (open) pile excavation, and tremie methods may be required for the placement of concrete. Continuous flight auger (CFA) piles may be required locally near the eastern corner of the site where deeper, weathered and fractured rock (Unit 3a) is present below the groundwater table.

A heavy-duty, high torque drilling rig is likely to be required to obtain significant socket (i.e. embedment) into medium and high strength sandstone, as is expected at this site, particularly given the medium and high strength sandstone present in the Unit 3b material.

Given the depth of excavation, anchors would generally be required to provide temporary lateral support to the shoring wall, with final support provided by the basement structure.

Inspections are recommended during the pile excavation to allow for geotechnical assessment of the foundation material, deepening of the piles where necessary, and advance notice of areas where poorer ground conditions are present. Inspections of the exposed rock face between soldier piles during excavation is also recommended at 1.5 m drops, prior to placement of mesh and shotcrete, to allow assessment of possible steep joints or defects which might require additional support.

If encountered, the presence of dykes or thrust faulting may result in locally poorer rock conditions, which may lead to additional support being required in some areas of the site. Detailed investigation and/or careful monitoring and inspection of ground conditions during excavation (including for soldier piles) would generally be appropriate to ensure that support is taken down to an appropriate depth in any affected areas. It is not likely to be practical to assess the presence of dykes in advance, unless a dyke location and orientation is determined during an earlier stage of works at the site.

The Unit 3a material is expected to be of relatively high permeability, and it is likely that a relatively impermeable shoring wall construction would be required in areas where Unit 3a is present in the excavation face below the groundwater table (particularly expected towards the eastern corner, see Bores 111, 110, 109), at least through the upper, Unit 3a materials. The upper levels of the shoring structure may also need to be designed to consider possible flooding of Shrimpton's Creek in the long-term.

Where the shoring walls are required to also serve as watertight walls to prevent or reduce groundwater inflows, then a secant pile wall type could possibly be adopted through the relevant Unit 1, 2a, 2b and 3a materials, socketed into Unit 3b, with selected 'hard' piles extended through the underlying Unit 3b materials, to found in the Unit 3c sandstone. A secant pile wall consists of overlapping primary and secondary piles, where the primary piles are a 'soft' mix of cement and bentonite, while the secondary piles are conventional reinforced concrete piles, installed to intersect the primary piles. Primary piles are typically installed at approximately 1.5D centres (where D = pile diameter). The secondary piles are installed before the primary piles have achieved strength, forming a relatively watertight construction. Groundwater is further discussed in Section 7.4.

### 7.3.2 Shoring Design

For a shoring wall supported by multiple rows of anchors or props, preliminary design may be based on a uniform rectangular earth pressure distribution of  $4H$  (where  $H$  is the wall height in metres, and pressure is in kPa), provided that deflections are not a concern. Where walls are constructed close to existing deflection-sensitive structures or utilities, a pressure of between  $6H$  and  $8H$  should be considered, depending on the sensitivity of the utilities and the soil profile to be retained. Higher pressures would be appropriate where batters (ie sloping ground) are present above the wall, or where concentrated loads are proposed behind the wall, either during construction (eg plant) or in the permanent case (eg elevated garden beds or roads).

The detailed design of shoring/retaining walls is nowadays normally undertaken using software that can account for the soil-structure interaction during the progressive excavation and support installation sequence (eg Wallap, Flac, Plaxis.)

Allowance should be made for the provision of drainage behind retaining structures, or alternatively the walls should be designed for full hydrostatic pressures. Appropriate drainage (eg strip or core drains) should be included to prevent hydrostatic water levels rising above the design hydrostatic level of the shoring/retaining wall/cut-off wall design.

For piled wall systems terminating above the bulk excavation level it may be necessary, depending on the design of wall restraint, to install 'toe bolts' or anchors at the base of each pile for stability purposes.

### 7.3.3 Anchor Design

The preliminary design of anchors may be based on the bond strengths indicated in Table 3.

**Table 3: Parameters for Preliminary Anchor Design**

Material	Ultimate Bond Strength
Variable sandstone (Unit 3a)	100 kPa
Low and medium strength sandstone (Unit 3b)	300 kPa
Medium and High strength Sandstone (Unit 3c)	1000 kPa

The above values assume that the anchor holes are adequately cleaned and free of clay smear. It would be appropriate for these values to be confirmed by the anchoring contractor based on their specific installation methods and experience, and for the rock conditions encountered during anchor installation at the site. Pull-out tests may be appropriate if higher bond values are to be adopted.

After installation, all temporary anchors should be proof loaded to 125% of the nominal working load, then locked off at 70% of the working load. For anchors supporting any structures on the boundaries, lock off values should be 90% of the working load. Checks should also be made at regular intervals to ensure that load is maintained in anchors and not lost due to creep effects.

While it is expected that the adjacent sites will be under the control of the developer at the time of construction, appropriate permissions from adjacent landowners would be required if support measures (eg anchors) are proposed across site boundaries. Anchors should also be de-stressed following the provision of permanent lateral support by the basement structure.

### 7.3.4 Shoring Wall and Excavation Movement

Typical horizontal movements in the order of 0.15% of the wall height would be expected for a well-constructed and designed, high stiffness shoring wall (ie with multiple rows of anchors), but depending on the excavation and support sequence and support provided. For a 6 m high shoring wall, this corresponds to approximately 10 mm movement.

In addition to retaining wall movements, basement excavations into medium and high strength sandstone bedrock may result in lateral movement of the sandstone faces due to stress relief effects.

Release of these stresses may cause horizontal movements along the rock bedding surfaces and defects, with estimated movements of between 0.5 mm and 2 mm per metre depth of excavation into medium and high strength sandstone, at the midpoint of the excavation. It is not practical to provide restraint against stress-relief movements, and appropriate allowance should instead be made for such movements in construction and planning.


Survey monitoring of the excavation and retaining walls would generally be appropriate to assess movement of any shoring walls during excavation, particularly where any deflection-sensitive structures or services are present behind the walls.

## **7.4 Groundwater and Dewatering**

### **7.4.1 Groundwater Inflows**

As can be seen from Drawings 402 to 405 in Appendix B, the proposed basement floor levels are below the measured groundwater levels, within bedrock, though close to the top of bedrock in the eastern corner of the site (see Bores 109, 110, 111). Groundwater inflow or seepage is therefore expected to occur through defects within the rock (eg bedding planes and joints). Inflow is expected to be greater in sandstone where fracturing is more closely spaced, or where existing iron-staining is present, suggesting past groundwater flows. Groundwater flow into the excavation through Units 3a, 3b and 3c are expected.

The results of permeability testing indicated hydraulic conductivities off  $1.9 \times 10^{-6}$  m/s to  $1.3 \times 10^{-7}$  m/s in the C4 area, though noting that higher variability in permeabilities can be seen from broader testing in the Stage 2 area. These permeabilities are broadly consistent with expected permeabilities in Hawkesbury Sandstone, though they are relatively high compared to typical values. The permeabilities are nonetheless within previous DP experience in similar ground conditions. The test results did not indicate a strong correlation between hydraulic conductivity and the units of the geotechnical model, as can be seen in Figure 3, although the variability in hydraulic conductivity does appear to reduce in the Unit 3D materials.



**Figure 3: Summary of results of Hydraulic Conductivity (k) for Stage 2 area permeability tests, with respect to the Geotechnical Model Units 3A, 3C and 3D**

In considering these results, it is noted that the gravel pack (and screened length) interval was often located at depths where the rock core indicated higher fracture spacings, in order to capture data from expected higher permeability zones.

Estimates of medium to long-term groundwater inflow to a drained C4 basement excavation have been separately analysed by Seep/W, and reported in DP Memo 86043.06.R.005, dated 18 June 2021. This analysis suggested likely groundwater inflows to the proposed basement excavation of around 3 to 4 ML/year. Higher inflows would be expected immediately following initial excavation, as stored water is lost to the excavation and groundwater levels around the basement stabilise, with inflow levels expected to stabilise to long-term typical inflows in approximately one year after excavation. Fluctuations in groundwater inflow will still occur following periods of rainfall.

While not identified by the current investigation, dykes or thrust faults may be associated with significantly increased permeabilities, relative to those considered in the inflow estimates, if encountered during excavation. While initial inflows from the defects would be significantly higher, their medium and long-term influence on inflows will depend on their continuity and connectivity to defects within and beyond the site.

## 7.4.2 Management of Groundwater Seepage

Based on the above inflow estimates, it is considered that a tanked basement would be a prudent approach to design of the basement at the C4 site, given the estimated inflows and the risks associated with potential unexpected groundwater inflows so close to a recharge area (ie Shrimpton's Creek).

During excavation, groundwater inflows will still need to be managed to a reasonable level, which is likely to require 'cut-off' walls through the more variable Unit 3a materials. Grouting may also be required to manage excess inflows through defects within the bedrock.

As discussed in the following section, however, current government regulations should be considered as well as the long-term costs of maintaining such a drainage/pumping system and any levies or costs associated with groundwater treatment (if required) and disposal.

A Water Access Licence is likely to be required, at least during construction, based on the inflow estimates of more than 3 ML/year. Exemptions should generally apply if inflows of less than 3 ML/year occur.

Ultimately, options for management of groundwater inflows include:

- A tanked basement may be a more sustainable solution and reduce or remove the risks associated with obtaining licenses, and ongoing management and maintenance of a drained basement. A Water Access Licence would still be required during the excavation stage; and
- Alternatively, design and construction of a drained basement, provided that the groundwater take is approved and properly accounted for under a Water Access Licence. This would involve an ongoing commitment to the costs associated with obtaining and maintaining the Water Access Licence, potentially for the life of the building, and would be subject to licensing and approval. Obtaining the necessary entitlements is a separate process to DA, and early discussions with the Natural Resources Access Regulator (NRAR) would be key to confirm that the license and entitlements (and therefore a drained basement) are achievable. This option would allow groundwater inflows to revert to an exemption in the long term, if groundwater inflows can be managed to less than 3 ML/year, though this may not be practical or economical, depending on conditions during excavation.

It is noted that a tanked basement may potentially be a requirement of the regulator at the C4 site, given the relatively high predicted inflows and proximity to Shrimpton's Creek.

The selection of an appropriate strategy for basement design should include consideration of the regulatory risks (ie whether or not the necessary approvals and licenses can be obtained, or conditions of consent become too onerous), construction stage risks (eg excessive costs or delays due to grouting and groundwater management, and dewatering or design changes), long-term risks (eg cost of ongoing groundwater management/licenses), and geotechnical risks (eg presence of a high-permeability defect at the base of the excavation), as well as the known costs of design and construction.

Prior to excavation, it is expected that a watertight wall will need to be installed to prevent or limit inflows into the excavation through the more variable (and higher permeability) Unit 3a sandstone. This may require secant pile or closely spaced piles, with gaps progressively infilled, through the upper, 3a materials and socketed into the underlying 3b or 3c sandstone, noting that piles to be used for shoring should be taken down to bear in at least Unit 3c sandstone, where closely spaced piles are used, the infill of any gaps between piles may be challenging if high inflows occur, and backfill and grouting treatment may be required.

Targeted grouting (eg by microfine grout) may be useful to reduce inflows through discrete fractures within the rock, and can be used between piles in the upper 3a materials, or in fractures in the sandstone. These methods can be slow and expensive, particularly given the size of the C4 basement, but may be



necessary to manage and reduce inflows through defects within otherwise medium and high strength rock.

The construction of a tanked basement would involve the construction of a waterproof basement floor and walls, to prevent groundwater inflows into the basement. Given that groundwater fluctuations in the order of 3 m have been observed, it is recommended that allowance be made for potential deep groundwater level rises of a further 1.0 m above even transient measured values (ie tanked to RL 45.3). This should be raised to above the level of any potential flooding of Shrimpton's Creek, if higher. These considerations are expected to also cater for the anticipated groundwater level increase of less than 0.5 m anticipated on the upslope side of the basement due to the damming effect of the basement. This should be confirmed by groundwater modelling and analysis, based on the proposed tanking design, noting that excessive groundwater increases may require drainage around the outside of the tanked basement.

Seepage above the level of (partial) basement tanking may still occur due to higher, transient groundwater levels, particularly following periods of wet weather, and as such the basement design should allow for drainage of any groundwater seepage above the level of the tanked basement design, such as a series of relief drains at the design level of tanking. For a tanked design based on the above recommendations, such seepage is expected to be below the 3 ML/year threshold, but would still require monitoring and reporting of this seepage 'take'. Alternatively, the basement may be designed as fully tanked (i.e. waterproof walls to the ground surface), to effectively eliminate even short-term seepage into the basement. Any tanked (or partially tanked) basement design must also consider uplift forces that may arise.

Seepage is likely to be iron-rich and a precipitate (gelatinous 'sludge') may develop within drains over time, which could cause 'clogging' and blockage of drainage lines and pumps. Allowance should be made for future maintenance to clear such material from the drainage lines and from pump fixtures.

It is noted that, given the relatively low permeability of the sandstone, any dewatering activities are expected to only cause drawdown to a relatively short distance from the C4 basement, provided that no hydraulic connection (eg high permeability defect) is present, which may cause drawdown to greater distance. Given that the groundwater levels are within bedrock, dewatering activities are not expected to create any risk of ground surface settlement or have any influence on acid sulphate soils in the vicinity of the development.

## 7.5 Foundations

The excavation for the Basement 3 level of the C4 site will extend into Unit 3c and Unit 3d sandstone, typically high strength, possibly with medium strength bands. The excavation for the Basement 1 level, towards the south-western corner, will extend into Unit 3b and Unit 3c sandstone, apparently typically medium and high strength in that area, but near the boundary with 3a materials, with some significant bands of core loss, extremely low and very low strength rock.

Preliminary rock classification of the sandstone near foundation level has been undertaken based on Pells et al (1998), assuming a 1.0 m plan footing dimension. Table 4 summarises the rock classifications below RL 43, for bores near the extended footprint of Basement 1, while Table 5 summarises the results below RL 37.5, for bores in or immediately adjacent to the proposed Basement 3 footprint. These



classifications are for foundation performance only and accordingly the rock 'strength' has been downgraded due to defects.

**Table 4: Sandstone Foundation Classification at Bore Locations Below RL43 (Basement 1)**

Sandstone Class	RL at Bore				
	107	113	114	115	116
III/IV	43.0	43.0	43.0	43.0	43.0
II/III	39.0	43.0	42.8	43.0	42.3
I/II	39.0	43.0	40.7	40.3	40.3

Note: The classification is based on an interval of rock below the foundation level, with the interval dependent on the plan dimension of the footings. Defects at greater depth have not been considered, and classification may change with increased depth.

**Table 5: Sandstone Foundation Classification at Bore Locations Below RL37.5 (Basement 3)**

Sandstone Class	RL at Bore												
	104	105	107	108	109	110	111	112	113	114	115	116	118
III/IV	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5	37.5
II/III	37.5	36.1	37.5	37.2	37.2	37.5	37.5	36.2	37.1	36.7	36.3	37.5	-
I/II	37.5	35.1	37.5	36.3	36.8	37.1	35.8	36.2	37.1	36.7	36.3	37.5	-

Note: The classification is based on an interval of rock below the foundation level, with the interval dependent on the plan dimension of the footings. Defects at greater depth have not been considered, and classification may change with increased depth.

As can be observed in the above table, a range of allowable bearing pressures may be adopted, though higher classifications may be more difficult to achieve on site and so require additional excavation and/or re-design during the construction stage, depending on local conditions.

Maximum allowable and ultimate bearing pressures for the design of shallow footings founded on sandstone below bulk excavation level are provided in Table 6, together with typical values for Youngs Modulus for each defined rock classification. These values assume that the foundations are in a confined state, and lower values (generally 50% of those given in Table 6) would apply where foundations are above a line drawn up at 45 degrees from the corner of adjacent basement excavations, and provided that geotechnical assessment is undertaken to assess the presence of adversely oriented defects that may daylight in the C4 excavation.

Maximum allowable bearing pressures for the design of shallow foundations founded on sandstone below bulk excavation level are provided in Table 6.

**Table 6: Foundation Design Parameters**

<b>Sandstone Class</b>	<b>Allowable Bearing Pressure<sup>1,2</sup> (MPa)</b>	<b>Ultimate Bearing Pressure<sup>2,3</sup> (MPa)</b>	<b>Typical Youngs Modulus (MPa)</b>	<b>Minimum Additional Testing / Requirements<sup>4</sup></b>
III/IV	3.5	15	350	-
II/III	6	40	900	Spoon testing of 1/3 of footings
I/II	10	100	1500	Additional cored boreholes (e.g. after excavation to basement level), and spoon testing of 1/2 of footings

- Note: 1. Allowable pressures assume a confined state, and allowable settlements of less than 1% of the minimum footing plan dimension. Alternative, settlements can be estimated for the proposed load based on the typical Youngs Modulus.
2. All bearing pressures may be limited by defects, or lack of confinement, subject to inspection of the excavation and possible spoon testing, which may require the bearing pressure to be downgraded. Bearing pressures assume that the bedrock is in a confined state, and that no nearby current or future excavations are present below an imaginary 'influence' line drawn at 1H:1V down from the edge of the footing. Such excavations would require inspection to confirm that adverse jointing is not present, and reduced values may apply.
3. Ultimate values assume settlement of more than 5% to 10% of the minimum footing plan dimension.
4. Geotechnical inspection of all footing excavations is recommended to confirm that the material is consistent with the design requirements; the minimum testing is to provide additional information on defects to confirm that foundation performance is as expected. Additional or lesser testing may be warranted, subject to the results of initial foundation testing and depending on the design bearing pressures.

All foundations should be inspected by a geotechnical professional following excavation and cleaning, to confirm that the foundation material is consistent with the design requirements.

The higher bearing pressures given in Table 6 require the additional testing outlined in that table and may be associated with a higher risk of inspection 'failures'. This use of a 10 MPa design bearing pressure would require additional cored borehole investigation, which may indicate that the sandstone does not meet the requirements of Class I/II Sandstone.

Spoon testing should be carried out in at least one third of all footings that are designed for an allowable end bearing capacity of more than 3.5 MPa. Spoon testing involves drilling a 50 mm diameter hole below the base of the footing, to a depth of at least 1.5 times the footing width, with the hole left full of water for 24 hours prior to testing to check for the presence of weak/clay bands. If excessive weak seams are detected then the foundation capacity may need to be downgraded, or the footings taken deeper to reach suitable foundation material.

For shoring piles founded in Class 3c materials, but above bulk excavation level, the ultimate bearing capacity will be the unconfined strength of the underlying bedrock, but may be reduced by adverse defects, if present below the foundation. Given these risks, it is suggested that design be based on an ultimate bearing pressure of no greater than 3 MPa, and an 'allowable' bearing pressure of no greater than 1 MPa. The vertical component of any anchors should be considered in the total loads on the pile. The vertical bearing pressure should be reviewed during excavation, prior to vertical loading of the piles.

Should thrust faults or dykes be identified near foundation level then the foundation parameters given in Table 6 may not be achieved, and re-design may be required in the affected area to suit to the conditions encountered.

## 7.6 Further Investigation and Assessment

Additional investigation and/or assessment may be appropriate, depending on the detailed design and planning decisions for the proposed site, and to support a dewatering management plan, if required. Such works may include:

- Water quality tests to provide information on the chemical composition of groundwater at the site, to support groundwater licenses or disposal assessment;
- Repeat permeability tests at standpipe locations, to confirm the 'repeatability' of the current test data, particularly if a drained basement is proposed; and
- Additional investigation, to reduce the geotechnical risk of excessive inflows to the excavation. This may include inclined boreholes, to provide greater coverage of the site area, and reduce (though not eliminate) the risk of unexpected defects that may cause concentrated seepage inflows to the excavation, and/or 'pilot' excavation to observe inflows to a test pit or similar, excavated to bulk excavation level.

It is noted that data loggers have been installed in Bores 106 and 118A (and Bores 114 and 111A, downslope) to monitor groundwater levels. This monitoring is ongoing, and the results of the groundwater monitoring will be reported, separately.

## 8. References

Pells, P. J., Mostyn, G., & Walker, B. F. (1998). Foundations on Sandstone and Shale in the Sydney Region. *Australian Geomechanics, No 33 Part 3*, 17-29.

## 9. Limitations

Douglas Partners (DP) has prepared this report for this project at Midtown, Macquarie Park in accordance with the Consultancy Services Agreement dated 26 April 2021 and approved variations. This report is provided for the exclusive use of Frasers Property Ivanhoe Pty Ltd for this project only and for the purposes as described in the report. It should not be used by or relied upon for other projects or purposes on the same or other site or by a third party. Any party so relying upon this report beyond its exclusive use and purpose as stated above, and without the express written consent of DP, does so entirely at its own risk and without recourse to DP for any loss or damage. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions on the site only at the specific sampling and/or testing locations, and then only to the depths investigated and at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of human influences. Such changes may occur after DP's field testing has been completed.

DP's advice is based upon the conditions encountered during this investigation. The accuracy of the advice provided by DP in this report may be affected by undetected variations in ground conditions

across the site between and beyond the sampling and/or testing locations. The advice may also be limited by budget constraints imposed by others or by site accessibility.

The assessment of atypical safety hazards arising from this advice is restricted to the geotechnical components set out in this report and based on known project conditions and stated design advice and assumptions. While some recommendations for safe controls may be provided, detailed 'safety in design' assessment is outside the current scope of this report and requires additional project data and assessment.

This report must be read in conjunction with all of the attached and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion stated in this report.

This report, or sections from this report, should not be used as part of a specification for a project, without review and agreement by DP. This is because this report has been written as advice and opinion rather than instructions for construction.

The scope for work for this investigation/report did not include the assessment of surface or sub-surface materials or groundwater for contaminants, within or adjacent to the site. Should evidence of fill of unknown origin be noted in the report, and in particular the presence of building demolition materials, it should be recognised that there may be some risk that such fill may contain contaminants and hazardous building materials.

---

**Douglas Partners Pty Ltd**

---

## Appendix A

---

About This Report

# About this Report

# Douglas Partners



## Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

## Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

## Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

## Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

## Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

# *About this Report*

## **Site Anomalies**

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

## **Information for Contractual Purposes**

Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

## **Site Inspection**

The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.



---

## Appendix B

---

Drawings






Locality Plan

**LEGEND**


- ◆ Cored Bore Location (2021, C4 Site)
- ◆ Cored Bore Location (2021, Beyond C4 Site)
- ◆ Previous (2017) Cored Bore Location
- Standpipe Location (Current)
- Standpipe Location (Damaged or Missing)
- C4 Area Boundary
- Site Boundary
- Proposed Basement Footprint (Basement 1)
- Proposed Basement Footprint (Basement 3)

NOTE:  
1: Base image from MetroMap (Dated 15.04.2021)




CLIENT: Frasers Property Ivanhoe Pty Ltd	
OFFICE: Sydney	DRAWN BY: PSCH/MG
SCALE: 1:1000 @ A3	DATE: 11.06.2021


TITLE: **Test Location Plan - C4 Site**  
**Proposed Residential Development**  
**Midtown, Macquarie Park**




PROJECT No:	86043.06
DRAWING No:	401
REVISION:	1









- 1 - FILL  
2a - Alluvial Soil  
2b - Residual Soil  
3a - Sandstone (variable)  
3b - Sandstone (Low & Medium Strength)  
3c - Sandstone (Medium & High Strength)  
3d - Sandstone (High Strength)

LEGEND

	Core Loss		Sandstone coarse grained
	Clayey Sand		Sandstone fine grained
	Filling		Sandy Clay
	Sandstone		Silty Clay
	Topsoil		

NOTES:

1. Subsurface conditions are accurate at the borehole locations only.  
Variations in subsurface conditions may occur between borehole locations.  
Interpreted strata boundaries are approximate and should be used as a guide only.

2. Summary logs only and should be read in conjunction with detailed logs.

3. Horizontal and vertical scales are not equal.

4. Greyed out bore have not been included in the interpreted boundaries, but are near the section and included for comparison

ROCK STRENGTH	TESTS / OTHER
EL - Extremely Low	N - Standard penetration test value
VL - Very Low	- - - - - Interpreted geotechnical boundary
L - Low	▽ - Water level
M - Medium	- - - - - Interpreted deep water table (2021)
H - High	- - - - - Interpreted water table (2017-2018)
VH - Very High	- - - - - Interpreted intermediate water table (2021)
	- - - - - Standpipe Gravel Pack Length

0 8  
Horizontal Scale (metres)  
Vertical Exaggeration = 4.0




CLIENT: Frasers Property Ivanhoe Pty Ltd	
OFFICE: Sydney	DRAWN BY: CJ/MG
SCALE: 1:400 (H) 1:100 (V) @ A3	DATE: 11.06.2021

TITLE: **Interpreted Geotechnical Cross-Section C-C'**  
**Proposed Stage 2 Development - C4 Site**  
**Midtown, Maquarie Park**

PROJECT No:	86043.06
DRAWING No:	404
REVISION:	1





---

## Appendix C

---

Results of Field Work



### Sampling

Sampling is carried out during drilling or test pitting to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling provide information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing it to obtain a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

### Test Pits

Test pits are usually excavated with a backhoe or an excavator, allowing close examination of the in-situ soil if it is safe to enter into the pit. The depth of excavation is limited to about 3 m for a backhoe and up to 6 m for a large excavator. A potential disadvantage of this investigation method is the larger area of disturbance to the site.

### Large Diameter Augers

Boreholes can be drilled using a rotating plate or short spiral auger, generally 300 mm or larger in diameter commonly mounted on a standard piling rig. The cuttings are returned to the surface at intervals (generally not more than 0.5 m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube samples.

### Continuous Spiral Flight Augers

The borehole is advanced using 90-115 mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or in-situ testing. This is a relatively economical means of drilling in clays and sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are disturbed and may be mixed with soils from the sides of the hole. Information from the drilling (as distinct from specific sampling by SPTs or undisturbed samples) is of relatively low

reliability, due to the remoulding, possible mixing or softening of samples by groundwater.

### Non-core Rotary Drilling

The borehole is advanced using a rotary bit, with water or drilling mud being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from the rate of penetration. Where drilling mud is used this can mask the cuttings and reliable identification is only possible from separate sampling such as SPTs.

### Continuous Core Drilling

A continuous core sample can be obtained using a diamond tipped core barrel, usually with a 50 mm internal diameter. Provided full core recovery is achieved (which is not always possible in weak rocks and granular soils), this technique provides a very reliable method of investigation.

### Standard Penetration Tests

Standard penetration tests (SPT) are used as a means of estimating the density or strength of soils and also of obtaining a relatively undisturbed sample. The test procedure is described in Australian Standard 1289, Methods of Testing Soils for Engineering Purposes - Test 6.3.1.

The test is carried out in a borehole by driving a 50 mm diameter split sample tube under the impact of a 63 kg hammer with a free fall of 760 mm. It is normal for the tube to be driven in three successive 150 mm increments and the 'N' value is taken as the number of blows for the last 300 mm. In dense sands, very hard clays or weak rock, the full 450 mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150 mm of, say, 4, 6 and 7 as:  
4,6,7  
N=13
- In the case where the test is discontinued before the full penetration depth, say after 15 blows for the first 150 mm and 30 blows for the next 40 mm as:  
15, 30/40 mm

# *Sampling Methods*

The results of the SPT tests can be related empirically to the engineering properties of the soils.

## **Dynamic Cone Penetrometer Tests / Perth Sand Penetrometer Tests**

Dynamic penetrometer tests (DCP or PSP) are carried out by driving a steel rod into the ground using a standard weight of hammer falling a specified distance. As the rod penetrates the soil the number of blows required to penetrate each successive 150 mm depth are recorded. Normally there is a depth limitation of 1.2 m, but this may be extended in certain conditions by the use of extension rods. Two types of penetrometer are commonly used.

- Perth sand penetrometer - a 16 mm diameter flat ended rod is driven using a 9 kg hammer dropping 600 mm (AS 1289, Test 6.3.3). This test was developed for testing the density of sands and is mainly used in granular soils and filling.
- Cone penetrometer - a 16 mm diameter rod with a 20 mm diameter cone end is driven using a 9 kg hammer dropping 510 mm (AS 1289, Test 6.3.2). This test was developed initially for pavement subgrade investigations, and correlations of the test results with California Bearing Ratio have been published by various road authorities.





## Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are generally based on Australian Standard AS1726:2017, Geotechnical Site Investigations. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

## Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle size (mm)
Boulder	>200
Cobble	63 - 200
Gravel	2.36 - 63
Sand	0.075 - 2.36
Silt	0.002 - 0.075
Clay	<0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle size (mm)
Coarse gravel	19 - 63
Medium gravel	6.7 - 19
Fine gravel	2.36 - 6.7
Coarse sand	0.6 - 2.36
Medium sand	0.21 - 0.6
Fine sand	0.075 - 0.21

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

The proportions of secondary constituents of soils are described as follows:

In fine grained soils (>35% fines)

Term	Proportion of sand or gravel	Example
And	Specify	Clay (60%) and Sand (40%)
Adjective	>30%	Sandy Clay
With	15 - 30%	Clay with sand
Trace	0 - 15%	Clay with trace sand

In coarse grained soils (>65% coarse)

- with clays or silts

Term	Proportion of fines	Example
And	Specify	Sand (70%) and Clay (30%)
Adjective	>12%	Clayey Sand
With	5 - 12%	Sand with clay
Trace	0 - 5%	Sand with trace clay

In coarse grained soils (>65% coarse)

- with coarser fraction

Term	Proportion of coarser fraction	Example
And	Specify	Sand (60%) and Gravel (40%)
Adjective	>30%	Gravelly Sand
With	15 - 30%	Sand with gravel
Trace	0 - 15%	Sand with trace gravel

The presence of cobbles and boulders shall be specifically noted by beginning the description with 'Mix of Soil and Cobbles/Boulders' with the word order indicating the dominant first and the proportion of cobbles and boulders described together.

# Soil Descriptions

## Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained shear strength (kPa)
Very soft	VS	<12
Soft	S	12 - 25
Firm	F	25 - 50
Stiff	St	50 - 100
Very stiff	VSt	100 - 200
Hard	H	>200
Friable	Fr	-

## Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (PSP). The relative density terms are given below:

Relative Density	Abbreviation	Density Index (%)
Very loose	VL	<15
Loose	L	15-35
Medium dense	MD	35-65
Dense	D	65-85
Very dense	VD	>85

## Soil Origin

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Extremely weathered material – formed from in-situ weathering of geological formations. Has soil strength but retains the structure or fabric of the parent rock;
- Alluvial soil – deposited by streams and rivers;

- Estuarine soil – deposited in coastal estuaries;
- Marine soil – deposited in a marine environment;
- Lacustrine soil – deposited in freshwater lakes;
- Aeolian soil – carried and deposited by wind;
- Colluvial soil – soil and rock debris transported down slopes by gravity;
- Topsoil – mantle of surface soil, often with high levels of organic material.
- Fill – any material which has been moved by man.

## Moisture Condition – Coarse Grained Soils

For coarse grained soils the moisture condition should be described by appearance and feel using the following terms:

- Dry (D) Non-cohesive and free-running.
- Moist (M) Soil feels cool, darkened in colour.  
Soil tends to stick together.  
Sand forms weak ball but breaks easily.
- Wet (W) Soil feels cool, darkened in colour.  
Soil tends to stick together, free water forms when handling.

## Moisture Condition – Fine Grained Soils

For fine grained soils the assessment of moisture content is relative to their plastic limit or liquid limit, as follows:

- 'Moist, dry of plastic limit' or 'w < PL' (i.e. hard and friable or powdery).
- 'Moist, near plastic limit' or 'w ≈ PL' (i.e. soil can be moulded at moisture content approximately equal to the plastic limit).
- 'Moist, wet of plastic limit' or 'w > PL' (i.e. soils usually weakened and free water forms on the hands when handling).
- 'Wet' or 'w ≈ LL' (i.e. near the liquid limit).
- 'Wet' or 'w > LL' (i.e. wet of the liquid limit).



## Rock Strength

Rock strength is defined by the Unconfined Compressive Strength and it refers to the strength of the rock substance and not the strength of the overall rock mass, which may be considerably weaker due to defects.

The Point Load Strength Index  $Is_{(50)}$  is commonly used to provide an estimate of the rock strength and site specific correlations should be developed to allow UCS values to be determined. The point load strength test procedure is described by Australian Standard AS4133.4.1-2007. The terms used to describe rock strength are as follows:

Strength Term	Abbreviation	Unconfined Compressive Strength MPa	Point Load Index * $Is_{(50)}$ MPa
Very low	VL	0.6 - 2	0.03 - 0.1
Low	L	2 - 6	0.1 - 0.3
Medium	M	6 - 20	0.3 - 1.0
High	H	20 - 60	1 - 3
Very high	VH	60 - 200	3 - 10
Extremely high	EH	>200	>10

\* Assumes a ratio of 20:1 for UCS to  $Is_{(50)}$ . It should be noted that the UCS to  $Is_{(50)}$  ratio varies significantly for different rock types and specific ratios should be determined for each site.

## Degree of Weathering

The degree of weathering of rock is classified as follows:

Term	Abbreviation	Description
Residual Soil	RS	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are no longer visible, but the soil has not been significantly transported.
Extremely weathered	XW	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are still visible
Highly weathered	HW	The whole of the rock material is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable. Rock strength is significantly changed by weathering. Some primary minerals have weathered to clay minerals. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores.
Moderately weathered	MW	The whole of the rock material is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable, but shows little or no change of strength from fresh rock.
Slightly weathered	SW	Rock is partially discoloured with staining or bleaching along joints but shows little or no change of strength from fresh rock.
Fresh	FR	No signs of decomposition or staining.
<i>Note: If HW and MW cannot be differentiated use DW (see below)</i>		
Distinctly weathered	DW	Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching or may be decreased due to deposition of weathered products in pores.

# Rock Descriptions

## Degree of Fracturing

The following classification applies to the spacing of natural fractures in diamond drill cores. It includes bedding plane partings, joints and other defects, but excludes drilling breaks.

Term	Description
Fragmented	Fragments of <20 mm
Highly Fractured	Core lengths of 20-40 mm with occasional fragments
Fractured	Core lengths of 30-100 mm with occasional shorter and longer sections
Slightly Fractured	Core lengths of 300 mm or longer with occasional sections of 100-300 mm
Unbroken	Core contains very few fractures

## Rock Quality Designation

The quality of the cored rock can be measured using the Rock Quality Designation (RQD) index, defined as:

$$\text{RQD \%} = \frac{\text{cumulative length of 'sound' core sections} \geq 100 \text{ mm long}}{\text{total drilled length of section being assessed}}$$

where 'sound' rock is assessed to be rock of low strength or stronger. The RQD applies only to natural fractures. If the core is broken by drilling or handling (i.e. drilling breaks) then the broken pieces are fitted back together and are not included in the calculation of RQD.

## Stratification Spacing

For sedimentary rocks the following terms may be used to describe the spacing of bedding partings:

Term	Separation of Stratification Planes
Thinly laminated	< 6 mm
Laminated	6 mm to 20 mm
Very thinly bedded	20 mm to 60 mm
Thinly bedded	60 mm to 0.2 m
Medium bedded	0.2 m to 0.6 m
Thickly bedded	0.6 m to 2 m
Very thickly bedded	> 2 m

# Symbols & Abbreviations

## Douglas Partners



### Introduction

These notes summarise abbreviations commonly used on borehole logs and test pit reports.

### Drilling or Excavation Methods

C	Core drilling
R	Rotary drilling
SFA	Spiral flight augers
NMLC	Diamond core - 52 mm dia
NQ	Diamond core - 47 mm dia
HQ	Diamond core - 63 mm dia
PQ	Diamond core - 81 mm dia

### Water

▷	Water seep
▽	Water level

### Sampling and Testing

A	Auger sample
B	Bulk sample
D	Disturbed sample
E	Environmental sample
U <sub>50</sub>	Undisturbed tube sample (50mm)
W	Water sample
pp	Pocket penetrometer (kPa)
PID	Photo ionisation detector
PL	Point load strength Is(50) MPa
S	Standard Penetration Test
V	Shear vane (kPa)

### Description of Defects in Rock

The abbreviated descriptions of the defects should be in the following order: Depth, Type, Orientation, Coating, Shape, Roughness and Other. Drilling and handling breaks are not usually included on the logs.

### Defect Type

B	Bedding plane
Cs	Clay seam
Cv	Cleavage
Cz	Crushed zone
Ds	Decomposed seam
F	Fault
J	Joint
Lam	Lamination
Pt	Parting
Sz	Sheared Zone
V	Vein

### Orientation

The inclination of defects is always measured from the perpendicular to the core axis.

h	horizontal
v	vertical
sh	sub-horizontal
sv	sub-vertical

### Coating or Infilling Term

cln	clean
co	coating
he	healed
inf	infilled
stn	stained
ti	tight
vn	veneer

### Coating Descriptor

ca	calcite
cbs	carbonaceous
cly	clay
fe	iron oxide
mn	manganese
slt	silty

### Shape

cu	curved
ir	irregular
pl	planar
st	stepped
un	undulating

### Roughness

po	polished
ro	rough
sl	slickensided
sm	smooth
vr	very rough

### Other

fg	fragmented
bnd	band
qtz	quartz


# Symbols & Abbreviations

## Graphic Symbols for Soil and Rock

### General



Asphalt



Road base



Concrete



Filling

### Soils




Topsoil




Peat



Clay




Silty clay




Sandy clay




Gravelly clay



Shaly clay




Silt




Clayey silt




Sandy silt



Sand



Clayey sand



Silty sand



Gravel



Sandy gravel



Cobbles, boulders



Talus

### Sedimentary Rocks



Boulder conglomerate



Conglomerate




Conglomeratic sandstone




Sandstone



Siltstone




Laminite



Mudstone, claystone, shale




Coal




Limestone


### Metamorphic Rocks



Slate, phyllite, schist




Gneiss



Quartzite


### Igneous Rocks




Granite



Dolerite, basalt, andesite



Dacite, epidote



Tuff, breccia



Porphyry

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 52.4 AHD  
**EASTING:** 325617.7  
**NORTHING:** 6260365.1  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 103  
**PROJECT No:** 86043.06  
**DATE:** 28/4/2021  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
52.4	0.1	FILL/ Clayey SAND: fine to medium, brown, trace fine to medium sandstone gravel, moist  LEAN MIX CONCRETE																				
52.2	0.2																					
51.1	1.1	SANDSTONE: fine to medium grained, yellow-brown, very low strength, highly weathered, Hawkesbury Sandstone																				25/70 mm refusal
51.2	1.2																					PL(A) = 0.17
50.2	2.0	SANDSTONE: fine to medium grained, red-brown and pale grey, very low to medium strength with an extremely low strength band, highly weathered, fractured, Hawkesbury Sandstone																				PL(A) = 0.3
50.0	2.4																					PL(A) = 0.73
49.0	3.0	SANDSTONE: fine to medium grained, pale grey with some red-brown and orange-brown staining, low and medium strength, moderately weathered, fractured to slightly fractured, Hawkesbury Sandstone																				PL(A) = 0.36
48.0	4.0																					PL(A) = 0.53
47.0	5.0																					PL(A) = 0.4
46.0	6.0																					PL(A) = 0.53
45.0	7.0																					PL(A) = 1.9
44.0	8.0																					PL(A) = 0.39
43.0	9.0																					
		Below 9.4m: high strength																				

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.1m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.1m; NMLC-Coring to 17.1m; PCD to 11.0 m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 15.0m (screen 15.0-12.0m; blank 12.0-0.0m; gravel 15.0-11.5m; bentonite 11.5-11.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 52.4 AHD  
**EASTING:** 325617.7  
**NORTHING:** 6260365.1  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 103  
**PROJECT No:** 86043.06  
**DATE:** 28/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
42		SANDSTONE: medium to coarse grained, yellow-brown and pale grey, medium and high strength, moderately to slightly weathered, slightly fractured, Hawkesbury Sandstone <i>(continued)</i>																C	100	82	PL(A) = 1.6
11		Below 11.07m: slightly fractured to unbroken																			PL(A) = 1.2
41																					
12																					PL(A) = 1.6
40																		C	100	100	
13																					PL(A) = 1.5
39																					
14																					PL(A) = 2
38																					
14.88		SANDSTONE: medium to coarse grained, pale grey, strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone																C	100	99	PL(A) = 3.5
15																					PL(A) = 1.9
37																					
16																					
36																					PL(A) = 1
17																					
17.1		Bore discontinued at 17.1m Target depth reached																			
35																					
18																					
34																					
19																					
33																					

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.1m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.1m; NMLC-Coring to 17.1m; PCD to 11.0 m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 15.0m (screen 15.0-12.0m; blank 12.0-0.0m; gravel 15.0-11.5m; bentonite 11.5-11.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 103

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 103

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 103

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 103

PROJECT: MACQUARIE PARK

APRIL 2021



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 51.8 AHD  
**EASTING:** 325637.8  
**NORTHING:** 6260346.9  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 104  
**PROJECT No:** 86043.06  
**DATE:** 27/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	51 1	FILL/ Sandy CLAY: low to medium plasticity, brown, fine to medium sand, with fine to medium sandstone gravel, w<PL																A			3,3,6 N = 9 PL(A) = 0.06
	1.2	Sandy CLAY CL-CI: low to medium plasticity, yellow-brown, fine to medium sand, w<PL, stiff, residual																A			
	1.5	SANDSTONE: fine to medium grained, yellow-brown then pale grey and red-brown, very low to low strength with some medium strength bands, highly weathered, fractured, Hawkesbury Sandstone																S			
	2																	C	100	70	PL(A) = 0.08
	3																				PL(A) = 0.19
	4																	C	100	75	PL(A) = 0.23
	5																				PL(A) = 0.26
	5.41																				
	6	SANDSTONE: medium to coarse grained, orange brown and pale grey, high strength, slightly weathered, slightly fractured, Hawkesbury Sandstone																C	97	65	PL(A) = 1.1
	7																				PL(A) = 1.8
	8																				PL(A) = 1.1
	9																	C	100	100	PL(A) = 1.5
	10.0																				

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 16.25m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 51.8 AHD  
**EASTING:** 325637.8  
**NORTHING:** 6260346.9  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 104  
**PROJECT No:** 86043.06  
**DATE:** 27/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
	41	SANDSTONE: medium to coarse grained, orange brown and pale grey, high strength, slightly weathered, slightly fractured, Hawkesbury Sandstone (continued)																				PL(A) = 1.6
	11																10.74m: B5°, pl, ro, cln	C	100	100		PL(A) = 1.6
	40																11.41m: J30°, pl, ro, cly vn					
	12																11.71m: Cs 10mm	C	80	65		
	12.12	Between 12.12-14.70m: red brown, moderately weathered															11.79m: B0°, pl, ro, cly vn					PL(A) = 2.2
																	11.93m: CORE LOSS: 190mm					
	39																12.32m: B0°, pl, ro, fe stn					
	13																12.5m: J80°, pl, ro, fe stn					
	13.09																12.82m: B0°, pl, ro, cly vn					PL(A) = 1.6
																	12.87m: Cs 10mm	C	95	83		
																	12.9m: Ds 100mm					
	38																13m: CORE LOSS: 90mm					
	14																13.25m: B0°-5° (x2), pl, ro, fe stn					PL(A) = 2.9
	37																					
	15	SANDSTONE: medium to coarse grained, pale grey, high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone																				PL(A) = 1.7
	36																					
	16																					
	16.25	Bore discontinued at 16.25m Target depth reached																				PL(A) = 1.7
	35																					
	17																					
	34																					
	18																					
	33																					
	19																					
	32																					

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 16.25m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	SP	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 104

PROJECT: MACQUARIE PARK

APRIL 2021



1.50 – 6.00m

BORE: 104

PROJECT: MACQUARIE PARK

APRIL 2021



6.00 – 11.00m

BORE: 104

PROJECT: MACQUARIE PARK

APRIL 2021



11.00 – 16.00m

BORE: 104

PROJECT: MACQUARIE PARK

APRIL 2021



16.00 – 16.25m



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.9 AHD  
**EASTING:** 325665.6  
**NORTHING:** 6260360.3  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 105  
**PROJECT No:** 86043.06  
**DATE:** 24/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	0.8	FILL/ SAND: fine to medium, dark brown, with clay, moist																A			4.5,10 N = 15
	1	Sandy CLAY CI: medium plasticity, yellow-brown, fine to medium sand, w<PL, stiff, residual																A			
	2.1	Clayey SAND SC: fine to medium sand, pale grey and red-brown, moist, very dense, extremely weathered Hawkesbury Sandstone																A			
	2.7																	S			
	3	SANDSTONE: fine to medium, pale grey and red-brown, very low to medium strength, highly weathered, fractured, Hawkesbury Sandstone																C	100	75	PL(A) = 1.7
	4																				PL(A) = 0.38
	4.77	SANDSTONE: medium to coarse grained, orange-brown and pale grey, high strength, moderately to slightly weathered, slightly fractured, Hawkesbury Sandstone																C	98	90	PL(A) = 0.75
	6																				PL(A) = 1.4
	6.88																				PL(A) = 1.3
	8																	C	99	99	PL(A) = 1
	9																				PL(A) = 1
	10.0																	C	100	100	PL(A) = 2.1

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 2.5m, HQ to 2.7m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.7m; NMLC-Coring to 15.9m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering  
**REMARKS:** Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	> Water seep	S Standard penetration test	
E Environmental sample	≡ Water level	V Shear vane (kPa)	

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.9 AHD  
**EASTING:** 325665.6  
**NORTHING:** 6260360.3  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 105  
**PROJECT No:** 86043.06  
**DATE:** 24/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering						Graphic Log	Rock Strength						Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
			EW	HW	MW	SW	FS	FR		Ex Low	Very Low	Low	Medium	High	Very High			Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
39	11	SANDSTONE: medium to coarse grained, orange-brown and pale grey, high strength, moderately to slightly weathered, slightly fractured to unbroken, Hawkesbury Sandstone <i>(continued)</i>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							</

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.5m, HQ to 2.7m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.7m; NMLC-Coring to 15.9m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 105

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 105

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 105

PROJECT: MACQUARIE PARK

APRIL 2021



12.00 – 15.90m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.5 AHD  
**EASTING:** 325658.4  
**NORTHING:** 6260394.7  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 106  
**PROJECT No:** 86043.06  
**DATE:** 28/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
	0.3	FILL/ Sandy CLAY: low plasticity, brown, trace rootlets and fine to medium igneous gravel, w<PL  Sandy CLAY CL-CI: low to medium plasticity, yellow-brown, fine to medium sand, trace fine to medium sandstone gravel, w<PL, stiff, residual																A			3,6,17 N = 23	
49																		A				
1																		A				
48																		S				
1.5																						
2		SANDSTONE: fine to medium grained, pale grey and red-brown, very low to medium strength, highly weathered, fractured, Hawkesbury Sandstone																C	100	0	PL(A) = 0.09	
47																					PL(A) = 0.7	
3																						
3.4		SANDSTONE: fine to medium grained, pale grey, orange-brown and red-brown, low to medium strength, moderately weathered, slightly fractured																C	100	70	PL(A) = 0.16	
46																						
4																						
45																						
5																						
5.7		SANDSTONE: medium to coarse grained, red-brown, orange-brown and pale grey, high strength, slightly weathered to fresh, slightly fractured, Hawkesbury Sandstone																C	100	95	PL(A) = 2.6	
6																						
7																					PL(A) = 1.2	
42		Below 7.4m: moderately weathered band																				PL(A) = 1.1
8																						
41																		C	100	96	PL(A) = 1.5	
9																						
40																		C	100	98	PL(A) = 1.6	

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 1.0m, HQ to 1.5m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 13.8m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering  
**REMARKS:** Groundwater well installed to 11.0m (screen 11.0-8.0m; blank 8.0-0.0m; gravel 11.0-7.5m; bentonite 7.5-7.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	> Water seep	S Standard penetration test	
E Environmental sample	≡ Water level	V Shear vane (kPa)	



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.5 AHD  
**EASTING:** 325658.4  
**NORTHING:** 6260394.7  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 106  
**PROJECT No:** 86043.06  
**DATE:** 28/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
	39	SANDSTONE: medium to coarse grained, red-brown, orange-brown and pale grey, high strength, slightly weathered to fresh, slightly fractured, Hawkesbury Sandstone (continued)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 1.0m, HQ to 1.5m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 13.8m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering  
**REMARKS:** Groundwater well installed to 11.0m (screen 11.0-8.0m; blank 8.0-0.0m; gravel 11.0-7.5m; bentonite 7.5-7.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	>	Water seep
E	Environmental sample	≡	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

BORE: 106

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 106

PROJECT: MACQUARIE PARK

APRIL 2021





BORE: 106

PROJECT: MACQUARIE PARK

APRIL 2021



10.00 – 13.80m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.7 AHD  
**EASTING:** 325658.7  
**NORTHING:** 6260313.1  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 107  
**PROJECT No:** 86043.06  
**DATE:** 16/4/2021  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		Ex Low	Very Low	Low	Medium	High	Very High		B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	0.7	FILL/ Silty SAND: fine to medium sand, yellow-brown, moist																A			13,20,25/140 mm refusal
	1	Clayey SAND SC: fine to medium grained, pale grey and red-brown, moist, very dense, extremely weathered Hawkesbury Sandstone																A			
	1.5	SANDSTONE: fine to medium grained, pale grey and red, low strength with very low strength bands, highly weathered, fractured, Hawkesbury Sandstone																S			
	2																				PL(A) = 0.19
	2.06																	C	95	55	
	2.1																				PL(A) = 0.97
	2.36																				
	2.65																				PL(A) = 1.2
	2.86																				
	3.08																				PL(A) = 1.5
	3.12																				
	3.12m																				PL(A) = 1.1
	3.12m																				
	4																				PL(A) = 1
	4.77																				
	5.16																				PL(A) = 2
	5.91																				
	6.44																				PL(A) = 1.3
	6.84																				
	7.17																				PL(A) = 2.1
	7.86																				
	8.22																				PL(A) = 2.1
	8.22m																				
	9.29																				PL(A) = 2.1
	9.37																				

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 1.5m, HQ to 1.5m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 17.2m; PCD to 17.2m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 80% drilling flush return below 15.8m  
**REMARKS:** Groundwater well installed to 17.2m (screen 17.2-14.2m; blank 14.2-0.0m; gravel 17.2-13.7m; bentonite 13.7-13.2m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	W Water seep	S Standard penetration test	
E Environmental sample	W Water level	V Shear vane (kPa)	

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.7 AHD  
**EASTING:** 325658.7  
**NORTHING:** 6260313.1  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 107  
**PROJECT No:** 86043.06  
**DATE:** 16/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
	39	SANDSTONE: medium to coarse grained, yellow-brown, medium to high strength, moderately weathered, slightly fractured to unbroken, Hawkesbury Sandstone (continued)																				
11																						
	38	SANDSTONE: medium to coarse grained, pale grey, high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone																C	100	100	PL(A) = 1.7	
11.83																					PL(A) = 2.8	
12																						
	37																				PL(A) = 1.2	
13																						
	36																				PL(A) = 2.2	
14																						
	35																		C	100	98	PL(A) = 1.2
15																						
	34																					
16																				PL(A) = 1.8		
	33																	C	100	90		
17																						
	32	Bore discontinued at 17.2m Target depth reached																			PL(A) = 1.4	
18																						
	31																					
19																						
	30																					

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.5m, HQ to 1.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 17.2m; PCD to 17.2m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 80% drilling flush return below 15.8m

**REMARKS:** Groundwater well installed to 17.2m (screen 17.2-14.2m; blank 14.2-0.0m; gravel 17.2-13.7m; bentonite 13.7-13.2m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS


## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

BORE: 107

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 107

PROJECT: MACQUARIE PARK

APRIL 2021





BORE: 107

PROJECT: MACQUARIE PARK

APRIL 2021



11.00 – 16.00m

BORE: 107

PROJECT: MACQUARIE PARK

APRIL 2021



16.00 – 17.20m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.2 AHD  
**EASTING:** 325705.3  
**NORTHING:** 6260372.4  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 108  
**PROJECT No:** 86043.06  
**DATE:** 13/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering				Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing					
			EW	HW	MW	SW		FS	FR	Ex Low	Very Low	Low			Medium	High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
46	0.1	BRICK PAVERS																				
	0.5	FILL/ SAND: fine to medium, dark yellow then brown, trace fine to medium igneous and ironstone gravel, moist																A				
1		Clayey SAND SC: fine to medium sand, red brown and pale grey, trace fine to medium ironstone gravel, moist, very dense, extremely weathered Hawkesbury Sandstone																A				25/70 mm refusal
45	1.5	SANDSTONE: medium to coarse grained, pale grey with some red-brown and orange-brown staining, medium strength, moderately weathered, slightly fractured, Hawkesbury Sandstone																				
44	2																					PL(A) = 0.52

**RIG:** Explora

**DRILLER:** LC

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.3m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.3m; NMLC-Coring to 14.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	sp	Standard penetration test
E	Environmental sample	≡	Water level	S	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.2 AHD  
**EASTING:** 325705.3  
**NORTHING:** 6260372.4  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 108  
**PROJECT No:** 86043.06  
**DATE:** 13/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering						Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS	FR		Ex Low	Very Low	Low	Medium	High			Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
36		SANDSTONE: medium to coarse, pale grey with some yellow brown, medium to high strength, moderately weathered to fresh, slightly fractured to unbroken, Hawkesbury Sandstone <i>(continued)</i>															9.88m: B5°, pl, ro, fe stn & cly vn	C	100	99	PL(A) = 2.5	
11																						
35																						PL(A) = 1.9
11.82		SANDSTONE: medium to coarse, pale grey, crossbedded at 10-20°, high strength, fresh, unbroken, Hawkesbury Sandstone															12.54m: B5°, pl, sm, cly 1mm	C	100	98	PL(A) = 1.7	
12																						
34																					PL(A) = 2.2	
13																						
33																						
14	14.0	Bore discontinued at 14.0m Target depth reached																				
32																						
15																						
31																						
16																						
30																						
17																						
29																						
18																						
28																						
19																						
27																						

**RIG:** Explora

**DRILLER:** LC

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.3m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.3m; NMLC-Coring to 14.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)



BORE: 108

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 108

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 108

PROJECT: MACQUARIE PARK

APRIL 2021



10.00 – 14.00m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.1 AHD  
**EASTING:** 325716  
**NORTHING:** 6260351.1  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 109  
**PROJECT No:** 86043.06  
**DATE:** 20/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Low	Medium	High			Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
46	0.5	FILL/ Sandy CLAY: low to medium plasticity, brown to yellow-brown, fine to medium sand, w<PL															A			25/110 mm refusal	
		Sandy CLAY CL: low plasticity, orange-brown and yellow, fine to medium sand, w<PL, very stiff, residual															A				
1																	A				
45																	S				
1.63																1.11m: CORE LOSS: 520mm	C	65	10	PL(A) = 0.31	
2	2.15	SANDSTONE: medium to coarse grained, pale grey and red-brown, very low then medium strength, highly then moderately weathered, highly fractured to fractured, Hawkesbury Sandstone														1.61m: Ds 40mm 1.7m: B0°, pl, ro, fe stn 1.86m: B0°, pl, ro, fe stn 1.9m: Ds 20mm 2m: CORE LOSS: 150mm	C	65	0		
2.51																2.22m: B0°, pl, ro, cln 2.46m: CORE LOSS: 50mm 2.57m: J20° (x2), pl, ro, fe stn					
3		SANDSTONE: medium to coarse grained, orange brown, high strength, slightly to moderately weathered, fractured, Hawkesbury Sandstone														2.73m: B0°, pl, ro, fe stn 2.91m: B0°, pl, ro, fe stn 3.03-3.82m: B0°-5° (x9), pl, ro, cly vn & ti	C	96	35	PL(A) = 0.47	
4	3.93															3.88m: CORE LOSS: 50mm 4.13m: B0°, pl, ro, fe stn 4.24m: B0°, pl, ro, fe stn				PL(A) = 0.79	
42		From 4.3m: slightly fractured																			
5																					
41	5.4															5.1m: B0°, pl, ro, cly vn 5.19m: B0°, pl, ro, cly vn & J70°, pl, ro, cln	C	98	93	PL(A) = 0.56	
6		SANDSTONE: medium to coarse grained, orange and pale grey, high strength, slightly to moderately weathered, slightly fractured, Hawkesbury Sandstone														6.03m: B0°, pl, sm, cly 1mm				PL(A) = 1.2	
7																					
39	7.57															7.23m: B0°, pl, ro, cly vn  7.48m: B0°, pl, ro, cly vn, fe stn CORE LOSS: 90mm				PL(A) = 1.2	
8																					
38																				PL(A) = 2.2	
9	9.05															8.86m: B5°, pl, ro, fe stn 8.9m: Cs 10mm  9.23m: B5°, un, ro, cbs co				PL(A) = 2.6	
37		SANDSTONE: medium to coarse grained, pale grey, high strength, fresh, unbroken, Hawkesbury Sandstone															C	100	100	PL(A) = 1.7	



**Douglas Partners**  
Geotechnics | Environment | Groundwater

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.1 AHD  
**EASTING:** 325716  
**NORTHING:** 6260351.1  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 109  
**PROJECT No:** 86043.06  
**DATE:** 20/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
36		SANDSTONE: medium to coarse grained, pale grey, high strength, fresh, unbroken, Hawkesbury Sandstone <i>(continued)</i>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.5m, HQ to 2.8m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.8m; NMLC-Coring to 13.8m; PCD to 13.8m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 13.8m (screen 13.8-10.8m; blank 10.8-0.0m; gravel 13.8-10.3m; bentonite 10.3-9.5m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.1 AHD  
**EASTING:** 325716  
**NORTHING:** 6260351.1  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 109A  
**PROJECT No:** 86043.06  
**DATE:** 29/4/2021  
**SHEET** 1 OF 1

RL	Depth (m)	Description of Strata	Degree of Weathering						Graphic Log	Rock Strength						Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS	FR		Ex Low	Very Low	Low	Medium	High	Very High			Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
46	0.5	FILL/ Sandy CLAY: low to medium plasticity, brown to yellow-brown, fine to medium sand, w<PL																					
		Sandy CLAY CL: low plasticity, orange-brown and yellow, w<PL, very stiff, residual																					
45	1																						
	1.6	SANDSTONE: medium to coarse grained, pale grey and red-brown, very low, low and medium strength, highly weathered, highly fractured, Hawkesbury Sandstone																					
44	2																						
	2.5	SANDSTONE: medium to coarse grained, orange brown, high strength, slightly to moderately weathered, fractured, Hawkesbury Sandstone																					
43	3																						
	4																						
42	4																						
	5																						
41	5																						
	5.4	SANDSTONE: medium to coarse grained, orange and pale grey, high strength, slightly to moderately weathered, slightly fractured, Hawkesbury Sandstone																					
40	6																						
	7																						
39	7																						
	8																						
38	8																						
	8.5	Bore discontinued at 8.5m Target depth reached																					
37	9																						

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 8.5

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 8.5m (screen 8.5-5.5m; blank 5.5-0.0m; gravel 8.5-5.0m; bentonite 5.0-4.5m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)



BORE: 109

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 109

PROJECT: MACQUARIE PARK

APRIL 2021





BORE: 109

PROJECT: MACQUARIE PARK

APRIL 2021



10.00 – 13.80m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.5 AHD  
**EASTING:** 325727.9  
**NORTHING:** 6260334.9  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 110  
**PROJECT No:** 86043.06  
**DATE:** 13/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
45	0.4	FILL/ Clayey SAND: fine to medium sand, brown, trace fine to medium sandstone gravel, silt and rootlets, moist, apparently reworked natural																A			2,13,9 N = 22
1		Sandy CLAY CL-CI: low to medium plasticity, dark yellow-brown, fine to medium sand, w<PL, very stiff, residual																A			
44																		S			
1.7		Clayey SAND SC: fine to medium, red-brown, moist, extremely weathered Hawkesbury Sandstone																			
2	2.22																	A			
2.22		SANDSTONE: medium to coarse grained, pale grey with some orange and red stained beds, moderately weathered, low strength, fractured then slightly fractured, Hawkesbury Sandstone															2.1m: CORE LOSS: 120mm				PL(A) = 0.14  PL(A) = 0.21   PL(A) = 0.2   PL(A) = 0.83   PL(A) = 0.6   PL(A) = 1.8   PL(A) = 2.7   PL(A) = 1.1   PL(A) = 1.2
2.81																	2.42m: B0°, pl, ro, cly vn 2.46m: CORE LOSS: 350mm				
3																	2.82m: B0°, pl, sm, cly 2mm 3.04m: Cs 10mm 3.13m: B0°, pl, ro, fe strn	C	70	60	
4																					
4.7		SANDSTONE: medium to coarse grained, pale grey and yellow-brown, medium then high strength, fresh then moderately weathered, fractured and slightly fractured, Hawkesbury Sandstone															4.32m: J80°, pl, ro, cln				
5	5.43																				
5.43																	5.28m: Cs 20mm 5.3m: CORE LOSS: 130mm 5.57m: Cs 10mm 5.65m: J80°, pl, ro, cln				
6																	6.08m: Cs 10mm 6.13m: Ds 70mm				
6.69																	6.69m: B0°, pl, ro fe strn				
7																					
8	8.05	SANDSTONE: medium to coarse grained, pale grey, high strength, crossbedded at 5-10°, fresh, slightly fractured, Hawkesbury Sandstone															7.82m: Cs 40mm				
8.4																	8.4m: J85°, pl, ro, cln				
9																					
9																					
36																					

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.1m, HQ to 2.1m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.1m; NMLC-Coring to 12.96m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.5 AHD  
**EASTING:** 325727.9  
**NORTHING:** 6260334.9  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 110  
**PROJECT No:** 86043.06  
**DATE:** 13/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding	J - Joint	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
35		SANDSTONE: medium to coarse grained, pale grey, high strength, crossbedded at 5-10°, fresh, slightly fractured, Hawkesbury Sandstone (continued)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.1m, HQ to 2.1m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.1m; NMLC-Coring to 12.96m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 110

PROJECT: MACQUARIE PARK

APRIL 2021



2.10 – 6.00m

BORE: 110

PROJECT: MACQUARIE PARK

APRIL 2021



6.00 – 11.00m

BORE: 110

PROJECT: MACQUARIE PARK

APRIL 2021



11.00 – 12.96m



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.8 AHD  
**EASTING:** 325729.6  
**NORTHING:** 6260317.2  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 111  
**PROJECT No:** 86043.06  
**DATE:** 19/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium				High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault
	45	FILL/ SAND: fine to medium, dark brown and yellow, trace fine to medium sandstone gravel, wood ash and rootlets, moist																			2.4,4 N = 8
	1.2	Sandy CLAY Cl: medium plasticity, yellow-brown, fine to medium sand, w<PL, stiff, residual															S				
	2.2	Sandy CLAY CL: low plasticity, pale grey, fine to medium sand, w<PL, hard, extremely weathered Hawkesbury Sandstone															S			19,25/100 mm refusal	
	2.8	SANDSTONE: medium to coarse grained, pale grey, very low then low strength, highly weathered, fractured, Hawkesbury Sandstone																			PL(A) = 0.39
	4																				
	4.28																				
	5																				
	5.1																				
	5.54	SANDSTONE: medium to coarse grained, orange, red and pale-grey, medium then high strength, moderately then slightly weathered, slightly fractured to unbroken, Hawkesbury Sandstone																			
	6																				
	7																				
	8																				
	8.52	SANDSTONE: medium to coarse grained, pale grey, medium to high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone																			
	9																				
	36																				

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 2.5m, HQ to 2.8m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.8m; NMLC-Coring to 12.87m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 11.8m (screen 11.8-8.8m; blank 8.8-0.0m; bentonite 12.87-11.8m; gravel 11.8-8.3m; bentonite 8.3-7.5m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	sp	Standard penetration test
E	Environmental sample	W	Water level	S	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.8 AHD  
**EASTING:** 325729.6  
**NORTHING:** 6260317.2  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 111  
**PROJECT No:** 86043.06  
**DATE:** 19/4/2021  
**SHEET** 2 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
	35 11	SANDSTONE: medium to coarse grained, pale grey, medium to high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone (continued)																				PL(A) = 2.2
	34 12																	C	100	100		PL(A) = 1.7
	33 12.87																					PL(A) = 1.8
	33 13	Bore discontinued at 12.87m Target depth reached																				
	32 14																					
	31 15																					
	30 16																					
	29 17																					
	28 18																					
	27 19																					
	26																					

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 2.5m, HQ to 2.8m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.8m; NMLC-Coring to 12.87m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering  
**REMARKS:** Groundwater well installed to 11.8m (screen 11.8-8.8m; blank 8.8-0.0m; bentonite 12.87-11.8m; gravel 11.8-8.3m; bentonite 8.3-7.5m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.8 AHD  
**EASTING:** 325729.6  
**NORTHING:** 6260317.2  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 111A  
**PROJECT No:** 86043.06  
**DATE:** 29/4/2021  
**SHEET** 1 OF 1

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	45.1	FILL/ SAND: fine to medium, dark brown and yellow, trace fine to medium sandstone gravel, wood ash and rootlets, moist																			
	44.2	Sandy CLAY Cl: medium plasticity, yellow-brown, fine to medium sand, w<PL, stiff, residual																			
	43.2	Sandy CLAY CL: low plasticity, pale grey, fine to medium sand, w<PL, hard, extremely weathered																			
	42.8	Hawkesbury Sandstone																			
	42.0	SANDSTONE: medium to coarse grained, pale grey, very low then low strength, highly weathered, fractured, Hawkesbury Sandstone																			
	41.0																				
	40.0																				
	39.0	SANDSTONE: medium to coarse grained, orange, red and pale-grey, medium then high strength, moderately then slightly weathered, slightly fractured to unbroken, Hawkesbury Sandstone																			
	38.0																				
	37.0	Bore discontinued at 8.5m Target depth reached																			
	36.0																				

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.7m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 8.5m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 8.5m (screen 8.5-5.5m; blank 5.5-0.0m; gravel 8.5-5.0m; bentonite 5.0-4.5m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 111

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 111

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 111

PROJECT: MACQUARIE PARK

APRIL 2021



12.00 – 12.87m



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.7 AHD  
**EASTING:** 325721.9  
**NORTHING:** 6260299.5  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 112  
**PROJECT No:** 86043.06  
**DATE:** 15 - 16/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)				Discontinuities		Sampling & In Situ Testing					
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium		High	Very High	Ex High	0.01	0.05	0.10	0.50	1.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
	45	Fill/ Clayey SAND: fine to medium sand, dark brown, trace fine to medium sandstone gravel, moist, apparently in very loose condition																								1,1,1 N = 2
	44																						A			
	43	SANDSTONE: medium to coarse grained, yellow-brown then pale grey, very low to low strength, highly weathered, Hawkesbury Sandstone																					S			
	42	SANDSTONE: medium to coarse grained, pale grey with some pale orange staining, medium strength, moderately weathered, unbroken, Hawkesbury Sandstone																						A		
	41	SANDSTONE: medium to coarse grained, red-brown, moderately and slightly weathered, high strength, fractured then unbroken, Hawkesbury Sandstone																								PL(A) = 0.87
	40																									
	39	6.80-7.00m: very high strength band																								PL(A) = 1.2
	38																									
	37																									
	36																									
		SANDSTONE: medium to coarse grained, pale grey, crossbedded at 5-10, high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone																								PL(A) = 1.4
																										PL(A) = 1.6
																										PL(A) = 3.1
																										PL(A) = 1.7
																										PL(A) = 1.1
																										PL(A) = 2.3

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 2.5m, HQ to 2.65m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.65m; NMLC-Coring to 12.8m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 90% drilling flush return below 7.0m  
**REMARKS:** Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	W Water seep	S Standard penetration test	
E Environmental sample	W Water level	V Shear vane (kPa)	

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 45.7 AHD  
**EASTING:** 325721.9  
**NORTHING:** 6260299.5  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 112  
**PROJECT No:** 86043.06  
**DATE:** 15 - 16/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing					
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium				High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
35	11	SANDSTONE: medium to coarse grained, pale grey, crossbedded at 5-10, high strength, fresh, slightly fractured to unbroken, Hawkesbury Sandstone <i>(continued)</i>															10.14m: B10°, pl, ro, cly vn	C	100	100	PL(A) = 1.1	
34	12																		C	100	100	PL(A) = 2.2
33	13																					PL(A) = 2.7
13.0	13.0	Bore discontinued at 13.0m Target depth reached																				
32	14																					
31	15																					
30	16																					
29	17																					
28	18																					
27	19																					
26																						

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 2.5m, HQ to 2.65m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.65m; NMLC-Coring to 12.8m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 90% drilling flush return below 7.0m  
**REMARKS:** Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

BORE: 112

PROJECT: MACQUARIE PARK

APRIL 2021



2.66 – 7.00m

BORE: 112

PROJECT: MACQUARIE PARK

APRIL 2021



7.00 – 12.00m

BORE: 112

PROJECT: MACQUARIE PARK

APRIL 2021



12.00 – 13.00m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.9 AHD  
**EASTING:** 325701.1  
**NORTHING:** 6260273.1  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 113  
**PROJECT No:** 86043.06  
**DATE:** 14/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	0.2	FILL/ Sandy CLAY: low to medium plasticity, brown, fine to medium sand, w<PL, apparently reworked natural																A			
	0.8	FILL/ SAND: fine to medium, yellow-brown, trace silt, moist, apparently medium dense, possibly natural																A			
	1																	S			25/30 mm refusal PL(A) = 0.09
	1.76	SANDSTONE: fine to medium grained, orange, very low then low strength, highly weathered, Hawkesbury Sandstone																C	60	15	PL(A) = 0.95
	1.95																	C	100	100	
	2	SANDSTONE: medium to coarse grained, red-brown and orange, medium strength with extremely low and very low strength bands, highly weathered, fractured to slightly fractured, Hawkesbury Sandstone																			PL(A) = 0.48
	2.89																	C	95	90	PL(A) = 0.99
	3.05	SANDSTONE: medium to coarse grained, orange and pale grey, crossbedded at 5-10°, medium to high strength, moderately to slightly weathered, slightly fractured to unbroken, Hawkesbury Sandstone																			
	4																				PL(A) = 1.1
	5																	C	99	99	PL(A) = 2.2
	6																				PL(A) = 1.4
	6.95																				PL(A) = 2.9
	8																	C	100	95	PL(A) = 2.5
	9																				PL(A) = 1.9
	9.85	SANDSTONE: (as below)																			

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 1.0m, HQ to 1.0m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.03m; NMLC-Coring to 14.29m; PCD to 14.29m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 90% drilling flush return below 10.0m  
**REMARKS:** Groundwater well installed to 14.29m (screen 14.29-11.29m; blank 11.29-0.0m; gravel 14.29-10.8m; bentonite 10.8-10.3m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	> Water seep	SP Standard penetration test	
E Environmental sample	≡ Water level	V Shear vane (kPa)	



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.9 AHD  
**EASTING:** 325701.1  
**NORTHING:** 6260273.1  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 113  
**PROJECT No:** 86043.06  
**DATE:** 14/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	10.0	SANDSTONE: medium to coarse grained, pale grey, cross bedded at 5-10, high strength, fresh, slightly fractured, Hawkesbury Sandstone																C	100	99	PL(A) = 1.5  <

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.0m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.03m; NMLC-Coring to 14.29m; PCD to 14.29m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 90% drilling flush return below 10.0m

**REMARKS:** Groundwater well installed to 14.29m (screen 14.29-11.29m; blank 11.29-0.0m; gravel 14.29-10.8m; bentonite 10.8-10.3m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

BORE: 113

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 113

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 113

PROJECT: MACQUARIE PARK

APRIL 2021



10.00 – 14.29m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 47.3 AHD  
**EASTING:** 325695.41  
**NORTHING:** 6260286.6  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 114  
**PROJECT No:** 86043.06  
**DATE:** 14 - 15/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering						Graphic Log	Rock Strength						Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
			EW	HW	MW	SW	FS	FR		Ex Low	Very Low	Low	Medium	High	Very High			Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
47	0.35	FILL/ Sandy CLAY: low to medium plasticity, brown, fine to medium sand, w<PL, apparently reworked natural																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						

**RIG:** Explora **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 1.1m, HQ to 1.1m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.13m; NMLC-Coring to 14.92m; PCD to 14.92m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 95% drilling flush return below 9.0m  
**REMARKS:** Groundwater well installed to 14.92m (screen 14.92-8.92m; blank 8.92-0.0m; gravel 14.92-8.3m; bentonite 8.3-7.8m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 47.3 AHD  
**EASTING:** 325695.41  
**NORTHING:** 6260286.6  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 114  
**PROJECT No:** 86043.06  
**DATE:** 14 - 15/4/2021  
**SHEET 2 OF 2**

[illegible]

**CASING:** HW to 1.1m, HQ to 1.1m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.13m; NMLC-Coring to 14.92m; PCD to 14.92m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering, 95% drilling flush return below 9.0m

**REMARKS:** Groundwater well installed to 14.92m (screen 14.92-8.92m; blank 8.92-0.0m; gravel 14.92-8.3m; bentonite 8.3-7.8m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U <sub>s</sub>	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W <sub>s</sub>	Water seep
E	Environmental sample	W <sub>l</sub>	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test ls(50) (MPa)
		PL(D)	Point load diametral test ls(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)





BORE: 114

PROJECT: MACQUARIE PARK

APRIL 2021



1.13 – 5.00m

BORE: 114

PROJECT: MACQUARIE PARK

APRIL 2021



5.00 – 10.00m

BORE: 114

PROJECT: MACQUARIE PARK

APRIL 2021



10.00 – 14.92m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.4 AHD  
**EASTING:** 325707.2  
**NORTHING:** 6260312  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 115  
**PROJECT No:** 86043.06  
**DATE:** 20 - 21/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
46	0.5	FILL/ Silty Clayey SAND: fine to medium sand, brown, moist																A			
1	1.22	SANDSTONE: fine to medium grained, pale yellow, medium to high strength, moderately weathered, Hawkesbury Sandstone																C	100	100	PL(A) = 1.3
2		SANDSTONE: medium to coarse grained, yellow-brown with some pale grey, medium strength, moderately then slightly weathered, slightly fractured, Hawkesbury Sandstone																C	100	96	PL(A) = 0.45
3																					PL(A) = 0.89
4		3.45m: fine to medium grained																C	100	100	PL(A) = 0.86
5	4.9	SANDSTONE: medium to coarse grained, red-brown, yellow-brown and pale grey, high strength, moderately to slightly weathered, slightly fractured to unbroken, Hawkesbury Sandstone																			PL(A) = 1.2
6	5.52																				PL(A) = 2
7																		C	98	95	PL(A) = 1.9
8		8.10-8.20m: siltstone clasts																			PL(A) = 1.7
9																		C	100	92	PL(A) = 2.4
9.47		SANDSTONE: (as below)																			PL(A) = 2
10.0																					

**RIG:** Ecproxa **DRILLER:** JD **LOGGED:** TM **CASING:** HW to 0.7m, HQ to 0.7m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 0.7m; NMLC-Coring to 14.27m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering  
**REMARKS:** Groundwater well installed to 11.0m (screen 11.0-8.0m; blank 8.0-0.0m; gravel 11.0-7.5m; bentonite 7.5-7.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
PID	Photo ionisation detector (ppm)	PL(A)	Point load axial test Is(50) (MPa)
PL(D)	Point load diametral test Is(50) (MPa)	pp	Pocket penetrometer (kPa)
S	Standard penetration test	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 46.4 AHD  
**EASTING:** 325707.2  
**NORTHING:** 6260312  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 115  
**PROJECT No:** 86043.06  
**DATE:** 20 - 21/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
36		SANDSTONE: medium to coarse grained, pale grey, high strength, fresh, unbroken, Hawkesbury Sandstone																			
11																		C	100	92	PL(A) = 2.2
35																					
12																					PL(A) = 1.8
34																					
13																		C	100	100	PL(A) = 2.1
33																					
14																					
14.27		Bore discontinued at 14.27m Target depth reached																			PL(A) = 1.8
32																					
15																					
31																					
16																					
30																					
17																					
29																					
18																					
28																					
19																					
27																					

**RIG:** Ecplora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 0.7m, HQ to 0.7m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 0.7m; NMLC-Coring to 14.27m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Groundwater well installed to 11.0m (screen 11.0-8.0m; blank 8.0-0.0m; gravel 11.0-7.5m; bentonite 7.5-7.0m; backfill to GL; gatic at surface); Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)



BORE: 115

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 115

PROJECT: MACQUARIE PARK

APRIL 2021






BORE: 115

PROJECT: MACQUARIE PARK

APRIL 2021



10.0 - 14.27m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 48.6 AHD  
**EASTING:** 325676.9  
**NORTHING:** 6260308  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 116  
**PROJECT No:** 86043.06  
**DATE:** 19/4/2021  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering				Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW		FS	FR	Ex Low	Very Low	Low			Medium	High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	48	FILL/ Clayey SAND: fine to medium sand, brown, moist																A			7,8,20 N = 28
	1	Clayey SAND SC: fine to medium grained, red-brown and yellow-brown, moist, dense, residual																A			
	1.5																	S			
	1.85	SANDSTONE: fine to medium grained, red-brown and pale grey, extremely low and very low strength with a medium strength band, highly weathered, highly fractured, Hawkesbury Sandstone																			PL(A) = 1.2
	2	SANDSTONE: medium to coarse grained, pale grey red-brown and orange, medium to high strength, moderately weathered, slightly fractured, Hawkesbury Sandstone																C	100	82	
	3																				PL(A) = 0.89
	4	4.00m: fine to medium grained																			
	4.83																				PL(A) = 0.99
	4.91																				
	5																				PL(A) = 0.96
	6																				
	6.2	SANDSTONE: fine to medium grained, red-brown and orange, high strength, slightly to moderately weathered, slightly fractured to unbroken, Hawkesbury Sandstone																			PL(A) = 2.2
	7																				
	8	8.05m: medium to coarse grained																			PL(A) = 1.3
	9																				
	40																				PL(A) = 2
	39																				
																					PL(A) = 2.2

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 15.79m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 48.6 AHD  
**EASTING:** 325676.9  
**NORTHING:** 6260308  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 116  
**PROJECT No:** 86043.06  
**DATE:** 19/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering						Graphic Log	Rock Strength						Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
			EW	HW	MW	SW	FS	FR		Ex Low	Very Low	Low	Medium	High	Very High			Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	38	SANDSTONE: fine to medium grained, red-brown and orange, high strength, slightly to moderately weathered, slightly fractured to unbroken, Hawkesbury Sandstone (continued)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 1.0m, HQ to 1.5m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary to 1.5m; NMLC-Coring to 15.79m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

BORE: 116

PROJECT: MACQUARIE PARK

APRIL 2021



BORE: 116

PROJECT: MACQUARIE PARK

APRIL 2021





BORE: 116

PROJECT: MACQUARIE PARK

APRIL 2021



0.70 – 5.00m



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.6 AHD  
**EASTING:** 325675  
**NORTHING:** 6260377.6  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 118  
**PROJECT No:** 86043.06  
**DATE:** 27/4/2021  
**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)				Discontinuities		Sampling & In Situ Testing							
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium		High	Very High	Ex High	0.01	0.05	0.10	0.50	1.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
49	1	FILL/ Sandy CLAY: medium plasticity, dark brown, fine to medium sand, trace rootlets and fine to medium sandstone gravel, w<PL																									6,5,5 N = 10	
48	1.4	Sandy CLAY Cl: medium plasticity, yellow-brown, fine to medium sand, w<PL, stiff, residual																				A						
47	2.1	Clayey SAND SC: fine to medium, pale grey and red-brown, trace fine to medium ironstone gravel, moist, very dense, extremely weathered Hawkesbury Sandstone																				S						
46	2.8	SANDSTONE: fine to medium,pale grey and red-brown,very low to low strength, highly weathered, fractured, Hawkesbury Sandstone																					S				20,25/130 mm refusal	
45	2.95																										PL(A) = 0.2	
44	3																											PL(A) = 0.94
43	4																											
42	5																										PL(A) = 0.23	
41	5.53	SANDSTONE: medium to coarse grained, red-brown then orange-brown and pale grey, high strength, moderately weathered to fresh, slightly fractured to unbroken, Hawkesbury Sandstone																										PL(A) = 1.6
40	6																											
39	7																										PL(A) = 1.1	
38	8																											PL(A) = 1.1
37	9																											
36	10																											

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.5m, HQ to 2.8m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.8m; NMLC-Coring to 14.17m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	>	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Stage 2 Development  
**LOCATION:** Midtown, Maquarie Park

**SURFACE LEVEL:** 49.6 AHD  
**EASTING:** 325675  
**NORTHING:** 6260377.6  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 118  
**PROJECT No:** 86043.06  
**DATE:** 27/4/2021  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	39	SANDSTONE: medium to coarse grained, red-brown then orange-brown and pale grey, high strength, moderately weathered to fresh, slightly fractured to unbroken, Hawkesbury Sandstone <i>(continued)</i>																			PL(A) = 1
	11																				PL(A) = 2.2
	38																				
	12																				PL(A) = 1.5
	37																				
	13																				PL(A) = 2.2
	36																				
	14																				PL(A) = 1.9
	14.17	Bore discontinued at 14.17m Target depth reached																			
	35																				
	15																				
	34																				
	16																				
	33																				
	17																				
	32																				
	18																				
	31																				
	19																				
	30																				

**RIG:** Explora

**DRILLER:** JD

**LOGGED:** TM

**CASING:** HW to 2.5m, HQ to 2.8m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.5m; Rotary to 2.8m; NMLC-Coring to 14.17m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Coordinates and surface levels obtained from differential GPS

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

BORE: 118

PROJECT: MACQUARIE PARK

APRIL 2021



2.80 – 7.00m

BORE: 118

PROJECT: MACQUARIE PARK

APRIL 2021



8.00 – 12.00m

BORE: 118

PROJECT: MACQUARIE PARK

APRIL 2021



12.00 – 14.17m

## Permeability Testing - Rising Head Test Report

[illegible]



## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 28-May-21  
Tested by: LS

## Test Location

Description:	Unit 3C
Material type:	Sandstone


<b>Test No.</b>	BH104A	
Easting:	325637.8	m
Northing	6260346.9	m
Surface Level:	51.8	m AHD

### Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	2	m

Depth to water before test	10.15	m
Depth to water at start of test	1.7	m

## Test Results

[illegible]

To = 2.3 mins  
138 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e$$
 To

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k = 4.2E-06 m/sec**  
**= 1.504 cm/hour**

4.2E-04 cm/sec

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 28-May-21  
Tested by: LS

## Test Location

Description:	Unit 3C
Material type:	Sandstone


<b>Test No.</b>	<b>BH106</b>	
Easting:	325661.8	m
Northing	6260395.3	m
Surface Level:	49.4	m AHD

## Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	3.5	m

Depth to water before test	4.98	m
Depth to water at start of test	0.37	m

## Test Results

[illegible]

To = 65 mins  
3900 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e$$
 To

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change


### Hydraulic Conductivity

**k = 9.7E-08 m/sec 9.7E-06 cm/sec**  
**= 0.035 cm/hour**

## Permeability Testing - Falling Head Test Report

[illegible]

## Permeability Testing - Falling Head Test Report

Client: <span style="color: blue;">Frasers Property Ivanhoe</span> Project: <span style="color: blue;">Stage 2 - Midtown</span> Location: <span style="color: blue;">Herring Road, Macquarie Park</span>	Project No: <span style="color: blue;">86043.06</span> Date: <span style="color: blue;">28-May-21</span> Tested by: <span style="color: blue;">LS</span>																																																																																																																
<b>Test Location</b> Description: <span style="color: blue;">Unit 3D</span> Material type: <span style="color: blue;">Sandstone</span>	<b>Test No.</b> <span style="color: blue;">BH109</span> Easting: <span style="color: blue;">325716</span> m Northing: <span style="color: blue;">6260351.1</span> m Surface Level: <span style="color: blue;">46.1</span> m AHD																																																																																																																
<b>Details of Well Installation</b> Well casing diameter (2r) <span style="color: blue;">50</span> mm Well screen diameter (2R) <span style="color: blue;">100</span> mm Length of well screen (Le) <span style="color: blue;">3.5</span> m																																																																																																																	
Depth to water before test <span style="color: blue;">6.34</span> m Depth to water at start of test <span style="color: blue;">0.38</span> m																																																																																																																	
<b>Test Results</b> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th>Time (min)</th> <th>Depth (m)</th> <th>Change in Head: <math>\delta H</math> (m)</th> <th><math>\delta H/H_0</math></th> </tr> </thead> <tbody> <tr><td>0.00</td><td>0.38</td><td>5.96</td><td>1.000</td></tr> <tr><td>0.25</td><td>0.44</td><td>5.90</td><td>0.990</td></tr> <tr><td>0.50</td><td>0.5</td><td>5.84</td><td>0.980</td></tr> <tr><td>0.75</td><td>0.55</td><td>5.79</td><td>0.971</td></tr> <tr><td>1.00</td><td>0.61</td><td>5.73</td><td>0.961</td></tr> <tr><td>1.50</td><td>0.7</td><td>5.64</td><td>0.946</td></tr> <tr><td>2.00</td><td>0.8</td><td>5.54</td><td>0.930</td></tr> <tr><td>2.50</td><td>0.87</td><td>5.47</td><td>0.918</td></tr> <tr><td>5.00</td><td>1.3</td><td>5.04</td><td>0.846</td></tr> <tr><td>7.5</td><td>1.7</td><td>4.64</td><td>0.779</td></tr> <tr><td>10</td><td>2</td><td>4.34</td><td>0.728</td></tr> <tr><td>15</td><td>2.54</td><td>3.80</td><td>0.638</td></tr> <tr><td>30</td><td>3.45</td><td>2.89</td><td>0.485</td></tr> <tr><td>60</td><td>4.52</td><td>1.82</td><td>0.305</td></tr> <tr><td>90</td><td>5.18</td><td>1.16</td><td>0.195</td></tr> <tr><td>120</td><td>5.48</td><td>0.86</td><td>0.144</td></tr> <tr><td>200</td><td>5.81</td><td>0.53</td><td>0.089</td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>		Time (min)	Depth (m)	Change in Head: $\delta H$ (m)	$\delta H/H_0$	0.00	0.38	5.96	1.000	0.25	0.44	5.90	0.990	0.50	0.5	5.84	0.980	0.75	0.55	5.79	0.971	1.00	0.61	5.73	0.961	1.50	0.7	5.64	0.946	2.00	0.8	5.54	0.930	2.50	0.87	5.47	0.918	5.00	1.3	5.04	0.846	7.5	1.7	4.64	0.779	10	2	4.34	0.728	15	2.54	3.80	0.638	30	3.45	2.89	0.485	60	4.52	1.82	0.305	90	5.18	1.16	0.195	120	5.48	0.86	0.144	200	5.81	0.53	0.089																																								
Time (min)	Depth (m)	Change in Head: $\delta H$ (m)	$\delta H/H_0$																																																																																																														
0.00	0.38	5.96	1.000																																																																																																														
0.25	0.44	5.90	0.990																																																																																																														
0.50	0.5	5.84	0.980																																																																																																														
0.75	0.55	5.79	0.971																																																																																																														
1.00	0.61	5.73	0.961																																																																																																														
1.50	0.7	5.64	0.946																																																																																																														
2.00	0.8	5.54	0.930																																																																																																														
2.50	0.87	5.47	0.918																																																																																																														
5.00	1.3	5.04	0.846																																																																																																														
7.5	1.7	4.64	0.779																																																																																																														
10	2	4.34	0.728																																																																																																														
15	2.54	3.80	0.638																																																																																																														
30	3.45	2.89	0.485																																																																																																														
60	4.52	1.82	0.305																																																																																																														
90	5.18	1.16	0.195																																																																																																														
120	5.48	0.86	0.144																																																																																																														
200	5.81	0.53	0.089																																																																																																														
<div style="display: flex; align-items: center;">  <div style="margin-left: 20px;"> <p><math>T_o = </math> <span style="color: blue;">47.8</span> mins 2868 secs</p> </div> </div>																																																																																																																	
<b>Theory:</b> Falling Head Permeability calculated using equation by Hvorslev $k = [r^2 \ln(L_e/R)] / 2L_e T_o$ where $r$ = radius of casing $R$ = radius of well screen $L_e$ = length of well screen $T_o$ = time taken to rise or fall to 37% of initial change																																																																																																																	
<table style="width: 100%;"> <tr> <td style="width: 30%;"><b>Hydraulic Conductivity</b></td> <td style="width: 10%;">k =</td> <td style="width: 20%;"><span style="color: blue;">1.3E-07</span></td> <td style="width: 10%;">m/sec</td> <td style="width: 30%;"><span style="color: blue;">1.3E-05</span> cm/sec</td> </tr> <tr> <td></td> <td>=</td> <td><span style="color: blue;">0.048</span></td> <td>cm/hour</td> <td></td> </tr> </table>		<b>Hydraulic Conductivity</b>	k =	<span style="color: blue;">1.3E-07</span>	m/sec	<span style="color: blue;">1.3E-05</span> cm/sec		=	<span style="color: blue;">0.048</span>	cm/hour																																																																																																							
<b>Hydraulic Conductivity</b>	k =	<span style="color: blue;">1.3E-07</span>	m/sec	<span style="color: blue;">1.3E-05</span> cm/sec																																																																																																													
	=	<span style="color: blue;">0.048</span>	cm/hour																																																																																																														

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 28-May-21  
Tested by: LS

## Test Location

Description:	Unit 3C
Material type:	Sandstone


<b>Test No.</b>	BH109A	
Easting:	325716	m
Northing	6260351.1	m
Surface Level:	46.1	m AHD

### Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	3.5	m

Depth to water before test	6.1	m
Depth to water at start of test	0.7	m

## Test Results

[illegible]

To = 22.7 mins  
1362 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e$$
 To

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k =**      **2.8E-07**      m/sec      2.8E-05 cm/sec  
**=**      **0.100**      cm/hour



## Permeability Testing - Falling Head Test Report

[illegible]

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 27-May-21  
Tested by: LS

## Test Location

Description:	Unit 3D
Material type:	Sandstone


<b>Test No.</b>	BH111A	
Easting:	325729.6	m
Northing	6260317.2	m
Surface Level:	45.8	m AHD

## Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	3.5	m

Depth to water before test	5.54	m
Depth to water at start of test	0	m

## Test Results

[illegible]

To = 16.7 mins  
1002 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e \text{ To}$$

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k = 3.8E-07 m/sec 3.8E-05 cm/sec**  
**= 0.136 cm/hour**

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 27-May-21  
Tested by: LS

## Test Location

Description:	Unit 3D
Material type:	Sandstone


<b>Test No.</b>	BH113	
Easting:	325701.1	m
Northing	6260273.1	m
Surface Level:	46.9	m AHD

## Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	3.5	m

Depth to water before test	6	m
Depth to water at start of test	0	m

## Test Results

[illegible]

To = 6.6 mins  
396 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e \text{ To}$$

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k = 9.6E-07 m/sec**  
**= 0.345 cm/hour**

9.6E-05 cm/sec

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 28-May-21  
Tested by: LS

## Test Location

Description:	Unit 3D
Material type:	Sandstone


<b>Test No.</b>	BH114	
Easting:	325695.41	m
Northing	6260286.6	m
Surface Level:	47.3	m AHD

### Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	6.6	m

Depth to water before test	6.19	m
Depth to water at start of test	0	m

## Test Results

[illegible]

To = 7.1 mins  
426 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e \text{ To}$$

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k = 5.4E-07 m/sec**  
**= 0.195 cm/hour**

5.4E-05 cm/sec

## Permeability Testing - Falling Head Test Report

Client: Frasers Property Ivanhoe  
Project: Stage 2 - Midtown  
Location: Herring Road, Macquarie Park

Project No: 86043.06  
Date: 27-May-21  
Tested by: LS

## Test Location

Description:	Unit 3C
Material type:	Sandstone


<b>Test No.</b>	BH115	
Easting:	325707.2	m
Northing	6260312	m
Surface Level:	46.4	m AHD

## Details of Well Installation

Well casing diameter (2r)	50	mm
Well screen diameter (2R)	100	mm
Length of well screen (Le)	3.5	m

Depth to water before test	5.73	m
Depth to water at start of test	0.41	m

## Test Results

[illegible]

To = 3.3 mins  
198 secs

### Theory:

Falling Head Permeability calculated using equation by Hvorslev

$$k = [r^2 \ln(L_e/R)]/2L_e \text{ To}$$

where  $r$  = radius of casing

R = radius of well screen

Le = length of well screen

To = time taken to rise or fall to 37% of initial change

### Hydraulic Conductivity

**k = 1.9E-06 m/sec**  
**= 0.690 cm/hour**

1.9E-04 cm/sec



## Permeability Testing - Falling Head Test Report

[illegible]

---

## **Appendix D**

---

### Summary of Groundwater Measurements

## Appendix D - Summary of Groundwater Measurements - Midtown, Macquarie Park

Groundwater level measurements at standpipes in the vicinity of the Stage 2 development area of the Midtown site are summarised in Table D1, below, together with reference to the reports which provide the relevant logs. Standpipe construction details are summarised in Table D2.

**Table D1 – Summary of Groundwater Measurements – Stage 2 Midtown, Macquarie Park**

Test Location	Ground Surface RL	Depth to Water (m)	Water Level (RL)	Comment	Gravel Interval (m)	Status	Original Report(s)
07	59.1	13.2-13.9	45.2-45.8	Monitoring Period November 2017-June 2018	1.2-21.0	Destroyed	86043.01.R.005.Rev0; 86043.01.R.001.Rev1
10	45.2	4.4-4.9	40.3-40.8	Monitoring Period November 2017-June 2018	2.6-5.6	Missing	86043.01.R.005.Rev0; 86043.01.R.001.Rev1
12	45.2	3.3-4.3	40.8-41.8	Monitoring Period November 2017-June 2018; Responsive to rainfall events	2.3-6.93	Missing	86043.01.R.005.Rev0; 86043.01.R.001.Rev1
13	46.8	4.8-5.3	41.2-42.0	Monitoring Period November 2017-June 2018	1.8-7.0	Missing	86043.01.R.005.Rev0; 86043.01.R.001.Rev1
101	54.1	7.28	46.8	11/05/2021	7.5-11.0	Intact	86043.06.R.001
103	52.4	-	-	No reading obtained before destruction	11.5-15.0	Destroyed	86043.06.R.002
104A	51.7	10.15	41.55	28/05/21	11.5-13.5	Intact	86043.06.R.002
106	49.5	4.93-4.98	44.5-44.6	11&28/05/2021	7.5-11.0	Intact	86043.06.R.002
107	49.7	8.43-8.61	41.1-41.3	28/04/2021 (8.61m), 28/5/21 (8.43m)	13.7-17.2	Intact	86043.06.R.003
109	46.1	6.34-6.4	39.7-39.8	28/04/2021 (6.4m), 28/5/21 (6.34m)	10.3-13.8	Intact	86043.06.R.003
109A	46.1	2.2-6.1	40.0-43.9	17/5/21 (2.2m), 28/5/21 (6.1m); Nested well	5.0-8.5	Intact	86043.06.R.003
111	45.8	4.9-6.0	39.8-40.9	28/4/21 (6.0m), 17/5/21 (4.9m), 27/5/21 (5.95m)	8.3-11.8	Intact	86043.06.R.003
111A	45.8	2.9-5.54	40.3-42.9	17/5/21 (2.9m), 27/5/21 (5.54m); Nested well	5.0-8.5	Intact	86043.06.R.003
113	46.9	6.23-6.0	40.7-40.9	28/04/2021 (6.23m), 27/5/21 (6.0m)	10.8-14.29	Intact	86043.06.R.003

*Continued on next page*

**Table D1 – Summary of Groundwater Measurements – Stage 2 Midtown, Macquarie Park (continued)**

Test Location	Ground Surface RL	Depth to Water (m)	Water Level (RL)	Comment	Gravel Interval (m)	Status	Original Report(s)
114	47.3	6.28-6.19	41.0-41.1	28/04/2021 (6.28m), 28/5/21 (6.19m)	8.3-14.92	Intact	86043.06.R.003
114A	47.3	4.06	43.2	28/5/21; Nested well	1.5-4.5	Intact	86043.06.R.003
115	46.4	5.3-5.73	40.7-41.1	17/5/21 (5.3m), 27/5/21 (5.73m);	7.5-11.0	Intact	86043.06.R.003
118A	50.0	5.38	44.6	28/5/21	4.0-6.1	Intact	86043.06.R.002

**Table D2 – Summary of Well Construction – Stage 2 Midtown, Macquarie Park**

Bore	101	103	104A	106	107	109	109A
Ground Level	54.1	52.4	51.7	49.5	49.7	46.1	46.1
Backfill	0-7.0	0-11.0	0-10.5	0-7.0	0-13.2	0-9.5	0-4.5
Bento	7.0-7.5	11.0-11.5	10.5-11.5	7.0-7.5	13.2-13.7	9.5-10.3	4.5-5.0
Gravel	7.5-11.0	11.5-15.0	11.5-13.5	7.5-11.0	13.7-17.2	10.3-13.8	5.0-8.5
Blank PVC	0-8.0	0-12.0	0-12.0	0-8.0	0-14.2	0-10.8	0-5.5
Slotted PVC	8.0-11.0	12.0-15.0	12.0-13.5	8.0-11.0	14.2-17.2	10.8-13.8	5.5-8.5

Bore	111	111A	113	114	114A	115	118A
Ground Level	45.8	45.8	46.9	47.3	47.3	46.4	50
Backfill	0-7.5	0-4.5	0-10.3	0-7.8	0-0.5	0-7.0	0-3.0
Bento	7.5-8.3	4.5-5.0	10.3-10.8	7.8-8.3	0.5-1.5	7.0-7.5	3.0-4.0
Gravel	8.3-11.8	5.0-8.5	10.8-14.29	8.3-14.92	1.5-4.5	7.5-11.0	4.0-6.1
Blank PVC	0-8.8	0-5.5	0-11.29	0-8.92	0-2.0	0-8.0	0.0-4.5
Slotted PVC	8.8-11.8	5.5-8.5	11.29-14.29	14.92-8.92	2.0-4.5	8.0-11.0	4.5-6.1

---

## **Appendix E**

---

Selected Results of Previous Field Work





## Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are based on Australian Standard AS 1726-1993, Geotechnical Site Investigations Code. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

## Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle size (mm)
Boulder	>200
Cobble	63 - 200
Gravel	2.36 - 63
Sand	0.075 - 2.36
Silt	0.002 - 0.075
Clay	<0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle size (mm)
Coarse gravel	20 - 63
Medium gravel	6 - 20
Fine gravel	2.36 - 6
Coarse sand	0.6 - 2.36
Medium sand	0.2 - 0.6
Fine sand	0.075 - 0.2

The proportions of secondary constituents of soils are described as:

Term	Proportion	Example
And	Specify	Clay (60%) and Sand (40%)
Adjective	20 - 35%	Sandy Clay
Slightly	12 - 20%	Slightly Sandy Clay
With some	5 - 12%	Clay with some sand
With a trace of	0 - 5%	Clay with a trace of sand

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

## Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained shear strength (kPa)
Very soft	vs	<12
Soft	s	12 - 25
Firm	f	25 - 50
Stiff	st	50 - 100
Very stiff	vst	100 - 200
Hard	h	>200

## Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (PSP). The relative density terms are given below:

Relative Density	Abbreviation	SPT N value	CPT qc value (MPa)
Very loose	vl	<4	<2
Loose	l	4 - 10	2 - 5
Medium dense	md	10 - 30	5 - 15
Dense	d	30 - 50	15 - 25
Very dense	vd	>50	>25

# *Soil Descriptions*

## **Soil Origin**

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Transported soils - formed somewhere else and transported by nature to the site; or
- Filling - moved by man.

Transported soils may be further subdivided into:

- Alluvium - river deposits
- Lacustrine - lake deposits
- Aeolian - wind deposits
- Littoral - beach deposits
- Estuarine - tidal river deposits
- Talus - scree or coarse colluvium
- Slopewash or Colluvium - transported downslope by gravity assisted by water. Often includes angular rock fragments and boulders.



## Rock Strength

Rock strength is defined by the Point Load Strength Index ( $Is_{(50)}$ ) and refers to the strength of the rock substance and not the strength of the overall rock mass, which may be considerably weaker due to defects. The test procedure is described by Australian Standard 4133.4.1 - 2007. The terms used to describe rock strength are as follows:

Term	Abbreviation	Point Load Index $Is_{(50)}$ MPa	Approximate Unconfined Compressive Strength MPa*
Extremely low	EL	<0.03	<0.6
Very low	VL	0.03 - 0.1	0.6 - 2
Low	L	0.1 - 0.3	2 - 6
Medium	M	0.3 - 1.0	6 - 20
High	H	1 - 3	20 - 60
Very high	VH	3 - 10	60 - 200
Extremely high	EH	>10	>200

\* Assumes a ratio of 20:1 for UCS to  $Is_{(50)}$ . It should be noted that the UCS to  $Is_{(50)}$  ratio varies significantly for different rock types and specific ratios should be determined for each site.

## Degree of Weathering

The degree of weathering of rock is classified as follows:

Term	Abbreviation	Description
Extremely weathered	EW	Rock substance has soil properties, i.e. it can be remoulded and classified as a soil but the texture of the original rock is still evident.
Highly weathered	HW	Limonite staining or bleaching affects whole of rock substance and other signs of decomposition are evident. Porosity and strength may be altered as a result of iron leaching or deposition. Colour and strength of original fresh rock is not recognisable
Moderately weathered	MW	Staining and discolouration of rock substance has taken place
Slightly weathered	SW	Rock substance is slightly discoloured but shows little or no change of strength from fresh rock
Fresh stained	Fs	Rock substance unaffected by weathering but staining visible along defects
Fresh	Fr	No signs of decomposition or staining

## Degree of Fracturing

The following classification applies to the spacing of natural fractures in diamond drill cores. It includes bedding plane partings, joints and other defects, but excludes drilling breaks.

Term	Description
Fragmented	Fragments of <20 mm
Highly Fractured	Core lengths of 20-40 mm with some fragments
Fractured	Core lengths of 40-200 mm with some shorter and longer sections
Slightly Fractured	Core lengths of 200-1000 mm with some shorter and longer sections
Unbroken	Core lengths mostly > 1000 mm

# Rock Descriptions

## Rock Quality Designation

The quality of the cored rock can be measured using the Rock Quality Designation (RQD) index, defined as:

$$\text{RQD \%} = \frac{\text{cumulative length of 'sound' core sections} \geq 100 \text{ mm long}}{\text{total drilled length of section being assessed}}$$

where 'sound' rock is assessed to be rock of low strength or better. The RQD applies only to natural fractures. If the core is broken by drilling or handling (i.e. drilling breaks) then the broken pieces are fitted back together and are not included in the calculation of RQD.

## Stratification Spacing

For sedimentary rocks the following terms may be used to describe the spacing of bedding partings:

Term	Separation of Stratification Planes
Thinly laminated	< 6 mm
Laminated	6 mm to 20 mm
Very thinly bedded	20 mm to 60 mm
Thinly bedded	60 mm to 0.2 m
Medium bedded	0.2 m to 0.6 m
Thickly bedded	0.6 m to 2 m
Very thickly bedded	> 2 m

# Symbols & Abbreviations

## Douglas Partners



### Introduction

These notes summarise abbreviations commonly used on borehole logs and test pit reports.

### Drilling or Excavation Methods

C	Core drilling
R	Rotary drilling
SFA	Spiral flight augers
NMLC	Diamond core - 52 mm dia
NQ	Diamond core - 47 mm dia
HQ	Diamond core - 63 mm dia
PQ	Diamond core - 81 mm dia

### Water

▷	Water seep
▽	Water level

### Sampling and Testing

A	Auger sample
B	Bulk sample
D	Disturbed sample
E	Environmental sample
U <sub>50</sub>	Undisturbed tube sample (50mm)
W	Water sample
pp	Pocket penetrometer (kPa)
PID	Photo ionisation detector
PL	Point load strength Is(50) MPa
S	Standard Penetration Test
V	Shear vane (kPa)

### Description of Defects in Rock

The abbreviated descriptions of the defects should be in the following order: Depth, Type, Orientation, Coating, Shape, Roughness and Other. Drilling and handling breaks are not usually included on the logs.

### Defect Type

B	Bedding plane
Cs	Clay seam
Cv	Cleavage
Cz	Crushed zone
Ds	Decomposed seam
F	Fault
J	Joint
Lam	Lamination
Pt	Parting
Sz	Sheared Zone
V	Vein

### Orientation

The inclination of defects is always measured from the perpendicular to the core axis.

h	horizontal
v	vertical
sh	sub-horizontal
sv	sub-vertical

### Coating or Infilling Term

cln	clean
co	coating
he	healed
inf	infilled
stn	stained
ti	tight
vn	veneer

### Coating Descriptor

ca	calcite
cbs	carbonaceous
cly	clay
fe	iron oxide
mn	manganese
slt	silty

### Shape

cu	curved
ir	irregular
pl	planar
st	stepped
un	undulating

### Roughness

po	polished
ro	rough
sl	slickensided
sm	smooth
vr	very rough

### Other

fg	fragmented
bnd	band
qtz	quartz



# Symbols & Abbreviations

## Graphic Symbols for Soil and Rock

### General



Asphalt



Road base



Concrete



Filling

### Soils



Topsoil



Peat



Clay



Silty clay



Sandy clay



Gravelly clay



Shaly clay



Silt



Clayey silt



Sandy silt



Sand



Clayey sand



Silty sand



Gravel



Sandy gravel



Cobbles, boulders



Talus

### Sedimentary Rocks



Boulder conglomerate



Conglomerate



Conglomeratic sandstone



Sandstone



Siltstone



Laminite



Mudstone, claystone, shale



Coal



Limestone

### Metamorphic Rocks



Slate, phyllite, schist



Gneiss



Quartzite

### Igneous Rocks



Granite



Dolerite, basalt, andesite



Dacite, epidote



Tuff, breccia



Porphyry

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Residential Development  
**LOCATION:** Ivanhoe Estate, Macquarie Park

**SURFACE LEVEL:** 45.2 AHD  
**EASTING:** 325736  
**NORTHING:** 6260351  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 10  
**PROJECT No:** 86043.01  
**DATE:** 2-11-2017  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
45	0.2	FILLING - dark brown clayey sand filling with ironstone gravel and a trace of concrete fragments, moist - root affected to 0.05m  FILLING - red-brown silty clay filling with some fine sandstone and roadbase gravel, moist  SILTY SAND - medium dense, dark brown, fine to medium silty sand with some clay and a trace of ironstone gravel, moist  SANDY CLAY - soft to firm, light brown, fine to medium sandy clay, moist  SANDSTONE - low and medium strength, light grey and orange-brown sandstone with extremely low strength bands																A/E			pp = 100 1,1,3 N = 4	
	0.6																		A/E			
1	1.0																		A/E			
44	2.1																		S			
	2.75	SANDSTONE - medium and high strength, moderately weathered to fresh, slightly fractured and unbroken, medium grained sandstone, thinly to medium bedded  <																				

**RIG:** Scout 2 **DRILLER:** Ground Test **LOGGED:** LS **CASING:** HW to 2.4m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.4m; NMLC-Coring to 8.97m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering. Water level at 4.5m depth on 12/12/17  
**REMARKS:** Well installed to 5.6m (blank 0.0-2.5m; screen 2.5-5.6m; bentonite 1.3-2.6m; gravel 2.6-5.6m)

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	W Water seep	SP Standard penetration test	
E Environmental sample	W Water level	V Shear vane (kPa)	


BORE: 10

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: 5410  
Depth: 2.40 - 7.0m  
Core Box No.: 1 of 2



2.4 - 7.0m

BORE: 10

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: 5410  
Depth: 7.0 - 9.0m  
Core Box No.: 2 of 2



7.0 - 8.97m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Residential Development  
**LOCATION:** Ivanhoe Estate, Macquarie Park

**SURFACE LEVEL:** 43.2 AHD  
**EASTING:** 325768  
**NORTHING:** 6260337  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 11  
**PROJECT No:** 86043.01  
**DATE:** 2-11-2017  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
43	0.16	CONCRETE - 20mm reinforcement at 60mm and 80mm																A			pp = 340  2.5,6 N = 11  6.3,7/40mm refusal bouncing
	0.21	SUBBASE - roadbase gravel, 25-30mm, angular to sub-angular																A/E			
	0.7	FILLING - light brown, sandy clay filling, MC>PL																A/E			
1		CLAYEY SILT - stiff, grey mottled orange-brown, clayey silt and fine sand, moist																A/E			
2	1.9	SILTY CLAY - firm, red-brown mottled grey, silty clay with a trace of fine and coarse sand, moist																S			
	2.6	2.6m: becoming wet, gravelly MC>PL																			
3	2.8	LATERITIC SANDSTONE - high strength, highly weathered, fragmented, dark red-brown mottled dark grey and orange-brown lateritic sandstone																			PL(A) = 1   PL(A) = 1.1  PL(A) = 1.2  PL(A) = 1.3   PL(A) = 1.3  PL(A) = 2.4
	3.8	SANDSTONE - high strength, slightly weathered, light red-grey, medium grained sandstone, thickly bedded																C	81	42	
4																					
5	5.31																				
6	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				
	6.0																				

**RIG:** Scout 2 **DRILLER:** Ground Test **LOGGED:** LS **CASING:** HW to 2.85m

**TYPE OF BORING:** Diacore to 0.16m; Solid flight auger (TC-bit) to 2.5m; Washbore to 2.85m; NMLC-Coring to 8.6m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** MC = Moisture Content; PL = Plastic Limit

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston Sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	> Water seep	S Standard penetration test	
E Environmental sample	≡ Water level	V Shear vane (kPa)	



BORE: 11

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: BH11  
Depth: 2.85- 7.0m  
Core Box No.: 1 of 2



2.85 – 7.0m

BORE: 11

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: BH11  
Depth: 7.0- 8.60m  
Core Box No.: 2 of 2



7.0 – 8.60m



# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Residential Development  
**LOCATION:** Ivanhoe Estate, Macquarie Park

**SURFACE LEVEL:** 45.2 AHD  
**EASTING:** 325735  
**NORTHING:** 6260295  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 12  
**PROJECT No:** 86043.01  
**DATE:** 3-11-2017  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Degree of Weathering				Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing				
			EW	HW	MW	SW		FS	FR	Ex Low	Very Low	Low				Medium	High	Very High	Ex High	B - Bedding S - Shear
45	0.15	FILLING - dark grey, medium to fine sand filling (topsoil), slightly clayey with bark and rootlets and a trace of ironstone gravel, damp															A/E			4,5,5 N = 10
		FILLING - brown, medium to fine clayey sand filling with some ironstone gravel and trace of rootlets, damp															A/E			
1		0.4-0.5m: metal and plastic wire fragment															A			
44	1.2	SANDY CLAY - stiff, brown, medium grained sandy clay, moist															S			
																	A/E			
2	2.1	SANDSTONE - extremely low to very low strength, red-brown and light grey sandstone																		
43	2.4	SANDSTONE - medium strength, moderately to highly weathered, fractured to slightly fractured, red-brown medium grained sandstone																		
3																				
42																				
	3.69																			
4	4.0	SANDSTONE - high strength, moderately weathered, slightly fractured, red-brown medium to coarse grained sandstone																		
41																				
5																				
40																				
6																				
39																				
7	6.93	Bore discontinued at 6.93m - target depth reached																		
38																				
8																				
37																				
9																				
36																				

**RIG:** Scout 2 **DRILLER:** Ground Test **LOGGED:** LS **CASING:** HW to 2.4m  
**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.4m; NMLC-Coring to 6.93m  
**WATER OBSERVATIONS:** No free groundwater observed whilst augering. Water level at 4.1m depth on 12/12/17  
**REMARKS:** Well installed to 6.93m (blank 0.0-2.1m; screen 2.1-6.93m; filling 0.0-1.5m; bentonite 1.5-2.3m; sand 2.3-6.93m)

SAMPLING & IN SITU TESTING LEGEND			
A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)	
B Bulk sample	P Piston sample	PL(A) Point load axial test Is(50) (MPa)	
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test Is(50) (MPa)	
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)	
D Disturbed sample	W Water seep	S Standard penetration test	
E Environmental sample	W Water level	V Shear vane (kPa)	

BORE: 12

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: BH12  
Depth: 2.4 - 6.95m  
Core Box No.: 1051



2.4 - 6.93m

# BOREHOLE LOG

**CLIENT:** Frasers Property Ivanhoe Pty Ltd  
**PROJECT:** Proposed Residential Development  
**LOCATION:** Ivanhoe Estate, Macquarie Park

**SURFACE LEVEL:** 46.8 AHD  
**EASTING:** 325702  
**NORTHING:** 6260260  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 13  
**PROJECT No:** 86043.01  
**DATE:** 3-11-2017  
**SHEET 1 OF 1**

[illegible]

**RIG:** Scout 2

**DRILLER:** Ground Test

**LOGGED: LS**

**CASING:** HW to 2.3m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 2.3m; NMLC-Coring to 7.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering. Water level at 4.9m depth on 12/12/17

**REMARKS:** Well installed to 7.0m (blank 0.0-2.1m; screen 2.1-7.0m; filling 0.0-1.3m; bentonite 1.5-1.8m; gravel 1.8-7.0m; gravel bridge in hole)

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test (s(50) (MPa)
		PL(D)	Point load diametral test (s(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)




BORE: 13

PROJECT: MACQUARIE PARK

OCTOBER 2017



Project No: 86043.01  
BH ID: BH 13  
Depth: 2.5 - 7.0m  
Core Box No.: 1051



2.3 - 7.0m