




ATTACHMENT 3



# WOLLONGONG COAL LTD

## Russell Vale Colliery

### Bellambi Creek Diversion Pipeline Assessment



**December 2017**

N1800\_001

[www.engeny.com.au](http://www.engeny.com.au)

P: 02 4926 1225

Suite 5, Level 1, 19 Bolton Street Newcastle 2300 | PO Box 787 Newcastle 2300

## DISCLAIMER

*This report has been prepared on behalf of and for the exclusive use of WOLLONGONG COAL LTD and is subject to and issued in accordance with WOLLONGONG COAL LTD instruction to Engeny Water Management (Engeny). The content of this report was based on previous information and studies supplied by WOLLONGONG COAL LTD.*

*Engeny accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this report by any third party. Copying this report without the permission of WOLLONGONG COAL LTD or Engeny is not permitted.*



N1800_001 Stormwater Pipeline Assessment					
D:\Desktop\N1800_001_Bellambi_Pipeline_Assessment_Rev0.docx					
REV	DESCRIPTION	AUTHOR	REVIEWER	APPROVED BY	DATE
Rev 0	Client Issue	Tim Evans - Engeny	Susan Shield - Engeny	Susan Shield - Engeny	18 December 2017
Rev 1	Client Issue	Tim Evans - Engeny	Susan Shield - Engeny	Susan Shield - Engeny	21 December 2017
Signatures					

## CONTENTS

1.	INTRODUCTION .....	4
1.1	Background .....	4
1.2	Scope of Work .....	4
1.3	Information Sources.....	5
2.	RISK ASSESSMENT .....	6
3.	KEY ISSUES AND RECOMMENDATIONS .....	8
3.1	Location Manhole B to Manhole A .....	8
3.2	Location Manhole B to Manhole C .....	10
4.	COST ESTIMATE .....	13
5.	MONITORING PROGRAM .....	14
6.	QUALIFICATIONS.....	15

## Appendices

APPENDIX A .....INTERFLOW INSPECTION REPORT AND PLANS

APPENDIX B - DETAILED PIPELINE OBSERVATIONS, RISK PROFILE AND PROPOSED REMEDIATION

## List of Tables

Table 1 - Risk matrix .....	6
Table 2 - Pollution consequence category description.....	6
Table 3 - Pollution likelihood category description .....	7
Table 4 - Suggested actions and timeframes by risk category .....	7
Table 5 - Suggested Actions. MH B to MH A .....	9
Table 6 - Suggested Actions. MH B to MH C .....	11
Table 7 – Order of Magnitude Cost Estimate – 12 month works program .....	13

## **List of Figures**

Figure 1 - Identified defects MH B to MH A.....	8
Figure 2 - Identified defects MH B to MHC, part 1 .....	10
Figure 3 - Identified defects MH B to MHC, part 2 .....	10

## 1. INTRODUCTION

### 1.1 Background

Wollongong Coal Ltd (WCL) has been issued with a Pollution Reduction Program (PRP) (PRP 8) on their Environment Protection Licence (EPL) (EPL 12040) for the Russell Vale Colliery site. The PRP has stemmed from the observance of turbid stormwater, with a grey/brown colour, that is discharged from the premises during and after high volume rainfall events.

*PRP 8 – Stormwater Turbidity Reduction Program – Part 1 – Stormwater Pipelines* identified that discharge of turbid groundwater has occurred due to groundwater ingress from fractures and degraded connections in to the Bellambi Gully clean stormwater diversion pipe.

The PRP stipulates that the licensee (WCL), must arrange for inspections of the Bellambi Gully Diversion Pipe to determine the condition of the pipe network and the maintenance required to prevent ingress of turbid water. A remote closed-circuit television (CCTV) inspection of the pipeline was conducted by Interflow on 13/20 June 2017.

### 1.2 Scope of Work

Engeny Water Management (Engeny) has been engaged to:

- Collate and review background information.
- Prepare a report detailing:
  - The work carried out as part of the pipeline inspection program.
  - Identification of works required to minimise ingress of water
  - A suggested timeframe for rectification based on a risk analysis for the defects.
  - Order of magnitude cost estimate for the repair works.
  - Outline monitoring that can be used to assess the effectiveness of the works.

### 1.3 Information Sources

The following information was used for the purpose of this review:

- Interflow pipeline inspection report and inspection plan.
  - 20170613 - DN1800.pdf
  - Bellambi Creek Diversion Inspection from MHB to MHA.pdf
  - Bellambi Creek Diversion Inspection from MHB to MHC.pdf
- EPL 12040

#### Pipeline Description

The Bellambi Gully Pipeline is a clean water diversion pipe that conveys upslope runoff from the Bellambi Gully catchment area under the coal stockpile at the Russell Vale Colliery pit top to the creek line downstream.

The pipe is an 1800 mm diameter concrete pipe of approximately 608 metres long. Some sections of the pipe have a concrete based constructed in them, other sections are lined with corrugated pipe.

#### Pipeline inspection and previous work

Interflow conducted a remote CCTV inspection of the Bellambi Gully Diversion Pipeline on 16 and 20 June 2017. A total of 76 observations, including 62 defects were recorded. The Interflow report for the inspection and the plans produced can be viewed in Appendix A.

The Interflow inspection identifies defects in the pipeline, but does not provide a risk based monitoring and maintenance program to minimise water ingress into the diversion, as per the PRP.

The following types of defects were noted by Interflow from the CCTV inspection:

- Connections with poor workmanship, possibly due to displacement
- Infiltration at pipe joints
- Encrustation/scale
- Defective repairs, including major and irregular gaps in the pipe wall
- Deformation/bulging of pipe walls (in corrugated lined sections).
- Rusting of exposed reinforcing

## 2. RISK ASSESSMENT

A risk matrix was developed to categorise the pipe defects according to their pollution risk. Each identified pipe defect was assessed according to the probability that it would allow turbid groundwater inflows into the clean water system, as well as the estimated consequence/severity of the pollution scenario.

A risk profile for each defect was applied using the risk matrix. The risk profile, ranging from Very Low to Critical, was then used to inform the timeframes for the required rectification and pipe maintenance.

The risk matrix developed for the pipeline assessment is presented in Table 1. The descriptions of the pollution consequence and likelihood categories are presented in Table 2 and Table 3 respectively. While the suggested actions and associated timeframes for each risk category are presented in Table 4.

Table 1 - Risk matrix

		Almost certain	Likely	Moderate Likelihood	Unlikely	Rare
CONSEQUENCES	5	Critical	Critical	High	High	Moderate
	4	Critical	High	High	Moderate	Low
	3	High	High	Moderate	Low	Low
	2	High	Moderate	Low	Low	Very Low
	1	Moderate	Low	Low	Very Low	Very Low

Table 2 - Pollution consequence category description

Consequence category	Description
5	Extreme damage to pipe, total failure. Large volume of turbid water discharged off site.
4	Major damage to pipe, large volume of turbid water discharged off site.
3	Moderate damage to pipe, small to medium volume of turbid water discharged off site. Or obstruction with potential to back up pipe in large storm events to cause a small to medium volume of turbid water discharged off site.
2	Minor impact to pipe. Minor volumes of turbid water inflow into pipe.
1	Minor degradation to pipe, negligible impact on conveyance or containment. No inflow of turbid water.



**Table 3 - Pollution likelihood category description**

Likelihood	Description
Almost certain	Pollution is currently likely to be occurring, or will likely happen within a month.
Likely	Pollution is likely to happen within 6-12 months.
Moderate Likelihood	Pollution is likely within approximately 1-5 years without amelioration.
Unlikely	Pollution potential without amelioration within 5+ years.
Rare	Pollution potential negligible.

**Table 4 - Suggested actions and timeframes by risk category**

Risk Category	Timeframe and required actions.
Critical	Urgent remediation works required. Works to be implemented to reduce the risk exposure to an acceptable level (i.e. low or very low).
High	Remediation works required within 1 to 6 months. Works to be implemented to reduce the risk exposure to an acceptable level (i.e. low or very low).
Moderate	Monitor ongoing risk of pollution and deterioration of the pipe. Remediation works required within 6-18 months.
Low	Annual monitoring required. Remediation works likely to be required within 1 - 5 years
Very Low	Annual monitoring required.

### 3. KEY ISSUES AND RECOMMENDATIONS

Based on the review of the supplied data and the risk assessment process undertaken for the identified defects, the following summary of the suggested remediation works and associated timeframes has been developed. The full list of defects and suggested remediation method is presented in Appendix B.

Based on the risk ranking, defects assessed as being *moderate* to *critical* require remediation works, while defects assessed as having a *low* to *very low* pollution risk are unlikely to require remediation works in the next year. An ongoing monitoring program is to be implemented to regularly inspect the defects to determine the efficacy of the remediation works and any worsening of the low and very low ranked risk defects. Refer to Section 4 for details.

#### 3.1 Location Manhole B to Manhole A

The Bellambi Gully Diversion Pipeline extends approximately 167 m from Manhole B to Manhole A. The pipeline consists of 1800 mm diameter reinforced concrete pipe or corrugated metal pipe. A summary of the observations by chainage and their assessed risk profile is presented below in Figure 1.




Figure 1 - Identified defects MH B to MH A

A total of 29 defects or observations were made on the Bellambi pipeline between Manhole B to Manhole A. Most of the defects occur between chainages 3 – 56 m, with an isolated observation of a wooden obstruction at Chainage 166.70 m. The risk ranking for the defects range from Very Low to High.

Structural damage to the pipeline has been identified between chainages 3 – 16 m, as indicated by exposed reinforcement and cracking. This suggests that the serviceability limit state for the pipeline has locally been exceeded, likely from an external surface loading.

A number of external connections have been identified between chainage 16 – 22 m. These external connections pose a risk of directing turbid water directly in to the pipeline. Even if the connections are redundant and blocked off, a risk exists that turbid groundwater will be able to seep around the penetration in to the clean water system.

A summary of the suggested pipeline remediation works is presented in Table 5.

**Table 5 - Suggested Actions. MH B to MH A**

Chainage (m) and Number of Defects	Action	Timeframe
3 – 16 (7 defects – structural)	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1 – 6 months
16 – 22 (7 defects – external penetrations)	The source of the external connections needs to be investigated, only clean water sources are to be directed to the pipeline. Repair the external connections by either epoxy pressure grouting the annulus between the RCP and the penetration or remove the penetration, and reinstate RCP wall by scrubbing/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1 – 6 months
28 – 56 (7 defects – suspected deteriorated seals causing infiltration. Encrustation/scale present)	For infiltration and deteriorated jointing mechanisms Remediate defects by cement pressure grouting annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.  Within the 28 m length of pipe, there are 4 pipe jointing mechanisms that are failing, some in multiple places with varying risk categories at each failure point. In total the risk ratings of the defects in the area are 1 x High, 3 x Moderate and 2 x Low. Due to the similar nature of the repairs in this area, the defects have been grouped together for remediation.	1-6 months  An opportunity exists to only remediate the defects identified as presenting a High or Moderate risk. The remaining defects could be assessed through the ongoing monitoring program.
166.72	Confirm if pit and external connection are still required. If not, construct reinforced concrete plug, dowelled in to RCP/Manhole. If still required, make sure lid is adequately seals.	1-6 months

### 3.2 Location Manhole B to Manhole C

The Bellambi Gully Diversion Pipeline extends approximately 441 m from Manhole B to Manhole C. The pipeline consists of 1800 mm diameter reinforced concrete or corrugated iron. A summary of the observations by chainage and assessed risk profile is presented below in Figures 2 and 3.




Figure 2 - Identified defects MH B to MHC, part 1




Figure 3 - Identified defects MH B to MHC, part 2

A total of 47 defects or observations were made on the Bellambi Gully pipeline between Manhole B to Manhole C. The risk ranking for the defects range from Very Low to Moderate. The majority of the moderate risk defects were recorded between chainages 320 – 395 m.

The moderate risk observations generally pertain to suspected infiltration, vertical deformations of the pipeline – likely from a dynamic surface loading, or longitudinal wall cracks, again suggesting structural damage to the pipeline.

A summary of the suggested pipeline remediation works is presented in Table 6.

**Table 6 - Suggested Actions. MH B to MH C**

Chainage (m) and Number of Defects	Action	Timeframe
<p>0 - 307</p> <p>(17 defects: 5 moderate; 8 low; 4 very low)</p>	<p>Localised repairs and pipe cleaning required. Refer to detailed observations and suggested remediation works in Appendix B. Further investigation of some defects is required, refer to Appendix B. Suggest an ongoing pipeline monitoring program be initiated to assess the lower risk category defects.</p> <p>For infiltration and deteriorated jointing mechanisms Remediate defects by cement pressure grouting annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.</p> <p>Remove blockages, defective connections and clean pipe as required.</p> <p>Bulging of the pipe wall and bellies in the line identified. Where safe to do so, install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.</p> <p>Within the 307 m length of pipe, there are 17 recorded defects. In total the risk ratings of the defects in the area are 5 x Moderate, 8 x Low and 4 x Very Low. It is anticipated that only the Moderate risk defects will be initially remediated, however an opportunity exists to group some of the remediation of the lower risk defects due to the similar nature of the repairs.</p> <p>The moderate defects in general consist of deteriorated pipe joint seals, or bulges/bellies in the corrugated metal pipe wall/floor.</p>	<p>6 to 18 months</p> <p>(As per identified risk profile for each hazard. Ranging from 6-18 months for 'Moderate' risk defects, or as identified by ongoing pipeline monitoring program.</p>
<p>70.84, 349.96, 375 – 386, 416.35</p> <p>(10 defects, 7 moderate, 3 very low)</p>	<p>Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.</p>	<p>6-18 months</p>

Chainage (m) and Number of Defects	Action	Timeframe
320 – 440 (17 defects: 16 Moderate, 1 low)	<p>Localised repairs and pipe cleaning required. Refer to detailed observations and suggested remediation works in Appendix B.</p> <p>Within the 120 m length of pipe, there are 17 recorded defects. In total the risk ratings of the defects in the area are 16 x Moderate and 1 x Low. It is anticipated that only the Moderate risk defects will be initially remediated. Further investigation of the low risk defect (dropped invert) at Ch 400 is required to determine the appropriate repair method if deemed to be required.</p> <p>For infiltration and deteriorated jointing mechanisms Remediate defects by cement pressure grouting annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.</p> <p>Epoxy pressure grout longitudinal wall and surface cracks.</p>	6-18 months
38.06, 306.27 (2 defects: To be determined if potential for groundwater ingress exists at the pits)	Unknown pits identified. Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	As identified by ongoing pipeline monitoring program.

## 4. COST ESTIMATE

An order of magnitude cost estimate has been developed for the remediation works. The full costs associated with the repair of each defect can be seen in Appendix B. Table 7 presents a summary of the repair works grouped by risk category and timeframe.

Table 7 – Order of Magnitude Cost Estimate – 18 month works program

Risk Category	Total estimated cost of remediation works (ex GST)	Timeframe
Critical	\$0	Immediate
High	\$270,000	1 – 6 months
Moderate	\$225,000	6 – 18 months
Total	\$495,000	-

The cost estimate is based on two programs of work by a single contractor for each program. The cost estimates include mobilisation/demobilisation and site access estimate of \$20,000 (ex GST) per works program (i.e. one for high risk category works and one for moderate risk category works).

## **5. MONITORING PROGRAM**

A monitoring program of the Bellambi Gully Diversion Pipeline is required to be implemented as part of the PRP for the Russell Vale Colliery Site. The ongoing monitoring program is required to ascertain the efficacy of the proposed remediation works and to identify any worsening of non-remediated defects.

A yearly CCTV inspection program is to be implemented. The CCTV monitoring should be undertaken following the suggested remediation works to the pipeline. The monitoring program should address the following points:

- Investigation of the remediation works on defective areas previously identified as having a risk category of Moderate – Critical. The inspection should ascertain that the remediation has been successful and that there are no indications of further groundwater ingress from the defect.
- Investigate defects assessed as having a Very Low to Low risk category. The inspection should note if any worsening of the defect is observed to allow for reassessment of the defect's risk category.

WCL will review the yearly inspections and document in the Annual Review the following:

- All current defects on the pipeline.
- Identification of incidents or failures of all previous remediation works and necessary/adopted corrective actions.
- Any worsening of defective areas that have not been remediated, relative to previous pipeline inspections.



## **6. QUALIFICATIONS**


- a. In preparing this document, including all relevant calculation and modelling, Engeny Water Management (Engeny) has exercised the degree of skill, care and diligence normally exercised by members of the engineering profession and has acted in accordance with accepted practices of engineering principles.
- b. Engeny has used reasonable endeavours to inform itself of the parameters and requirements of the project and has taken reasonable steps to ensure that the works and document is as accurate and comprehensive as possible given the information upon which it has been based including information that may have been provided or obtained by any third party or external sources which has not been independently verified.
- c. Engeny reserves the right to review and amend any aspect of the works performed including any opinions and recommendations from the works included or referred to in the works if:
  - (i) Additional sources of information not presently available (for whatever reason) are provided or become known to Engeny; or
  - (ii) Engeny considers it prudent to revise any aspect of the works in light of any information which becomes known to it after the date of submission.
- d. Engeny does not give any warranty nor accept any liability in relation to the completeness or accuracy of the works, which may be inherently reliant upon the completeness and accuracy of the input data and the agreed scope of works. All limitations of liability shall apply for the benefit of the employees, agents and representatives of Engeny to the same extent that they apply for the benefit of Engeny.
- e. This document is for the use of the party to whom it is addressed and for no other persons. No responsibility is accepted to any third party for the whole or part of the contents of this report.
- f. If any claim or demand is made by any person against Engeny on the basis of detriment sustained or alleged to have been sustained as a result of reliance upon the report or information therein, Engeny will rely upon this provision as a defence to any such claim or demand.
- g. This report does not provide legal advice.

# APPENDIX A

## Interflow Inspection Report and Plans









WCL RUSSELL VALE COLLIERY  
WOLLONGONG COAL LIMITED  
7 Princes Highway, Corrimal, NSW 2518  
ABN 28 111 244 896

TITLE		
Bellambi Creek Diversion Pipe Inspection Plan		
NAME	DATE	
DRN	RT	20/10/2017
CKD		
APP		
SCALE	Not in Scale @A2	
DRAWING NUMBER		REV
RVC-ENV-xxx		0







WCL RUSSELL VALE COLLIERY  
WOLLONGONG COAL LIMITED  
7 Princes Highway, Corimal, NSW 2518  
ABN 28 111 244 896

TITLE		
Bellambi Creek Diversion Pipe Inspection Plan		
DRN	NAME	DATE
CKD	RT	20/10/2017
APP		
SCALE	Not in Scale @A2	
DRAWING NUMBER	REV	
RVC-ENV-xxx	0	



## WSA assessment

Date: <b>13/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>1</b>	Pipe Asset Id: <b>SW001 (Section 3)</b>
Time of inspection: <b>10:56:43</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH B</b> <b>downstream</b> <b>MH C</b> <b>119.21 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>1.5</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>0</b>

Remarks :

1:945	Position	Code	Observation						
	0.00	STMS	Start node, maintenance shaft, Nodename: MH B	<p>19.74 m</p>					
	19.74	CNPC	Connection, poor workmanship, connection appears to be open , diameter approx 225mm , General Comments suspect a possible displacement	<p>23.77 m</p>					
	23.77	SWS	Wall Staining is present on the surface of the conduit, at joint, General Comments Possible infiltration is present, at 4 o'clock	<p>26.45 m</p>					
	26.45	IR	Infiltration, running, at joint, General Comments Wall staining also present, at 4 o'clock	<p>26.45 m</p>					
	26.45	DEE	Encrustation/Scale is attached to the wall above the water line, at joint, Obstruction: <5%, General Comments from infiltration , at 4 o'clock	<p>34.20 m</p>					
	34.20	SRV	Steel reinforcement is visible with little or no corrosion evident , at 12 o'clock	<p>38.06 m</p>					
	38.06	GC	General Comments Unknown Pit found	<p>70.84 m</p>					
	70.84	MC	New material, Corrugated Iron , General Comments Reduces diameter of pipe	<p>70.84 m</p>					
	70.84	RXM	Defective repair, major or irregular gaps or both in the pipe wall , General Comments Packer is hanging loose	<p>70.84 m</p>					
	70.84	S1 DM	Deformation, mixed orientation , change in diameter 5-10%, length of deformation 500mm, General Comments Corrugated iron causing deformed pipe shape, from 12 to 1	<p>107.30 m</p>					
	107.30	RXB	Defective repair, bellies in the line , General Comments dropping of corrugated iron	<p>26.45 m</p>					
	119.21	DEW	Other Deposits on the wall, Rusting , Obstruction: <5% , at 1 o'clock	<p>34.2 m</p>					
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>13/06/2017</b>	Section number: <b>1</b>	Sewer Ref.: <b>SW001 (Section 3)</b>
---	-----------------	-----------------------------	-----------------------------	---



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_110637\_A.jpg  
19.74m, Connection, poor workmanship, connection appears to be open , diameter approx 225mm , General Comments suspect a possible displacement



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_110739\_A.jpg  
23.77m, Wall Staining is present on the surface of the conduit, at joint, General Comments Possible infiltration is present, at 4 o'clock



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111022\_A.jpg  
26.45m, Infiltration, running, at joint, General Comments Wall staining also present, at 4 o'clock



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111019\_A.jpg  
26.45m, Encrustation/Scale is attached to the wall above the water line, at joint, Obstruction: <5%, General Comments from infiltration , at 4 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>13/06/2017</b>	Section number: <b>1</b>	Sewer Ref.: <b>SW001 (Section 3)</b>
---	-----------------	-----------------------------	-----------------------------	---



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111118\_A.jpg  
34.2m, Steel reinforcement is visible with little or no corrosion evident , at 12 o'clock



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111243\_A.jpg  
38.06m, General Comments Unknown Pit found



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111620\_A.jpg  
70.84m, New material, Corrugated Iron , General Comments Reduces diameter of pipe



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111631\_B.jpg  
70.84m, New material, Corrugated Iron , General Comments Reduces diameter of pipe



## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>13/06/2017</b>	Section number: <b>1</b>	Sewer Ref.: <b>SW001 (Section 3)</b>
---	-----------------	-----------------------------	-----------------------------	---



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_111827\_A.jpg  
70.84m, Defective repair, major or irregular gaps or both in the pipe wall , General Comments Packer is hanging loose



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_112122\_A.jpg  
107.3m, Defective repair, bellies in the line , General Comments dropping of corrugated iron



Photo: SW001 (Section 3)\_MH B\_MH  
C\_20062017\_112234\_A.jpg  
119.21m, Other Deposits on the wall, Rusting , Obstruction: <5% , at 1 o'clock




## WSA assessment

Date: <b>20/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>2</b>	Pipe Asset Id: <b>SW001 (Section 3A)</b>
Time of inspection: <b>11:25:13</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH B</b> <b>downstream</b> <b>MH C</b> <b>130.03 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>1.5</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>0</b>

Remarks :

**1:1035 Position Code Observation**



6.26 m



12.77 m



19.86 m



116.29 m

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>2</b>	Sewer Ref.: <b>SW001 (Section 3A)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3A)\_MH B\_MH  
C\_20062017\_112729\_A.jpg  
6.26m, New material, Corrugated Iron



Photo: SW001 (Section 3A)\_MH B\_MH  
C\_20062017\_112849\_A.jpg  
12.77m, Defective repair, bellies in the line , General Comments  
Drooping of corrugated iron



Photo: SW001 (Section 3A)\_MH B\_MH  
C\_20062017\_113011\_A.jpg  
19.86m, General Comments Multiple joining mechanisms on  
pipe wall to hold corrugated iron in place; rusting present



Photo: SW001 (Section 3A)\_MH B\_MH  
C\_20062017\_113837\_A.jpg  
116.29m, Defective repair , other defects: Bulging of pipe wall  
@ 3 o'clock

## WSA assessment

Date: <b>20/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>3</b>	Pipe Asset Id: <b>SW001 (Section 3B)</b>
Time of inspection: <b>11:40:25</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH B</b> <b>downstream</b> <b>MH C</b> <b>129.67 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>1.5</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>0</b>


Remarks :

1:918	Position	Code	Observation	
	9.56	MC	New material, Corrugated Iron	11.92 m
	11.92	RXZ	Defective repair , other defects: Bulging of corrugated iron in invert	
	21.35	RXZ	Defective repair , other defects: Bulging of corrugated iron, General Comments on left hand side of pipe wall	21.35 m
	44.67	MC	New material, Reinforced Concrete Pipe , General Comments Returns to original pipe material	
	52.60	GC	General Comments Large repair	
	53.45	DI	Dropped invert , depth of drop 8mm, General Comments slight dip in invert	
	58.03	GC	General Comments Unknown Pit found	
	58.03	CLW	Longitudinal wall crack , width 2mm, General Comments on unknown pit wall, at 11 o'clock	52.6 m
	71.65	IYY	Suspected Infiltration , General Comments at pipe joint, from 4 to 6 o'clock	
	74.02	IYY	Suspected Infiltration, at joint, General Comments from pipe joint, from 4 to 6 o'clock	
	82.00	IYY	Suspected Infiltration, at joint, General Comments at joint, from 4 to 6 o'clock	53.45 m
	88.72	IYY	Suspected Infiltration, at joint , from 2 to 6 o'clock	
	101.72	DV	Vertical deformation , change in diameter 5-10%, length of deformation 200mm, General Comments pipe has been squashed, at 10 o'clock	
	112.54	IYY	Suspected Infiltration, at joint , from 6 to 9 o'clock	58.03 m
	114.94	IYY	Suspected Infiltration, at joint , from 6 to 9 o'clock	

## Inspection Report

Date : <b>20/06/2017</b>	Job number :	Weather :	Operator : <b>A.Thoms</b>	Counter : <b>3</b>	Pipe Asset Id :
Present :	Vehicle :	Camera :	Preset :	Cleaned : <b>not cleaned</b>	Rate :

**1:918 Position Code Observation**



STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>3</b>	Sewer Ref.: <b>SW001 (Section 3B)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_120205\_A.jpg  
11.92m, Defective repair , other defects: Bulging of corrugated iron in invert



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_120355\_A.jpg  
21.35m, Defective repair , other defects: Bulging of corrugated iron, General Comments on left hand side of pipe wall



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_120712\_A.jpg  
52.6m, General Comments Large repair



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_120811\_A.jpg  
53.45m, Dropped invert , depth of drop 8mm, General Comments slight dip in invert



## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>3</b>	Sewer Ref.: <b>SW001 (Section 3B)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_120915\_A.jpg  
58.03m, General Comments Unknown Pit found



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121016\_A.jpg  
58.03m, Longitudinal wall crack , width 2mm, General  
Comments on unknown pit wall, at 11 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121123\_A.jpg  
71.65m, Suspected Infiltration , General Comments at pipe joint,  
from 4 to 6 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121153\_A.jpg  
74.02m, Suspected Infiltration, at joint, General Comments from  
pipe joint, from 4 to 6 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>3</b>	Sewer Ref.: <b>SW001 (Section 3B)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121227\_A.jpg  
82m, Suspected Infiltration, at joint, General Comments at joint, from 4 to 6 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121306\_A.jpg  
88.72m, Suspected Infiltration, at joint , from 2 to 6 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121447\_A.jpg  
101.72m, Vertical deformation , change in diameter 5-10%, length of deformation 200mm, General Comments pipe has been squashed, at 10 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121530\_A.jpg  
112.54m, Suspected Infiltration, at joint , from 6 to 9 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>3</b>	Sewer Ref.: <b>SW001 (Section 3B)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121553\_A.jpg  
114.94m, Suspected Infiltration, at joint , from 6 to 9 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121637\_A.jpg  
117.98m, Longitudinal wall crack , width 2mm, General  
Comments runs through to pipe sections, at 12 o'clock, Start



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121722\_A.jpg  
127.22m, Vertical deformation , change in diameter 5-10%,  
length of deformation 300mm , at 12 o'clock



Photo: SW001 (Section 3B)\_MH B\_MH  
C\_20062017\_121827\_A.jpg  
129.67m, Vertical deformation , change in diameter 5-10%,  
length of deformation 200mm , at 12 o'clock



--

Town:		Catchment:		US MH:	<b>MH B</b>
Suburb:	<b>Russell Vale</b>	Asset Owner:	<b>Wollongong Coal</b>	Survey Dir:	<b>downstream</b>
Street:	<b>Wollongong Coal</b>	Precipitation.:		DS MH:	<b>MH C</b>
Asset Location	<b>Private property, industrial site</b>	Flow control	<b>No measures</b>	Inspect Length :	<b>129.50 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>		Shape :	<b>Circular</b>	
Use of Conduit:	<b>Drain</b>		Dia/Height:	<b>1800 mm</b>	
Type of Conduit:	<b>Storm water drain</b>		Start Depth To Invert:	<b>1.5</b>	
Pipe Material:	<b>Concrete pipe</b>		End Depth To Invert:	<b>0</b>	
Remarks :					

1:1020	Position	Code	Observation	
	66.58	GC	General Comments Unknown starting meterage	
	71.04	S1	CLW	Longitudinal wall crack , width 2mm , at 12 o'clock, Start
	74.34	DV	Vertical deformation , change in diameter 5-10%, length of deformation 200mm , at 11 o'clock	
	74.96	E1	CLW	Longitudinal wall crack , width 2mm , at 12 o'clock, End
	83.61	CLS	Longitudinal surface crack , width 2mm , at 12 o'clock	
	88.95	DI	Dropped invert , depth of drop 10mm, General Comments dip in pipe invert	
	105.02	DV	Vertical deformation , change in diameter 5-10%, length of deformation 500mm , at 12 o'clock	
	128.77	GC	General Comments Unknown Pit found	
	128.82	LR	The conduit curves to the right, length of curved section 500mm	
STR no def	STR peak	STR mean	STR total	STR grade
4	12129.50	0.22	FHO	0
SER no def				
SER peak				
SER mean				
SER total				
SER grade				
0				
0				
1				
Node name: MH C				

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>4</b>	Sewer Ref.: <b>SW001 (Section 3C)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122312\_A.jpg  
71.04m, Longitudinal wall crack , width 2mm , at 12 o'clock,  
Start



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122345\_A.jpg  
74.34m, Vertical deformation , change in diameter 5-10%,  
length of deformation 200mm , at 11 o'clock



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122402\_A.jpg  
74.96m, Longitudinal wall crack , width 2mm , at 12 o'clock,  
End



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122457\_A.jpg  
83.61m, Longitudinal surface crack , width 2mm , at 12 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>4</b>	Sewer Ref.: <b>SW001 (Section 3C)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122557\_A.jpg  
88.95m, Dropped invert , depth of drop 10mm, General  
Comments dip in pipe invert



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122614\_B.jpg  
88.95m, Dropped invert , depth of drop 10mm, General  
Comments dip in pipe invert



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_122831\_A.jpg  
105.02m, Vertical deformation , change in diameter 5-10%,  
length of deformation 500mm , at 12 o'clock



Photo: SW001 (Section 3C)\_MH B\_MH  
C\_20062017\_123342\_A.jpg  
129.5m, Finish node, outfall or culvert headwall, Nodename:  
MH C

## WSA assessment

Date: <b>20/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>5</b>	Pipe Asset Id: <b>SW001 (U/S Part 1)</b>
Time of inspection: <b>12:34:56</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH A</b> <b>upstream</b> <b>MH B</b> <b>34.41 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>0</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>1.5</b>

Remarks :

**1:180 Position Code Observation**

	3.34	SRV	Steel reinforcement is visible with little or no corrosion evident , from 11 to 1 o'clock
	3.34	SY	Suspected Surface Damage , Obstruction: 5-20%, General Comments Hole in pipe obvert has been repaired using a steel sheet, from 10 to 2 o'clock
	3.75	SRV	Steel reinforcement is visible with little or no corrosion evident , from 11 to 1 o'clock
	10.44	SRC	Reinforcement is exposed and corroded , General Comments possible repair of pipe hole, from 11 to 1 o'clock
	10.55	DEE	Encrustation/Scale is attached to the wall above the water line , Obstruction: <5%, General Comments Possibly caused by infiltration , at 10 o'clock
	15.83	SRV	Steel reinforcement is visible with little or no corrosion evident , at 12 o'clock
	15.92	SH	Hole in wall, at joint, General Comments with reinforcement exposed, at 12 o'clock
	15.92	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments protruding into line with reinforcement exposed, at 10 o'clock
	15.92	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line, at 10 o'clock
	18.85	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line, at 10 o'clock
	19.23	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 11 o'clock
	19.23	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 12 o'clock
	19.23	CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 12 o'clock
	20.90	GC	General Comments Unknown Pit found
	21.24	CXD	Defective Connection - The connecting pipe is damaged, magnitude of obstruction 51-75%, General Comments Collapsed 600mm junction, at 3 o'clock



3.34 m



3.34 m



3.75 m



10.44 m




10.55 m

## Inspection Report

Date : <b>20/06/2017</b>	Job number :	Weather :	Operator : <b>A.Thoms</b>	Counter : <b>5</b>	Pipe Asset Id :
Present :	Vehicle :	Camera :	Preset :	Cleaned : <b>not cleaned</b>	Rate :

**1:180 Position Code Observation**



STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade



## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>5</b>	Sewer Ref.: <b>SW001 (U/S Part 1)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_123939\_A.jpg  
3.34m, Steel reinforcement is visible with little or no corrosion evident , from 11 to 1 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124126\_A.jpg  
3.34m, Suspected Surface Damage , Obstruction: 5-20%, General Comments Hole in pipe obvert has been repaired using a steel sheet, from 10 to 2 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124203\_A.jpg  
3.75m, Steel reinforcement is visible with little or no corrosion evident , from 11 to 1 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124258\_A.jpg  
10.44m, Reinforcement is exposed and corroded , General Comments possible repair of pipe hole, from 11 to 1 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>5</b>	Sewer Ref.: <b>SW001 (U/S Part 1)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124444\_A.jpg  
10.55m, Encrustation/Scale is attached to the wall above the water line , Obstruction: <5%, General Comments Possibly caused by infiltration , at 10 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124517\_A.jpg  
15.83m, Steel reinforcement is visible with little or no corrosion evident , at 12 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124615\_A.jpg  
15.92m, Hole in wall, at joint, General Comments with reinforcement exposed, at 12 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124734\_A.jpg  
15.92m, Intruding connection, magnitude of intrusion: 5-20%, General Comments protruding into line with reinforcement exposed, at 10 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>5</b>	Sewer Ref.: <b>SW001 (U/S Part 1)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124808\_A.jpg  
15.92m, Intruding connection, magnitude of intrusion: 5-20%,  
General Comments Protruding into line, at 10 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124838\_A.jpg  
18.85m, Intruding connection, magnitude of intrusion: 5-20%,  
General Comments Protruding into line, at 10 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_124943\_A.jpg  
19.23m, Intruding connection, magnitude of intrusion: 5-20%,  
General Comments Protruding into line with reinforcement exposed, at 11 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_125011\_A.jpg  
19.23m, Intruding connection, magnitude of intrusion: 5-20%,  
General Comments Protruding into line with reinforcement exposed, at 12 o'clock



## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>5</b>	Sewer Ref.: <b>SW001 (U/S Part 1)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_125036\_A.jpg  
19.23m, Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 12 o'clock



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_125105\_A.jpg  
20.9m, General Comments Unknown Pit found



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_125115\_B.jpg  
20.9m, General Comments Unknown Pit found



Photo: SW001 (US Part 1)\_MH A\_MH B\_20062017\_125206\_A.jpg  
21.24m, Defective Connection - The connecting pipe is damaged, magnitude of obstruction 51-75%, General Comments Collapsed 600mm junction, at 3 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>5</b>	Sewer Ref.: <b>SW001 (U/S Part 1)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 1)\_MH A\_MH  
B\_20062017\_125234\_A.jpg  
21.36m, New material, Corrugated Iron



Photo: SW001 (US Part 1)\_MH A\_MH  
B\_20062017\_125504\_A.jpg  
28.35m, Suspected Infiltration , General Comments through  
corrugated iron, at 2 o'clock


## WSA assessment

Date: <b>20/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>6</b>	Pipe Asset Id: <b>SW001 ( U/S Part 2)</b>
Time of inspection: <b>13:15:42</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH A</b> <b>upstream</b> <b>MH B</b> <b>132.31 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>0</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>1.5</b>

Remarks :

**1:1050 Position Code Observation**




14.48 m



18.17 m



18.23 m



18.23 m



20.94 m

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade



## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>6</b>	Sewer Ref.: <b>SW001 ( U/S Part 2)</b>
---	-----------------	-----------------------------	-----------------------------	---



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132300\_A.jpg  
14.48m, Encrustation/Scale is attached to the wall above the water line , Obstruction: <5%, General Comments possibly due to infiltration , from 2 to 6 o'clock



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132436\_A.jpg  
18.17m, Dropped invert , depth of drop 10mm, General Comments drop in invert of pipe- uneven surface



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132535\_A.jpg  
18.23m, Other Deposits on the wall, Jointing Material , Obstruction: <5%, General Comments rusting/staining of joining mechanism, from 12 to 4 o'clock



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132632\_A.jpg  
18.23m, Encrustation/Scale is attached to the wall above the water line , Obstruction: <5%, General Comments rusting/staining/possible infiltration of joining mechanism , from 7 to 12 o'clock

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>6</b>	Sewer Ref.: <b>SW001 ( U/S Part 2)</b>
---	-----------------	-----------------------------	-----------------------------	---




Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132806\_A.jpg  
20.94m, Infiltration, running , General Comments spurting out  
pipe wal, from 7 to 8 o'clock




Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_132803\_A.jpg  
20.94m, Encrustation/Scale is attached to the wall above the  
water line , Obstruction: <5%, General Comments due to  
infiltration , from 6 to 12 o'clock



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_133200\_A.jpg  
129.42m, New material, Concrete Pipe , General Comments  
returns to original pipe material



Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_133414\_A.jpg  
132.29m, Connection, good workmanship, connection appears  
to be open, diameter approx 600mm , at 3 o'clock, General  
Comments Large wooden object wedged at pipe entrance

## Inspection Pictures

Location/Street  
**Wollongong Coal**

Town or suburb:

Date :  
**20/06/2017**

Section number:  
**6**

Sewer Ref.:  
**SW001 ( U/S Part 2)**




Photo: SW001 ( US Part 2)\_MH A\_MH  
B\_20062017\_133306\_A.jpg  
132.31m, General Comments Unknown pit found


## WSA assessment

Date: <b>20/06/2017</b>	Asset owner's job ref.:	Asset Owner: <b>Wollongong Coal</b>	Operator : <b>A.Thoms</b>	Section number: <b>7</b>	Pipe Asset Id: <b>SW001 (U/S Part 3)</b>
Time of inspection: <b>13:36:29</b>	Cleaning: <b>not cleaned</b>	Standard: <b>WSA 05-2008 2.2</b>	LRP <b>Inside Face of the Wall</b>	Conduit Unit Length	Method of Inspection <b>Television Camera</b>

Town: Suburb: Street: Asset Location	<b>Russell Vale</b> <b>Wollongong Coal</b> <b>Private property, industrial site</b>	Catchment: Asset Owner: Precipitation.: Flow control	<b>Wollongong Coal</b> <b>No measures</b>	US MH: Survey Dir: DS MH: Inspect Length :	<b>MH A</b> <b>upstream</b> <b>MH B</b> <b>125.29 m</b>
Purpose of inspection :	<b>Structural Condition Inspection</b>			Shape :	<b>Circular</b>
Use of Conduit:	<b>Drain</b>			Dia/Height:	<b>1800 mm</b>
Type of Conduit:	<b>Storm water drain</b>			Start Depth To Invert:	<b>0</b>
Pipe Material:	<b>Concrete pipe</b>			End Depth To Invert:	<b>1.5</b>

Remarks :

**1:990 Position Code Observation**



125.29 m

120.48

GC

General Comments starting at 120.48m

125.29

FHO

Finish node, outfall or culvert headwall, Nodename: ,  
General Comments Unable to completely reach end

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

## Inspection Pictures

Location/Street <b>Wollongong Coal</b>	Town or suburb:	Date : <b>20/06/2017</b>	Section number: <b>7</b>	Sewer Ref.: <b>SW001 (U/S Part 3)</b>
---	-----------------	-----------------------------	-----------------------------	--



Photo: SW001 (US Part 3)\_MH A\_MH  
B\_20062017\_134032\_A.jpg  
125.29m, Finish node, outfall or culvert headwall, Nodename:  
, General Comments Unable to completely reach end



## **APPENDIX B**

### **Detailed pipeline observations, risk profile and proposed remediation**

# Bellambi Gully Pipeline MHB to MHA

Total Chainage	Listed Chainage	Code	Observation	Consequence rating	Likelihood	Risk category	Remediation	Qty	Unit	Rate	Cost
3.34		SRV	Steel reinforcement is visible with little or no corrosion evident, from 11 to 1 o'clock	4	Moderate Likelihood	High	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	13	m	\$ 15,000	\$ 195,000
3.34		SYV	Suspected Surface Damage, Obstruction: 5-20%, General Comments Hole in pipe obvert has been repaired using a steel sheet, from 10 to 2 o'clock	4	Likely	High	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 15,000	\$ -
3.75		SRV	Steel reinforcement is visible with little or no corrosion evident, from 11 to 1 o'clock	3	Rare	Low	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 15,000	\$ -
10.44		SRC	Reinforcement is exposed and corroded, General Comments possible repair of pipe hole, from 11 to 1 o'clock	4	Moderate Likelihood	High	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 15,000	\$ -
10.55		DEE	Encrustation/Scale is attached to the wall above the waterline, Obstruction: <5%, General Comments Possibly caused by infiltration, at 10 o'clock	1	Almost certain	Moderate	Clean pipe.	0	Item	\$ 1,000	\$ -
15.83		SRV	Steel reinforcement is visible with little or no corrosion evident, at 12 o'clock	4	Moderate Likelihood	High	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 15,000	\$ -
15.92		SH	Hole in wall, at joint, General Comments with reinforcement exposed, at 12 o'clock	4	Moderate Likelihood	High	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 15,000	\$ -
15.92		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments protruding into line with reinforcement exposed, at 10 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
15.92		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line, at 10 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
18.85		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line, at 10 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
19.23		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 11 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
19.23		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 12 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
19.23		CI	Intruding connection, magnitude of intrusion: 5-20%, General Comments Protruding into line with reinforcement exposed, at 12 o'clock	3	Likely	High	Investigate source of connection, only clean water sources to be directed to pipeline. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scabbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 5,200	\$ 5,200
20.90		GC	General Comments Unknown Pit found	0	N/A	Comment	Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	1	Item	\$ 10,500	\$ 10,500
21.24		CXD	Defective Connection - The connecting pipe is damaged, magnitude of obstruction 51-75%, General Comments Collapsed 600mm junction, at 3 o'clock	3	Likely	High	Construct reinforced concrete plug, dowelled in to connecting RCP.	1	Item	\$ 10,500	\$ 10,500
21.36		MC	New material, Corrugated Iron	0	N/A	Comment					
23.92		GC	General Comments Multiple attachments on pipe wall to hold corrugated iron in place; rusting present throughout	0	N/A	Comment					
28.35		IYY	Suspected Infiltration, General Comments through corrugated iron, at 2 o'clock	1	Almost certain	Moderate	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
34.41		GC	General Comments Section completed	0	N/A	Comment					
46.91	12.50	GC	General Comments Starts at 12.5m	0	N/A	Comment					
48.89	14.48	DEE	Encrustation/Scale is attached to the wall above the waterline, Obstruction: <5%, General Comments possibly due to infiltration, from 2 to 6 o'clock	1	Likely	Low	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
52.58	18.17	DI	Dropped invert, depth of drop 10mm, General Comments drop in invert of pipe- uneven surface	1	Unlikely	Very Low	Is this due to displacement of a pipe joint or erosion of the concrete floor or something else? Requires further inspection to determine appropriate repair.	1	Item	Investigate	
52.64	18.23	DEW	Other Deposits on the wall, Jointing Material, Obstruction:<5%, General Comments rusting/staining of joining mechanism, from 12 to 4 o'clock	1	Likely	Low	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
52.64	18.23	DEE	Encrustation/Scale is attached to the wall above the waterline, Obstruction: <5%, General Comments rusting/staining/possible infiltration of joining mechanism, from 7 to 12 o'clock	1	Almost certain	Moderate	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
55.35	20.94	IR	Infiltration, running, General Comments spurting out pipe wall, from 7 to 8 o'clock	2	Almost certain	High	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
55.35	20.94	DEE	Encrustation/Scale is attached to the wall above the waterline, Obstruction: <5%, General Comments due to infiltration, from 6 to 12 o'clock	1	Almost certain	Moderate	Cement pressure grout annulus behind CMP / replace band connection, or seal band / CMP gap with expanding sealant.	1	Item	\$ 10,500	\$ 10,500
163.48	129.07	MC	New material, Concrete Pipe, General Comments returns to original pipe material	0	N/A	Comment					
166.70	132.29	CNGO	Connection, good workmanship, connection appears to be open, diameter approx. 600mm, at 3 o'clock, General Comments Large wooden object wedged at pipe entrance	1	Rare	Very Low	Remove blockage	1	Item	\$ 4,000	\$ 4,000
166.72	132.31	GC	General Comments Unknown pit found	0	N/A	Comment	Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	1	Item	\$ 10,500	\$ 10,500

# Bellambi Gully Pipeline MHB to MHC

Total Chainage	Listed Chainage		Code	Observation	Consequence rating	Likelihood	Risk category	Remediation	Qty	Unit	Rate	Cost
0.00	0.00		STMS	Start node, maintenance shaft, Node name: MH B	0	N/A	Comment					
19.74	19.74		CNPC	Connection, poor workmanship, connection appears to be open, diameter approx. 225mm, General Comments suspect a possible displacement	1	Likely	Low	Penetration appears to have been capped. Potential for seepage around annulus. Either epoxy pressure grout annulus between RCP and penetration or remove penetration, and reinstate RCP wall by scrubbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 10,500	\$ 10,500
23.77	23.77		SWS	Wall Staining is present on the surface of the conduit, at joint, General Comments Possible infiltration is present, at 4 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
26.45	26.45		IR	Infiltration, running, at joint, General Comments Wall staining also present, at 4 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
26.45	26.45		DEE	Encrustation/Scale is attached to the wall above the waterline, at joint, Obstruction: <5%, General Comments from infiltration, at 4 o'clock	1	Unlikely	Very Low	Clean pipewall during repair of pipe joint seal	0	N/A	\$ -	\$ -
34.20	34.20		SRV	Steel reinforcement is visible with little or no corrosion evident, at 12 o'clock	2	Moderate Likelihood	Low	Non cracking noted. Likely local concrete spalling. Repair by scrubbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 10,500	\$ 10,500
38.06	38.06		GC	General Comments Unknown Pit found	0	N/A	Comment	Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	1	Item	\$ 10,500	\$ 10,500
70.84	70.84		MC	New material, Corrugated Iron, General Comments Reduces diameter of pipe	2	Rare	Very Low	Confirm if the annulus between the CMP and RCP has been cement pressure grouted. If not, cement pressure grout the annulus.	1	Item	\$ 10,500	\$ 10,500
70.84	70.84		RXM	Defective repair, major or irregular gaps or both in the pipe wall, General Comments Packer is hanging loose	1	Unlikely	Very Low	Cement pressure grout annulus.	1	Item	\$ 10,500	\$ 10,500
70.84	70.84	S1	DM	Deformation, mixed orientation, change in diameter 5-10%,length of deformation 500mm, General Comments Corrugated iron causing deformed pipe shape, from 12 to 1	1	Unlikely	Very Low	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
107.30	107.30		RXB	Defective repair, bellies in the line, General Comments dropping of corrugated iron	3	Moderate Likelihood	Moderate	Possible multiple causes. Where safe to do so, cut out bulge and install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
119.21	119.21		DEW	Other Deposits on the wall, Rusting, Obstruction: <5%, at 1 o'clock	2	Moderate Likelihood	Low	Where safe to do so, install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
125.47	6.26		MC	New material, Corrugated Iron	0	N/A	Comment					
131.98	12.77		RXB	Defective repair, bellies in the line, General Comments Drooping of corrugated iron	2	Moderate Likelihood	Low	Where safe to do so, install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
139.07	19.86		GC	General Comments Multiple joining mechanisms on pipe wall to hold corrugated iron in place; rusting present	0	N/A	Comment	Consider re-lining pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	0	m	\$ 10,500	\$ -
235.50	116.29		RXZ	Defective repair, other defects: Bulging of pipe wall @ 3 o'clock	2	Moderate Likelihood	Low	Possible multiple causes. Where safe to do so, cut out bulge and install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
249.24	130.03		GC	General Comments Full length of cable reached	0	N/A	Comment					
258.80	9.56		MC	New material, Corrugated Iron	0	N/A	Comment					
260.16	11.92		RXZ	Defective repair, other defects: Bulging of corrugated iron in invert	3	Moderate Likelihood	Moderate	Possible multiple causes. Where safe to do so, cut out bulge and install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
269.59	21.35		RXZ	Defective repair, other defects: Bulging of corrugated iron, General Comments on left hand side of pipe wall	3	Moderate Likelihood	Moderate	Possible multiple causes. Where safe to do so, cut out bulge and install bolted strengthening plate/ring. Cement pressure grout outside CMP to fill any voids.	1	Item	\$ 10,500	\$ 10,500
292.91	44.67		MC	New material, Reinforced Concrete Pipe, General Comments Returns to original pipe material	0	N/A	Comment					
300.84	52.60		GC	General Comments Large repair	2	Moderate Likelihood	Low	Non cracking noted. Likely local concrete spalling. Repair by scrubbling/cleaning the concrete surface, applying a bonding agent (e.g. Epirez 133) and repair with non-shrink cement mortar repair.	1	Item	\$ 10,500	\$ 10,500
301.69	53.45		DI	Dropped invert, depth of drop 8mm, General Comments slight dip in invert	2	Moderate Likelihood	Low	Is this due to displacement of a pipe joint or erosion of the concrete floor or something else? Requires further inspection to determine appropriate repair.	1	Item	Investigate	
306.27	58.03		GC	General Comments Unknown Pit found	0	N/A	Comment	Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	1	Item	\$ 10,500	\$ 10,500
306.27	58.03		CLW	Longitudinal wall crack, width 2mm, General Comments on unknown pit wall, at 11 o'clock	2	Unlikely	Low	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
319.89	71.65		IYY	Suspected Infiltration, General Comments at pipe joint, from 4 to 6 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
322.26	74.02		IYY	Suspected Infiltration, at joint, General Comments from pipe joint, from 4 to 6 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
330.24	82.00		IYY	Suspected Infiltration, at joint, General Comments at joint, from 4 to 6 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
336.96	88.72		IYY	Suspected Infiltration, at joint, from 2 to 6 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
349.96	101.72		DV	Vertical deformation, change in diameter 5-10%, length of deformation 200mm, General Comments pipe has been squashed, at 10 o'clock	3	Moderate Likelihood	Moderate	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
360.78	112.54		IYY	Suspected Infiltration, at joint, from 6 to 9 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
363.18	114.94		IYY	Suspected Infiltration, at joint, from 6 to 9 o'clock	1	Almost certain	Moderate	Likely a deteriorated pipe joint seal. Either epoxy pressure grout joint (more permanent) or install internal expanding seal to joint (e.g. Trelborg).	1	Item	\$ 5,200	\$ 5,200
366.22	117.98	S1	CLW	Longitudinal wall crack, width 2mm, General Comments runs through to pipe sections, at 12 o'clock, Start	3	Moderate Likelihood	Moderate	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
375.56	127.22		DV	Vertical deformation, change in diameter 5-10%, length of deformation 300mm, at 12 o'clock	3	Moderate Likelihood	Moderate	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
377.28	128.94	E1	CLW	Longitudinal wall crack, width 2mm, General Comments runs through to pipe sections, at 12 o'clock, End	3	Moderate Likelihood	Moderate	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
378.01	129.67		DV	Vertical deformation, change in diameter 5-10%, length of deformation 200mm, at 12 o'clock	3	Moderate Likelihood	Moderate	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
378.01	129.67		GC	General Comments Full length of cable has been reached again	0	N/A	Comment					
378.01	66.58		GC	General Comments Unknown starting meterage	0	N/A	Comment					
382.47	71.04	S1	CLW	Longitudinal wall crack, width 2mm, at 12 o'clock, Start	3	Moderate Likelihood	Moderate	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
385.77	74.34		DV	Vertical deformation, change in diameter 5-10%, length of deformation 200mm, at 11 o'clock	3	Moderate Likelihood	Moderate	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
386.39	74.96	E1	CLW	Longitudinal wall crack, width 2mm, at 12 o'clock, End	3	Moderate Likelihood	Moderate	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
395.04	83.61		CLS	Longitudinal surface crack, width 2mm , at 12 o'clock	3	Moderate Likelihood	Moderate	Epoxy pressure grout crack.	1	Item	\$ 5,200	\$ 5,200
400.28	88.95		DI	Dropped invert, depth of drop 10mm, General Comments dip in pipe invert	2	Moderate Likelihood	Low	Is this due to displacement of a pipe joint or erosion of the concrete floor or something else? Requires further inspection to determine appropriate repair.	1	Item	Investigate	

Total Chainage	Listed Chainage		Code	Observation	Consequence rating	Likelihood	Risk category	Remediation	Qty	Unit	Rate	Cost
416.35	105.02		DV	Vertical deformation, change in diameter 5-10%, length of deformation 500mm, at 12 o'clock	3	Moderate Likelihood	Moderate	Re-line pipe (i.e. installing CMP / Polypipe pipe and cement pressure grouting the annulus or installing an insitu reinforced concrete pipe (e.g. Tunneline system). Note the pipe invert appears to have a concrete floor. This may need to be demolished prior to relining.	1	m	\$ 15,000	\$ 15,000
440.10	128.77		GC	General Comments Unknown Pit found	0	N/A	Comment	Confirm if pit is still required. If not, construct reinforced concrete plug, dowelled in to RCP / Manhole.	1	Item	\$ 10,500	\$ 10,500
440.78	128.82		LR	The conduit curves to the right, length of curved section 500mm	0	N/A	Comment					
441.46	129.50		FHO	Finish node, outfall or culvert headwall, Node name: MH C	0	N/A	Comment					