


# GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK EARTHWORKS & ROAD DESIGN STAGE 1 MAJOR PROJECT APPLICATION SSD 5248

DRAWING LIST

|                            |  |
|----------------------------|--|
| GENERAL                    |  |
| 000                        | COVER SHEET  |
| 001                        | STANDARD NOTES & LEGEND                              |
| ROADWORKS                  |  |
| 101                        | CIVIL ENGINEERING PLAN                               |
| 201                        | ROAD No. 1 & 2 LONGITUDINAL & TYPICAL CROSS SECTIONS |
| SITE REGRADING             |  |
| 601                        | SITE REGRADING PLAN & SITE SECTIONS                  |
| SEDIMENT & EROSION CONTROL |  |
| 701                        | SEDIMENT & EROSION CONTROL PLAN                      |
| 702                        | SEDIMENT & EROSION CONTROL NOTES & DETAILS           |



LOCALITY PLAN  
N.T.S.

LGA FAIRFIELD CITY COUNCIL  
LOT 5, D.P. 24094

GAZCORP PTY. LTD.



GAZCORP INDUSTRIAL ESTATE  
WALLGROVE ROAD, HORSLEY PARK  
EARTHWORKS & ROAD DESIGN

STANDARD NOTES

1. ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S STANDARDS AND SPECIFICATIONS AND/OR AS DIRECTED BY THE ENGINEER.

2. THE CONTRACTOR SHALL LOCATE AND LEVEL ALL EXISTING SERVICES PRIOR TO COMMENCING CONSTRUCTION AND SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE RELEVANT AUTHORITY TO RELOCATE OR ADJUST AS FOUND NECESSARY. ALL COSTS TO BE BORNE BY THE APPLICANT, (NOT AT COUNCIL'S EXPENSE)

3. THE CONTRACTOR SHALL NOT ENTER UPON OR DO ANY WORK WITHIN ADJACENT LANDS WITHOUT PRIOR WRITTEN PERMISSION OF THE LAND OWNER.

4. SURVEY MARKS SHOWN THUS SHALL BE MAINTAINED AT ALL TIMES. WHERE RETENTION IS NOT POSSIBLE THE ENGINEER SHALL BE NOTIFIED AND CONSENT RECEIVED PRIOR TO THEIR REMOVAL.

5. ALL NEW WORKS SHALL MAKE SMOOTH JUNCTION WITH EXISTING CONDITIONS.

6. SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO SOIL DISTURBANCE IN KEEPING WITH THE "MANAGING STORMWATER MANUAL", 2004 BY LANDCOM AND TO THE SATISFACTION OF THE ENGINEER AND AS SHOWN IN THESE DRAWINGS.

7. THE CONTRACTOR SHALL CLEAR AND DISPOSE OF ONLY THOSE TREES THAT ARE CONDEMNED BY THE ENGINEER. COUNCIL'S TREE PRESERVATION ORDER SHALL BE OBSERVED AND NO TREE SHALL BE FELLED, LOPPED OR REMOVED WITHOUT PRIOR APPROVAL.

8. THE CONTRACTOR SHALL CLEAR THE SITE BY REMOVING ALL RUBBISH, FENCES, OUT HOUSES, CAR BODIES, DEBRIS ETC. THE CONTRACTOR SHALL NOT DISPOSE OF ANY DEBRIS BY BURNING OFF IN AN OPEN FIRE.

9. UNSOUND MATERIALS AS DETERMINED BY THE ENGINEER SHALL BE REMOVED FROM ROADS AND LOTS PRIOR TO ANY FILLING. REFER NOTE 37.

10. ALL SITE REGRADING AREAS SHALL BE GRADED IN ACCORDANCE WITH BCC GUIDELINES AND WORK SPECIFICATIONS. THE CONTRACTOR SHALL TAKE LEVELS ON THE EXISTING SURFACE AFTER STRIPPING TOPSOIL AND PRIOR TO COMMENCING ANY FILL OPERATIONS.

11. SURPLUS EXCAVATED MATERIAL SHALL BE PLACED WHERE DIRECTED BY THE ENGINEER.

12. 100 DIA. SUBSOIL DRAINAGE PIPE 3000 LONG WRAPPED IN FABRIC SOCK TO BE PROVIDED ADJACENT TO INLET PIPES, TO COUNCIL'S STANDARD DRAWINGS FOR PITS.

13. MINIMUM 100mm THICK TOPSOIL SHALL BE SPREAD ON ALL FOOTPATHS, BERMS, BATTERS AND SITE REGRADING AREAS. EXCESS TOPSOIL SHALL BE DISPOSED OF AS DIRECTED BY THE ENGINEER.

14. ALL LAND DISTURBED BY EARTHWORKS SHALL BE SPRAY-GRASSED, OR SIMILARLY TREATED TO ESTABLISH GRASS COVER. SEED MIXTURES ARE TO BE APPROVED BY COUNCIL PRIOR TO SPRAYING. ALL GRASSED AREAS SHALL BE REGULARLY WATERED AND MAINTAINED UNTIL EXPIRATION OF THE MAINTENANCE PERIOD.

15. THE CONTRACTOR SHALL MAINTAIN DUST CONTROL THROUGHOUT THE DURATION OF THE PROJECT.

16. ALL PITS DEEPER THAN 1.2m SHALL HAVE STEP IRONS PROVIDED IN ACCORDANCE WITH COUNCIL'S STANDARDS.

17. ALL DRAINAGE LINES THROUGH LOTS SHALL BE CONTAINED WITHIN THEIR EASEMENTS AND CONFORM WITH COUNCIL'S STANDARDS.

18. ALL DRAINAGE LINES ON HIGH SIDE AND UNDER ROADS SHALL BE BACKFILLED WITH SHARP SAND AND HAVE 3.0m OF AGRICULTURAL LINE WRAPPED IN AN APPROVED FILTER FABRIC, DISCHARGING INTO THE DOWNSTREAM PIT.

19. SUBSOIL DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH BCC GUIDELINES AND SPECIFICATIONS.

20. PRECAST KERB INLET LINTELS SHALL BE USED ON GULLY PITS. GULLY PITS SHALL BE IN ACCORDANCE WITH A(BS)106M.

21. INTERALLOTMENT DRAINAGE LINES SHALL HAVE A MINIMUM 300mm COVER AND DESIRABLE MINIMUM GRADE OF 1%.

22. 100mm DIAMETER ROOF DRAINAGE HOLES SHALL BE PROVIDED TO ALL LOTS DRAINING TO THE KERB AT THEIR DOWNSTREAM BOUNDARY.

23. PROVIDE VEHICULAR CROSSING IN KERB AND GUTTER WHERE SHOWN VC OR WHERE DIRECTED BY THE ENGINEER.

24. GUIDE POSTS SHALL BE 100mm X 50mm HARDWOOD, PAINTED WHITE WITH REFLECTORS.

25. ERECT STREET NAME SIGNS, CONDUIT WARNING SIGNS AND NO THROUGH ROAD SIGNS WHERE SHOWN
26. ERECT STREET NAME SIGNS, CONDUIT WARNING SIGNS AND NO THROUGH ROAD SIGNS WHERE SHOWN THUS SP OR WHERE DIRECTED BY THE ENGINEER.

27. CONDUITS SHALL BE LAID AFTER POSITIONS HAVE BEEN DETERMINED BY THE RELEVANT AUTHORITIES AND BEFORE FINAL A.C. IS LAID.

28. POSITION OF ALL CONDUITS SHALL BE MARKED ON THE KERB.

29. FELLED TREES SHALL BE SALVAGED FOR REUSE AS WOODCHIP MULCH OR LOG FORM FOR SITE REHABILITATION, NON-SALVAGEABLE MATERIAL SUCH AS STUMPS AND ROOTS SHALL BE DISPOSED OF OFF SITE.

30. THE CONTRACTOR SHALL PROVIDE MINIMUM 24 HOURS NOTICE TO THE ENGINEER AND COUNCIL INSPECTOR FOR ALL INSPECTIONS.

31. THE CONTRACTOR SHALL MAINTAIN SERVICES AND ALL WEATHER ACCESS AT ALL TIMES TO THE ADJOINING PROPERTIES.

32. THE CONTRACTOR SHALL UNDERTAKE TRAFFIC CONTROL MEASURES TO ENGINEERS SATISFACTION AND SHALL DISPLAY ALL APPROPRIATE WARNING SIGNS THROUGHOUT THE DURATION OF CONSTRUCTION.

33. ALL NATURAL SURFACE DATA HAS BEEN DETERMINED BY TERRAIN MODELLING. ALL CONSTRUCTION SITE WORKS MUST BE CARRIED OUT USING THE BENCH MARKS SHOWN ON THESE DRAWINGS.

34. THAT ALL LIGHT POLES, STREET NAME POLES AND BUS SHELTERS IN THIS SUBDIVISION WILL BE BLACK POWDER COATED TO THE SATISFACTION OF THE B.C.C.

35. PRAM RAMPS AND PATHPAVING TO BE CONSTRUCTED AS SHOWN ON PLANS AND AS DIRECTED BY COUNCIL ON SITE.

36. ALL BATTERS ARE TO HAVE A MAXIMUM SLOPE OF 5(H):1(V).

37. PRIOR TO CONSTRUCTION THE CONTRACTOR SHOULD OBTAIN COPIES OF ALL RELEVANT GEOTECHNICAL REPORTS. WORKS SHOULD BE UNDERTAKEN IN ACCORDANCE WITH ADVICE AND RECOMMENDATIONS CONTAINED THEREIN.

38. UPON COMPLETION OF THE SITE REGRADE & APPROVED ROAD AND DRAINAGE WORKS AND PRIOR TO THE ISSUE OF THE SUBDIVISION CERTIFICATE, THE APPLICANT IS REQUIRED TO SUBMIT TO COUNCIL WRITTEN CERTIFICATION FROM APPROPRIATELY QUALIFIED GEOTECHNICAL CONSULTANTS THAT ALL THE RECOMMENDATIONS IN THE REPORTS REFERRED TO IN ITEM 37 ABOVE HAVE BEEN COMPILED WITH.

39. 100 YEAR FLOW PATHS TO BE FORMED AT TIME OF CONSTRUCTION.

40. A TRAFFIC CONTROL PLAN IS TO BE PROVIDED TO COUNCIL PRIOR TO COMMENCEMENT OF WORKS.

LEGEND

| DESCRIPTION  | PROPOSED | EXISTING | FUTURE |
|--|----------|----------|--------|
| STORMWATER PIPELINE  |          |          |        |
| STORMWATER DRAINAGE PITS   |          |          |        |
| DRAINAGE LINE No. 3<br>DRAINAGE PIT No. 10                                     |          |          |        |
| CONCRETE HEADWALL  |          |          |        |
| SUBSOIL DRAIN  |          |          |        |
| STANDARD 150mm KERB AND GUTTER   |          |          |        |
| STANDARD ROLL KERB AND GUTTER  |          |          |        |
| STANDARD KERB ONLY   |          |          |        |
| STANDARD EDGE STRIP  |          |          |        |
| STANDARD MOUNTABLE KERB  |          |          |        |
| STANDARD DISH CROSSING   |          |          |        |
| VEHICULAR CROSSING   |          |          |        |
| PEDESTRIAN RAMP  |          |          |        |
| EDGE OF BITUMEN  |          |          |        |
| ROAD PAVEMENT  |          |          |        |
| BENCHMARK  |          |          |        |
| BATTERS  |          |          |        |
| CONCRETE PATHWAY   |          |          |        |
| CONTOURS   |          |          |        |
| SITE REGRADING AREA  |          |          |        |
| SERVICE LINES<br>SEWER, GAS, WATER, ELECTRICITY                                |          |          |        |
| COMMUNICATION LINES<br>TELSTRA, FIBRE OPTIC                                    |          |          |        |
| OVER HEAD LINES AND POLES  |          |          |        |
| SERVICE PITS<br>TELECOM PIT, ACCESS CHAMBER,<br>HYDRANT, STOP VALVE, AIR VALVE |          |          |        |
| LIMIT OF CONSTRUCTION  |          |          |        |
| LIMIT OF STAGE   |          |          |        |
| FENCE<br>POST AND RAIL FENCE<br>SECURITY FENCE                                 |          |          |        |
| LOT NUMBERS  |          |          |        |
| TREES TO REMOVE  |          |          |        |
| TREES  |          |          |        |
| RETAINING WALL   |          |          |        |

MAJOR PROJECT APPLICATION SSD 5248

Revisions

|             |        |       |       |           |                     |
|-------------|--------|-------|-------|-----------|---------------------|
| 00          | AW     | DD    | CB    | 9/05/2013 | ISSUED FOR REVIEW   |
| 01          | AW     | DD    | CB    | 2/08/2013 | ISSUED FOR APPROVAL |
| First Issue | AW     | DD    | CB    | 9/05/2013 |                     |
| Drawn       | Design | Check | Appd. | Date      | Revision Details    |

Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting Pty Ltd

Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPEng  
MIEAust, Manager Urban Development  
SIGN:   
DATE: 2/8/13

Client:  
GAZCORP PTY. LTD.  
Project:  
GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK  
EARTHWORKS & ROAD DESIGN

©2012  
www.brownconsulting.com.au


Drawing Title:  
STANDARD NOTES & LEGEND  
Project No.: X12254.01  
Stage: 01  
Milestone: DA  
Dwg No.: 001  
Revision: 01

FILE: H:\PROJECTS - WALLGROVE RD INDUSTRIAL ESTATE\DWG\SSD5248.DWG  
PRINTED: 8/21/2013 10:41:00 AM  
DRAWN: KAMM HANNO






NOTES:  
BUILDINGS AND CARPARKS LAYOUT INDICATIVE  
ONLY BASED ON ARCHITECTURAL DRAWINGS.  
REF: "MBMO 12026-OPT02-SK-10(F)".



## MAJOR PROJECT APPLICATION SSD 5248

| Revisions        |       |        |       |           |                     |  |
|------------------|-------|--------|-------|-----------|---------------------|--|
| 00               | AW    | DD     | CB    | 9/05/2013 | ISSUED FOR REVIEW   |  |
| 01               | AW    | DD     | CB    | 2/08/2013 | ISSUED FOR APPROVAL |  |
| First            | AW    | DD     | CB    | 9/05/2013 |                     |  |
| Issue            | Drawn | Design | Check | Appd.     | Date                |  |
| Revision Details |       |        |       |           |                     |  |



Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY  
SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT  
SCALE.

© Brown Consulting Pty Ltd




Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPEng  
MIEAust, Manager Urban Development  
SIGN:   
DATE: 2/8/13


Client:  
**GAZCORP PTY. LTD.**  
Project:  
GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK  
EARTHWORKS & ROAD DESIGN



Drawing Title:  
**CIVIL ENGINEERING PLAN**  
Project No.: X12254.01  
Stage: 01  
Milestone: DA  
Dwg No.: 101  
Revision: 01



TYPICAL CROSS SECTION - ROAD No.2  
SCALE 1:100 (NATURAL)



LONGITUDINAL SECTION - ROAD No.2  
SCALE 1:2000 (H)  
SCALE 1:400 (V)

**BROWN**  
*Smart Consulting*  
©2012 [www.brownconsulting.com.au](http://www.brownconsulting.com.au)

|              |        |            |          |           |
|--------------|--------|------------|----------|-----------|
| Project No.: | Stage: | Milestone: | Dwg No.: | Revision: |
| X12254.01    | 01     | DA         | 201      | 01        |



CONSULT AUSTRALIA  
Member Firm



|          |  |
|----------|--|
| Client:  | GAZCORN PTY. LTD.  |
| Project: | GAZCORN INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK<br>EARTHWORKS & ROAD DESIGN |





LEGEND

24.0





EXISTING CONTOUR

23.5

PROPOSED CONTOUR

CUT AREA

FILL AREA



MAJOR PROJECT APPLICATION SSD 5248

Revisions

| No.         | By | Check | Date | Description                   |
|-------------|----|-------|------|-------------------------------|
| 00          | AW | DD    | CB   | 9/05/2013 ISSUED FOR REVIEW   |
| 01          | AW | DD    | CB   | 2/08/2013 ISSUED FOR APPROVAL |
| First Issue | AW | DD    | CB   | 9/05/2013                     |

Revision Details

0 20 40 60 80 100 120 140 160 180 200

SCALE 1:2000 (A1)

0 10 20 30 40 50 60 70 80 90 100

SCALE 1:1000 (A1)

SCALE 1:2000 (A3)

SCALE 1:2000 (A3)

Disclaimer and Copyright:

ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting Pty Ltd

Approval:

BY: TOBY TAMES

BE (Hons) GradDipMgt CPEng

MIEAust, Manager Urban Development

SIGN:

DATE: 2/8/13

Client:

GAZCORP PTY. LTD.

Project:

GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK

EARTHWORKS & ROAD DESIGN

BROWN

Smart Consulting

©2012

www.brownconsulting.com.au

Drawn Title:

SITE REGRADING PLAN & SITE SECTIONS

Project No.:

X12254.01

Stage:

01

Milestone:

DA

Dwg No.:

601

Revision:

01




SEDIMENT & EROSION  
CONTROL LEGEND

SEDIMENT FENCE

BARRIER FENCE


STABILISED SITE ACCESS

DIVERSION DRAIN/EARTH BANK



MAJOR PROJECT APPLICATION SSD 5248

| Revisions   |        |       |       |           |                     |  |
|-------------|--------|-------|-------|-----------|---------------------|--|
| 00          | AW     | DD    | CB    | 9/05/2013 | ISSUED FOR REVIEW   |  |
| 01          | AW     | DD    | CB    | 2/08/2013 | ISSUED FOR APPROVAL |  |
| First Issue | AW     | DD    | CB    | 9/05/2013 |                     |  |
| Drawn       | Design | Check | Appd. | Date      | Revision Details    |  |



Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY. DO NOT SCALE.

Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPEng  
MIEAust, Manager Urban Development  
SIGN:   
DATE: 2/8/13

Client:  
**GAZCORP PTY. LTD.**

Project:  
GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK  
EARTHWORKS & ROAD DESIGN

**Smart Consulting**  
©2012  
www.brownconsulting.com.au


Drawing Title:  
**SEDIMENT & EROSION CONTROL PLAN**

Project No.: X12254.01  
Stage: 01  
Milestone: DA  
Dwg No.: 701  
Revision: 01



## SEDIMENT & EROSION CONTROL NOTES

- THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE COMMENCEMENT OF ANY WORKS BEING CARRIED OUT. ALL SOIL AND EROSION MEASURES SHALL BE MAINTAINED AND KEPT IN PLACE FOR THE FULL DURATION OF THE WORKS AND SHALL ONLY BE REMOVED AT FINAL STABILISATION OF THE WORKS, WHERE IT IS NECESSARY TO UNDERTAKE STRIPPING IN ORDER TO CONSTRUCT A SEDIMENT CONTROL DEVICE ONLY SUFFICIENT GROUND SHALL BE STRIPPED TO ALLOW CONSTRUCTION.
- ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED AS INDICATED ON THESE DRAWINGS. LOCATION AND EXTENT OF SOIL AND WATER MANAGEMENT DEVICES IS DIAGRAMMATIC ONLY AND THE ACTUAL REQUIREMENTS SHALL BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT.
- CONFORMITY WITH THIS PLAN SHALL IN NO WAY REDUCE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AGAINST WATER DAMAGE DURING THE COURSE OF THE CONTRACT. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ANY NECESSARY CONTROL IS IN PLACE EVEN THOUGH SUCH CONTROL MAY NOT BE SHOWN ON THE PLAN.
- THE CONTRACTOR SHALL INFORM ALL SUBCONTRACTORS AND ALL EMPLOYEES OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSTREAM AREAS.
- APART FROM SEDIMENT BASINS, THE CONTRACTOR SHALL REGULARLY MAINTAIN SEDIMENT AND EROSION CONTROL STRUCTURES AND DESILT SUCH STRUCTURES PRIOR TO THE REDUCTION IN CAPACITY OF 30% DUE TO ACCUMULATED SEDIMENT. THE SEDIMENT SHALL BE DISPOSED OF ON SITE IN A MANNER APPROVED BY THE ENGINEER.
- THE CONTRACTOR SHALL TEMPORARILY REHABILITATE WITHIN TEN (10) DAYS ANY DISTURBED AREAS PROVIDING A MINIMUM 60% COVER. FINAL REHABILITATION IS TO BE PROVIDED WITHIN A FURTHER 60 DAYS WITH A MINIMUM 70% COVER.
- THE CONTRACTOR SHALL PROVIDE WATERING OF THE VEGETATED BATTERS FOR MAINTENANCE PERIOD. PLANT, MACHINERY AND VEHICLES SHALL NOT BE DRIVEN OVER GRASSED AREAS UNLESS ON AN APPROVED HAULAGE ROUTE.
- ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS QUICKLY AS POSSIBLE TO MINIMISE RISK OF EROSION.
- SITE ACCESS SHALL BE RESTRICTED TO THE NOMINATED POINTS. THE CONTRACTOR SHALL PROVIDE STABILISED SITE ACCESS.
- DUST AND SITE DISTURBANCE MUST BE KEPT TO A MINIMUM. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS MUST BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO REDUCE WIND EROSION. ERECT BARRIER FENCING TO MINIMISE LAND DISTURBANCE BY PREVENTING VEHICULAR AND PEDESTRIAN ACCESS TO AREAS BEING REHABILITATED AND LANDS THAT DO NOT NEED TO BE DISTURBED BY THIS PROJECT.
- STOCKPILE TOPSOILS, SUBSOILS AND OTHER MATERIALS SEPARATELY.
- TOPSOIL SHALL BE STORED IN LOW MOUNDS NO MORE THAN 2 METRES HIGH AND RE-USED WITHIN TWO MONTHS TO MAINTAIN ACTIVE POPULATIONS OF BENEFICIAL SOIL MICROBES AND SEED.
- PLACE ALL STOCKPILES AT LEAST FIVE METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS, ESPECIALLY EARTH BANKS AND ROADS. IF NECESSARY, EARTH BANKS OR DRAINS WILL BE CONSTRUCTED TO DIVERT LOCALISED RUN-ON.
- TURN TOPSOIL STOCKPILES OVER TO AERATE THEM AT MONTHLY INTERVALS. ENSURE VEGETATION IS NOT INCORPORATED INTO THE SOIL.
- AVOID REVERSING THE SOIL PROFILE MATERIALS DURING FILL OPERATIONS - REPLACE DISTURBED SOILS IN THEIR ORIGINAL ORDER.
- ON COMPLETION OF MAJOR EARTHWORKS AND BEFORE ADDING TOPSOIL, LEAVE DISTURBED LANDS WITH A LOOSE SURFACE. ALTERNATELY, DISTURBED AREAS PREVIOUSLY COMPACTED BY CONSTRUCTION WORKS WILL BE RIPPED TO MORE THAN 200-MM ALONG THE CONTOUR BEFORE APPLYING TOPSOIL.
- PROVIDING MATERIALS ARE AVAILABLE, SPREAD TOPSOIL TO A MINIMUM DEPTH OF 75mm IN REVEGETATION AREAS ON SLOPES OF 4(H):1(V) OR LESS AND TO A DEPTH OF 40 TO 60mm IN REVEGETATION AREAS STEEPER THAN 4:1.
- LEAVE TOPSOIL IN A SCARIFIED OR ROUGH CONDITION ONCE REPLACED TO HELP MOISTURE INFILTRATION AND REDUCE SOIL EROSION.
- ENSURE SOIL IS THOROUGHLY SOAKED TO A DEPTH OF 75mm (RAIN OR IRRIGATION) IMMEDIATELY BEFORE PLANTING.
- HANDLE TOPSOIL ONLY WHEN IT IS MOIST (NOT WET OR DRY) TO AVOID DECLINE OF SOIL STRUCTURE.
- THE CONTRACTOR SHALL MAINTAIN A LOG BOOK DETAILING:
  - RECORDS OF ALL RAINFALL
  - CONDITION OF SOIL AND WATER MANAGEMENT STRUCTURES
  - ANY APPLICATION OF FLOCCULATING AGENTS TO SEDIMENT BASIN
  - VOLUMES OF ALL WATER DISCHARGED FROM SEDIMENT BASINS
  - ANY ADDITIONAL REMEDIAL WORKS REQUIRED.
- THE LOG BOOK SHALL BE MAINTAINED ON A WEEKLY BASIS AND BE MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. THE ORIGINAL LOG BOOK SHALL BE ISSUED TO THE PROJECT MANAGER AT THE COMPLETION OF WORKS.
- ALL ROAD EMBANKMENTS TO BE STABILISED AS PER LANDSCAPE ARCHITECTS DETAILS.
- A SELF AUDITING PROGRAM SHOULD BE ESTABLISHED BASED ON A CHECK SHEET DEVELOPED FOR THE SITE. A SITE INSPECTION USING THE CHECK SHEET SHOULD BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE AND IMMEDIATELY FOLLOWING RAINFALL EVENTS THAT CAUSE RUNOFF.
- UNDERTAKE THE SELF AUDIT BY:
  - WALKING AROUND THE SITE SYSTEMATICALLY (E.G. CLOCKWISE)
  - RECORDING THE CONDITION OF EVERY BMP EMPLOYED
  - RECORDING MAINTENANCE REQUIREMENTS (IF ANY) FOR EACH BMP
  - RECORDING THE SITE WHERE SEDIMENT IS DISPOSED
  - FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET TO THE PROJECT MANAGER/DEVELOPER/SITE OPERATOR FOR THEIR INFORMATION
- IN PARTICULAR, INSPECT:
  - LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE
  - ALL INSTALLED EROSION AND SEDIMENT CONTROL MEASURES, ENSURING THEY ARE OPERATING CORRECTLY
  - AREAS THAT MIGHT SHOW WHETHER SEDIMENT OR OTHER POLLUTANTS ARE LEAVING THE SITE OR HAVE POTENTIAL TO DO SO
  - ALL DISCHARGE POINTS, TO ASSESS WHETHER THE EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING IMPACTS TO THE RECEIVING WATERS
- A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE, AND IMMEDIATELY FOLLOWING RAINFALL EVENTS GREATER THAN 5mm IN 24 HOURS.




### Construction Notes

- Construct at the gradient specified on the ESCP or SWMP, normally between 1 and 5 percent.
- Avoid removing trees and shrubs if possible - work around them.
- Ensure the structures are free of projections or other irregularities that could impede water flow.
- Build the drains with circular, parabolic or trapezoidal cross sections, not V-shaped, at the dimensions shown on the SWMP.
- Ensure the banks are properly compacted to prevent failure.
- Complete permanent or temporary stabilisation within 10 days of construction following Table 5.2 in Landcom (2004).
- Where discharging to erodible lands, ensure they outlet through a properly constructed level spreader.
- Construct the level spreader at the gradient specified on the ESCP or SWMP, normally less than 1 percent or level.
- Where possible, ensure they discharge waters onto either stabilised or undisturbed disposal sites within the same subcatchment area from which the water originated. Approval might be required to discharge into other subcatchments.

## EARTH BANK (HIGH FLOWS)

SD 5-6




### Construction Notes

- Construct sediment fences as close as possible to being parallel to the contours of the site, but with small returns as shown in the drawing to limit the catchment area of any one section. The catchment area should be small enough to limit water flow if concentrated at one point to 50 litres per second in the design storm event, usually the 10-year event.
- Cut a 150-mm deep trench along the upslope line of the fence for the bottom of the fabric to be entrenched.
- Drive 15 metre long star pickets into ground at 2.5 metre intervals (max) at the downslope edge of the trench. Ensure any star pickets are fitted with safety caps.
- Fix self-supporting geotextile to the upslope side of the posts ensuring it goes to the base of the trench. Fix the geotextile with wire ties or as recommended by the manufacturer. Only use geotextile specifically produced for sediment fencing. The use of shade cloth for this purpose is not satisfactory.
- Join sections of fabric at a support post with a 150-mm overlap.
- Backfill the trench over the base of the fabric and compact it thoroughly over the geotextile.

## SEDIMENT FENCE

SD 6-8




### Construction Notes

- Fabricate a sediment barrier made from geotextile or straw bales.
- Follow Standard Drawing 6-8 for installation procedures for geofabric. Reduce the picket spacing to 1 metre centres.
- In waterways, artificial sag points can be created with sandbags or earth banks as shown in the drawing.
- Do not cover the inlet with geotextile unless the design is adequate to allow for all waters to bypass it.

## GEOTEXTILE INLET FILTER

SD 6-12




### Construction Notes

- Install a 400 mm minimum wide roll of turf on the footpath next to the kerb and at the same level as the top of the kerb.
- Lay 14 metre long turf strips normal to the kerb every 10 metres.
- Rehabilitate disturbed soil behind the turf strip following the ESCP/SWMP.

## KERBSIDE TURF STRIP

SD 6-13




NOTE: Only to be used as temporary bank where maximum upslope length is 80 metres.

### Construction Notes

- Build with gradients between 1 percent and 5 percent.
- Avoid removing trees and shrubs if possible - work around them.
- Ensure the structures are free of projections or other irregularities that could impede water flow.
- Build the drains with circular, parabolic or trapezoidal cross sections, not V shaped.
- Ensure the banks are properly compacted to prevent failure.
- Complete permanent or temporary stabilisation within 10 days of construction.

## EARTH BANK (LOW FLOW)

SD 5-5




### Construction Notes

- Strip the topsoil, level the site and compact the subgrade.
- Cover the area with needle-punched geotextile.
- Construct a 200 mm thick pad over the geotextile using road base or 30 mm aggregate.
- Ensure the structure is at least 15 metres long or to building alignment and at least 3 metres wide.
- Where a sediment fence joins onto the stabilised access, construct a hump in the stabilised access to divert water to the sediment fence.

## STABILISED SITE ACCESS

SD 6-14



### Construction Notes

- Place stockpiles more than 2 (preferably 5) metres from existing vegetation, concentrated water flow, roads and hazard areas.
- Construct on the contour as low, flat, elongated mounds.
- Where there is sufficient area, topsoil stockpiles shall be less than 2 metres in height.
- Where they are to be in place for more than 10 days, stabilise following the approved ESCP or SWMP to reduce the C-factor to less than 0.10.
- Construct earth banks (Standard Drawing 5-5) on the upslope side to divert water around stockpiles and sediment fences (Standard Drawing 6-8) 1 to 2 metres downslope.

## STOCKPILES

SD 4-1

# MAJOR PROJECT APPLICATION SSD 5248

| Revisions | Issue | Drawn | Design | Check | Appd. | Date      | Revision Details    |
|-----------|-------|-------|--------|-------|-------|-----------|---------------------|
| 00        | AW    | DD    | CB     |       |       | 9/05/2013 | ISSUED FOR REVIEW   |
| 01        | AW    | DD    | CB     |       |       | 2/08/2013 | ISSUED FOR APPROVAL |
| First     | AW    | DD    | CB     |       |       | 9/05/2013 |                     |

Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY  
SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT  
SCALE.



© Brown Consulting Pty Ltd



Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPEng  
MIEAust, Manager Urban Development  
SIGN:   
DATE: 2/8/13

Client:  
**GAZCORP PTY. LTD.**  
Project:  
GAZCORP INDUSTRIAL ESTATE WALLGROVE ROAD, HORSLEY PARK  
EARTHWORKS & ROAD DESIGN



Drawing Title:  
**SEDIMENT & EROSION CONTROL  
NOTES & DETAILS**  
Project No.: X12254.01  
Stage: 01  
Milestone: DA  
Dwg No.: 702  
Revision: 01