

1. ALL TOPSOIL IS TO BE STOCKPILED IN AREAS DESIGNATED ON PLAN.
2. ALL FORMED EMBANKMENTS (CUT & FILL) ARE TO BE LANDSCAPED WITHIN 7 DAYS.
3. ALL DISTURBED AREAS, INCLUDING ANY CONTROLLED FILL ARE TO BE TOPSOILED & SEEDDED PRIOR TO COMPLETION OF WORKS. ALL DISTURBED AREAS THAT WILL NOT BE

4. THE GROUND SHALL BE TYNED / SCARIFIED TO A MIN DEPTH 100mm PRIOR TO SEEDING.
5. ANY SEEDED AREAS WHICH FAIL TO GERMINATE OR WHERE GERMINATION IS SPARSE AFTER

6. FOR TEMPORARY REVEGETATION PURPOSES, THE REVEGETATION MIXTURE SHOULD INCLUDE THE FOLLOWING SPECIES FOR BOTH AUTUMN & SPRING SOWINGS - DURADORE PARK BLEND (Mighty Stephenson Seed Mix) THICKGRASSED TURF TALL FESCUE (15kg/ha) UNHILLED COUCH (4kg/ha) PERENNIAL RYEGRASS (37kg/ha) CHEWINGS FESCUE (5kg/ha) MULTIGROW / ENRICH FERTILIZER AT 500kg/ha

7. REVEGETATION AND STABILIZATION WILL NOT BE CONSIDERED SATISFACTORY UNLESS A MIN 70% GROUND COVER, AT LEAST 100mm HIGH IS ACHIEVED OVER ALL DISTURBED

8. ALL GULLY PITS ARE TO BE PROVIDED WITH SEDIMENT FILTER BARRIERS SUCH AS SANDBAGS OR FILTER SOCKS.

INSTALLATION & BACKFILLING & IMMEDIATELY SEEDED/FERTILIZED.

10. DESIGNATED PLANT AND MACHINERY ACCESSWAYS TO BE DEFINED UNSITE BY THE INSTALLATION OF PARAMWEBBING FENCING TO MINIMIZE UNNECESSARY SITE DISTURBANCE.

## MAINTENANCE PROCEDURES DURING CONSTRUCTION

1. ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED AT ALL TIMES SO THAT THOSE MEASURES ARE FULLY FUNCTIONAL / OPERATIONAL DURING THE CURRENCY OF WORKS. ALL SUCH CONTROLS MUST ALSO BE FULLY FUNCTIONAL / OPERATIONAL SHOULD WORK OPERATIONS CEASE TEMPORARILY, (e.g WEEKENDS, ROSTERED DAYS OFF, etc.)

←

0.6m  
↓  
puno

- area

---

rain

PLOTTED BY :  FILENAME: