



MATERIALS & FINISHES SCHEDULE (Refer to Sample Board for Further Information)

- BAL1** Balustrade Type 1:
Framed balustrade system. Framing system, aluminium, powder coat finish. Colour to match GW1.
- CL1** Cladding Type 1:
Metal cladding system. Prefinished coating system. Colour and finish to match Alpolic 'Charcoal'.
- CL2** Cladding Type 2:
Metal cladding system with expressed vertical aluminium fins over, frequency of expressed fins vary. Metal cladding prefinished coating system, colour and finish to match Alpolic 'Medium Bronze Metallic'. Aluminium fins powder coat finish, colour equal to GW2.
- CL3** Cladding Type 3:
Metal cladding system with integrated louvres for building services. Prefinished coating system. Colour and finish to match Alpolic 'Silver Metallic' and 'Medium Grey Metallic'. Distribution of panel type i.e solid / louvre and colour varies across façade.
- CL4** Cladding Type 4: **NOT USED**
- GW1** Glazed Wall System, Type 1:
Flush lined aluminium framed glazed wall system to façade engineers specification.
Vision panel clear glass, green tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame powder coat finish, colour equal to Interpon 'Monument Matt'.
Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- GW2** Glazed Wall System, Type 2:
Expressed mullions aluminium framed glazed wall system, frequency of expressed mullions vary.
Vision panel clear glass, no tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame including expressed mullions, powder coat finish, colour equal to Dulux 'Eternity Bronze Pearl Satin'.
Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- GW3** Glazed Wall System, Type 3:
Expressed mullions aluminium framed glazed wall system, frequency of expressed mullions vary.
Vision panel translucent glass, light grey tint. Non-vision panel opaque colour back glass, colour to match. Aluminium frame including expressed mullions, powder coat finish, colour equal to GW2.
Performance of overall system to meet ESD and façade engineers requirements. Reflectivity to be less than 20%.
- PF1** Paint Finish, Type 1:
Paint finish with cement render and / or FC lining to substrate. Colour to match Dulux 'Domino'.
- SC1** Screen, Type 1:
Vertical aluminium sun shade screen system, full height. Powder coat finish, colours equal to Interpon 'Gilded Green Matt', 'Cottage Green Matt', 'Wilderness Matt' and 'Headland Matt'.
- SC2** Screen, Type 2:
Vertical aluminium fins with integrated subframe. Powder coat finish, colour equal to GW2.

NOTES:
1. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.
2. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.
3. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.
4. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.
5. ALL DIMENSIONS ARE TO FACE UNLESS OTHERWISE SPECIFIED.

CLIENT
THE GPT GROUP
Level 51 MLC Centre 19 Martin Pl Sydney
NSW 2000 AU

PROJECT MANAGER
LEND LEASE
The Bond, 30 Hickson Road, Millers Point,
NSW 2000 AU

GPT
The GPT Group

Lend Lease

Project Title
4MR
4 Murray Rose Avenue SOP NSW 2127 AU

SECTIONS
Section B

Rev. 14.12.02 DS Section 96 Submission
Date 14.12.02 Approved by
Scale 1:100 @A0, 15% @A3
Drawing Title
SSD SUBMISSION - S06
Project No. **12022**
Drawn by **CM**
Rev. **E**

turner

Level 1 & 415 Green Street
Sydney NSW 2000 0001
1 & 415 Green Street
Sydney NSW 2000 0001