Certificate number: 0000162339 Certificate Date: 02 Sep 2015 ★ Star rating: 3.8



#### **Assessor details**

Accreditation

number: VIC/BDAV/12/1457

Name: **B Carr** Organisation: **STS** 

Email: ENQUIRIES@SUSTAINABLETHERMAL

Phone: **0420312721** 

Declaration No potential conflicts of interest to

of interest: declare

Software: AccuRate Sustainability V2.3.3.13 SP2

AAO: BDAV

### **Overview**

#### **Dwelling details**

Street: Unit G4, 175-177 Cleveland STREET

Suburb: REDFERN

State: NSW Postcode: 2016

Type: New NCC Class: 2

NatHERS

climate zone: **56** 

number: Lot 15,1,10,3,4,5/DI Exposure: Suburban

#### Key construction and insulation materials

(see following pages for details)

Construction: Brick Veneer

Roof - N/A Plywood

Insulation: R2.0 wall insulation

Ceiling (uninsulated) R2.0 floor insulation

Glazing: Aluminium Sliding Door SG 5Clr

52

### Net floor area (m²)

Conditioned: 48
Unconditioned: 4
Garage:

TOTAL:

# Annual thermal performance loads (MJ/m²)

 Heating:
 63


 Cooling:
 31

 TOTAL:
 94

#### Plan documents

Plan reference: 2014067

Prepared by: JPRA Architects



#### **Ceiling penetrations**

(see following pages for details)

Sealed: 0

TOTAL:\*\*

Unsealed:

\*\*NOTE: This total is the maximum number of ceiling penetrations allowed to a ceiling (under a roof) for this certificate. If this number is exceded in construction then this certificate IS NOT VALID and a new certificate is required. Loss of ceiling insulation for the penetrations listed has been taken into account with the rating.

Principle downlight type: No downlights modelled

0

# Window selection - default windows only

Note on allowable window values: With a 10% tolerance to the nominated SHGC window values shown on page 2, the following ratings are achieved:

-10% SHGC 3.8

+10% SHGC 3.8

NB: This tolerance ONLY applies to SHGC, the U-value can always be lower but not higher than the values stated on page 2.

If the rating listed above falls below 6.0 stars or the required rating, then the window with this tolerance can NOT be selected.

Scan to access this certificate online and confirm this is valid.



Certificate number: **0000162339** Certificate Date:

AIR-006-03 A

AIR-006-03 A

living

bed

02 Sep 2015

2500

3000

★ Star rating:

Е

W



3.8

None

None

# **Building features**

Kitchen/Living

Bed

Window type	and performand	e value				
Window ID	Window type				U-value	SHGC
AIR-006-03 A	ALL-WINDOWS	: Aluminium Slid	ling Door SG 5Cl	r	6.20	0.73
Window sche	dule					
Location	Window ID	Window no.	Height (mm)	Width (mm)	Orientation	Outdoor shade
Kitchen/Living	AIR-006-03 A	living	1200	1699	Е	None
Kitchen/Living	AIR-006-03 A	living	2700	850	N	None
Kitchen/Living	AIR-006-03 A	living	2700	1300	N	None

2700

1500

ID	Window type	9			U-value	SHGC
None Present	i					
Roof window	w and skylight so	chedule				
Location	ID	Roof window/skylight	Area (m²)	Orientation	Outdoor shade	Indoor shade/diffuser

External wall type				
Туре	Insulation	Wall wrap or foil		
EW-003: Brick Veneer	Glass fibre batt: R2.0	Yes		
EW-004: Plasterboard	Glass fibre batt: R1.5	No		
EW-005: Plasterboard	Glass fibre batt: R1.5	No		

#### **External wall schedule**

Location	Wall type	Width (mm)	Height (mm)	Orientation	Fixed Shade	Eaves (mm)
Kitchen/Living	EW-004	8100	2700	S	No	
Kitchen/Living	EW-003	1700	2700	Е	No	
Kitchen/Living	EW-003	2900	2700	N	Yes	2650
Kitchen/Living	EW-003	2650	2700	Е	Yes	1800
Bed	EW-004	3000	2700	S	No	
Bed	EW-003	3500	2700	W	Yes	600
Bath	EW-004	1570	2700	S	No	
Entrance/Hall	EW-003	3500	2700	W	No	
Entrance/Hall	EW-005	1400	2700	N	Yes	16900

Internal wall type			
Wall type	Area (m²)	Insulation	Wall wrap or foil



02 Sep 2015





# **Building features continued**

IW-001: Plasterboard 37.8		No
IW-002: Plasterboard 29.5	Glass fibre batt: R1.5	No

Floors					
Location	Construction	Area (m²)	Sub floor ventilation	Added insulation	Covering
Kitchen/Living/Out door Air	Concrete Suspended Slab 100 mm: ceramic tile/R2.0	5.5		R2.0	Ceramic tile
Kitchen/Living/Out door Air	Concrete Suspended Slab 100 mm: timber/R2.0	22.7		R2.0	
Bed/Outdoor Air	Concrete Suspended Slab 100 mm: carpet/R2.0	10.8		R2.0	Carpet 10 + rubber underlay 8
Bath/Outdoor Air	Concrete Suspended Slab 100 mm: ceramic tile/R2.0	3.8		R2.0	Ceramic tile
Entrance/Hall/Outd oor Air	Concrete Suspended Slab 100 mm: timber/R2.0	9.5		R2.0	

Location	Construction	Added insulation	Roof space above
Neighbour/Kitchen/ Living	Concrete Suspended Slab 150 mm: ceramic tile/air gap/plasterboard		No
Neighbour/Kitchen/ Living	Concrete Suspended Slab 150 mm: timber/air gap/plasterboard		No
Neighbour/Bed	Concrete Suspended Slab 150 mm: timber/air gap/plasterboard		No
Neighbour/Bath	Concrete Suspended Slab 150 mm: ceramic tile/air gap/plasterboard		No
Neighbour/Entranc e/Hall	Concrete Suspended Slab 150 mm: timber/air gap/plasterboard		No

Ceiling penet	rations		
Location	Number	Туре	Diameter (mm) Sealed/unsealed
Kitchen/Living	8	Downlight	Unsealed
Bed	4	Downlight	Unsealed
Bath	3	Downlight	Unsealed
Entrance/Hall	3	Downlight	Unsealed
Emilanoo/mail		25Willight	Officoalog

Ceiling fans		
Location	Number	Diameter (mm)
None Present		

# **Roof type**

Certificate number: **0000162339** Certificate Date:

02 Sep 2015

★ Star rating:

3.8

# NATIONWIDE HOUSE ENERGY RATING SCHEME

# **Building features continued**

Construction	Added insulation	Roof colour
None Present		



Additional information		

# **Explanatory notes**

## **About this report**

Residential energy ratings address the quality of the building fabric i.e. walls, windows, floors and roof/ceilings. Ratings do not cover the energy or water efficiency of appliances including heating and cooling, hot water, dishwashers, ovens, fridges, TVs etc. or solar panel or water tank requirements. The efficiency or specification of these items is generally covered by other regulations, standards or guidelines.

#### **General Information**

A NatHERS House Energy Rating is a comprehensive, dynamic computer modelling evaluation of the floorplans, elevations and specifications to predict an energy load of a home. Not all of us use our homes in the same way, so ratings are generated using standard assumptions. This means homes can be compared across the country.

The actual energy consumption of your home may vary significantly from the predicted energy load figures in this report depending on issues such as the size of your household and your personal preferences, e.g. in terms of heating or cooling.

While the figures are an indicative guide to energy use, they can be used as a reliable guide for comparative purposes between different house designs and for demonstrating that the design meets the required regulatory compliance.

Homes that are energy efficient use less energy, are warmer in winter, cooler in summer and cost less to run. The higher the star rating the more energy efficient.

This NatHERS House Energy Rating report was carefully prepared by your assessor on the basis of comprehensive modelling using standard procedures to rate your home using an underlying engine developed by the Australian Commonwealth Scientific and Industrial Research Organisation (CSIRO).

All information relating to energy loads presented in this report is based on a range of standard assumptions in order to allow for comparisons with reports prepared for other homes and to demonstrate minimum regulatory compliance. The standard assumptions include figures for occupancy, indoor air temperature and are based on a unique climate file for your region.

#### **Accredited Assessors**

To ensure you get a high-quality, professional NatHERS House Energy Rating report, you should always use an accredited assessor, accredited assessors are members of a professional body called an Assessor Accrediting Organisation (AAO).

AAOs have specific quality assurance processes in place and continuing professional development requirements to maintain a high and consistent standard of assessments across the country. Non-accredited assessors do not have this level of quality assurance or any on-going training requirements.

If you have any questions or concerns about this report, please direct them to your assessor in the first instance.

If your assessor is unable to address your questions or concerns, please contact their AAO listed under 'assessor details'. You can also find a range of information about accredited assessors on the AAO websites.

#### **Disclaimer**

The energy values quoted are for comparison purposes only; they are not a prediction of actual energy use. This rating only applies to the floor plan, construction details, orientation and climate as submitted and included in the attached drawing set that bears a stamp with the same number as this certificate. Changes to any of these details could affect the rating.

#### Contact

For more information on the Nationwide House Energy Rating Scheme (NatHERS), visit www.nathers.gov.au For more information on energy efficient design and insulation visit www.yourhome.gov.au