

Development Consent

Section 89E of the Environmental Planning and Assessment Act 1979

As delegate of the Minister for Planning under delegation executed on 11 October 2017, I determine:

- (a) to grant consent to the concept development application referred to in Schedule 1, subject to the conditions specified in Schedules 2 to 3; and
- (b) that pursuant to section 89D(2) of the *Environmental Planning and Assessment Act 1979*, I determine that any subsequent stage of the development not having a capital investment value in excess of \$10 million is to be determined by the relevant authority and that stage of the development ceases to be State significant development.

These conditions are required to:

- prevent, minimise, and/or offset adverse environmental impacts;
- set standards and performance measures for acceptable environmental performance;
- require regular monitoring and reporting; and
- provide for the ongoing environmental management of the development.

Anthea Sargeant
Executive Director
Key Sites and Industry Assessments

Sydney

9 November 2017

The Department has prepared a consolidated version of the consent which is intended to include all modifications to the original determination instrument.

The consolidated version of the consent has been prepared by the Department with all due care. This consolidated version is intended to aid the consent holder by combining all consents relating to the original determination instrument but it does not relieve a consent holder of its obligation to be aware of and fully comply with all consent obligations as they are set out in the legal instruments, including the original determination instrument and all subsequent modification instruments.

CONSOLIDATED CONSENT

SCHEDULE 1

Application Number:	SSD-7664
Applicant:	Western Sydney Parklands
Consent Authority:	Minister for Planning
Land:	Horsley Drive, Wetherill Park (Lots 17-22 DP 13961 and Lot 2 DP 1212087)
Development:	<p>Horsley Drive Business Park Stage 2 concept development application, comprising:</p> <ul style="list-style-type: none">• a Concept Proposal for up to 88,700 m² of Gross Floor Area for general industrial, light industrial, warehouse and distribution and ancillary office land uses, building envelopes and levels for Lots 1 – 4, road layout and sites access and landscape designs; and• Stage 1 project approval works including subdivision of the site, construction of a public access road off, demolition, bulk earthworks, site infrastructure and landscaping.

FOR INFORMATION

CONSOLIDATED CONSENT

SUMMARY OF MODIFICATIONS

Application Number	Determination Date	Decider	Modification Description
SSD-7664-Mod-1	10 August 2020	Director	Revised location and configuration of vehicular access to the site; consolidation of warehouses 1 and 2, minor reductions in lots size and development footprint for warehouses 3 and 4; consolidation of subdivided lots from seven to four.
SSD-7664-Mod-2	19 March 2021	Director	Amendment of Building Height
SSD-7664-Mod-3	23 May 2022	Team Leader	Subdivision and GFA Amendment

TABLE OF CONTENTS

DEFINITIONS	ii
SCHEDULE 2: CONDITIONS OF CONSENT FOR CONCEPT DEVELOPMENT	1
PART A TERMS OF CONSENT FOR CONCEPT DEVELOPMENT	1
TERMS OF CONSENT	1
STATUTORY REQUIREMENTS	1
DETERMINATION OF FUTURE DEVELOPMENT APPLICATIONS	1
LIMITS OF CONSENT	1
STAGED SUBMISSION OF PLANS OR PROGRAMS	2
EVIDENCE OF CONSULTATION	2
PART B CONDITIONS TO BE MET IN FUTURE DEVELOPMENT APPLICATIONS	2
TRAFFIC AND ACCESS	2
BICYCLE PARKING AND END OF TRIP FACILITIES	3
SOIL AND WATER	3
LANDSCAPING	3
NOISE AND VIBRATION	4
TRANSMISSION LINE EASEMENT	4
SCHEDULE 3: CONDITIONS OF CONSENT FOR STAGE 1	5
PART A ADMINISTRATIVE CONDITIONS	5
TERMS OF CONSENT	5
OBLIGATION TO MINIMISE HARM TO THE ENVIRONMENT	6
CONSTRUCTION CERTIFICATE REQUIRED	6
EASEMENTS	6
UTILITIES AND SERVICES	7
PROTECTION OF PUBLIC INFRASTRUCTURE	7
COMPLIANCE	7
WORKS-AS-EXECUTED PLANS	7
DEVELOPMENT CONTRIBUTIONS	7
SUBDIVISION	7
PART B ENVIRONMENTAL PERFORMANCE	8
TRAFFIC AND ACCESS	8
SOIL AND WATER	9
NOISE AND VIBRATION	10
HERITAGE	11
BIODIVERSITY	11
AIR QUALITY	12
HAZARDS AND RISK	12
CONTAMINATION AND REMEDIATION	12
WASTE	13
VISUAL AMENITY	13
TRANSMISSION LINE EASEMENT	13
FENCING	13
PART C ENVIRONMENTAL MANAGEMENT	15
ENVIRONMENTAL MANAGEMENT	15
REPORTING	17

CONSOLIDATED CONSENT

(a) DEFINITIONS

Aboriginal object	Has the same meaning as the definition of the term in section 5 of the NP&W Act
Aboriginal place	Has the same meaning as the definition of the term in section 5 of the NP&W Act
Applicant	Western Sydney Parklands Trust, or any other person carrying out any development to which this consent applies
BCA	Building Code of Australia
Concept Proposal	The Concept Proposal comprises the establishment of up to 88,700 m ² of Gross Floor Area general industrial, light industrial, warehouse and distribution and ancillary office land uses and conceptual development levels, footprints and building envelopes, road layout and site access and landscape designs
Conditions of this consent	The conditions contained in Schedule 2 and 3 of this document
Construction	The demolition and removal of buildings or works, the carrying out of works for the purpose of the development, including earthworks, and other infrastructure permitted by this consent
Council	Fairfield City Council
Day	The period from 7am to 6pm on Monday to Saturday, and 8am to 6pm on Sundays and Public Holidays
Department	NSW Department of Planning, Industry and Environment
Development	The development as described in the EIS and Submissions Report as modified by and subject to the conditions of this consent
DPI	NSW Department of Primary Industries
Earthworks	Bulk earthworks, site levelling, import and compaction of fill material, excavation for installation of drainage and services
EES Group	Environment, Energy and Science Group of the Department
EIS	The Environmental Impact Statement submitted with the concept development application, titled Horsley Drive Business Park Stage 2 (SSD 7664) – Western Sydney Parklands Concept Proposal and Stage One DA, prepared by JBA Urban Planning Consultants Pty Ltd dated December 2016
EPA	NSW Environment Protection Authority
EP&A Act	<i>Environmental Planning & Assessment Act 1979</i>
EP&A Regulation	<i>Environmental Planning & Assessment Regulation 2000</i>
EPL	An Environment Protection Licence as defined in the POEO Act
Evening	The period from 6 pm to 10 pm
Feasible	Feasible relates to engineering considerations and what is practical to build
GFA	Gross floor area
Harm	to the environment includes any direct or indirect alteration of the environment that has the effect of degrading the environment and, without limiting the generality of the above, includes any act or omission that results in pollution, and such harm will be material if: (a) it involves actual or potential harm to the health or safety of human beings or to ecosystems that is not trivial, or (b) it results in actual or potential loss of property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment)
Heavy vehicle	A vehicle that has a Gross Vehicle Mass or Aggregate Trailer Mass of more than 4.5 tonnes
Heritage	Encompasses both Aboriginal and historic heritage including sites that predate European settlement, and a shared history since European settlement
Heritage Item	An Aboriginal object, an Aboriginal place, or a place, building, work, relic, moveable object, tree or precinct of heritage significance, that is listed under any of the following: the State Heritage Register under the <i>Heritage Act 1977</i> , a state agency heritage and conservation register under section 170 of the <i>Heritage Act 1977</i> , a Local Environmental Plan under the EP&A Act, the World Heritage List, or the National Heritage List or Commonwealth Heritage List under the <i>Environment Protection and Biodiversity Conservation Act 1999</i> , or anything identified as a heritage item under the conditions of this consent
Heritage NSW	Heritage NSW within the Department of Premier and Cabinet
Incident	An occurrence or set of circumstances that: (a) causes or threatens to cause material harm to the environment; or (b) results in non-compliance with this consent
Land	Has the same meaning as the definition of the term in section 4 of the EP&A A
Minister	NSW Minister for Planning and Public Spaces (or delegate)
Modification Assessments	The document assessing the environmental impact of a proposed modification of consent and any other information submitted with the following modification applications made under the EP&A Act: (a) SSD 7664 MOD 1 – Statement of Environmental Effects – Horsley Drive Business Park Stage 2, prepared by Ethos Urban Pty Ltd, dated 27 March 2020, and Response to Submissions, prepared by Ethos Urban Pty Ltd, dated 17 June 2020. (b) SSD-7664-Mod-2 – Statement of Environmental Effects – Horsley Drive Business Park Stage 2 (Section 4.55(1A) Modification Application (Mod No.2)),

CONSOLIDATED CONSENT

prepared by Ethos Urban Pty Ltd, dated 16 December 2020.

(c) State Significant Development 7664, Horsley Drive Business Park Stage 2, Section 4.55 (1A) Modification Application (Mod No. 3), prepared by Ethos Urban Pty Ltd, Revision V1, dated 11 November 2021.

NP&W Act	<i>National Parks and Wildlife Act 1974</i>
Night	The period from 10 pm to 7 am on Monday to Saturday, and 10 pm to 8 am on Sundays and Public Holidays
Planning Secretary	Secretary of the Department, or nominee
POEO Act	<i>Protection of the Environment Operations Act 1997</i>
Reasonable	Reasonable relates to the application of judgment in arriving at a decision, taking into account: mitigation benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements
Registered Aboriginal Parties	Means the Aboriginal persons identified in accordance with the document entitled "Aboriginal cultural heritage consultation requirements for proponents 2010" (DECCW)
Sensitive Receivers	Residence, education institution (e.g. school, university, TAFE college), health care facility (e.g. nursing home, hospital), religious facility (e.g. church) and children's day care facility
Site	The land listed in Schedule 1
Site Auditor	Has the same meaning as the definition of the term in section 4 of the <i>Contaminated Land Management Act 1997</i>
Submissions report	The report submitted to the Secretary under the EP&A Act comprising a response to written submissions made during the public exhibition period of the EIS, dated 17 July 2017
TfNSW	Transport for NSW
VENM	Virgin Excavated Natural Material as defined in the <i>Protection of the Environment Operations Act 1997</i>
Upper Canal	Upper Canal Heritage item listed on the NSW State Heritage Inventory located on land identified as Lot 1 DP 596354

CONSOLIDATED CONSENT

SCHEDULE 2: CONDITIONS OF CONSENT FOR CONCEPT DEVELOPMENT

PART A TERMS OF CONSENT FOR CONCEPT DEVELOPMENT

TERMS OF CONSENT

- A1. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the [Planning Secretary](#);
 - (c) in accordance with the EIS and Submissions report;
 - (c1) in accordance with the [Modification Assessments](#);
 - (d) the following drawings, except for:
 - i) any modifications which are 'Exempt' or 'Complying Development'; and
 - ii) otherwise provided by the conditions of this consent.

Drawings prepared by Watch This Space Design Pty Ltd			
Drawing No.	Revision	Name of Plan	Date
DA 02	Rev P6	Overall Site Plan	10/05/22
Subdivision Drawings prepared by Shawn Leclerc			
Drawing No.	Revision	Name of Plan	Date
10990-002 - Sheets 1 & 2	Rev D	Plan of Subdivision of Lots 18-22 in DP 13961 & Lot 2 in DP 1212087	26/04/22

- A2. If there is any inconsistency between the above documents, the most recent document shall prevail to the extent of the inconsistency. However, the conditions of this consent shall prevail to the extent of any inconsistency.
- A3. The Applicant must comply with any reasonable requirement(s) of the [Planning Secretary](#) arising from the Department's assessment of:
- (a) any reports, plans or correspondence that are submitted in accordance with this consent; and
 - (b) the implementation of any actions or measures contained within these reports, plans or correspondence.

STATUTORY REQUIREMENTS

- A4. The Applicant must ensure that all licences, permits, and approvals/consents are obtained as required by law and maintained as required throughout the life of the development. No condition of this consent removes the obligation for the Applicant to obtain, renew or comply with such licences, permits or approvals/consents.

DETERMINATION OF FUTURE DEVELOPMENT APPLICATIONS

- A5. In accordance with section 83B(3) of the EP&A Act, the subsequent stages are to be subject of future development applications.
- A6. The determination of the future development application(s) are to be consistent with the terms of this consent as described in Schedule 1, and subject to the conditions in Schedules 2 and 3.

LIMITS OF CONSENT

- A7. This consent lapses five years after the date from which it operates, unless the development has physically commenced on the land to which the consent applies before the date on which the consent would otherwise lapse under section 95 of the EP&A Act.

CONSOLIDATED CONSENT

- A9. This consent does not approve the erection of any buildings.
- A10. The Applicant shall ensure the future development of the site is consistent with the development controls in Table 1 below:

Table 1: Development Controls

Development Aspect	Control
Setback to Cowpasture Road	10 metres
Internal estate road setback	7.5 metres
Western boundary and canal setback to lot	4 metres
Height	16 metres
Floor space ratio	1:1
Site coverage	Maximum of 65 per cent
Minimum lot size for industrial lots	10,000 m ²

A10A. Notwithstanding Condition A10, the building height for Building 1 (floor level to top of rooftop plant / screening treatments) must not exceed 19.626 m (RL 87.126 m) (as described in the modification application SSD-10404-Mod-1).

- A11. The following limits apply to future development on the site:
- (a) the maximum GFA for the warehouses shall not exceed the limits outlined in Table 2 below; and
 - (b) loading docks, car parking and internal access driveways to buildings are not approved.

Table 2: GFA Maximum for Concept Development

Land Use	Maximum GFA (m ²)
Total Warehouse	85,700
Total Office	3,000
Total GFA	88,700

STAGED SUBMISSION OF PLANS OR PROGRAMS

- A12. With the approval of the [Planning Secretary](#), the Applicant may:
- (a) submit any strategy, plan or program required by this consent on a progressive basis; and/or
 - (b) combine any strategy, plan or program required by this consent.
- A13. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan or program. A clear relationship between the strategy, plan or program that is to be combined must be demonstrated.

EVIDENCE OF CONSULTATION

- A14. Where consultation with any public authority is required by the conditions of this consent, the Applicant must:
- (a) consult with the relevant public authority prior to submitting the required documentation to the [Planning Secretary](#) or the certifying authority for approval, where required;
 - (b) submit evidence of this consultation as part of the relevant documentation required by the conditions of this consent; and
 - (c) include the details of any outstanding issues raised by the relevant public authority and an explanation of disagreement between any public authority and the Applicant or any person acting on this development consent.

(b) PART B CONDITIONS TO BE MET IN FUTURE DEVELOPMENT APPLICATIONS

TRAFFIC AND ACCESS

- B1. Car parking must be provided in accordance with the *RMS Guide to Traffic Generating Developments* and at the following rates:
- (a) 1 space per 300 m² GFA for general and light industrial and warehouse and distribution centre uses;

CONSOLIDATED CONSENT

- (b) 1 space per 40 m² GFA for office uses; ~~and~~
 - (c) 1 space per 100 car parking spaces or part thereof for accessible car parking; or
 - (d) in accordance with an operationally specific Traffic Impact Assessment submitted with any future development applications.
- B2. Future development on the site must meet the following requirements:
- (a) internal roads, driveways and parking (including grades, turn paths, sight distance requirements, aisle widths, aisle lengths and parking bay dimensions) associated with the development are constructed and maintained in accordance with the latest version of AS 1428.1, AS 2890.1, AS 2890.2 and AS 2890.6;
 - (b) the swept path of the longest vehicle entering and exiting the site, as well as manoeuvrability through the site, is in accordance with the relevant AUSTRROADS guidelines;
 - (c) vehicles must not queue on the public road network;
 - (d) heavy vehicles and bins associated with the development are not parked on local roads or footpaths in the vicinity of the site;
 - (e) all vehicles are wholly contained on site before being required to stop;
 - (f) all loading and unloading of materials is carried out on-site;
 - (g) all vehicles enter and exit the site in a forward direction;
 - (h) all trucks entering or leaving the site with loads have their loads covered and do not track dirt onto the public road network; and
 - (i) the proposed turning areas in the car park are kept clear of any obstacles, including parked cars, at all times.
- B3. Access to lots must be provided in accordance with Council's specifications.

BICYCLE PARKING AND END OF TRIP FACILITIES

- B4. Bicycle parking or end of trip facilities is to be provided in accordance with relevant guidelines and standards.

SOIL AND WATER

- B5. The development must be designed and constructed to be capable of obtaining a section 73 Compliance Certificate from Sydney Water Corporation in accordance with the *Sydney Water Act 1994*. Prior to the commencement of operations on the site a section 73 Compliance Certificate must be obtained from Sydney Water Corporation.
- B6. All development on the site must comply with section 120 of the *Protection of the Environment Operations Act 1997*, which prohibits the pollution of waters, except as expressly provided in an Environment Protection Licence.
- B7. All building floor levels must be a minimum of 500 millimetres (mm) above the 1 in 100 year flood level.
- B8. Erosion and sediment control measures on-site must be in accordance with *Managing Urban Stormwater: Soils and Construction Vol. 1* (Landcom, 2004).

LANDSCAPING

- B9. Landscaping must be consistent with the key principles and plant species described in the Landscape Plans prepared by [Geoscapes Landscape Architects as referenced in Condition A1 – Schedule 3 Part A](#).
- B10. Landscaping must screen any acoustic barrier referenced in condition B13 of Schedule 2, blank walls or loading docks from any nearby sensitive receiver with a mix of shrub planting and trees and be provided to the satisfaction of the consent authority.

CONSOLIDATED CONSENT

- B11. In accordance with the recommendations provided in the Heritage Impact Statement, prepared by Biosis dated 9 November 2016, landscaping must include shrubs and trees capable of reaching and buffering proposed building heights and building design to avoid adverse impacts on the significance of the Upper Canal.

NOISE AND VIBRATION

Operational Noise Limits

- B12. For all future development at the site, noise generated during operations must not exceed the noise limits outlined in Table 3 when measured at the property located at 28 Trivet Street, Wetherill Park.

Table 3: Noise Limits dB(A)

Location	Day L _{Aeq} (15 minute)	Evening L _{Aeq} (15 minute)	Night L _{Aeq} (15 minute)	Night L _{A1} (1 minute)
28 Trivet Street, Wetherill Park	52	49	47	57

Note: Noise is to be measured in accordance with the relevant procedures and exemptions (including certain meteorological conditions) of the NSW Industrial Noise Policy.

- B13. If the construction of an acoustic barrier is required to achieve the noise limits in Condition B12 above, the barrier must be maintained as required and comprise a density of at least 10-15 kg/m².

TRANSMISSION LINE EASEMENT

- B14. Future development on the site which is located within 15 metres of a transmission tower or in close proximity to Endeavour Energy's electrical network must:
- be constructed of non-conducting materials;
 - must maintain the integrity of all line structures and stay pole/wires at all times; and
 - comply with AS/NZS 3000:2007 'Electrical installations' to ensure that there is adequate connection to the earth.
- B15. Final design drawings must be submitted to Endeavour Energy prior to the commencement of works to confirm no impact on Endeavour Energy's transmission towers.
- B16. Trees must not be planted within the transmission line easement.

Access

- B17. The Applicant must ensure that access to the transmission towers, lines and easement is maintained at all times.

Earthworks and Construction

- B18. Prior to the commencement of construction, the Applicant must obtain advice from the Dial Before You Dig 1100 service in accordance with the requirements of the *Electricity Supply Act 1995* (NSW) and associated regulations to identify the location of any underground electrical or other utility infrastructure on the site as well potential hazards associated with existing utilities on the site.
- B19. All construction works are to be carried out in accordance with the NSW WorkCover *Work near Overhead Powerlines Code of Practice 2006*.

CONSOLIDATED CONSENT

SCHEDULE 3: CONDITIONS OF CONSENT FOR STAGE 1

PART A ADMINISTRATIVE CONDITIONS

TERMS OF CONSENT

- A1. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the [Planning Secretary](#);
 - (c) in accordance with the EIS and Submissions Report;
 - (c1) in accordance with the [Modification Assessments](#);
 - (d) the following drawings, except for:
 - i) any modifications which are 'Exempt' or 'Complying Development'; and
 - ii) otherwise provided by the conditions of this consent.

Drawings prepared by Watch This Space Design Pty Ltd			
Drawing No.	Revision	Name of Plan	Date
DA 02	Rev P6	Overall Site Plan	10/05/22
Subdivision Drawings prepared by Shawn Leclerc			
Drawing No.	Revision	Name of Plan	Date
10990-002 – Sheets 1 & 2	Rev D	Plan of Subdivision of Lots 18-22 in DP 13961 & Lot 2 in DP 1212087	26/04/22
Civil Engineering Drawings prepared by Costin Roe Consulting Pty Ltd			
Drawing No.	Revision	Name of Plan	Date
CO11492.17-DA 10	C	Drawing List & General Notes	25/06/2020
CO11492.17-DA 20	C	Erosion & Sediment Control Plan	28/02/2020
CO11492.17-DA 25	A	Erosion & Sediment Control Details	11/12/2019
CO11492.17-DA 30	E	Bulk Earthworks Cut/Fill Plan	13/03/2020
CO11492.17-DA 31	A	Bulk Earthworks Cut/Fill Plan – Comparison to Current Approved Levels	23/06/2020
CO11492.17-DA 35	D	Bulk Earthworks Sections - Sheet 1	23/06/2020
CO11492.17-DA 36	D	Bulk Earthworks Sections - Sheet 2	23/06/2020
CO11492.17-DA 37	C	Bulk Earthworks Sections - Sheet 3	23/06/2020
CO11492.17-DA 40	B	Existing Stormwater Catchment Plan	11/12/2019
CO11492.17-DA 41	E	Concept Civil Works Plan - Sheet 1	13/03/2020
CO11492.17-DA 42	D	Concept Civil Works Plan - Sheet 2	13/03/2020
CO11492.17-DA 43	D	Concept 2 Basin Plan Northern Basin	05/02/2020
CO11492.17-DA 44	C	Concept Basin 3 Plan Western Basin	28/02/2020
CO11492.17-DA 45	C	Bio-Retention/OSD Basin Plan	05/02/2020
CO11492.17-DA 46	A	Stormwater Details - Sheet 1	11/12/2019
CO11492.17-DA 47	A	Stormwater Details - Sheet 2	11/12/2019
CO11492.17-DA 48	B	Stormwater Long Sections	28/02/2020
CO11492.17-DA 50	B	Access Road Details	11/12/2019
CO11492.17-DA 51	A	Access Track & Channel Details	11/12/2019

CONSOLIDATED CONSENT

CO11492.17-DA 52	C	Road Alignment Plan & Long Sections	13/03/2020
CO11492.17-DA 61	A	Retaining Wall Plan and Elevations – Sheet 1	25/06/2020
CO11492.17-DA 62	A	Retaining Wall Plan and Elevations – Sheet 2	25/06/2020
CO11492.17-DA 63	A	Retaining Wall Plan and Elevations – Sheet 3	25/06/2020
CO11492.17-DA 64	A	Retaining Wall Plan and Elevations – Sheet 4	25/06/2020
CO11492.17-DA 65	A	Retaining Wall Typical Details	25/06/2020
CO11492.17-DA 70	A	Intersection Functional Layout Plan	11/12/2019
Landscape Plans prepared by Geoscapes Landscape Architects			
Drawing No.	Revision	Name of Plan	Date
SSD-00	I	Landscape Cover Sheet	17/06/2020
SSD-01	I	Landscape Master Plan – North	17/06/2020
SSD-02	I	Landscape Master Plan – South	17/06/2020
SSD-03	I	Hydromulch Set-out Plan	17/06/2020
SSD-04	I	Landscape Detail Plan – Sheet 1	17/06/2020
SSD-05	I	Landscape Detail Plan – Sheet 2	17/06/2020
SSD-06	I	Landscape Detail Plan – Sheet 3	17/06/2020
SSD-07	I	Landscape Detail Plan – Sheet 4	17/06/2020
SSD-08	I	Landscape Detail Plan – Sheet 5	17/06/2020
SSD-09	I	Landscape Sections – Sheet 1	17/06/2020
SSD-10	I	Landscape Sections – Sheet 2	17/06/2020
SSD-11	I	Landscape Sections – Sheet 3	17/06/2020
SSD-12	I	Typical Specifications and Details	17/06/2020
SSD-13	I	Plant Schedules and imagery	17/06/2020

- A2. If there is any inconsistency between the above documents, the most recent document shall prevail to the extent of the inconsistency. However, the conditions of this consent shall prevail to the extent of any inconsistency.

OBLIGATION TO MINIMISE HARM TO THE ENVIRONMENT

- A3. In addition to meeting the specific performance criteria established under this consent, the Applicant must implement all reasonable and feasible measures to prevent and/or minimise any harm to the environment that may result from the development.

CONSTRUCTION CERTIFICATE REQUIRED

- A4. Prior to the commencement of any building and/or construction works, the Applicant must obtain a Construction Certificate from the Certifying Authority.

EASEMENTS

- A5. The creation of easements for services, rights of carriageway and restrictions in regards to the user are required under section 88E of the *Conveyancing Act 1919*, including (but not limited to) the following:
- (a) easements for sewer, water supply and drainage over all public services/infrastructure on private property;
 - (b) drainage easements are to be placed over all subsurface drains and interallotment drainage, benefiting and burdening the property owners;
 - (c) maintenance of the subsurface drains is to be included in the section 88E Instrument;
 - (d) restriction as to user and positive covenant relating to the:
 - i. on-site detention system/s;
 - ii. stormwater pre-treatment system/s; and
 - iii. overland flowpath works;

CONSOLIDATED CONSENT

- (e) flood control works.

Any section 88E Instrument creating restrictions as to user, rights of carriageway or easements which benefit Council shall contain a provision enabling such restrictions, easements or rights of way to be revoked, varied or modified only with the consent of Council.

- A6. Prior to the issue of a subdivision certificate, written confirmation must be provided from a Registered Surveyor that easements have been created for all encroaching services connections, or alternatively that all services are contained wholly within their respective allotments.

UTILITIES AND SERVICES

- A7. Prior to the construction of any utility works associated with the development, the Applicant shall obtain relevant approvals from service providers.

PROTECTION OF PUBLIC INFRASTRUCTURE

- A8. Prior to the commencement of construction, the Applicant must:
 - (a) consult with the relevant owner and/or provider of services that are likely to be affected by the development to make suitable arrangements for access to, diversion, protection, and/or support of the affected infrastructure;
 - (b) prepare a dilapidation report identifying the condition of all public infrastructure in the vicinity of the site (including roads, gutters and footpaths); and
 - (c) submit a copy of this report to the [Planning Secretary](#) and Council.
- A9. The Applicant must:
 - (a) repair, or pay the full costs associated with repairing any public infrastructure that is damaged by the development; and
 - (b) relocate, or pay the full costs associated with relocating any infrastructure that needs to be relocated as a result of the development.

COMPLIANCE

- A10. The Applicant must ensure that employees, contractors and sub-contractors are aware of, and comply with, the conditions of this consent relevant to their respective activities.
- A11. The Applicant must be responsible for environmental impacts resulting from the actions of all persons that it invites onto the site, including contractors, sub-contractors and visitors.

WORKS-AS-EXECUTED PLANS

- A12. On completion of works, the Applicant must submit to the Certifying Authority detailed works-as-executed drawings signed by a registered surveyor demonstrating the stormwater drainage, on-site detention, access road, lot filling and finished ground levels have been constructed as approved.

DEVELOPMENT CONTRIBUTIONS

- A13. Prior to the issue of the Subdivision Certificate, the Applicant must pay a Section 94A contribution in accordance with Council's *Indirect (Section 94A) Development Contribution Plan 2011*. The contribution amount payable must be confirmed by Council in writing.

Copies of Council's *Indirect (Section 94A) Development Contribution Plan 2011* may be obtained from Council's offices located at 86 Avoca Road, Wakeley.

SUBDIVISION

- A14. The Applicant must subdivide the site in accordance with the subdivision plan titled *Plan of Subdivision of Lots 18-22 in DP 13961 & Lot 2 in DP 1212087, drawing number 10990-002 Rev D - Sheets 1 & 2, prepared by Shawn Leclerc, dated 26 April 2022.*

PART B ENVIRONMENTAL PERFORMANCE

TRAFFIC AND ACCESS

- B1. The Applicant must ensure that:
- (a) the development does not result in any vehicles queuing on the public road network;
 - (b) heavy vehicles associated with the development do not park or stand on local roads or footpaths in the vicinity of the site;
 - (c) all vehicles are wholly contained on-site before being required to stop;
 - (d) all vehicles enter and exit the site in a forward direction;
 - (e) all loading and unloading of materials is carried out on-site; and
 - (f) the loading areas and turning areas in the car park are kept clear of any obstacles, including parked vehicles, at all times.

Intersection Works

- B2. The Applicant must enter into a Transport Infrastructure Contribution Deed with RMS for the upgrade works on the roundabout intersection at The Horsley Drive and Cowpasture Road. The Transport Infrastructure Contribution Deed shall be limited to a monetary contribution of \$300,000, being 1% of the anticipated cost of the upgrade works to The Horsley Drive and Cowpasture Road intersection.
- B3. Prior to the release of the Subdivision Certificate, the Applicant must provide written evidence to the satisfaction of the [Planning Secretary](#) demonstrating that a Transport Infrastructure Contribution Deed has been entered into with RMS for the payment of the intersection upgrade works.

Roadworks and Access

- B4. Prior to the commencement of construction works, the Applicant must submit a Road Safety Audit prepared by an accredited Road Safety Auditor to the satisfaction of the relevant roads authority to verify that access can be safely provided from the site to Cowpasture Road. The Applicant must provide a summary of any actions taken in response to the Road Safety Audit findings, demonstrating that any identified issues have been satisfactorily resolved, as is practicable.
- B5. [Prior to the commencement of construction works associated with the re-alignment of Cowpasture Road \(including the roundabout, estate road and eastern cul-de-sac\) the Applicant must submit detailed road design plans prepared by a qualified practicing Civil Engineer to the satisfaction of Council, as the relevant roads authority. The plans must:](#)
- [\(g\) demonstrate that the proposed re-alignment is designed in accordance with Council's engineering standards](#)
 - [\(h\) demonstrate that all new roads can accommodate up to a 25m/26m B-Double in accordance with AUSTROADS: Design Vehicles and Turning Path Templates; and](#)
 - [\(i\) demonstrate that a 25m/26m B-Double can safely access and exit the properties of 105, 109, 115-119 and 121-123 Cowpasture Road, Wetherill Park.](#)
- B6. Prior to the commencement of construction works for the access road that connects to the existing public road network, the Applicant must obtain approval for the works under section 138 of the *Roads Act 1993*.
- B7. Prior to the commencement of construction works, the Applicant must obtain a Road Occupancy Licence in accordance with the RMS Road Occupancy Manual.

Dedication of Roadway

CONSOLIDATED CONSENT

- B8. Prior to the issue of a Subdivision Certificate, the access road must be dedicated to the relevant roads authority. Prior to any dedication, the Applicant must ensure that the construction of the road has been completed to the satisfaction of the relevant roads authority.

Footpath

- B9. The Applicant must provide, at no cost to Council, footpath paving in accordance with Council's policies along the full length of the proposed access road (southern side only).

SOIL AND WATER

Erosion and Sediment Control

- B10. Prior to the commencement of construction, the Applicant must install and maintain suitable erosion and sediment control measures on-site, particularly where works are adjacent to the Upper Canal, in accordance with the latest version of *Managing Urban Stormwater: Soils and Construction Guideline* and the Erosion and Sediment Control Plan included in the CEMP required by condition C6 below.

Imported Soil

- B11. The Applicant must ensure that any material imported and used as fill on the site:
- (a) is VENM as defined in Schedule 1 of the *Protection of the Environment Operations Act 1997*; or
 - (b) meets the requirements of the EPA's *Excavated Natural Material Order 2014*, under the *Protection of the Environment Operations (Waste) Regulation 2014*.
- B12. The Applicant must:
- (c) keep accurate records of the volume and type of fill to be used; and
 - (d) make these records available to the [Planning Secretary](#) upon request.
- B13. Filling operations must be in accordance with the latest version of AS 3798 *Guidelines on Earthworks for Commercial and Residential Developments* and Level 1 Testing must be undertaken in accordance with the latest version of AS 1289 *Method of testing soils for engineering purposes* by a suitably qualified geotechnical engineer.

Pollution of Waters

- B14. The Applicant must comply with section 120 of the POEO Act, which prohibits the pollution of waters.
- B15. Prior to the commencement of works, the Applicant must notify WaterNSW of any works within 20 metres of the western boundary and submit to WaterNSW details of construction works along the boundary of the Upper Canal.
- B16. All site preparation and construction work carried out adjacent to the Upper Canal must not impact on water quality, or damage the Upper Canal. Should any damage occur as a result of the works being carried out for the development, the Applicant must rectify the damage to the satisfaction of WaterNSW and/or compensate WaterNSW for any associated costs.
- B17. No stockpiles are to be located within or close to the Upper Canal.

Stormwater

- B18. The development must not cause an increase in stormwater flows onto the Upper Canal or impede the pre-development levels of stormwater flowing from the Upper Canal onto the site.
- B19. Prior to the commencement of construction works, the Applicant must prepare a Stormwater Management Plan (SMP) to the satisfaction of the [Planning Secretary](#). The SMP must:
- (a) be prepared by a suitably qualified engineer prior to the commencement of the relevant works in consultation with Council;
 - (b) be prepared generally in accordance with the:

CONSOLIDATED CONSENT

- i. Civil Engineering Report for State Significant Development Application (SSD 7664), rev. D, report no. Co111492.11 prepared by Costin Roe Consulting Pty Ltd dated 16 June 2017;
 - ii. *Water Sensitive Design - Technical Guidelines for Western Sydney* prepared by URS Australia Pty Ltd dated May 2004;
 - iii. Council's engineering design guidelines including Council's *Stormwater Drainage Policy 2002*;
 - iv. Council's *Urban Area On-Site Detention Handbook 1997*;
 - v. Council's *Fairfield Citywide Development Control Plan 2013*;
- (c) ensure that public safety issues are addressed;
 - (d) incorporate design plans and accompanying design notes;
 - (e) incorporate bio-swales, gross pollutant traps and stormwater pollutant filters; and
 - (f) describe the measures that would be implemented to maintain this infrastructure during the life of the Development including:
 - i. a program for maintenance and monitoring to ensure stormwater quantity and quality is maintained, and detail the procedures to be undertaken if any non-compliance is detected; and
 - ii. all contractor's cleaning reports or certificates that will be provided to Council over the life of the development.

B20. The Applicant shall carry out the development in accordance with the SMP described in condition B19 of Schedule 3 as approved by the [Planning Secretary](#) (and as revised and approved by the [Planning Secretary](#) from time to time).

Groundwater Interception and Extraction

B21. The Applicant must obtain any necessary water related approvals from DPI in the event that groundwater is likely to be intercepted or extracted during construction works.

NOISE AND VIBRATION

Hours of Work

B22. The Applicant must comply with the hours detailed in Table 5, unless otherwise agreed in writing by the [Planning Secretary](#).

Table 5: Hours of Work

Activity	Day	Time
Earthworks and construction	Monday – Friday	7:00am to 6:00pm
	Saturday	8:00am to 1:00pm
	Sunday & Public Holiday	Nil

B23. Works outside of the hours identified in condition B22 may be undertaken in the following circumstances:

- (a) where works are agreed to in writing by the [Planning Secretary](#);
- (b) for the delivery of materials required outside these hours by the NSW Police Force or other authorities for safety reasons; or
- (c) where it is required in an emergency to avoid the loss of lives, property and/or to prevent environmental harm.

Road Traffic Noise

B24. Prior to the commencement of construction, the Applicant must prepare a Driver Code of Conduct and induction training for the development to minimise road traffic noise.

Noise Management

- B25. All earthworks and construction works must be carried out with the aim of achieving the construction noise management levels detailed in the *Interim Construction Noise Guideline* (Department of Environment and Climate Change, 2009).
- B26. The Applicant must:
- implement best practice, including all reasonable and feasible noise management and mitigation measures to prevent and minimise noise generated by the development;
 - minimise the noise impacts of the development during adverse meteorological conditions; and
 - regularly assess noise emissions and relocate, modify and/or stop works to ensure compliance with the relevant conditions of this consent.

Vibration

- B26A. Vibration caused by construction at any residence or structure outside the site, including the Upper Canal, must not exceed 8-10mm/s as set out in the latest version of DIN 4150-3 (1992-02) Structural Vibration, Part 3: Effects of vibration on structures (German Institute for Standardisation, 1999).

HERITAGE

Unexpected Finds Protocol

- B27. Prior to commencement of construction, the Applicant must prepare an Unexpected Finds Protocol for the development in consultation with the Registered Aboriginal Parties and must implement the Protocol in accordance with its terms.

Discovery of Human Remains or Aboriginal Objects or Places

- B28. If human remains are discovered on site, then all work surrounding the area must cease, and the area must be secured. The Applicant must immediately notify NSW Police and [Heritage NSW](#), and work must not recommence in the area until authorised by NSW Police and [Heritage NSW](#).
- B29. If any Aboriginal object or Aboriginal place is identified on site, or suspected to be on site:
- all work in the immediate vicinity of the object or place must cease immediately;
 - a 10 m buffer area around the object or place must be cordoned off; and
 - [Heritage NSW](#) must be contacted immediately.
- B30. Work in the immediate vicinity may only recommence if:
- the object or place is confirmed by [Heritage NSW](#) upon consultation with the Registered Aboriginal Parties not to be an Aboriginal object or Aboriginal Place; or
 - the Aboriginal Cultural Heritage Management Plan is revised to include the object or place and appropriated measures in respect of it, and approved by the [Planning Secretary](#); or
 - the [Planning Secretary](#) is satisfied as to the measures to be implemented in respect of the object or place and makes a written direction in that regard.

BIODIVERSITY

- B31. No more than 1.105 hectare (ha) of native vegetation as described in the *Biodiversity Assessment Report, Framework for Biodiversity Assessment* prepared by Ecoplanning Pty Ltd dated 24 November 2016 shall be removed from the site, including 0.76 ha of Cumberland Plain Woodland.
- B32. The Applicant must ensure vegetation to be retained is protected during construction works.
- B33. Prior to the commencement of construction, the Applicant must purchase and retire 40 ecosystem credits to offset the removal of native vegetation on site. The ecosystem credits shall be determined in accordance with the [EES Group's Frameworks for Biodiversity Assessment \(FBA\)](#) and the *Biobanking Assessment Methodology 2014 (BBAM)*.

CONSOLIDATED CONSENT

Note: If the Applicant seeks a variation to the offset rules, the Applicant must demonstrate that reasonable steps have been taken to find like-for-like offsets in accordance with Section 10.5.4.2 of the FBA and Appendix A of the OEH's NSW Biodiversity Offsets Policy for Major Projects 2014.

AIR QUALITY

Dust Minimisation

- B34. During construction, the Applicant must ensure that:
- (a) exposed surfaces and stockpiles are suppressed by regular watering;
 - (b) all trucks entering or leaving the site with loads have their loads covered;
 - (c) trucks associated with construction works do not track dirt onto the public road network;
 - (d) public roads used by these trucks are kept clean; and
 - (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

HAZARDS AND RISK

Bunding

- B35. The Applicant shall store all chemicals, fuels and oils used on site in appropriately banded areas in accordance with the requirements of all relevant Australian Standards, and/or the EPA's *Storing and Handling of Liquids: Environmental Protection – Participants Handbook* (as may be updated or replaced from time to time).

CONTAMINATION AND REMEDIATION

- B36. Prior to the commencement of any construction or remediation works on site, the Applicant must engage a Site Auditor accredited under the EPA *Contaminated Land Management Act 1997* NSW Site Auditor Scheme.
- B37. Prior to the commencement of construction, the Applicant must remediate the areas of environmental concern within the site identified in, and in accordance with the RAP. All remediation works at the site must be carried out by suitably qualified and experienced consultant(s) that have been engaged by the Applicant.
- B38. The Applicant shall ensure that any asbestos encountered during the remediation and construction works is monitored, handled, transported and disposed of by appropriately qualified and licensed contractors in accordance with the requirements of WorkCover and relevant guidelines, including:
- (a) *Work Health and Safety Regulation 2011*;
 - (b) *Model Code of Practice – How to Manage and Control Asbestos in the Workplace, 2011 Safe Work Australia*;
 - (c) *Model Code of Practice – How to Safely Remove Asbestos, 2011 Safe Work Australia*; and
 - (d) *Protection of the Environment Operations (Waste) Regulation 2005*.
- B39. During the remediation and construction works, the Applicant must ensure that no contaminated groundwater encountered on the site can discharge into waters including the Upper Canal or any other off-site location or waterway that could cause pollution of waters.
- B40. The Applicant must implement the unexpected finds protocol as described in the RAP prepared by Douglas Partners Pty Ltd dated 10 May 2017 for the duration of earthworks and construction.
- B41. Within 30 days of completion of remediation works, notice of the works completed must be given to Council in accordance with clause 17(2) of the *State Environmental Planning Policy No. 55 – Remediation of Land*. Clause 18 of *State Environmental Planning Policy No. 55 – Remediation of Land* details what must be provided in the notice.
- B42. Upon completion of the remediation works, the Applicant must submit to the [Planning Secretary](#) and Council, a Site Audit Report and a Site Audit Statement Section A for the relevant part of the site, prepared in accordance with the NSW *Contaminated Land Management – Guidelines for the NSW Site Auditor Scheme*, which demonstrates that the site is suitable for its intended industrial land use.

WASTE

- B43. The Applicant must assess and classify all liquid and non-liquid wastes to be taken off-site in accordance with the EPA's *Waste Classification Guidelines Part 1: Classifying Waste, November 2014*, or its latest version and dispose of all wastes to a facility that may lawfully accept the waste.
- B44. Waste generated outside the site must not be received at the site for storage, treatment, processing, reprocessing, or disposal.
- B45. The Applicant must retain all sampling and waste classification data for the life of the development in accordance with the requirements of the EPA.
- B46. The collection of waste generated during construction of the development shall be undertaken between 7 am to 10 pm Monday to Friday.

VISUAL AMENITY

Landscaping

- B47. The Applicant must maintain the landscaping and vegetation on the site for the life of the development.

TRANSMISSION LINE EASEMENT

- B48. Any construction works located within 15 metres of a transmission tower or in close proximity to Endeavour Energy's electrical network must:
- be constructed of non-conducting materials;
 - must maintain the integrity of all line structures and stay pole/wires at all times; and
 - comply with *AS/NZS 3000:2007 'Electrical installations'* to ensure that there is adequate connection to the earth.
- B49. Final design drawings must be submitted to Endeavour Energy prior to the commencement of works to confirm no impact on Endeavour Energy's transmission towers.

Access

- B50. The Applicant must ensure that access to the transmission towers, lines and easement is maintained at all times.

Construction

- B51. All works are to be carried out in accordance with the NSW WorkCover *Work near Overhead Powerlines Code of Practice 2006*.

B51A. Prior to the commencement of construction on Lot 1, the Applicant is to provide WaterNSW with detailed design plans for the batter and retaining walls, certified by an appropriately qualified engineer.

FENCING

Boundary Fencing

- B52. Boundary fencing to the same or better standard as fencing already in place to the north of the site is to be installed along the development site and the Upper Canal.
- B53. Any existing rural fencing must be removed and disposed of at an appropriate waste facility licenced to accept the waste.

Construction Fencing and Signage

- B54. Any hoarding erected during construction works shall comply with the following:
- No third-party advertising is permitted to be displayed on the subject hoarding/fencing;

CONSOLIDATED CONSENT

- (b) The construction site manager shall be responsible for the removal of graffiti from any construction hoarding/fencing or the like within the construction area within 48 hours of its application.
- B55. Prior to the commencement of works, a sign must be erected in a prominent position on-site for the duration of construction works. The sign shall:
- (a) state that unauthorised entry to the work site is prohibited;
 - (b) show the name of the person in charge of the work site and a telephone number at which that person may be contacted outside working hours; and
 - (c) show the name, address and a telephone number of the Certifying Authority for the development

FOR INFORMATION

PART C ENVIRONMENTAL MANAGEMENT

ENVIRONMENTAL MANAGEMENT

Construction Environmental Management Plan

- C1. The Applicant must prepare a **Construction Environmental Management Plan** (CEMP) to the satisfaction of the [Planning Secretary](#). The CEMP must:
- be approved by the [Planning Secretary](#) prior to the commencement of construction;
 - identify the statutory approvals that apply to the development;
 - be prepared by a suitably qualified and experienced person;
 - outline all environmental management practices and procedures to be followed during earthworks and construction;
 - describe all activities to be undertaken on the site during earthworks and construction, including a clear indication of construction stages;
 - describe the specific measures to be implemented to protect the Upper Canal during earthworks and construction;
 - detail how the environmental performance of the construction works will be monitored, and what actions will be taken to address identified adverse environmental impacts;
 - describe of the roles and responsibilities of all relevant employees involved in earthworks and construction; ~~and~~
 - include the management plans required under condition C2, Schedule 3 of this consent; ~~and~~
- C1A. Prior to the commencement of works subject to SSD-7664-Mod-1, update the CEMP required under Condition C1 to the satisfaction of the [Planning Secretary](#) to develop a consultation strategy to establish management and mitigation strategies to minimise interruption to the operations of 105, 109, 115-119 and 121-123 Cowpasture Road, and any other property whose access and operations are impacted by construction works. The strategies must be developed in consultation with the affected owners / occupiers.
- C2. As part of the CEMP required under condition C1, Schedule 3 of this consent, the Applicant must include the following:
- Construction Traffic Management Plan (see condition C4, Schedule 3);
 - Construction Noise Management Plan (see condition C5, Schedule 3); and
 - Erosion and Sediment Control Plan (see condition C6, Schedule 3).
- C3. The approved Construction Environmental Management Plan (as revised and approved by the [Planning Secretary](#) from time to time) must be implemented by the Applicant for the duration of earthworks and construction.

Environmental Management Plans

- C4. The Applicant must prepare a **Construction Traffic Management Plan** as part of the CEMP for the development. The plan must:
- be prepared in consultation with Council, RMS and the local bus service provider;
 - specify any potential impacts to traffic, pedestrians, cyclists and bus services within the vicinity of the development from construction vehicles;
 - identify potential impacts to pedestrian access or public transportation infrastructure;
 - demonstrate that sufficient parking facilities will be provided on-site, including for heavy vehicles and for site personnel to ensure that construction traffic associated with the development will not park on surrounding roads; and
 - assess the cumulative construction impacts of the adjacent developments.

CONSOLIDATED CONSENT

- C4A. Prior to the commencement of works subject to SSD-7664-Mod-1, update the Construction Traffic Management Plan required under Condition C4 to the satisfaction of the Planning Secretary to assess the cumulative construction impacts on the adjacent developments in consultation with the owners/operators of all properties whose property accesses are directly impacted by construction works associated with the Development and to develop (in consultation) a range of management and mitigation strategies to minimise interruption to the operation of these properties during road construction works.
- C5. The Applicant must prepare a **Construction Noise Management Plan** as part of the CEMP for the development. The plan must:
- be prepared by a suitably qualified and experienced noise expert;
 - describe procedures for achieving the noise management levels in the EPA's *Interim Construction Noise Guideline 2009*;
 - describe the measures to be implemented to manage high noise generating works such as piling and excavation in close proximity to sensitive receivers;
 - include strategies that have been developed with the community for managing high noise generating works;
 - describe the community consultation undertaken to develop the strategies in d) above;
 - include a complaints management system.
- C5A. Prior to the commencement of works subject to SSD-7664-Mod-1, update the Construction Noise Management Plan required under Condition C5, to the satisfaction of the Planning Secretary. The update is to include details of a vibration monitoring program prepared in consultation with WaterNSW to demonstrate the limits outlined in Condition B26A are being met. As a minimum, monitoring must occur at a location between the property boundary between proposed Lot 1 and the Upper Canal interface. Monitoring is to remain in place for the duration of construction activities within proposed Lot 1, or as agreed to by WaterNSW.
- C6. The Applicant must prepare an **Erosion and Sediment Control Plan** as part of the CEMP for the development. The plan must:
- be prepared by a suitably qualified engineer prior to the commencement of the relevant works in consultation with Council;
 - be prepared generally in accordance with the latest version of *Managing Urban Stormwater: Soils and Construction Vol. 1* (Landcom, 2004);
 - incorporate design plans and accompanying design notes; and
 - describe measures that would be implemented to maintain stormwater quantity and quality from the site during construction and detail the procedures to be undertaken if any non-compliance is detected.

Management Plan Requirements

- C7. The Applicant must ensure any environmental management plans/strategies required under this consent are prepared in accordance with any relevant guidelines and include:
- detailed baseline data;
 - a description of:
 - the relevant statutory requirements (including any relevant approval, licence or lease conditions);
 - any relevant limits or performance measures/criteria;
 - the specific performance indicators that are proposed to be used to judge the performance of, or guide the implementation of, the development or any management measures;
 - the measures that would be implemented to comply with the relevant statutory requirements, limits or performance measures/criteria;
 - a program to monitor and report on the:
 - impacts and environmental performance of the development;

CONSOLIDATED CONSENT

- (ii) effectiveness or any management measures;
 - (iii) a contingency plan to manage any unpredicted impacts and their consequences
 - (iv) a program to investigate and implement ways to improve the environmental performance of the development over time;
- (d) a protocol for managing and reporting any:
- (i) incidents;
 - (ii) complaints;
 - (iii) non-compliances with statutory requirements;
 - (iv) exceedances of the impact assessment criteria and/or performance criteria; and
 - (v) a protocol for periodic review of the plan.

Revision of Strategies, Plans and Programs

- C8. Within three months of:
- (a) approval of a modification; or
 - (b) submission of an incident report under condition C9 below;

the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent to the satisfaction of the [Planning Secretary](#).

Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development.


REPORTING

Incident Reporting

- C9. Upon detecting an exceedance of the limits/performance criteria in this consent or the occurrence of an incident that causes (or may cause) material harm to the environment, including the Upper Canal, the Applicant must immediately (or as soon as practical thereafter) notify the [Planning Secretary](#) and other relevant agencies of the exceedance/incident. Within seven days of the date of the incident, the Applicant must provide the [Planning Secretary](#) and any relevant agencies with a detailed report on the incident, and such further reports as may be requested.

CONSOLIDATED CONSENT

**APPENDIX A
DEVELOPMENT LAYOUT PLANS**



HORSLEY DRIVE BUSINESS PARK

Area Schedule

Warehouse 1 Site Area	87,916 sqm
Warehouse Area (GFA)	43,291 sqm
Total Office Area (GFA)	2,015 sqm
Total Carparking	539
Warehouse 2 Site Area	29,538 sqm
Warehouse Area (GFA)	14,803 sqm
Total Office Area (GFA)	416 sqm
Total Carparking	72
Warehouse 3 Site Area	25,151 sqm
Warehouse Area (GFA)	9,804 sqm
Total Office Area (GFA)	549 sqm
Total Carparking	48

WATCH THIS SPACE DESIGN PTY LTD
 SUITE 9, LEVEL 3, 35 BUCKINGHAM STREET,
 SUDBURY HILLS, NSW 2000
 Email: info@watchthisspacedesign.com
 www.watchthisspace.com.au
 Copyright of this design remains the property of WTSO March 2022

Charter Hall
 CHARTER HALL
 COWPASTURE ROAD,
 WETHERILL PARK
 NSW

Client
 HORSLEY DRIVE BUSINESS PARK
 Project number
 CH HDBP

Drawing title
 OVERALL SITE PLAN
 Drawing number
 DA 02 - Revision P6
 Scale
 1:2000@A3
 Date
 10/05/22
 Drawn by
 EC

Figure 1: Overall Site Plan, Drawing No. DA 02 – Revision P6, prepared by Watch this Space Design Pty Ltd and dated 10 May 2022




Figure 2a. Plan of Subdivision, Drawing No. 10990-002 Rev D - Sheet 1, prepared by Shawn Leclerc and dated 26 April 2022

CONSOLIDATED CONSENT




Figure 2b. Plan of Subdivision, Drawing No. 10990-002 Rev D - Sheet 2, prepared by Shawn Leclerc and dated 26 April 2022