

Memorandum

To	Brookfield Multiplex	Scott Grant	via Aconex
From	Scott Easton	Date	2 December 2016
Subject	UNSW Biological Sciences Stage 2 Preliminary Review of Contamination	Project No.	73492.09

This memorandum provides a preliminary review of potential contamination issues associated with the Biological Sciences Stage 2 Project.

Douglas Partners Pty Ltd (DP) previously carried out a preliminary site investigation for contamination for the Biological Sciences Stage 1 Project (Project 73492.09, dated 6 February 2015). DP subsequently carried out additional waste classification testing prior to, and during construction of the Stage 1 project.

DP has recently carried out a footing investigation within the existing D26 building on the Stage 2 site which included drilling of four boreholes through existing footings then into rock. The boreholes encountered sand and crushed sandstone filling overlying sandstone. Some soil samples were tested for waste classification purposes and indicated the filling was classifiable as General Solid Waste (non-putrescible).

Based on correspondence from Multiplex Constructions (aconex dated 30 November 2016) it is understood that the proposed Stage 2 SSD works include internal works associated with refurbishment to the lower ground floor level and to levels 2-6 of the existing D26 building, together with localised excavation for extension of the western lift. The existing lower ground level is RL53.47 m relative to Australia Height Datum (AHD) and will remain unchanged. The lower ground floor level for Stage 2 is the same as recently constructed for the Stage 1 project.

DP has not carried out a contamination assessment for the Stage 2 works. However, given that the Stage 2 works essentially include internal refurbishment, with only limited excavation for extension of a lift, and that there is no change to the current land use, it is considered that the proposed Stage 2 works will not result in an increased risk in relation to environmental issues.

Further sampling and testing will be required prior to construction to confirm the contamination status and waste classification of any soils within the proposed lift pit excavation.

We trust the above satisfies your present requirements. Please contact the undersigned should you have any queries.

Yours faithfully,
Douglas Partners Pty Ltd



Scott Easton
Principal

Attached: About this Report

Reviewed by



Paul Gorman
Senior Associate

About this Report

Douglas Partners



Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

About this Report

Site Anomalies

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

Information for Contractual Purposes

Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

Site Inspection

The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.