

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
<b>Administrative Conditions</b>						
A1	Except as amended by the conditions of this consent, development consent is granted only to carrying out the development as described in Condition A2 of this consent.	✓	✓	✓	✓	✓
A2	The Applicant must carry out the development in accordance with the conditions of this consent and generally in accordance with the: a) State Significant Development Application SSD 7968; b) EIS, except where amended by the RtS and RtS Addendum; c) following drawings, except for: i) any modifications which are Exempt or Complying Development; and ii) as otherwise provided by the conditions of this consent	✓	✓	✓	✓	✓
A3	The Secretary may make written direction to the Applicant: a) arising from the Department's assessment of any strategies, plans, programs, reviews, audits, notification, reports or correspondence that are submitted in accordance with this consent (including any stages of these documents); b) arising from the Department's assessment of any reviews, reports or audits undertaken or commissioned by the Department regarding compliance with this consent or in relation to an incident (whether notified to the Department or not); and c) in relation to the implementation of any actions or measures contained in any of the documents listed in (a) or (b) of this condition.	✓	✓	✓	✓	✓
A4	If there is any inconsistency between the plans and documentation referred to above the most recent document must prevail to the extent of the inconsistency. However, conditions of this consent prevail to the extent of any inconsistency. Where there is an inconsistency between approved elevations and plans, the elevations prevail.	✓	✓	✓	✓	✓
A5	It is the responsibility of the Applicant to meet all expenses incurred in undertaking the development, including expenses incurred in complying with conditions imposed under this consent.	✓	✓	✓	✓	✓
A6	This consent will lapse five years from the date of consent unless the works associated with the development have physically commenced.	✓	✓	✓	✓	✓
A7	The Applicant must comply with all relevant prescribed conditions of development consent under Part 6, Division 8A of the EP&A Regulation	✓	✓	✓	✓	✓
A8	In the event of a dispute between the Applicant and a public authority, in relation to an applicable requirement in this consent or relevant matter relating to the Development, either party may refer the matter to the Secretary for resolution. The Secretary's resolution of the matter must be binding on the parties.	✓	✓	✓	✓	✓
A9	The Applicant must notify the Department, Certifying Authority and Council in writing of the date of commencement of each of the following phases of the development, at least 48 hours prior to that date: a) construction; and b) operation.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
A10	Where consultation with any stakeholder identified in the conditions of this consent is required by any conditions of this consent, the Applicant must: a) consult with the relevant stakeholder prior to submitting the required document for approval; b) submit evidence of such consultation as part of the relevant document; c) describe how matters raised by the stakeholder have been addressed and identify any matters that have not been resolved; and d) include details of any outstanding issues raised by the stakeholder and an explanation of disagreement between any stakeholder and the Applicant	✓	✓	✓	✓	✓
A11	For work costing \$25,000 or more, a Long Service Levy must be paid. For further information please contact the Long Service Payments Corporation Helpline on 131 441	✓	-	-	-	-
A12	Any advice or notice to the consent authority must be served on the Secretary.	✓	✓	✓	✓	✓
A13	The Applicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this consent relevant to their respective activities	✓	✓	✓	✓	✓
A14	Within two months of: a) the submission of an annual review/compliance report required by conditions of this consent; b) the submission of an incident report required by conditions of this consent; c) the submission of an audit under required by conditions of this consent; and d) the approval of any modification to the conditions of this consent/approval; or e) a direction of the Secretary under Condition A3 of this consent,  <i>the Applicant must review and if necessary revise, the strategies, plans and programs required under this consent/approval to the satisfaction of the Secretary. Where this review leads to revisions in any such document, then within six weeks of the review the revised document must be submitted to the Secretary for approval, unless otherwise agreed with the Secretary</i>	✓	✓	✓	✓	✓
A15	The Department must be notified in writing to <a href="mailto:compliance@planning.nsw.gov.au">compliance@planning.nsw.gov.au</a> immediately after the Applicant becomes aware of an incident.	✓	✓	✓	✓	✓
A16	a) A written incident notification must also be emailed to the Department at the following address: <a href="mailto:compliance@planning.nsw.gov.au">compliance@planning.nsw.gov.au</a> within 24 hours after the Applicant becomes aware of an incident. Notification is required to be given under this condition even if the Applicant forms the view that an incident has not occurred. b) Written notification of an incident must: i) identify the development/project and application number; ii) provide details of the incident (date, time, location, a brief description of what occurred and why it is classified as an incident); iii) identify how the incident was detected; iv) identify when the applicant/proponent became aware of the incident; v) identify any actual or potential non-compliance with conditions of consent/approval; vi) describe what immediate steps were taken in relation to the incident;	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	vii) identify further action(s) that will be taken in relation to the incident; and viii) identify a project contact for further communication regarding the incident.					
A17	a) Within seven days of the date on which the incident occurred or as otherwise agreed to by the Secretary, the Applicant must provide the Secretary and any relevant public authorities (as determined by the Secretary) with a detailed report on the incident addressing all requirements for such reporting set out in Condition A17.b) of this consent, and such further reports as may be requested. b) The Incident Report must include: i) a summary of the incident; ii) outcomes of an incident investigation, including identification of the cause/s of the incident; iii) details of the corrective and preventative actions that have been, or will be, implemented to address the incident and prevent recurrence; and iv) details of any communication with other stakeholders regarding the incident.	✓	✓	✓	✓	✓
A18	Any written requirements of the Secretary or relevant public authority (as determined by the Secretary) which may be given at any point in time, to address the cause or impact of an incident must be complied with and within any timeframe specified by the Secretary or relevant public authority.	✓	✓	✓	✓	✓
A19	If statutory notification is provided to the EPA as required under the POEO Act in relation to the project, such notification must also be provided to the Secretary within 24 hours after the notification was provided to the EP	✓	✓	✓	✓	✓
A20	Incidents are to be notified as part of monitoring the carrying out of the Development to provide data on compliance with this consent or the environmental impact of the Development. Accordingly, Division 2B of Part 6 of the EP&A Act applies.	✓	✓	✓	✓	✓
A21	The project may be constructed and operated in stages. Where staged construction or operation is proposed, a Staging Report (for either or both construction and operation as the case may be) must be prepared and submitted for the approval of the Planning Secretary. The Staging Report must be submitted to the Planning Secretary no later than one month before the commencement of construction of the first of the proposed stages of construction (or if only staged operation is proposed, one month before the commencement of operation of the first of the proposed stages of operation) unless otherwise agreed to by the Planning Secretary.	✓	✓	✓	✓	✓
A22	The Staging Report must: 1. if staged construction is proposed, set out how the construction of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when construction of each stage will commence and finish; 2. if staged operation is proposed, set out how the operation of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when operation of each stage will commence and finish (if relevant); 3. specify how compliance with conditions will be achieved across and between each of the stages of the project; and	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	4. set out mechanisms for managing any cumulative impacts arising from the proposed staging.					
A23	The project must be staged in accordance with the Staging Report, as submitted to the Planning Secretary.	✓	✓	✓	✓	✓
A24	Where staging is proposed, the terms of this approval that apply or are relevant to the works or activities to be carried out in a specific stage must be complied with at the relevant time for that stage. Staging, Combining and Updating Strategies, Plans or Programs A15. With the approval of the Planning Secretary, the Applicant may: (a) prepare and submit any strategy, plan or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan or program); (b) combine any strategy, plan or program required by this consent (if a clear relationship is demonstrated between the strategies, plans or programs that are proposed to be combined); and (c) update any strategy, plan or program required by this consent (to ensure the strategies, plans and programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).	✓	✓	✓	✓	✓
A25	If the Planning Secretary agrees, a strategy, plan or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.	✓	✓	✓	✓	✓
A26	If approved by the Planning Secretary, updated strategies, plans or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan or program.	✓	✓	✓	✓	✓
<b>Prior to Commencement of Works</b>						
B1	Plans certified in accordance with section 109R of the EP&A Act must be submitted to the Certifying Authority and the Department prior to commencement of each stage of the construction works and must include details as required by any of the following conditions of this consent.	✓	✓	✓	✓	✓
B2	Prior to commencement of works, the Applicant must submit details of the chosen ESD measures incorporated into the final design, as identified in the <i>ESD Report</i> prepared by JHA Services dated 22 December 2016 <b>28 May 2019</b> . Details must be submitted to the satisfaction of the Certifying Authority.	✓	-	-	-	-
B3	The building materials used on the facades of the buildings must have a maximum normal specular reflectivity of visible light of 20 per cent and must be designed so as not to result in glare that causes any discomfort or threatens the safety of pedestrians or drivers. A statement demonstrating compliance with these requirements or where compliance cannot be met a report that demonstrates that the exceedance would not result in glare that causes any discomfort or threatens the safety of pedestrians or drivers	CC	CC	-	-	CC

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	must be submitted to the satisfaction of the Certifying Authority prior to the certification of above ground Crown building works.					
B4	All outdoor lighting within the Subject Site must comply with AS 1158.3.1:2005 <i>Lighting for roads and public spaces – Pedestrian area (Category P) lighting – Performance and design requirements</i> and AS 4282-1997 <i>Control of the obtrusive effects of outdoor lighting</i> . Details demonstrating compliance with these requirements must be submitted to the satisfaction of the Certifying Authority prior to the certification of Crown building works.	CC	CC	CC	CC	CC
B5	Plans demonstrating compliance with the following requirements for secure bicycle parking and end-of-trip facilities, identified in the <i>Traffic Report</i> , prepared by Woolacotts Consulting Engineers dated 5 September 2017, must be submitted to the satisfaction of the Certifying Authority: a) the provision of a minimum 100 bicycle parking spaces, including an appropriate number designated for staff-only usage; b) the layout, design and security of bicycle facilities must comply with the minimum requirements of AS 2890.3:2015 <i>Parking facilities - Bicycle parking</i> , and be located in easy to access, well-lit areas that incorporate passive surveillance; and c) the provision of end-of-trip facilities for staff in accordance with the Green Star Design & As Built rating tool.	-	CC	-	-	CC
B6	The works that are the subject of this application must be designed and constructed to provide access and facilities for people with a disability in accordance with the BCA. Prior to the commencement of any work, the Certifying Authority must ensure that evidence of compliance with this condition from an appropriately qualified person is provided and that the requirements are referenced on any certified plans	CC	CC	CC	CC	CC
B7	Soil erosion and sediment control measures must be designed in accordance with <i>Managing Urban Stormwater – Soils &amp; Construction Volume 1</i> (2004) by Landcom. Details must be submitted to the satisfaction of the Certifying Authority prior to the commencement of any works.	CC	CC	CC	CC	CC
B8	Prior to the commencement of any work, the Applicant is to engage a suitably qualified person to prepare a <b>Pre-Construction Dilapidation Report</b> detailing the current structural condition of all retained existing and adjoining buildings within the site, infrastructure and roads within the 'zone of influence'. Any entry into private land is subject to the consent of the owner(s) and any inspection of buildings on privately affected land must include details of the whole building where only part of the building falls within the 'zone of influence'. The report must be submitted to the satisfaction of the Certifying Authority prior to the commencement of any works. A copy of the report is to be forwarded to Council. In the event that access for undertaking a Pre-Construction Dilapidation Report is denied by an adjoining owner, the Applicant must demonstrate, in writing, to the satisfaction of the Secretary that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the report and that these steps have failed.	CC	-	-	-	-

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
B9	Plans demonstrating compliance with the following traffic and parking requirements must be submitted to the satisfaction of the Certifying Authority prior to the commencement of works: a) provision of a minimum 80 on-site Oran Park High School car parking spaces (including a minimum of four accessible car parking spaces) and a minimum of 69 on-site Oran Park Public School car parking spaces (including the existing 49 on-site spaces); b) all vehicles should enter and leave the Subject Site in a forward direction. If site constraints do not permit heavy rigid vehicles to enter and leave in a forward direction, then all reversing movements should be undertaken under the control of certified traffic controllers to ensure public safety when vehicles are reversing; c) all construction vehicles must be contained wholly within the site and vehicles must enter the site before stopping, unless otherwise approved prior in writing by Council; d) appropriate pedestrian advisory signs must be provided at the egress from the car park; e) all works/ regulatory signposting associated with the proposed development must be at no cost to the relevant roads authority; and f) the swept path of the longest vehicle entering and exiting the Subject Site in association with the new work, as well as manoeuvrability through the Subject Site, must be in accordance with AUSTROADS. In this regard, a plan must be submitted to Council for approval, which shows that the proposed development complies with this requirement.	CC (Involving 69 parking spaces for Public School)	CC (Involving 80 parking spaces for High School)	-	-	-
B10	Plans indicating line marking and signage, of public roads and footways must be submitted to the relevant roads authority for approval where required.	-	CC	-	-	CC
B11	A <b>Road Safety Audit</b> (RSA), prepared by suitably qualified consultant, must be undertaken of the pick-up/drop-off area, bus bay along Holden Drive and the service area, in consultation with Transport for New South Wales, and any recommendations of the <b>RSA</b> must be implemented into the final bus layby design. The Applicant must submit the <b>RSA</b> to the satisfaction of the Secretary prior to works commencing.	CC	-	-	-	-
B12	Prior to the commencement of building works, the Applicant must submit to the satisfaction of the Certifying Authority structural drawings prepared and signed by a suitably qualified practising Structural Engineer that demonstrates compliance with: a) the relevant clauses of the BCA; and b) the development consent.	CC	CC	-	-	CC
B13	<b>a)</b> All mechanical ventilation systems must be installed in accordance with Part F4.5 of the BCA and must comply with the AS 1668.2-2012 <i>The use of air conditioning in buildings – Mechanical ventilation in buildings</i> and AS/NZS 3666.1:2011 <i>Air handling and water systems of buildings–Microbial control</i> to ensure adequate levels of health and amenity to the occupants of the building and to ensure environment protection. <b>b) The mechanical ventilation plant and conduits must be colour matched to the roof or where it is located on other areas of the building it must be matched to that part.</b> Details must be submitted to the satisfaction of the Certifying Authority prior to the commencement of building works.	CC	CC	-	-	CC

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
B14	Final drainage design plans of the stormwater drainage management system must be prepared by a suitably qualified engineer generally in accordance with the stormwater drainage drawings prepared by Woolacotts Consulting Engineers (as listed under Condition A2 of this consent) and Council's relevant engineering guidelines. The drainage design plans must be submitted to the Certifying Authority prior to the commencement of works.	CC	CC	CC	CC	CC
B15	The building plans and specifications accompanying the relevant plans submitted to the Certifying Authority prior to the commencement of relevant works associated with this consent must demonstrate that an appropriate area will be provided within the premises for the storage of garbage bins and recycling containers and all waste and recyclable material generated by the School. Requirements of these storage areas must be designed in consultation with Council and must: a) ensure all storage areas are covered and bunged; b) ensure all internal walls of the storage area are rendered to a smooth surface, coved at the floor/wall intersection, graded, appropriately drained with a tap in close proximity to facilitate cleaning and drained to sewer via an approved treatment device; c) include provision for the separation and storage, in appropriate categories, of material suitable for recycling; and d) include provision for separate storage and collection of organic/food waste.	-	CC	-	-	-
B16	All roads and traffic facilities must be designed to meet the requirements of Council or RMS (whichever is applicable). The necessary permits and approvals from the relevant road authority must be obtained prior to the commencement of road or pavement construction works.	-	CC	-	-	-
B17	a) Prior to the commencement of works on the Subject Site, a <b>Construction Environmental Management Plan</b> (CEMP) must be prepared for the development and must address, but not be limited to, the following matters where relevant: i) hours of work; ii) 24 hour contact details of site manager; iii) traffic management, prepared in consultation with Council; iv) construction noise and vibration management, prepared by a suitable qualified person; v) management of dust and odour to protect the amenity of the neighbourhood; vi) erosion and sediment control; vii) stormwater control and discharge; viii) measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the Subject Site; ix) groundwater management plan including measures to prevent groundwater contamination; x) external lighting in compliance with AS 4282-1997 <i>Control of the obtrusive effects of outdoor lighting</i> ; xi) an unexpected finds protocol; xii) waste classification (for materials to be removed) and validation (for materials to remain) be undertaken to confirm the contamination status in these areas of the site; and xiii) waste storage, recycling and litter control.	CC	-	-	-	-

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance



## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	b) The <b>CEMP</b> must not include works that have not been explicitly approved in the development consent. In the event of any inconsistency between the consent and the <b>CEMP</b> , the consent must prevail; and c) The Applicant must submit a copy of the CEMP to the Department and Council, prior to commencement of work.					
B18	The <b>CEMP</b> (as revised from time to time) must be implemented by the Applicant for the duration of the construction works.	✓	✓	✓	✓	✓
B19	a) Prior to the commencement of works on the Subject Site, a <b>Construction Noise and Vibration Management Plan</b> (CNVMP) must be prepared for the development and must address, but not be limited to, the following matters where relevant:  i) be prepared by a suitably qualified expert; ii) be prepared in consultation with Council and all noise sensitive receivers where noise levels exceed the construction noise management level, in accordance with EPA guidelines; iii) describe the measures that would be implemented to ensure: i. best management practice is being employed; ii. compliance with the relevant conditions of this consent;  iv) describe the proposed noise and vibration management measures in detail; v) include strategies that have been developed to address impacts to noise sensitive receivers where noise levels exceed the construction noise management level, for managing high noise generating works; vi) describe the consultation undertaken to develop the strategies in v) above; vii) evaluates and reports on the effectiveness of the noise and vibration management measures; and viii) include a complaints management system that would be implemented for the duration of the project.	CC	-	-	-	-
B20	The Applicant must submit a copy of the <b>CNVMP</b> to the Department and Council, prior to commencement of work.	CC	-	-	-	-
B21	The <b>CNVMP</b> (as revised from time to time) must be implemented by the Applicant for the duration of the construction works.	✓	✓	✓	✓	✓
B22	a) Prior to the commencement of works on the Subject Site, a <b>Construction Traffic and Pedestrian Management Plan</b> (CTPMP) must be prepared for the development by a suitably qualified expert and in consultation with Council. The <b>CTPMP</b> must specify, but not be limited to, the following: i) identification of construction traffic routes for all required vehicles during construction, inclusive of any crane delivery, including any known road closures and consideration of alternate routes and construction traffic volumes (including heavy vehicle/spoil haulage) on these routes; ii) details of construction vehicle movements including parking, dedicated vehicle turning areas, and ingress and egress points;	CC	-	-	-	-

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance



## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	<p>iii) discussion of construction impacts that could result in disruption of traffic, public transport, pedestrian and cycle access, access to public land, property access, including details of oversize load movements, and the nature and duration of those impacts;</p> <p>iv) discussion of potential cumulative construction impacts on the surrounding road network as a result of the simultaneous construction of adjoining developments</p> <p>v) details of management measures to minimise traffic impacts, including temporary road work traffic control measures and measures to minimise peak period congestion;</p> <p>vi) details of measures to maintain or provide alternative safe and accessible routes for pedestrians throughout the duration of construction;</p> <p>vii) details of measures to maintain connectivity for cyclists, with particular emphasis on providing adequate access between key existing cycle routes for commuter cyclists;</p> <p>viii) details of methods to be used to communicate proposed future traffic changes to affected road users, pedestrians and cyclists;</p> <p>ix) an adaptive response plan which sets out a process for response to any traffic, construction or other incident; and</p> <p>x) mechanisms for the monitoring, review and amendment of the <b>CTPMP</b>.</p> <p>b) The Applicant must submit a copy of the CTPMP to the Department and Council, prior to commencement of work.</p>					
B23	The <b>CTPMP</b> (as revised from time to time) must be implemented by the Applicant for the duration of the construction works.	✓	✓	✓	✓	✓
B24	<p>a) Prior to the commencement of works on the Subject Site, a <b>Construction Waste Management Plan</b> (CWMP) must be prepared for the development by a suitably qualified person and in consultation with the Council. The <b>CWMP</b> must address, but not be limited to, the following matters: i) removal of hazardous materials and disposal at an approved waste disposal facility in accordance with the requirements of the relevant legislation, codes, standards and guidelines, prior to the commencement of any building works;</p> <p>ii) details of methods to be used to prevent spill, escape of any dust, waste or spoil from the vehicles or trailers used to transport waste or excavation spoil from the site.</p> <p>b) details demonstrating compliance with the relevant legislative requirements, associated with the removal of hazardous waste, particularly the method of containment and control of emission of fibres to the air, must be submitted to the satisfaction of the Certifying Authority prior to the removal of any hazardous materials.</p> <p>c) the Applicant must notify the RMS Traffic Management Centre of the truck route(s) to be followed by trucks transporting waste material from the Subject Site, prior to the commencement of the removal of any waste material from the Subject Site; and</p> <p>d) the Applicant must submit a copy of the <b>CWMP</b> to the Department and Council, prior to commencement of work.</p>	CC	CC	CC	CC	CC
B25	The <b>CWMP</b> (as revised from time to time) must be implemented by the Applicant for the duration of the construction work.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
B26	Prior to the commencement of work the Applicant is to negotiate with the utility authorities (e.g. Ausgrid and telecommunication carriers) in connection with the relocation and/or adjustment of the services affected by the construction of the building structure.	CC	-	-	-	-
B27	Prior to the commencement of above ground works written advice must be obtained from the electricity supply authority, an approved telecommunications carrier and an approved gas carrier (where relevant) stating that satisfactory arrangements have been made to ensure provisions of adequate services.	CC	-	-	-	-
B28	Prior to the commencement of works, or as otherwise agreed by the Secretary, the following must be made available for community enquiries and complaints for the duration of construction: a) a toll-free 24 hour telephone number(s) on which complaints and enquiries about the application may be registered; b) a postal address to which written complaints and enquires may be sent; and c) an email address to which electronic complaints and enquiries may be transmitted.	CC	✓	✓	✓	✓
B29	A <b>Complaints Management System</b> must be prepared before the commencement of any works and be implemented and maintained for the duration of works. The <b>Complaints Management System</b> must include a <b>Complaints Register</b> to be maintained recording information on all complaints received about the development during the carrying out of any works associated with the development. The <b>Complaints Register</b> must record the: a) number of complaints received; b) number of people affected in relation to a complaint; and c) nature of the complaint and means by which the complaint was addressed and whether resolution was reached, with or without mediation.  The <b>Complaints Register</b> must be provided to the Secretary upon request, within the timeframe stated in the request.	CC	✓	✓	✓	✓
B30	A <b>Pre-Construction Compliance Report</b> must be prepared and submitted to the Secretary for information before the commencement of construction. The <b>Pre-Construction Compliance Report</b> must include: a) details of how the terms of this approval that must be addressed before the commencement of construction have been complied with; and b) the commencement date for construction.  Construction must not commence until the <b>Pre-Construction Compliance Report</b> has been submitted to the Secretary.	CC	✓	✓	✓	✓
During Construction						
C1	The hours of construction, including the delivery of materials to and from the Subject Site, must be restricted as follows: a) between 7 am and 6 pm, Mondays to Fridays inclusive;	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	b) between 8 am and 1 pm, Saturdays; and c) no work on Sundays and public holidays. Works may be undertaken outside these hours where: i) the delivery of materials is required outside these hours by the Police or other authorities; or ii) it is required in an emergency to avoid the loss of life, damage to property and/or to prevent environmental harm; or iii) variation is approved in advance in writing by the Secretary or her nominee.					
C2	All construction vehicles (including concrete agitator trucks) are not to arrive at the project site or surrounding residential areas prior to the approved start time of works for the day.	✓	✓	✓	✓	✓
C3	Should any new information come to light during construction works which has the potential to alter previous conclusions about site contamination, then the Certifying Authority must be immediately notified and works must cease. The Certifying Authority will determine whether further investigation, or the need for remediation, is required before construction works can recommence.	✓	✓	✓	✓	✓
C4	All erosion and sediment control measures, must be effectively implemented and maintained at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works have been stabilised and rehabilitated so that it no longer acts as a source of sediment	✓	✓	✓	✓	✓
C5	Any seepage or rainwater collected on-site during construction or groundwater must not be pumped to the street stormwater system unless separate prior approval is given in writing by the Environment Protection Authority in accordance with the <i>Protection of the Environment Operations Act 1997</i> .	✓	✓	✓	✓	✓
C6	A copy of the approved and certified plans, specifications and documents incorporating conditions of approval and certification must be kept on the Subject Site at all times and must be readily available for perusal by any officer of the Department, Council or the Certifying Authority.	✓	✓	✓	✓	✓
C7	The development must be constructed with the aim of achieving the construction noise management levels detailed in the <i>Interim Construction Noise Guideline</i> (Department of Environment and Climate Change, 2009). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the <b>CNVMP</b> .	✓	✓	✓	✓	✓
C8	If the noise from a construction activity is substantially tonal or impulsive in nature (as described in Chapter 4 of the NSW <i>Industrial Noise Policy</i> ), 5 dB(A) must be added to the measured construction noise level when comparing the measured noise with the construction noise management levels	✓	✓	✓	✓	✓
C9	The Applicant must schedule intra-day 'respite periods' for construction activities identified in the <i>Interim Construction Noise Guideline</i> as being particularly annoying to surrounding residents and other noise sensitive receivers or where construction activities	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

# SSD 7968 | Oran Park Public School and Oran Park High School

## Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	result in those residents and sensitive receivers being exposed to construction noise levels above 75 dB(A) (i.e. "highly noise affected").					
C10	The Applicant must schedule rock breaking, rock hammering, sheet piling, pile driving and any similar activity only between the following hours unless otherwise approved by the Secretary: a) 9 am to 12 pm, Monday to Friday; b) 2 pm to 5 pm Monday to Friday; and c) 9 am to 12 pm, Saturday.	✓	✓	✓	✓	✓
C11	Any noise generated during the construction of the development must not be offensive noise within the meaning of the <i>Protection of the Environment Operations Act 1997</i> or exceed approved noise limits for the Subject Site.	✓	✓	✓	✓	✓
C12	Vibration caused by construction at any residence or structure outside the Subject Site must be limited to: a) for structural damage vibration, German Standard DIN 4150-3 <i>Structural Vibration – Effects of vibration on structures</i> ; and b) for human exposure to vibration, the evaluation criteria presented in British Standard BS 6472-1:2008 <i>Guide to evaluation of human exposure to vibration in buildings. Vibration sources other than blasting</i> (1 Hz to 80 Hz) for low probability of adverse comment.	✓	✓	✓	✓	✓
C13	Vibratory compactors must not be used closer than 30 metres from residential buildings unless vibration monitoring confirms compliance with the vibration criteria specified above.	✓	✓	✓	✓	✓
C14	These limits apply unless otherwise outlined in the <b>CNVMP</b> , required under Condition B22 of this consent and submitted to the satisfaction of the Certifying Authority.	✓	✓	✓	✓	✓
C15	a) street trees must not be trimmed or removed unless it forms a part of this development consent or prior written approval from Council is obtained or is required in an emergency to avoid the loss of life or damage to property;  b) all street trees must be protected at all times during construction. Any tree on the footpath, which is damaged or removed during construction due to an emergency, must be replaced, to the satisfaction of Council;  c) all trees on the Subject Site that are not approved for removal must be suitably protected during construction; and  d) if access to the area within any protective barrier is required during the works, it must be carried out under the supervision of a qualified arborist. Alternative tree protection measures must be installed, as required. The removal of tree protection measures, following completion of the works, must be carried out under the supervision of a qualified arborist and must avoid both direct mechanical injury to the structure of the tree and soil compaction within the canopy or the limit of the former protective fencing, whichever is the greater.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
C16	Any trees planted (that would reach a height of greater than eight metres at maturity) as part of the approved Landscape Plan must be of a suitable advanced stage, be a locally endemic species and be endorsed by a suitably qualified and experienced person/s. Confirmation that all trees have been planted in accordance with this condition (including number of trees) must be provided to the Certifying Authority prior to operation unless otherwise agreed by the Secretary	✓	✓	✓	✓	✓
C17	Waste Management provisions must be implemented in general accordance with the approved <b>CWMP</b> .	✓	✓	✓	✓	✓
C18	The body of any vehicle or trailer used to transport waste or excavation spoil must be covered before leaving the premises to prevent any spillage or escape of any dust, waste or spoil. Mud, splatter, dust and other material likely to fall from or be cast off the wheels, underside or body of any vehicle, trailer or motorised plant leaving the site must be removed before leaving the premises	✓	✓	✓	✓	✓
C19	A site notice(s) must be prominently displayed at the boundaries of the Subject Site for the purposes of informing the public of project details including, but not limited to the details of the Builder, Certifying Authority and Structural Engineer. b) The site notice(s) is to satisfy all but not be limited to, the following requirements:  i) minimum dimensions of the notice must measure 841 mm x 594 mm (A1) with any text on the notice to be a minimum of 30 point type size; ii) the notice is to be durable and weatherproof and is to be displayed throughout the works period; iii) the approved hours of work, the name of the site/ project manager, the responsible managing company (if any), its address and 24 hour contact phone number for any inquiries, including construction/ noise complaint must be displayed on the site notice; and iv) the notice(s) is to be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the Subject Site is not permitted.	✓	✓	✓	✓	✓
C20	To protect the safety of work personnel and the public, the work site must be adequately secured to prevent access by unauthorised personnel, and work must be conducted at all times in accordance with relevant SafeWork requirements.	✓	✓	✓	✓	✓
C21	The following hoarding requirements must be complied with: a) no third party advertising is permitted to be displayed on the subject hoarding/ fencing; b) the construction site manager must be responsible for the removal of all graffiti from any construction hoardings or the like within the construction area within 48 hours of its application; and c) the Applicant must submit a hoarding application to Council for the installation of any hoardings over Council footways or road reserve.	✓	✓	✓	✓	✓
C22	The public way (outside of any construction works zone) must not be obstructed by any materials, vehicles, refuse, skips or the like, under and circumstances. Non-compliance with this requirement will result in the issue of a notice by the relevant Authority to stop all works on site.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | **CC** = Crown Certificate Issued for Compliance | **OC** = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
C23	If any unexpected archaeological relics are uncovered during the course of the work, then all works must cease immediately in that area and the Heritage Office contacted. Depending on the possible significance of the relics, an archaeological assessment and management strategy may be required before further works can continue in that area. Works may only recommence with the written approval of the Heritage Office.	✓	✓	✓	✓	✓
C24	In the event that surface disturbance identifies a new Aboriginal object, all works must halt in the immediate area to prevent any further impacts to the object(s). A suitably qualified archaeologist and the registered Aboriginal representatives must be contacted to determine the significance of the objects. The site is to be registered in the Aboriginal Heritage Information Management System (AHIMS) which is managed by OEH and the management outcome for the site included in the information provided to AHIMS. The Applicant must consult with the Aboriginal community representatives, the archaeologists and OEH to develop and implement management strategies for all projects/sites. Works may only recommence with the written approval of OEH.	✓	✓	✓	✓	✓
C25	Within 24 hours of the occurrence of an incident that causes (or may cause) harm to the environment, the Applicant must notify the Secretary and any other relevant agencies of the incident in accordance with the requirements outlined in Conditions A15 to A20 of this consent.	✓	✓	✓	✓	✓
C26	Within seven days of the detection of the incident, the Applicant must provide the Secretary and any relevant agencies with a detailed report on the incident, and such further reports as may be requested in accordance with Condition A17 of this consent.	✓	✓	✓	✓	✓
C27	The Applicant must provide regular reporting on the environmental performance of the Development on its website, in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent.	✓	✓	✓	✓	✓
C28	Within six months of the date of this consent the Applicant must make the following information publicly available on its website and keep the information up to date: a) the EIS; b) current statutory approvals for the Development; c) approved strategies, plans or programs; d) a complaints register, updated on an annual basis; and e) any other matter required by the Secretary.	✓	✓	✓	✓	✓
C29	The Applicant must ensure that employees, contractors and sub-contractors are aware of, and comply with, the conditions of this consent relevant to their respective activities	✓	✓	✓	✓	✓
C30	The Applicant must be responsible for environmental impacts resulting from the actions of all persons that it invites onto the site, including contractors, sub-contractors and visitors.	✓	✓	✓	✓	✓
C31	<b>Construction Compliance Reports</b> must be prepared and submitted to the Secretary for information every six months from the date of the commencement of construction or within another timeframe agreed with the Secretary, for the duration of construction. The <b>Construction Compliance Reports</b> must include: a) a results summary and analysis of environmental monitoring;	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	b) the number of any complaints received, including a summary of main areas of complaint, action taken, response given and proposed strategies for reducing the recurrence of such complaints; c) details of any review of, and minor amendments made to, the <b>CEMP</b> as a result of construction carried out during the reporting period; d) a register of any consistency assessments undertaken and their status; e) results of any independent environmental audits and details of any actions taken in response to the recommendations of an audit; f) a summary of all incidents notified in accordance with this approval; and g) any other matter relating to compliance with the terms of this approval or as requested by the Secretary.					
C32	Damage to any grass verge, footpath, kerb and guttering, utility services or road within the road reserve as a result of construction works related to the development shall be immediately reinstated to the satisfaction of Council	✓	✓	✓	✓	✓
C33	All excavations and backfilling on public land associated with the development must be executed in accordance with the appropriate safety standards. All excavations must be properly guarded and protected to prevent them from being dangerous to life and property.	✓	✓	✓	✓	✓
Prior to Occupation or Commencement of Use						
D1	An <b>Operational Noise Management Plan</b> (ONMP) must be prepared prior to the commencement of use of the Oran Park High School hall and sports field for uses outside of school hours, that addresses, but is not limited to: a) a description of each type of event and/or use, including a description of any amplification systems and the types of activities to be undertaken; b) identification of noise sensitive receivers, existing and proposed, likely to be adversely affected by activities undertaken; c) details of a noise monitoring program that monitors sound levels from events undertaken outside of school hours and retains records of the results and details of the monitoring equipment used, including its location and settings; d) clearly defined noise management objectives, having regard to the recommended mitigation measures contained in the <i>Acoustic Assessment Report</i> , prepared by Day Design Pty Ltd, dated 14 September 2017; e) details of a noise complaints handling procedure and actions to be taken at the time of each complaint to monitor and minimise noise impacts. The procedures must include: i) the time and date each complaint was received; ii) how the complaint was received; iii) the contact details of the person lodging the complaint; iv) the proposed actions to prevent a reoccurrence of the noise impact;  f) a program for review of the <b>ONMP</b> , including ongoing assessment and improvement of the <b>ONMP</b> . The program must address the effectiveness of: i) community consultation (consultation prior to, during (complaints handling and response) and after events and consultation and part of the plan review process);	-	OC	-	-	-

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance



## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	<p>ii) the use of technology or the setup procedures to mitigate or prevent noise impact;</p> <p>iii) the use of real time mitigation measures to mitigate or prevent noise impact;</p> <p>iv) the use of monitoring programs, the monitoring data records and community consultation information to prevent or mitigate noise impacts; and</p> <p>g) the program of review must also provide an Implementation Strategy, that commits to specific management actions, including operational procedures to be implemented along with timeframes. The specific management actions must incorporate best management practice that adequately addresses the identified problems and issues with both non-structural and structural aspects of noise management, such as community consultation, equipment setup, use of technology, real time noise mitigation measures, and monitoring program.</p>					
D2	Details must be provided to the satisfaction of the Certifying Authority demonstrating that the <b>ONMP</b> has been prepared in consultation with Council and identified sensitive receivers.	-	OC	-	-	-
D3	The <b>ONMP</b> (as revised from time to time) must be implemented by the Applicant for the life of the development.	-	✓	✓	✓	✓
D4	<p>An <b>Operational Traffic Management Plan</b> (OTMP), prepared by suitably qualified consultant, must be prepared prior to the commencement of use demonstrating that road safety and traffic efficiency is not compromised on the surrounding road network. The <b>OTMP</b> must address, but not limited to:</p> <p>a) bus stop locations, kerb side space and associated infrastructure requirements;</p> <p>b) pedestrian management controls along key pedestrian desire lines before and after school hours; and</p> <p>c) bus routes and bus services, and the level of reliability and service;</p> <p>d) management arrangements for on-site school parking facilities and kerb-side pick-up/drop-off activities;</p> <p>e) traffic management measures on the surrounding road;</p> <p>f) appropriate scheduling of school deliveries outside of peak commuter travel and school start/finish times to reduce associated impacts and potential conflicts with pedestrians.</p>	-	OC	-	-	-
D5	The <b>OTMP</b> is to be prepared in consultation with Council, RMS, TfNSW and local bus service providers (where relevant) and submitted to the satisfaction of the Certifying Authority	-	✓	✓	✓	✓
D6	<p>Following completion, installation and testing of all mechanical ventilation systems, the Applicant must provide evidence to the satisfaction of the Certifying Authority, prior to the final occupation, that the installation and performance of the mechanical systems complies with:</p> <p>a) the BCA;</p> <p>b) AS 1668.2-2012 <i>The use of air conditioning in buildings – Mechanical ventilation in buildings</i> and other relevant codes;</p> <p>c) the development consent and any relevant modifications; and</p> <p>d) any dispensation granted by the NSW Fire Brigade.</p>	OC	OC	-	-	OC

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
D7	The cost of repairing any damage caused to Council or other Public Authority's assets in the vicinity of the Subject Site as a result of construction works associated with the approved development is to be met in full by the Applicant prior to the occupation of the new development.	✓	✓	✓	✓	✓
D8	A Section 73 Compliance Certificate under the <i>Sydney Water Act 1994</i> must be obtained from Sydney Water Corporation. Application must be made through an authorised Water Servicing Coordinator. Please refer to the "Your Business" section of the web site <a href="http://www.sydneywater.com.au">www.sydneywater.com.au</a> then follow the "e-Developer" icon or telephone 13 20 92 for assistance. The Section 73 Certificate must be submitted to the Certifying Authority prior to the commencement of use.	OC	OC	-	-	OC
D9	a) Prior to commencement of use of the development, the Applicant must engage a suitably qualified person to prepare a post-construction dilapidation report at the completion of the construction works. This report is to ascertain whether the construction works created any structural damage to adjoining buildings or infrastructure. b) The report is to be submitted to the Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings or infrastructure, the Certifying Authority must: i) compare the post-construction dilapidation report with the pre-construction dilapidation report required by these conditions; and ii) have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads. c) A copy of this report is to be forwarded to Council.	OC	OC	-	-	OC
D10	Prior to the final occupation of the school, a <b>Fire Safety Certificate</b> must be obtained for all the Essential Fire or Other Safety Measures forming part of this consent. A copy of the Fire Safety Certificate must be submitted to the relevant authority and Council. The Fire Safety Certificate must be prominently displayed in the building.	OC	OC	-	-	OC
D11	A <b>Structural Inspection Certificate</b> or a <b>Compliance Certificate</b> must be submitted to the satisfaction of the Certifying Authority prior to the occupation of the relevant parts of any new or refurbished buildings. A copy of the Certificate with an electronic set of final drawings (contact approval authority for specific electronic format) must be submitted to the approval authority and the Council after: a) the site has been periodically inspected and the Certifier is satisfied that the structural works is deemed to comply with the final design drawings; and b) the drawings listed on the Inspection Certificate have been checked with those listed on the final Design Certificate/s.	OC	OC	-	-	OC
D12	Way-finding signage and signage identifying the location of staff car parking must be installed prior to occupation.	OC	OC	-	-	OC
D13	Bicycle way-finding signage must be installed within the site to direct cyclists from footpaths to designated bicycle parking areas prior to occupation	OC	OC	-	-	OC

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
D14	'Do not drink' signage on non-potable water used for toilet flushing and to new hose taps and irrigation systems for landscaped areas must be installed within the site prior to occupation.	OC	OC	OC	OC	OC
D15	Installation of all required School Zone signage, speed management signage and associated pavement markings along Holden Drive is to be completed prior to commencement of use of the development.	-	OC	✓	✓	✓
D16	The Applicant is to must maintain records of all dates in relation to installing, altering and removing traffic control devices related to speed.	-	✓	✓	✓	✓
D17	Following installation of School Zone signage, speed management signage and associated pavement markings along Holden Drive, as required by Condition D15 of this consent, the Applicant must arrange an inspection with Roads and Maritime Services for formal handover of assets. The handover of assets must occur prior to commencement of use of the development	-	OC	-	-	-
D18	An <b>Operation and Maintenance Plan</b> (OMP) is to be prepared to ensure proposed stormwater quality measures remain effective. The <b>OMP</b> must contain the following: a) maintenance schedule of all stormwater quality treatment devices; b) record and reporting details; c) relevant contact information; and d) Work Health and Safety requirements. Details demonstrating compliance must be submitted to the Certifying Authority prior to occupation.	OC	OC	-	-	OC
D19	A <b>Pre-Operation Compliance Report</b> must be prepared and submitted to the Secretary for information no later than one month before the commencement of operation or within another timeframe agreed with the Secretary. The Pre-Operation Compliance Report must include: a) details of how the terms of this approval that must be addressed before the commencement of operation have been complied with; and b) the commencement date for operation. Operation of the building must not commence until the Pre-Operation Compliance Report has been submitted for information to the Secretary	-	OC	-	-	OC
D20	A <b>Parking Management Strategy</b> (PMS) must be prepared by a suitability qualified traffic consultant and submitted to the satisfaction of the Secretary prior to occupation. The Strategy must be prepared in consultation with Council and other relevant stakeholders and must include, but not be limited to, identification of measures to manage parking behaviours generated by the development and address any road safety and any congestion impacts	-	OC	-	-	OC
D21	Where relevant, the <b>PMS</b> must include evidence of written correspondence from Council indicating that a formal agreement has been reached with the Applicant for use of car parking associated with the Jack Brabham Reserve by the Applicant	-	OC	-	-	OC
D22	The nominated student pick-up/drop-off area along the northern side of Holden Drive, identified in the Holden Drive Layout (Dwg. P1) approved in Condition A2 of this consent,	-	OC	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
	must be restricted to school days between 8:00 am to 9:30 am and 2:30 pm and 4:00 pm on school days and signposted accordingly					
D23	Provision of minimum 149 on-site car parking spaces (including the existing 49 on-site Oran Park Public School parking spaces) must be provided prior to occupation. The car parking area/s must be in accordance with AS/NZS 2890.1:2004 <i>Parking facilities Part 1: Off-street car parking</i> , AS/NZS 2890.6:2009 <i>Parking facilities – Off-street parking for people with disabilities</i>	OC (Total of 69 parking spaces)	OC (Total of 80 parking spaces)	✓	✓	✓
D24	The <b>Green Travel Plan</b> (GTP), prepared by Woolacotts Consulting Engineers dated 5 September 2017, must be amended by a suitably qualified traffic consultant and submitted to the satisfaction of the Secretary prior to occupation. The GTP must address, but not limited to, the following: a) objectives and modes share targets (i.e. site and land use specific, measureable and achievable and timeframes for implementation) to define the direction and purpose of the <b>GTP</b> ; b) specific tools and actions to help achieve the objectives and mode share targets; c) measures to promote and support the implementation of the plan, including financial and human resource requirements, roles and responsibilities for relevant employees involved in the implementation of the <b>GTP</b> ; d) details regarding the methodology and monitoring/review program to measure the effectiveness of the objectives and mode share targets of the <b>GTP</b> , including the frequency of monitoring and the requirement for travel surveys to identify travel behaviours of students and staff to and from both schools at appropriate times throughout the academic year.	-	OC	-	-	-
D25	The <b>GTP</b> (as revised from time to time) must be implemented by the Applicant, or person/s authorised to, for the life of the development	✓	✓	✓	✓	✓
D26	The Applicant is to obtain a certificate from a suitably qualified tradesperson, certifying that the kitchen, food storage and food preparation areas have been fitted in accordance with the AS 4674 <i>Design, construction and fit-out of food premises</i> . The Applicant shall provide evidence of receipt of the certificate to the satisfaction of the Certifying Authority prior to occupation.	-	-	-	-	OC
D27	Prior to the occupation of the development, the Applicant shall submit details, prepared by a suitability qualified person, to the Certifying Authority demonstrating that ESD initiatives identified under Condition B2 of this consent have been incorporated in the new buildings	-	OC	-	-	-
D28	In connection with the Works-As-Executed drawings, the Applicant must submit to Council an electronic listing of all road, stormwater, water and sewer assets generated by the development. Copies of the Asset spreadsheet are available from Council's website	-	-	-	-	OC
D29	The Applicant must provide Transport for New South Wales a copy of the final school catchment prior to occupation of the development	-	-	-	-	OC

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
D30	Where relevant, construction of the road network, including bus bays, footpaths and pedestrian crossing points, directly adjoining the site must be completed in accordance with Council's relevant Engineering Guidelines and prior to commencement of use of the development.	-	OC	-	-	OC
D31	The external walls of the buildings, including attachments must comply with the relevant requirements of the National Construction Code (NCC). Prior to the certification of Crown building works and occupation of the development, the Certifying Authority must: a) be satisfied that suitable evidence is provided to demonstrate that the products and systems proposed for use or used in the construction of external walls including finishes and cladding, such as synthetic or aluminium composite panels, comply with the relevant requirements of the NCC b) ensure that the documentation relied upon in the approval process include the appropriate level of detail to demonstrate compliance with the NCC as proposed and as built.	OC	OC	-	-	OC
D32	A copy of the documentation required under Condition D31 (b) must be provided to the Secretary within seven days of being accepted by the Certifying Authority.	OC	OC	-	-	OC
<b>Post Occupation</b>						
E1	The <b>GTP</b> must be updated and reviewed annually and implemented accordingly.	✓	✓	✓	✓	✓
E2	The <b>PMS</b> required under Condition D20 of this consent must be updated and reviewed annually, in consultation with Council, and implemented accordingly	✓	✓	✓	✓	✓
E3	The use of the school hall and sports field outside of school hours must at all times comply with the approved <b>ONMP</b> required under Condition D1 of this consent.	✓	✓	✓	✓	✓
E4	All driveways, footways and parking areas must be unobstructed at all times. Driveways, footways and car spaces must not be used for the manufacture, storage or display of goods, materials, refuse, skips or any other equipment and must be used solely for vehicular and/or pedestrian access and for the parking of vehicles associated with the use of the premises	✓	✓	✓	✓	✓
E5	Noise associated with the operation of any plant, machinery, School public address system, School bell or other equipment on the Subject Site and community use of the School hall and playing field outside of school hours, must not exceed 5 dB(A) above the background noise level when measured at the boundary of any sensitive receiver	✓	✓	✓	✓	✓
E6	Grounds maintenance involving the use of power equipment must be restricted to between: a) 7:30 am and 6 pm Mondays to Fridays; and b) 8 am and 1 pm on Saturday.	✓	✓	✓	✓	✓
E7	Waste collection services must only be undertaken between the hours of 7:30 am and 6:00 pm Mondays to Fridays.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | **CC** = Crown Certificate Issued for Compliance | **OC** = Occupation Certificate Issued for Compliance

## SSD 7968 | Oran Park Public School and Oran Park High School

### Appendix 4 – Staging Matrix for Conditions of Approval

Staging Matrix for Conditions of Approval – Application of Conditions to Stages – SSD7968						
Cond.	Description	Stage 1a	Stage 1b	Stage 2a	Stage 2b	Stage 2c
E8	The Applicant must undertake short-term noise monitoring, in accordance with the <i>Noise Policy for Industry 2017</i> , to collect valid data and provide a quantitative assessment of operational noise impacts following the commencement of use of Oran Park High School and occupation of the expanded Oran Park Public School. The noise monitoring must be carried out by an appropriately qualified person and a monitoring report must be submitted to the Secretary within six months of full occupation of the building to verify that operational noise levels do not exceed the recommended noise levels identified in <i>Acoustic Assessment Report</i> , prepared by Day Design Pty Ltd, dated 14 September 2017 <b>or in Air Conditioning Noise Assessment, prepared by Day Design Pty Ltd, dated 6 May 2019.</b>	✓	✓	✓	✓	✓
E9	Should the short-term noise monitoring required under Condition E8 of this consent identify any exceedance of the recommended noise levels, the Applicant must implement appropriate on-site noise attenuation measures to ensure operational noise levels do not exceed the recommended noise levels and/or provide noise attenuation measures at the affected noise sensitive receivers.  The implementation of noise attenuation measures, either on-site or at the affected receiver(s), must be provided within three months of the completion of the short-term noise monitoring required under Condition E8 of this consent, or other appropriate time period as agreed by the Secretary.	✓	✓	✓	✓	✓
E10	All loading and unloading of service vehicles in connection with the use of the premises must be carried out wholly within the Subject Site at all times.	✓	✓	✓	✓	✓
E11	All vehicles must enter and leave the Subject Site in a forward direction	✓	✓	✓	✓	✓
E12	The public way must not be obstructed by any materials, vehicles, refuse, skips or the like under any circumstances.	✓	✓	✓	✓	✓
E13	External Lighting must comply with AS 4282-1997 <i>Control of the obtrusive effects of outdoor lighting</i> . Upon installation of lighting, but before it is finally commissioned, the Applicant must submit to the Certifying Authority evidence from a qualified practitioner demonstrating compliance in accordance with this condition.	✓	✓	✓	✓	✓
E14	The owner must submit to Council an Annual Fire Safety Statement, each 12 months after the final Safety Certificate is issued. The certificate must be on, or to the effect of, Council's Fire Safety Statement.	✓	✓	✓	✓	✓
E15	The landscaping is to be maintained at all times following its installation in accordance with the approved Landscape Plan.	✓	✓	✓	✓	✓

✓ = Applicable/Complies Without Certificate | CC = Crown Certificate Issued for Compliance | OC = Occupation Certificate Issued for Compliance