Modification of Development Consent

Section 4.55(1A) of the Environmental Planning and Assessment Act 1979

As delegate of the Minister for Planning and Public Spaces, the Independent Planning Commission modifies the development consent referred to in Schedule 1, subject to the conditions in Schedule 2.

Commission Member

Sydney 2019

SCHEDULE 1

Development consent: SSD 8449 granted by the Independent Planning Commission on

February 22 2019

For the following: Adaptive reuse of the Locomotive Workshop (Bays 5-15) including:

• a maximum of 27,458 m² GFA for commercial premises

including 156 m² for retail uses

· associated heritage conservation works

external illumination and signage.

Applicant: Mirvac Projects Pty Ltd

Consent Authority: Minister for Planning

The Land: Locomotive Workshop (Bays 5-15), 2 Locomotive Street, Australian

Technology Park, Eveleigh (Lot 4000 DP 1194309)

Modification: SSD 8449 (MOD 1): Modification of Condition B25 relating to

stormwater post development pollutant loads.

NSW Government Department of Planning, Industry and Environment

SCHEDULE 2

The above approval is modified as follows:

- 1. Condition B25 is amended by the insertion of the **bold and underlined** words/numbers and the deletion of **bold strikethrough** words/numbers as follows:
- B25. Prior to a Construction Certificate being issued for any excavation, civil construction, drainage or building work (whichever is earlier), but excluding approved preparatory or demolition work, a stormwater quality assessment must be undertaken and must be approved by the PCA.

The stormwater quality assessment must:

- (a) be prepared by a suitably qualified drainage engineer with experience in Water Sensitive Urban Design;
- (b) use modelling from an industry-standard water quality model; and
- (c) demonstrate what water sensitive urban design and other drainage measures will be used to ensure that the development will achieve the following post-development pollutant loads relative to pre-development pollutant loads:
 - (i) reduce the baseline annual pollutant load for litter and vegetation larger than 5mm by 90% ≥25%;
 - (ii) reduce the baseline annual pollutant load for total suspended solids by 85% ≥30%;
 - (iii) reduce the baseline annual pollutant load for total phosphorous by 65% ≥10%;
 - (iv) reduce the baseline annual pollutant load for total nitrogen by 45% ≥10%

End of Modification to SSD 8449 MOD 1

NSW Government Department of Planning, Industry and Environment