



# TAFE NSW Construction Centre of Excellence

2-44 O'Connell Street, Kingswood NSW 2747



CIVIL ENGINEERING: SSDA DESIGN REPORT

PREPARED FOR  
Gray Puksand  
17-56 Clarence Street  
Sydney NSW 2000  
Tel: +61(0)2 9247 9422

Ref: S202025-01-CR02  
Rev: 3  
Date: 4<sup>th</sup> March 2021





# Civil Engineering SSDA Design Report

## Revision Schedule

Date	Revision	Issue	Prepared By	Approved By
18.12.20	1	Draft	J. Gilligan	J. Gilligan
10.02.21	2	Final	J. Gilligan	J. Gilligan
04.03.21	3	Final	A. Carvalhaes	J. Gilligan

Northrop Consulting Engineers Pty Ltd

ACN 064 775 088 | ABN 81 094 433 100

Level 11, 345 George Street, Sydney NSW 2000

02 9241 4188 | sydney@northrop.com.au | www.northrop.com.au

© 2021 Northrop Consulting Engineers Pty Ltd. All rights reserved.

This document has been prepared on behalf of and for the exclusive use of Gray Puksand and is subject to and issued in accordance with the agreement between Gray Puksand and Northrop Consulting Engineers. Northrop Consulting Engineers accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this document by any third party. Copying this document without the permission of Gray Puksand or Northrop Consulting Engineers is not permitted.

# Executive Summary

This report has been prepared to accompany a detailed State Significant Development Application (SSDA) SSD\_8571481 for the development of an educational facility at the TAFE Nepean Kingswood Campus, located at 2-44 O'Connell Street, Kingswood (the site). The legal description of the site is Lot 1 in DP 866081. The site comprises a rectangular lot with an area of approximately 23 hectares.

The purpose of this report is identify and describe the civil engineering design elements required for the proposed development.

Specifically, the SSDA seeks development consent for the construction and operation of the TAFE NSW Construction Centre of Excellence (TAFE CCoE) a multi-level, integrated educational facility designed to accommodate specialised training and education for construction-related TAFE NSW courses (the project).

The TAFE CCoE will be a new learning environment with an emphasis on flexibility and adaptability, to encourage cross-disciplinary collaboration, industry engagement and educational excellence. On 27 February 2019, the NSW Government announced the delivery and associated funding for the CCoE.

The proposed development is classified as State Significant Development (SSD) on the basis that it falls within the requirements of clause 4, Schedule 19 of the State Environmental Planning Policy (State and Regional Development) 2011 (SRD SEPP), being 'development for the purpose of a tertiary institution that has a capital investment value of more than \$30 million'.

The Minister for Planning, or their delegate, is the consent authority for the SSDA and this application is lodged with the NSW Department of Planning, Industry and Environment (NSW DPIE) for assessment.

This report has been prepared in response to the requirements contained within the Secretary's Environmental Assessment Requirements (SEARs) issued for the project. Specifically, this report has been prepared to respond to the following SEARs:

SEARs	Report Section
<p>15. Water Quality</p> <ul style="list-style-type: none"> <li>- Demonstrate that all practical measures to avoid or minimise water pollution and protect human health and the environment from harm are investigated and implemented; and</li> <li>- Identify sensitive receiving environments and develop a strategy to avoid or minimise impacts on these environments.</li> </ul>	Section 3.1 and 6.2
<p>18. Stormwater Management</p> <p>Detail any steps/measures to be taken to protect existing stormwater assets such as avoiding over and/or adjacent to stormwater assets and building bridges over stormwater assets, if required. Outline measures to minimise or eliminate flooding, degradation of water quality, and avoid adverse impacts on any heritage items, and create pipeline easements where required.</p> <ul style="list-style-type: none"> <li>- Detail how the design of the proposal would ensure that post-development stormwater flows match pre-development flows. Provide, where applicable, a preliminary stormwater management plan for the development that:</li> <li>- is prepared by a suitably qualified person in consultation with Council and any other relevant drainage authority.</li> <li>- details of proposed drainage design for the site including on-site detention facilities, water quality measures and the nominated discharge point.</li> <li>- demonstrates compliance with Council or other drainage authority requirements; and</li> <li>- stormwater plans detailing the proposed methods of drainage without impacting on the downstream properties.</li> </ul>	Section 6.1 and 6.2
<p>20. Drainage</p> <p>Detail measures to minimise operational water quality impacts on surface waters and groundwater.</p>	Section 3.1 and 6.2
<p>24. Water and Soils</p> <p>Provide:</p> <ul style="list-style-type: none"> <li>- an assessment of potential impacts on surface and groundwater (quality and quantity), soil, related infrastructure and watercourse(s) where relevant;</li> <li>- details of measures and procedures to minimise and manage the generation and off-site transmission of sediment, dust and fine particles; and</li> <li>- an assessment of salinity and acid sulphate soil impacts, including a Salinity Management Plan and/or Acid Sulphate Soils Management Plan, where relevant.</li> </ul>	Section 3.1

Table of Contents

1. General .....2

1.1 Introduction.....2

1.2 Related Reports and Documents .....2

2. Existing Site Conditions .....3

2.1 Subject Site .....3

2.2 Site Topography.....4

2.3 Contamination and Geotechnical Conditions.....4

2.4 Access to Site.....5

2.5 Existing Infrastructure .....6

2.6 Flooding.....8

3. Sediment and Soil Erosion Control.....9

3.1 Sediment and Erosion Control .....9

4. Bulk Earthworks .....10

4.1 Construction Sequencing.....10

5. Pavements .....11

6. Stormwater Management Strategy .....12

6.1 Stormwater Quantity Management .....12

6.2 Stormwater Quality Management .....14

7. Conclusion .....16

Appendix A – MUSIC Catchment Plan .....18

Appendix B – Engineering Plans .....19



# 1. General

## 1.1 Introduction

Northrop Consulting Engineers Pty Ltd (Northrop) have been engaged by Gray Puksand to prepare the Civil Engineering design and documentation in support of a SSDA submission to DPIE for the proposed TAFE NSW Construction Centre of Excellence located at the TAFE NSW Kingswood Campus, in the suburb of Kingswood within the Penrith Local Government Area (LGA).

This report covers the works shown as the Northrop Drawing Package required for the development of the site including:

- Sediment and Soil Erosion Control
- Stormwater Management (Quantity and Quality)

In addition, some commentary has also been provided on bulk earthworks and pavements which will be further developed in the following stages of the project.

## 1.2 Related Reports and Documents

This report is to be read in conjunction with the following reports and documents:

- Design Standards as provided by Penrith City Council regarding On-site Stormwater Detention (OSD) and water quality.
- Detailed site survey plan provided by Surveying & Spatial Information Services dated 7th February 2020.
- Site survey plan provided by Rygate Surveyors dated 6<sup>th</sup> November 2020
- Geotechnical Investigation Report prepared by PSM dated 8<sup>th</sup> December 2020 (PSM4240-004L)



## 2. Existing Site Conditions

### 2.1 Subject Site

The TAFE NSW Construction Centre of Excellence is to be located at the TAFE NSW Kingswood Campus, in the suburb of Kingswood within the Penrith Local Government Area (LGA). The site is located at 2-44 O'Connell Street, Kingswood and legally described as Lot 1 in Deposited Plan (DP) 866081. It has an area of approximately 22 hectares (ha) and is bound by the Great Western Highway to the north and O'Connell Street to the west. The site directly abuts two residential properties to the south and the Western Sydney University, Werrington Campus to the east.

A proposed building location has been identified by the project Architect in the north eastern portion of the site as shown in Figure 2.



Figure 1 – Existing Site Plan (SIX Maps, 2020)




Figure 2 – Proposed Building Layout (Gray Puksand, 2021)



## 2.2 Site Topography

Levels in the north eastern portion of the site fall from approx. RL 56.00 AHD to RL 50.00m AHD at an approximate grade of 5-6% where the proposed building location has been identified. This corresponds to approximately 6.0m difference in elevation. Beyond the potential building locations, the surface falls at a similar grade to north west towards an existing basin with a permanent pond of water at approx. RL 47.00m AHD.

## 2.3 Contamination and Geotechnical Conditions

### 2.3.1 Geotechnical

A Geotechnical Investigation Report has been prepared by PSM dated 8<sup>th</sup> December 2020 (PSM4240-004L). A design CBR 2% has been recommended for the purposes of new pavement design subject to further testing once bulk earthworks operations have been undertaken.

Further Geotechnical Advice has been sought with regards to ground improvement methodologies to achieve CBR 3% or greater to establish new pavement profiles for the proposed development.

For the purposes of bulk earthworks calculations, a nominal 200mm depth of topsoil has been identified in the Geotechnical Investigation Report that will need to be stripped to expose the natural subgrade material. Topsoil may be stockpiled and ameliorated for reuse / spreading in open space grassed areas.

Temporary and permanent batter slope angles have been nominated in the Geotechnical Investigation Report and have been considered as part of the proposed works as summarised below:

*Table 1 – Batter Slopes*

Unit	Temporary	Permanent
Engineered Fill / Natural Soil	1.5H: 1V	2H: 1V
Bedrock Units	1H: 1V	1.5H: 1V

Investigation Report Engineer that will need to be revised once the project Geotechnical Engineer has reviewed the proposed earthworks design for the development.

### 2.3.2 Contamination

A preliminary contamination investigation and report has been undertaken by JBS&G dated 8th December 2020 (59831/134229 Rev A). The report indicates that the risk of contamination at the site is low. It further states that as fill is present at the site, given the nature of the investigation that an unexpected finds protocol for the proposed development works is considered if unidentified contamination is encountered.



## 2.4 Access to Site

The site has street frontages to the Great Western Highway and O'Connell Street, approximately 550m and 440m in length, respectively.

There are two vehicular entrances to the site along O'Connell Street (Gate 1 North and Gate 2 South), which provide access to internal circulation roadways and car parking however these are not connected. A circulation road extends from the Gate 2 access on O'Connell Street through the site adjacent to buildings along the southern boundary leading to an existing carpark near the proposed development area.

The existing road surfaces are made up of an asphaltic concrete wearing course overlaid on a granular road base material. The condition of the road surface wearing course is variable which has degraded over time.



Figure 3 – Gate 2 Existing Site Access

Remnants of an existing road were observed in the green space central to the existing basin / pond and the eastern boundary. It is understood that this road extended from a private road in an adjacent property to the south, through the green space and once connected with the Great Western Highway. The road is slightly elevated above the surrounding natural surface and covered in vegetation.




Figure 4 – Remnant Road extending from the Great Western Highway towards Block T



## 2.5 Existing Infrastructure

Northrop has undertaken a preliminary investigation of existing infrastructure in the vicinity of the proposed development site. Our assessment has been based on limited survey information as well as publicly available information from Penrith City Council, and site inspections undertaken on the 20<sup>th</sup> September 2020 and 29<sup>th</sup> October 2020.

### 2.5.1 Existing stormwater infrastructure

Four headwalls were identified along the northern edge of Building T (3 x 300mm and 1 x 450mm) discharging stormwater to the green space. From here flows are directed north west over land towards the existing basin / pond.

A single headwall was identified in the north east portion of the site discharging flows from Western Sydney University, through the green space. Flows are directed from the headwall in a natural channel west towards the existing basin / pond.

An additional headwall was identified under the remnant road (approx. 450mm diameter) to direct surface flows blocked by the remnant road towards the existing basin / pond

The outlet of the existing pond was not accessible at the time of inspection. Based on limited visibility of the pond, it is understood that water from the pond overflows to another depression outside the property boundary. From here it is piped to a smaller depression before it discharges to the north via a series of headwalls under the Great Western Highway.

On the northern side of the Great Western Highway flows continue north through private property. They are directed under St Charbel Boulevard in a series of box culverts before being conveyed further north.

From review of the Spatial Information Exchange maps data, the depression through the site, the channel extending from Western Sydney University and the basin / pond are plotted as watercourses / tributaries connecting to Werrington Creek. Further consultation with the Office of Water is to be undertaken to determine the constraints associated with these existing features.



Figure 5 – Existing Site Plan nominating watercourses (SIX Maps, 2020)





*Figures 6-10 (Clockwise from top left) - Headwalls near Block T, Flow path from Block T to Basin, Headwall and channel discharging flows from Western Sydney University, Outlet configuration from Basin / Pond in the verge of Great Western Highway, Culvert Crossing under Great Western Highway*



## 2.6 Flooding

From review of the College, Orth and Werrington Creeks Catchment and Overland Flow Study commissioned by Penrith City Council, the site is flood affected to the north in the location of the existing basin / pond up to RL 47.00m AHD for the 1% AEP Flood. The project team have commissioned a Flood Consultant to provide further advice with respect to the existing conditions and the proposed development.



Figure 11 – Peak Design Flood Level for the 1% AEP Flood (College, Orth and Werrington Creeks Catchment Overland Flow Flood Study, June 2017).



## 3. Sediment and Soil Erosion Control

### 3.1 Sediment and Erosion Control

The objectives of the erosion and sediment control for the development site will be to ensure:

- Adequate erosion and sediment control measures are applied prior to the commencement of construction and are maintained throughout construction; and
- Construction site runoff is appropriately treated in accordance with Penrith City Council requirements prior to discharge.

As part of the works, the erosion and sedimentation control will need to be provided during the construction phase of the development in accordance with Penrith City Councils requirements and the NSW Department of Housing Manual, "Managing Urban Stormwater Soil & Construction" 2004 (Blue Book) - prior to any earthworks commencing on site.

#### 3.1.1 Sediment Basin

A temporary sediment basin has been designed to capture site runoff during construction and has been located towards the north eastern side of the site, in the lowest point. The construction of the basin will be undertaken in stages to enable maximum runoff capture assisted by diversion swales and direct runoff to the basin.

Calculations to determine the concept design basin size have been based on available geotechnical information regarding soil types and through the use of the Soils and Construction Volume 1 Manual.

To ensure the sediment basin is working effectively it will be maintained throughout the construction works. Maintenance includes ensuring adequate settlement times or flocculation and pumping of clean water to reach the minimum storage volume at the lower level of the settling zone. The settling zone will be identified by pegs to clearly show the level at which design storage capacity is available.

The pumped water from the sediment basin can be reused for dust control during construction.

Overflow weirs are to be provided to control overflows for rainfall events in excess of the design criteria which caters for a storm event up to and including the 1% AEP storm event.

The concept sediment basin sizing is summarised in the table below. Detailed sediment basin sizing, configuration and location shall form part of the Construction Certificate application.

The sediment basin has been located for future conversion into the permanent water quality basin.

Table 2 – Sediment Basin Volumes

Total Disturbed Area	2.5	Settling zone volume	288m <sup>3</sup>
Soil Texture Group	F	Sediment storage volume	144 m <sup>3</sup>
Design rainfall depth (days)	5	Total Basin Volume	432m <sup>3</sup>
Design rainfall depth (percentile)	80		
x-day, y-percentile rainfall event	27.4		
CV	0.42		

#### 3.1.2 Sediment and Erosion Control Measures

Prior to any earthworks commencing on site, sediment and erosion control measure shall be implemented generally in accordance with the engineering drawings and the "Blue Book". The measures are intended to be a minimum treatment only as the contractor will be required to modify and stage the erosion and sedimentation control measures to suit the construction program, sequencing, and techniques. These measures may include:

- A temporary site security/safety fence is to be constructed around the site, the site office area, and the proposed sediment basin.
- Sediment fencing provided downstream of disturbed areas, including any topsoil stockpiles.
- Dust control measures including covering stockpiles, installing fence hessian and watering exposed areas.
- Placement of hay bales or mesh and gravel inlet filters around and along proposed catch drains and around stormwater inlets pits; and
- The construction of a temporary sediment basin as noted above.
- Stabilised site access at the construction vehicle entry/exits.

Any stockpiled material, including topsoil, shall be located as far away as possible from any associated natural watercourses or temporary overland flow paths. Sediment fences shall be installed to the downstream side of stockpiles and any embankment formation. All stockpiles and embankment formations shall be stabilised by hydroseeding or hydro mulching on formation.



Figure 12 – Sediment Fence



## 4. Bulk Earthworks

The proposed works will generally consist of earthworks cut and fill operations to establish working platform levels consistent and reflective of the design of the proposed TAFE NSW Construction Centre of Excellence. The levels are to be designed to optimise and balance cut to fill material across the site where possible. Due to the sloping nature of the site and the layout of the proposed development, the site will predominantly be in cut to cater for the proposed development. Surplus material generated from the proposed development is to be spread over existing open areas.

### 4.1 Construction Sequencing

The sequence of work for the bulk earthworks will generally include:

- Provision of site establishment erosion and sediment control measures typically outlined in this report's section Erosion & Sediment Control.
- Clearing of vegetation from the proposed development site and either removal or mulching.
- Demolition of existing structures and pavements (as required).
- Stripping and stockpiling of topsoil suitable for reuse.
- Inspection of exposed natural material to ensure conformity with design assumptions and requirements.
- Placement of cut to fill layers not greater than 200mm in thickness and compacted to not less than 98% Standard Maximum Dry Density (SMDD) in accordance with the geotechnical report; and
- Spread topsoil to a maximum depth of 200mm and hydroseed or hydro mulch disturbed areas.



## 5. Pavements

Based on the Geotechnical Investigation Report prepared by PSM dated 8th December 2020 (PSM4240-004L) a design CBR 2% has been recommended for the purposes of new pavement design subject to further testing once bulk earthworks operations have been undertaken.

Further Geotechnical Advice has been sought with regards to ground improvement methodologies to achieve CBR 3% or greater to determine new pavement profiles for the proposed development.

With consideration to traffic loading specified in the Austroads ( $5.5 \times 10^5$  ESAs – 40 Year Design Life), a proposed flexible pavement profile may be as follows:

- 50mm AC10 Wearing Course (Polymer Modified)
- 150mm DGB20 Base Course Material compacted to 98% MMDD
- 350mm DGS40 Subbase Material compacted to 98% MMDD
- Ground Improvement to achieve minimum CBR 3%.

Based on discussion with the broader project team it is understood that the existing road pavements may be utilised during the construction and operational phase of the development within the TAFE site and the adjacent Western Sydney University site.

Further Geotechnical Investigation of existing road pavement profiles will need to be undertaken to assess whether they are suitable for ongoing use during construction and operation of the facility or if upgrades are required.



## 6. Stormwater Management Strategy

### 6.1 Stormwater Quantity Management

#### 6.1.1 Stormwater Policy and Guidelines

The stormwater drainage for the proposed TAFE NSW Construction Centre of Excellence has been designed to comply with the following guidelines:

- Australian Rainfall and Runoff
- Penrith City Council's Water Sensitive Urban Design (WSUD) Policy (2013)
- Penrith City Council's WSUD Technical Guidelines (2015)
- Managing Urban Stormwater: Soils and Construction Volume 1, 4th Edition, March 2004

#### 6.1.2 Stormwater Drainage

##### 6.1.2.1 On-Site Stormwater Detention (OSD)

According to Penrith City Council's Stormwater Drainage Guidelines for Building Developments, On-site Stormwater Detention (OSD) is generally required for all types of developments in the Penrith City Council Local Government area to limit post development flows to predevelopment rates. This is typically provided on most developments to avoid nuisance flooding of downstream properties.

To control flows generated during storm events, water is stored and released at controlled rate on the development site. Storage is typically provided either of the following:

- below ground in a purpose made holding tanks; or
- above ground in landscaped basins or on the surface of hardstand areas such as car parks.

Recent discussion with Penrith City Council has indicated that the proposed development is not required to provide On-site Stormwater Detention. As such it has not been included as a feature of the proposed design. Formal correspondence from Council regarding this matter has been requested.

##### 6.1.2.2 Major / Minor Drainage System

The major/minor approach to stormwater drainage is the recognised drainage concept for urban catchments within the Penrith City Council Local Government Area

The minor drainage system is comprised of below ground pit and pipe network and is designed to control nuisance flooding and enable effective stormwater management for the site. Council requires the minor drainage system to be designed for the critical 5% Annual Exceedance Probability (AEP) with overland flow safely catering for the 1% AEP.

The major drainage system will be designed to control and convey flows from the critical 1% AEP event. This incorporates suitably designed overland flow paths and drainage to direct flows into the OSD, system for all events up to the critical 1% AEP storm event.

In accordance with Council's requirements, overland flow paths are to be designed to contain a 1% AEP storm flow are to be provided over all pipelines that are not designed to cater for this flow. The design of the overland flowpath must consider the velocity-depth hazard.

Modelling has been undertaken to establish a proposed stormwater pit and pipe network. The proposed stormwater network has been documented on civil engineering drawings presented in Appendix B.

##### 6.1.2.3 Connection to Councils Drainage System

Typically outflow pipes from stormwater drainage systems connect either directly to Council's stormwater infrastructure or utilise existing site stormwater connections within the site.

In the vicinity of the proposed development area, both Council's drainage system and any existing pipes appear to be a significant distance away. Flows generated on the site are proposed to discharge via a headwall and be conveyed overland towards the existing basin / pond.

Detailed survey will be required to determine the location and size of existing infrastructure, and where the current pond discharges to the Council stormwater network. Any existing private stormwater infrastructure will have to have condition assessment and capacity modelled before being used as part of the development.

Existing stormwater lines may need to be decommissioned, replaced or extended, and/or rerouted to a suitable connection point within the site.

Ultimately, connection points (in this case analysis of the pond and its overflow / connection) will be subject to Council review and approval following verification of additional survey information.

#### 6.1.3 Proposed System

The 12d drainage Model for the proposed site was developed based upon the following methodology

- The site pit and pipe network are proposed to discharge freely to a headwall and convey flows overland towards the existing basin.
- An indicative pit and pipe network was developed for the proposed siteworks (refer civil engineering plans for details).
- No tailwater conditions have been considered (discharge free to atmosphere).
- 70% of the roof catchment from the new building is to drain directly to rainwater harvesting tank for the 1:100-year storm event which then overflows to the piped network.
- Designs for roof drainage shall be undertaken as either conventional or siphonic drainage by a certified Hydraulic Engineer during the detail design stage of the works.
- For the purposes of modelling, the rainwater tanks are considered full during simulation.
- All paved areas are collected within grated pits and drains.
- 20yr and 100yr ARI events were considered for all standard durations; and
- For the major system (100yr ARI storm event), a conservative blockage factor of 30% has been applied to all stormwater pits within the development area in accordance with Penrith City Council's requirements.
- As part of the proposed stormwater system for the site, connections to the existing headwalls on the northern side of Block T have been proposed to drain the flows to the west of the site and discharge in direction to the pond.
- The pit DIV01\01 has been included in the design to cater for overflows of the upstream catchment on the eastern side of the site. This pit has been designed as a sag pit, with 100% blockage and the piped system convey the flows away from the building entrance, to the northern side of the site, where it discharges to.



#### **6.1.4 Results**

Iterations were performed in the 12d Drainage model to determine the size of the proposed piped network in order to satisfy major / minor system requirements in accordance with Penrith City Council standards.

The proposed piped drainage system has been designed to cater for the 1 in 20-year ARI event leading to the outlet headwall. A provision for overland flows for events greater than the 1 in 20-year ARI event has also been considered on surface not conveying the 1 in 100-year ARI event below ground.

Results indicate that the major / minor system requirements are satisfied at all proposed pits in the development area and that the piped system sufficiently conveys minor storm flows with safe provision for major system flows.



## 6.2 Stormwater Quality Management

The stormwater management system for the site shall comply with section 3.2 of Penrith City Council's Water Sensitive Urban Design Policy. Council's policy requires improved water quality of the stormwater flow from the developed site prior to discharge into the authority's drainage system.

Council also requires the removal of target pollutants from the site during the construction phase as vehicles that may enter or exit could generate various pollutants such as silt, oil and grease. These target pollutants can be identified into five major groups of stormwater pollutants:

- Gross Pollutants
- Coarse, medium, and fine sediments
- Oil and grease
- Heavy Metals and
- Nutrients

### 6.2.1 Water Quality Objectives

In accordance with section 3.2 of Penrith City Council's Water Sensitive Urban Design Policy, we note the following targets have been set in relation to stormwater quality

Table 3 – Pollutant Reduction Targets

Reduction in annual average suspended solids (SS) export load	85%
Reduction in annual average total phosphorus (TP) export load	60%
Reduction in annual average total nitrogen (TN) export load	45%
Reduction in annual average gross pollutants (GP) export load	90%

To demonstrate compliance with Penrith City Council's Water Sensitive Urban Design (WSUD) Policy (2013), treatment removal loads will be analysed from pre-to post development scenarios using MUSIC (Model for Urban Stormwater Improvement Conceptualisation) for the main building works. It should be noted that there are some smaller areas of footpaths being provided to replace existing paths through the development site which are considered periphery works not included as part of the model.

Model development and results will be provided in subsequent reports and documentation for further review incorporating a combination of various treatment devices as described below.


## 6.2.2 Proposed Treatments

Possible stormwater quality treatment devices such as StormFilter Cartridges, Ocean guard Pit Inserts and Rainwater Tanks are discussed below

### 6.2.2.1 Rainwater Tank

A 60 kL Rainwater Tank is proposed for this development in accordance with the Penrith's Council WSUD policy. The rainwater tank should be able to cater for at least 80% of the non-potable demand of the development.

The rainwater should provide water for flushing for the 34 toilets in the building. The adopted reuse rate is 0.1kL/day per toilet. As the site will only be occupied 5 days of the week, the daily reuse rate has been proportioned by 5/7, resulting in a reuse rate of 2.428kL/day.



	Flow (ML/yr)	TSS (kg/yr)	TP (kg/yr)	TN (kg/yr)	GP (kg/yr)
<b>Flow In</b>	2.99	77.25	0.46	6.65	83.83
<b>ET Loss</b>	0.00	0.00	0.00	0.00	0.00
<b>Infiltration Loss</b>	0.00	0.00	0.00	0.00	0.00
<b>Low Flow Bypass Out</b>	0.00	0.00	0.00	0.00	0.00
<b>High Flow Bypass Out</b>	0.00	0.00	0.00	0.00	0.00
<b>Pipe Out</b>	1.03	21.82	0.15	2.20	0.00
<b>Weir Out</b>	1.25	27.26	0.19	2.70	0.00
<b>Transfer Function Out</b>	0.00	0.00	0.00	0.00	0.00
<b>Reuse Supplied</b>	0.71	9.85	0.10	1.33	0.00
<b>Reuse Requested</b>	0.88	0.00	0.00	0.00	0.00
<b>% Reuse Demand Met</b>	80.23	0.00	0.00	0.00	0.00
<b>% Load Reduction</b>	23.90	36.47	26.73	26.35	100.00

Figure 13: Node Water Balance Results

### 6.2.2.2 Stormfilter Cartridges

Filtration cartridges in the form of Stormfilters are to be provided as an end of line treatment device to treat stormwater runoff from the proposed development. The Stormfilter system targets a full range of pollutants including total suspended solids, soluble heavy metals, oil and grease and total nutrients. Each cartridge has a treatable flow rate of 1~1.6L/s and is designed to capture and treat the first flush volume of a rainfall event.

In developing the MUSIC model for the proposed works, an offline 12 x 690mm cartridge system by Ocean Protect has been proposed as an end of line treatment prior to discharge. The position of the Stormfilter units have been proposed to maximise flows and allow easy access for maintenance.



### 6.2.2.3 Ocean Guard Pit Inserts

Surface Inlet Pits within the development area have been designed to be provided with Ocean Guard Pit Inserts including oil absorbent media. The pit inserts will sit beneath the stormwater pit grates and will collect gross pollutants and larger sediments prior to treatment by the Stormfilter cartridges.




Figure 14 (Left) – Stormfilter Cartridge System, Figure 14 (Right) – Stormwater Pit Litter Basket Insert

### 6.2.3 Water Quality Modelling – MUSIC Model, Parameters and Methodology

A water quality modelling tool, MUSIC was utilised to simulate urban stormwater systems operating at a range of temporal and spatial scales. MUSIC Models the total amount of gross pollutants and nutrients produced within various types of catchments. It allows the user to simulate the removal rates expected with implementing removal filters to reduce the increased gross pollutant and nutrient levels created by the proposed development.

The following methodology and parameters were incorporated in the MUSIC Modelling

- The MUSIC model was created to assess the effectiveness of water quality nodes which are to be constructed as part of the proposed development
- In accordance with Council's requirements Penrith MUSIC link and standard nodes have been used in the model.
- A Music Model was established to represent the post-developed site. From architectural plans, the site was then categorized into the following areas
  - Roof
  - Road
  - Hardstand
  - Landscape

A treatment train was designed to incorporate a series of treatment nodes including a Rainwater Tank, Stormfilter Cartridges, Ocean Guard Pit Inserts The effectiveness of the proposed treatments is summarised below.

### 6.2.4 Results

The following results were achieved in the model

Table 4 – Ocean Guard MUSIC Input Parameters (upstream of Stormfilter)

Pollutant	Post-Development with no WSUD measures (kg/yr.)	Post-Development with WSUD measures (kg/yr.)	Removal Rate (%)	Target Removal Rate (%)
Suspended Solids (mg/L)	907	126	85.6	85
Phosphorus (mg/L)	1.91	0.702	61.9	60
Nitrogen (mg/L)	16.7	9.12	45	45
Gross Pollutants (kg/ML)	183	0	100	90

Results of the MUSIC analysis indicate that the proposed treatment train consisting of a 60kL Rainwater Tank, 12 x Stormfilter Cartridges and 16 x Ocean Guard Pit Inserts generally satisfies Council's statutory requirements for target pollutant removal rates.




Figure 15 – MUSIC Model and Results



## 7. Conclusion


In summary, the requirements for the proposed development are as follows:

- Stormwater Infrastructure – OSD storage is not required based on discussion with Penrith City Council. Water Quality measures will be required for the proposed development. Water quality treatment is achieved using a rainwater tank, propriety filter cartridge devices and pit insert baskets.
- On-going maintenance of water quality and quantity systems will be required for the development. As the design for the proposed development is progressed, information regarding on-going maintenance costs will be considered by the Project Team to ensure systems are financially feasible for the operational life of the development.
- Development runoff is generally distributed to suit the drainage direction of existing catchment areas. On this basis, stormwater from the proposed development is proposed to drain towards the existing pond / basin to the north west before discharge to the creek in direction to the Great Western Highway.

## Appendix A – MUSIC Catchment Plan



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:



LEGEND	
	LIMIT OF WORKS
	LANDSCAPED AREA = 134.79m <sup>2</sup>
	ROOF = 7227 m <sup>2</sup>
	FOOTPATH = 1425 m <sup>2</sup>
	ROAD = 1846 m <sup>2</sup>
	BYPASS AREA = 824m <sup>2</sup>
	LANDSCAPE AREA DRAINING TO UPSTREAM CATCHMENT PIT= 1069m <sup>2</sup>

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
1	ISSUED FOR INFORMATION	AC	SH	JG	04.03.21

CLIENT


 

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS  
VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT


**GRAY PUKSAND**

THE COPYRIGHT OF THIS DRAWING REMAINS WITH  
NORTHROP CONSULTING ENGINEERS PTY LTD



ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE  
COMMENCING WORK.  
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE  
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS  
TRANSFERRED ELECTRONICALLY.  
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,  
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:500@A1





Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email [sydney@northrop.com.au](mailto:sydney@northrop.com.au) ABN 81 094 433 100

PROJECT

**TAFE NSW CONSTRUCTION  
CENTRE OF EXCELLENCE**

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE**

**CATCHMENT PLAN**

JOB NUMBER

**202025**

DRAWING NUMBER	REVISION
<b>DAC04.51</b>	<b>1</b>

DRAWING SHEET SIZE = A1



## Appendix B – Engineering Plans



PROPOSED SITE

TAFE NSW





HILLSONG CHURCH

GREAT WESTERN HIGHWAY

SOURCE : NEARMAP.COM.AU (©2021)

DWG No.	DRAWING TITLE
DAC01.01	COVER SHEET, DRAWING SCHEDULE AND LOCALITY PLAN
DAC01.11	SPECIFICATION NOTES
DAC02.01	SEDIMENT AND SOIL EROSION CONTROL PLAN
DAC02.11	SEDIMENT AND SOIL EROSION CONTROL DETAILS
DAC03.01	BULK EARTHWORKS CUT TO FILL PLAN
DAC04.01	SEWERWORKS AND STORMWATER MANAGEMENT PLAN
DAC04.21	STORMWATER LONGITUDINAL SECTIONS - SHEET 01
DAC04.22	STORMWATER LONGITUDINAL SECTIONS - SHEET 02
DAC04.23	STORMWATER LONGITUDINAL SECTIONS - SHEET 03
DAC04.24	STORMWATER LONGITUDINAL SECTIONS - SHEET 04
DAC04.25	STORMWATER LONGITUDINAL SECTIONS - SHEET 05
DAC04.51	STORMWATER CATCHMENT PLAN
DAC04.61	STORMWATER MANAGEMENT DEVICES

DRAWN: C. PASKE      DESIGNED: J. GRINSELL      JOB MANAGER: J. GILLIGAN      VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT	PROJECT	DRAWING TITLE	JOB NUMBER	
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21	 	 <b>GRAY PUKSAND</b>	 <b>NORTHROP</b> Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	<b>TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE</b>	<b>CIVIL ENGINEERING PACKAGE</b>	<b>202025</b>
2	ISSUED FOR INFORMATION	TB		JG	04.03.21						
									<b>COVER SHEET, DRAWING SCHEDULE AND LOCALITY PLAN</b>	DRAWING SHEET SIZE = A1	



NOTE: ALL CIVIL ENGINEERING CONSTRUCTION WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PENRITH CITY COUNCIL DEVELOPMENT GUIDELINES .THE AFOREMENTIONED GUIDELINES INCLUSIVE OF ALL SPECIFICATIONS TAKE PRECEDENCE OVER NOTES PROVIDED BELOW.

STORMWATER DRAINAGE
<div>1. ALL DRAINAGE LINES SHALL BE UPVC (CLASS SN4) SEWER GRADE DRAINAGE PIPE, U.N.O.</div> <div>2. ALL DRAINAGE LINES SHALL BE LAID AT 1% MIN. FALL, UNO.</div> <div>3. ALL LEVELS ARE AUSTRALIAN HEIGHT DATUM (AHD).</div> <div>4. ALL DOWNPIPES GUTTERS TO BE DESIGNED IN ACCORDANCE WITH AS/NZS 3500.3.2 – 2003 'STORMWATER' DRAINAGE.</div> <div>5. THE STORMWATER DRAINAGE DESIGN HAS BEEN CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500.3.2-2003 'STORMWATER' DRAINAGE.</div> <div>6. ANY VARIATIONS TO THE NOMINATED LEVELS SHALL BE REFERRED TO ENGINEER IMMEDIATELY.</div> <div>7. SUBSOIL DRAINAGE SHALL BE PROVIDED TO ALL RETAINING WALLS &amp; EMBANKMENTS, WITH THE LINES FEEDING INTO THE STORMWATER DRAINAGE SYSTEM.</div> <div>8. ALL GRATES TO BE GALVANISED STEEL WITH HINGES AND CHILD PROOF LOCK.</div> <div>9. ALL GRATES TO BE HEEL SAFE WITHIN AGED CARE DEVELOPMENTS.</div> <div>10. THE STORMWATER DRAINAGE IS DESIGNED IN ACCORDANCE WITH PENRITH CITY COUNCIL DEVELOPMENT GUIDELINES.</div>

RAINWATER RE-USE
<div>1. PROVIDE RAINWATER RE-USE SYSTEM TO SUPPLY WATER FOR TOILET FLUSHING.</div> <div>2. GUTTER GUARD TO BE INSTALLED ON ALL EAVES GUTTERS.</div> <div>3. A PERMANENT SIGN IS TO BE LOCATED IN THE VICINITY OF THE TANK STATING THE WATER IS "NON POTABLE WATER" WITH APPROPRIATE HAZARD IDENTIFICATION.</div> <div>4. PIPEWORK USED FOR RAINWATER SERVICES SHALL BE COLOURED LILAC IN ACCORDANCE WITH AS1345.</div> <div>5. ALL VALVES AND APERTURES SHALL BE CLEARLY AND PERMANENTLY LABELLED WITH SAFETY SIGNS TO COMPLY WITH AS1319.</div> <div>6. RAINWATER TANK RETICULATION SYSTEM AND MAINS WATER BYPASS ARRANGEMENT TO BE INSTALLED IN ACCORDANCE WITH AS/NZS 3500.1.2-2003 AND THE NSW CODE OF PRACTICE : PLUMBING AND DRAINING.</div> <div>7. A FIRST FLUSH FILTRATION DEVICE IS TO BE PROVIDED AT RAINWATER TANK.</div>

GENERAL NOTES
<div>THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH OTHER SUCH WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.</div> <div>ALL DIMENSIONS ARE IN MILLIMETRES &amp; ALL LEVELS ARE IN METRES, UNO (UNLESS NOTED OTHERWISE).</div> <div>NO DIMENSION SHALL BE OBTAINED BY SCALING THE DRAWINGS.</div> <div>ALL LEVELS AND SETTING OUT DIMENSIONS SHOWN ON THE DRAWINGS SHALL BE CHECKED ON SITE PRIOR TO THE COMMENCEMENT OF THE WORK.</div> <div>DETAIL SURVEY DATA WAS SUPPLIED BY RYGATE &amp; COMPANY PTY LIMITED, DRAWING DATED 17/12/20.</div> <div>EXISTING SERVICES WHERE SHOWN HAVE BEEN PLOTTED FROM SUPPLIED DATA AND SUCH THEIR ACCURACY CAN NOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF WORK.</div> <div>ON COMPLETION OF STORMWATER INSTALLATION, ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL CONDITION, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD PAVEMENTS, UNLESS DIRECTED OTHERWISE.</div>

ALL STORMWATER MANAGEMENT MEASURES SHOWN ON THIS DRAWING HAVE BEEN PREPARED FOR DEVELOPMENT APPLICATION PURPOSES TO DEMONSTRATE FEASIBILITY. ALL MEASURES WILL BE SUBJECT TO DETAIL DESIGN AT THE CONSTRUCTION CERTIFICATE STAGE AND MAY BE SUBJECT TO VARIATION PROVIDED THAT THE DESIGN INTENT IS MAINTAINED.
---




SEDIMENT AND SOIL EROSION
<div>1. THE SEDIMENT &amp; EROSION CONTROL PLAN PRESENTS CONCEPTS ONLY. THE CONTRACTOR SHALL AT ALL TIMES BE RESPONSIBLE FOR THE ESTABLISHMENT &amp; MANAGEMENT OF A DETAILED SCHEME MEETING COUNCILS AND OTHER REGULATORY AUTHORITY REQUIREMENTS AND MAKE PAYMENT OF ALL FEES.</div> <div>2. THE CONTRACTOR SHALL INSTIGATE ALL SEDIMENT AND EROSION CONTROL MEASURES IN ACCORDANCE WITH STATUTORY REQUIREMENTS AND IN PARTICULAR THE 'BLUE BOOK' (MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION), PRODUCED BY THE DEPARTMENT OF HOUSING AND COUNCIL'S POLICIES. THESE MEASURES ARE TO BE INSPECTED AND MAINTAINED ON A DAILY BASIS.</div> <div>3. THE CONTRACTOR SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS INSTRUCTED IN THE DRAWINGS AND ADHERE TO ALL REGULATORY AUTHORITY REQUIREMENTS.</div> <div>4. THE CONTRACTOR SHALL INFORM ALL SUB CONTRACTORS OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSTREAM LANDS AND WATERWAYS.</div> <div>5. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE SHALL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE;<div>5.1.CONSTRUCT TEMPORARY STABILISED SITE ACCESS INCLUSIVE OF SHAKE DOWN / WASH PAD.</div><div>5.2.INSTALL ALL TEMPORARY SEDIMENT FENCES AND BARRIER FENCES. WHERE FENCES ADJACENT EACH OTHER, THE SEDIMENT FENCE CAN BE INCORPORATED INTO THE BARRIER FENCE.</div><div>5.3.INSTALL SEDIMENT CONTROL MEASURES AS OUTLINED ON THE APPROVED PLANS.</div></div> <div>6. UNDERTAKE SITE DEVELOPMENT WORKS SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF MINIMUM WORKABLE SIZE.</div> <div>7. AT ALL TIMES AND IN PARTICULAR DURING WINDY AND DRY WEATHER, LARGE UNPROTECTED AREAS WILL BE STABILISED / KEPT MOIST (NOT WET) TO KEEP DUST UNDER CONTROL ENSURING CONFORMITY TO REGULATORY AUTHORITY REQUIREMENTS.</div> <div>8. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) SHALL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.</div> <div>9. WATER SHALL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN STABILISED AND/OR ANY LIKELY SEDIMENT BEEN FILTERED OUT.</div> <div>10. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES SHALL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE STABILISED / REHABILITATED.</div> <div>11. ALLOW FOR GRASS STABILISATION OF EXPOSED AREAS, OPEN CHANNELS AND ROCK BATTERS DURING ALL PHASES OF CONSTRUCTION.</div> <div>12. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED TO ENSURE THAT THEY OPERATE EFFECTIVELY. REPAIRS AND/OR MAINTENANCE SHALL BE UNDERTAKEN REGULARLY AND AS REQUIRED, PARTICULARLY FOLLOWING RAIN EVENTS.</div> <div>13. RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER SHALL BE DISPOSED OF IN ACCORDANCE WITH REGULATORY AUTHORITY REQUIREMENTS. CONTRACTOR TO PAY ALL FEES AND PROVIDE EVIDENCE OF SAFE DISPOSAL.</div> <div>14. IF A TEMPORARY SEDIMENT BASIN IS REQUIRED, ENSURE SAFE BATTER SLOPES IN ACCORDANCE WITH THE GEOTECHNICAL REPORT. MAINTAIN ADEQUATE STORAGE VOLUME IN ACCORDANCE WITH PLANS. TEMPORARY PUMP 'CLEAN FLOCCULATED' WATER TO AUTHORITIES STORMWATER SYSTEM. ENSURE WHOLE DISTURBED SITE RUN-OFF IS DIRECTED TO TEMPORARY SEDIMENT BASIN.</div>

VERIFIER:

JOB MANAGER: J. GILLIGAN

DESIGNED: J. GRINSELL


DRAWN: C.PASKE

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT		PROJECT	DRAWING TITLE	JOB NUMBER	
01	ISSUED FOR INFORMATION	TB		JG	04.03.21	<div><div></div><div></div></div>	GRAY PUKSAND	<div>ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK &amp; WHITE.</div>	<div><div>Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100</div></div>	TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE	CIVIL ENGINEERING PACKAGE	202025
										SPECIFICATION NOTES	DRAWING NUMBER	REVISION
											DAC01.11	01
												DRAWING SHEET SIZE = A1
						DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED	THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD					

NOT FOR CONSTRUCTION



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:



LEGEND	
	PROPOSED BOUNDARY LINE
	EXISTING BOUNDARY LINE
	EXISTING CONTOURS
	SEDIMENT FENCE
	SECURITY FENCE
	MESH AND GRAVEL INLET FILTER
	GEOTEXTILE INLET FILTER
	STABILISED SITE ACCESS
	STOCKPILE
	SEDIMENT BASIN
	TEMPORARY SWALE

SITE PARAMETERS	
CONSTRAINT	VALUE
TOTAL DISTURBED AREA (Ha)	2.5
SOIL TEXTURE GROUP	F
DESIGN RAINFALL DEPTH (DAYS)	5.0
DESIGN RAINFALL DEPTH (PERCENTILE)	80.0
X-DAY,Y-PERCENTILE RAINFALL EVENT	27.4
Cv	0.4
SETTLING ZONE VOLUME (m³)	288
SEDIMENT STORAGE VOLUME (m³)	144
TOTAL BASIN VOLUME (m³)	432

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
2	ISSUED FOR INFORMATION	TB		JG	04.03.21

CLIENT


 

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED


ARCHITECT

**GRAY PUKSAND**

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

 ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:500@A1



 **NORTHROP**

Sydney

Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

**TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE**

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE**

**SEDIMENT AND SOIL EROSION CONTROL PLAN**

JOB NUMBER

**202025**

DRAWING NUMBER


**DAC02.01**

REVISION

**2**

DRAWING SHEET SIZE = A1






The image contains two technical drawings of a star picket fence system:

- SECTION DETAIL:** A cross-sectional view of the fence. It shows a vertical post (15m STAR PICKETS AT MAX 2.5m CENTRES) embedded in a trench. The trench is filled with compacted backfill and rock, set into surface concrete. A self-supporting geotextile is shown behind the post. The flow direction is indicated by an arrow pointing right. Dimensions include a trench depth of 600 to 600 mm and a minimum depth of 600 mm.
- PLAN:** A top-down view of the fence line. It shows the fence posts (15m STAR PICKETS AT MAX 2.5m CENTRES) and the flow direction (FLOW). The fence is shown separating a disturbed area (hatched) from an undisturbed area (dotted). Dimensions include a maximum length of 20m (UNLESS STATED OTHERWISE ON SWMP/ESCP) and a minimum width of 1.5m.

1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
3. DRIVE 15 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.
6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.




The diagram is divided into two parts: a cross-sectional view of the drop inlet structure and a plan view of its application in a waterway.

**Cross-sectional view (top):** This view shows the internal structure of the drop inlet. It features a rectangular frame with a grid of "STAR PICKETS" on the sides, with a maximum width of "1 METRE MAX.". The top is covered by a "WIRE OR STEEL MESH (14 GAUGE x 150mm OPENINGS) WHERE GEOTEXTILE IS NOT SELF-SUPPORTING". The bottom is lined with a "WOVEN GEOTEXTILE". A "DROP INLET WITH GRATE" is shown at the top right.

**Plan view (bottom):** This view shows the drop inlet installed in a "WATERWAY". The inlet is represented by a rectangular structure with a grid pattern. It is flanked by "SANDBAGS" and an "EXCAVATION". The "EARTH BANK" is shown on the left. Arrows indicate the "FLOW" direction. A detailed inset on the right shows a "STAR PICKET FITTED WITH SAFETY CAP" driven into the ground. The "WOVEN GEOTEXTILE" is shown as a layer above the ground, and the "GEOTEXTILE EMBEDDED 150mm INTO GROUND" is shown below it. "RUNOFF WATER WITH SEDIMENT" flows into the inlet, and "FILTERED WATER" is shown exiting the bottom.

**Text at the bottom:** FOR DROP INLETS AT NON-SAG POINTS, SANDBAGS, EARTH BANK OR EXCAVATION USED TO CREATE ARTIFICIAL SAG POINT




1. FABRICATE A SEDIMENT BARRIER MADE FROM GEOTEXTILE OR STRAW BALES.
2. FOLLOW STANDARD DRAWING 6-7 AND STANDARD DRAWING 6-8 FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC. REDUCE THE PICKET SPACING TO 1 METRE CENTRES.
3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS SHOWN IN THE DRAWING.
4. DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS TO BYPASS IT.




2. REMOVE ALL VEGETATION AND TOPSOIL FROM UNDER THE DAM WALL AND FROM WITHIN THE STORAGE AREA.
3. CONSTRUCT A CUT-OFF TRENCH 500mm DEEP AND 1200mm WIDE ALONG THE CENTRELINE OF THE EMBANKMENT EXTENDING TO A POINT ON THE GULLY WALL LEVEL WITH THE RISER CREST.
3. MAINTAIN THE TRENCH FREE OF WATER AND RECOMPACT THE MATERIALS WITH EQUIPMENT AS SPECIFIED IN THE SWMP TO 95 PER CENT STANDARD PROCTOR DENSITY.
4. SELECT FILL FOLLOWING THE SWMP THAT IS FREE OF ROOTS, WOOD, ROCK, LARGE STONE OR FOREIGN MATERIAL.
5. PREPARE THE SITE UNDER THE EMBANKMENT BY RIPPING TO AT LEAST 100mm TO HELP BOND COMPACTED FILL TO THE EXISTING SUBSTRATE.
6. SPREAD THE FILL IN 100mm TO 150mm LAYERS AND COMPACT IT AT OPTIMUM MOISTURE CONTENT FOLLOWING THE SWMP.
7. CONSTRUCT THE EMERGENCY SPILLWAY.
8. REHABILITATE THE STRUCTURE FOLLOWING THE SWMP.

DRAWN: C. PASKE      DESIGNED: J. GRINSELL      JOB MANAGER: J. GILLIGAN      VERIFIER:

GEOTEXTILE INLET FILTER (SD 6-12)

REVISION		DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT		ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF LOADED TO BLACK & WHITE	PROJECT	DRAWING TITLE	JOB NUMBER			
01		ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21	 	GRAY PUKSAND	 Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE	CIVIL ENGINEERING PACKAGE	202025				
2		ISSUED FOR INFORMATION	TB		JG	04.03.21									DRAWING NUMBER	REVISION
															DAC02.11	2
															DRAWING SHEET SIZE = A1	
DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED.							THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD.		NOT TO SCALE	SEDIMENT AND SOIL EROSION CONTROL DETAILS						





**LEGEND**

PROPOSED BOUNDARY LINE

EXISTING BOUNDARY LINE

•

BEXX.XX

BULK EARTHWORKS SPOT HEIGHT

+ eRLXX.XX

EXISTING SPOT HEIGHT

BEXX.XX

BULK EARTHWORKS PAD LEVEL

X.X

DIRECTION OF GRADE

BATTERS

XX.XX

CONTOURS

**DEPTH OF CUT**

	- 99m	TO	- 15m
	- 15m	TO	- 10m
	- 10m	TO	- 5m
	- 5m	TO	- 2m
	- 2m	TO	- 1m
	- 1m	TO	- 0.5m
	- 0.5m	TO	- 0.25m
	- 0.25m	TO	- 0.0m

**DEPTH OF FILL**

	0.0m	TO	0.25m
	0.25m	TO	0.5m
	0.5m	TO	1m
	1m	TO	2m
	2m	TO	5m
	5m	TO	10m
	10m	TO	15m
	15m	TO	99m

**GENERAL NOTES:**

1.

ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL / RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS.

2.

CAD FILES / DTM FILES TO BE SUPPLIED IN AUTOCAD FORMAT FOR SETOUT PURPOSES (UPON REQUEST).

3.

NO ALLOWANCE HAS BEEN MADE FOR BULKING FACTORS. NOTE ALL VOLUMES DEPICTED ARE SOLID VOLUMES ONLY AND MAY NOT REFLECT DETAILED EARTHWORKS.

4.

NO ALLOWANCE HAS BEEN MADE FOR DETAILED EARTHWORKS, ie SERVICE TRENCHING, DETAILED EXCAVATION, FOOTINGS, RETAINING WALLS AND THE LIKE. CONTRACTOR IS TO ALLOW FOR REMOVAL OF ALL EXCESS MATERIAL GENERATED BY THE WORKS.

5.

THE CONTRACTOR SHALL USE FINAL SURFACE LEVELS AND TYPICAL PAVEMENT DETAILS FOR ACTUAL EARTHWORKS LEVELS.

6.

BULK EARTHWORKS ARE BASED ON THE FOLLOWING DEPTHS FROM FINISHED SURFACE LEVELS;

6.1.

LANDSCAPE AREA

200mm

6.2.

BUILDING SLAB

300mm (REFER STRUCTURAL DWGS)

6.3.

FOOTPATH PAVEMENT

150mm

6.4.

ROAD PAVEMENT

520mm

6.5.

SAND PIT

2300mm

7.

APPROXIMATE BULK EARTHWORK VALUES AS FOLLOWS;

7.1.

CUT

15 916 cu.m

7.2.

FILL

9 569 cu.m

7.3.

BALANCE

6 347 cu.m (EXCESS CUT OVER FILL)

7.4.

NOTE: A SITE STRIP OF 200mm HAS BEEN CONSIDERED. APPROX VOLUME 5,174cu.m.

NOT FOR CONSTRUCTION

DRAWN: C PASKE  
DESIGNED: J GRINSELL  
JOB MANAGER: J GILLIGAN  
VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
2	ISSUED FOR INFORMATION	TB		JG	04.03.21

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

GRAY PUKSAND

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.  
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.  
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:500@A1

Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

TAFE NSW CONSTRUCTION  
CENTRE OF EXCELLENCE

DRAWING TITLE

CIVIL ENGINEERING PACKAGE

BULK EARTHWORKS CUT TO FILL  
PLAN

JOB NUMBER

202025

DRAWING NUMBER

DAC03.01


REVISION

2

DRAWING SHEET SIZE = A1



VERIFIER: J. GILLIGAN  
JOB MANAGER: J. GRINSELL  
DESIGNED: J. GRINSELL  
DRAWN: C. PASKE



LEGEND	
	PROPOSED BOUNDARY LINE
	EXISTING BOUNDARY LINE
	PROPOSED KERB
	EXISTING KERB
	SAWCUT AND PAVEMENT INFILL
	KO KERB ONLY
	KG KERB AND GUTTER
	IK INTEGRAL KERB
	DD DISH DRAIN
	VC VEHICULAR CROSSING
	KR KERB RAMP
	WS WHEEL STOP
	MTE MATCH TO EXISTING
	RLXX.XX PROPOSED SPOT HEIGHT
	eRLXX.XX EXISTING SPOT HEIGHT
	FFLXX.XX PROPOSED FINISHED FLOOR LEVEL
	BATTERS
	CONTOURS
	EXISTING CONTOURS
	DRAINAGE SWALE
	DRAINAGE STRUCTURE WITH EXTENDED CHAMBER (NEW / EXTG)
	GRATED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	JUNCTION PIT (NEW / EXTG)
	1 A STORMWATER PIT TAG STRUCTURE No / LINE ID
	ROCK HEADWALL

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
02	ISSUED FOR INFORMATION - 100%	AC		JG	04.03.21

CLIENT

GRAY PUKSAND

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ARCHITECT

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:500@A1

0 5 10 15 20 25m

PROJECT

**TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE**

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE**

**SITWORKS AND STORMWATER MANAGEMENT PLAN**

JOB NUMBER

**202025**

DRAWING NUMBER

**DAC04.01**

REVISION

**02**


DRAWING SHEET SIZE = A1



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:

PIPE CLASS  
PIPE GRADE (%)  
PIPE SIZE (mm)  
MINIMUM COVER (m)  
Vf - FULL PIPE VELOCITY (m/s)  
Q - PIPE FLOW (L/s)

DATUM RL	47.0
H.G.L. (5% AEP)	54.204
FINISHED SURFACE	56.256
NATURAL SURFACE	57.599
PIPE INVERT LEVEL	54.186
DEPTH TO INVERT	2.071
CO-ORDINATED SETOUT	0.000 E290704.269 N6261488.224
CHAINAGE	0.000



LINE 01

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
2	ISSUED FOR INFORMATION	TB		JG	04.03.21



CLIENT

GRAY PUKSAND

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS  
VERIFICATION SIGNATURE HAS BEEN ADDED


ARCHITECT

GRAY PUKSAND

THE COPYRIGHT OF THIS DRAWING REMAINS WITH  
NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE  
COMMENCING WORK.  
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE  
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS  
TRANSFERRED ELECTRONICALLY.  
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,  
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE

SCALE 1:250 @ A1  
SCALE 1:100 @ A1



**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email [sydney@northrop.com.au](mailto:sydney@northrop.com.au) ABN 81 094 433 100

PROJECT

TAFE NSW CONSTRUCTION  
CENTRE OF EXCELLENCE

DRAWING TITLE

CIVIL ENGINEERING PACKAGE  
  
STORMWATER LONGITUDINAL  
SECTIONS - SHEET 01

JOB NUMBER  
202025

DRAWING NUMBER  
DAC04.21

REVISION  
2

DRAWING SHEET SIZE = A1



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:

PIPE CLASS  
PIPE GRADE (%)  
PIPE SIZE (mm)  
MINIMUM COVER (m)  
Vf - FULL PIPE VELOCITY (m/s)  
Q - PIPE FLOW (L/s)

DATUM RL	40.0
H.G.L. (5% AEP)	48.109 48.109 47.855
FINISHED SURFACE	48.563
NATURAL SURFACE	48.828
PIPE INVERT LEVEL	47.255 47.205
DEPTH TO INVERT	1.308 1.358
CO-ORDINATED SETOUT	E290634.847 N6261584.008
CHAINAGE	157.442

LINE 01

01\08  
900x900 G.SIP SAG EXT. CH  
-61°  
LINE 03: 120°  
HW OUTLET

47.747 47.747
47.794
47.794
46.918 46.918
0.876 0.876
E290661.607 N6261601.551
186.616

02\01  
G.G.P. 18m E.K.I.

53.244 53.100
53.789
54.616
52.973
0.816
N6261481.686
0.000

02\02  
G.SIP 900x900 1m GRASS SWALE  
-103°

53.028 53.017
53.955
55.092
52.905 52.855
1.050 1.100
E290661.612 N6261474.815
7.569

LINE 02

02\03  
G.SIP 900x900 1m GRASS SWALE  
-40°

52.713 52.557
53.162
55.749
52.500 52.416
0.662 0.746
E290674.722 N6261487.184
27.183

01\03  
G.SIP 900x900 1m GRASS SWALE  
LINE 01

52.348 51.964
52.966
55.583
52.147 51.806
0.819 1.159
E290677.696 N6261492.076
32.175

03\01  
G.SIP 900x900 1m GRASS SWALE

55.366 55.346
56.134
56.043
55.303
0.831
E290748.773 N6261622.789
0.000

LINE 03

03\02  
G.SIP 900x900 1m GRASS SWALE  
-35°

50.490 50.486
51.244
51.750
50.434
0.810
E290699.312 N6261653.734
58.422

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
02	ISSUED FOR INFORMATION	AC		JG	04.03.21



THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD


ARCHITECT

GRAY PUKSAND

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250 @ A1  
SCALE 1:100 @ A1





Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE

DRAWING TITLE

CIVIL ENGINEERING PACKAGE

STORMWATER LONGITUDINAL SECTIONS - SHEET 02

JOB NUMBER

202025

DRAWING NUMBER

DAC04.22

REVISION

02

DRAWING SHEET SIZE = A1



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:

PIPE CLASS  
PIPE GRADE (%)  
PIPE SIZE (mm)  
MINIMUM COVER (m)  
Vf - FULL PIPE VELOCITY (m/s)  
Q - PIPE FLOW (L/s)

DATUM RL	42.0
H.G.L. (5% AEP)	50.490 50.486 50.462
FINISHED SURFACE	51.244
NATURAL SURFACE	51.750
PIPE INVERT LEVEL	50.434 50.384
DEPTH TO INVERT	0.810 0.860
CO-ORDINATED SETOUT	E290699.312 N6261653.734
CHAINAGE	58.422

LINE 03

03\03

G.S.I.P. 900x900 1m GRASS SWALE  
-70°

03\04

G.S.I.P. 900x900 1m GRASS SWALE  
-9°

01\08

900x900 G.S.I.P. SAG EXT. CH.  
LINE 01

04\01

G.S.I.P. 600x600 1m GRASS SWALE

04\02

G.G.P. 18m E.K.I. EXT. CH.  
1°  
LINE 05 -102°  
LINE DP01: 66°

01\05

600x900 G.S.I.P. SAG EXT. CH.  
LINE 01

LINE 04

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION - 50%	CP		JG	29.01.21
02	ISSUED FOR INFORMATION	AC		JG	04.03.21



GRAY PUKSAND



DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS  
VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

THE COPYRIGHT OF THIS DRAWING REMAINS WITH  
NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE  
COMMENCING WORK.  
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE  
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS  
TRANSFERRED ELECTRONICALLY.  
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,  
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250 @ A1  
SCALE 1:100 @ A1





Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

TAFE NSW CONSTRUCTION  
CENTRE OF EXCELLENCE

DRAWING TITLE

CIVIL ENGINEERING PACKAGE  
  
STORMWATER LONGITUDINAL  
SECTIONS - SHEET 03


JOB NUMBER  
202025




DRAWING NUMBER  
DAC04.23

REVISION  
02

DRAWING SHEET SIZE = A1





REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT	ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE	PROJECT	DRAWING TITLE	JOB NUMBER
01	ISSUED FOR INFORMATION - 50%		CP	JG	29.01.21	 	<b>GRAY PUKSAND</b>	 <p>Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100</p>	<b>TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE</b>	<b>CIVIL ENGINEERING PACKAGE</b>  <b>STORMWATER LONGITUDINAL SECTIONS - SHEET 04</b>	<b>202025</b>
02	ISSUED FOR INFORMATION		AC	JG	04.03.21						
								SCALE 1:250 @ A1 SCALE 1:100 @ A1			DRAWING SHEET SIZE = A1



DRAWN: C. PASKE  
DESIGNED: J. GRINSELL  
JOB MANAGER: J. GILLIGAN  
VERIFIER:

PIPE CLASS  
PIPE GRADE (%)  
PIPE SIZE (mm)  
MINIMUM COVER (m)  
Vf - FULL PIPE VELOCITY (m/s)  
Q - PIPE FLOW (L/s)

DATUM RL		48.0					
H.G.L. (5% AEP)	56.182	56.182					
FINISHED SURFACE	57.116						
NATURAL SURFACE	57.063						
PIPE INVERT LEVEL	55.861	55.811					
DEPTH TO INVERT	1.255	1.305					
CO-ORDINATED SETOUT	E290665.673	N626144.6471					
CHAINAGE	20.128						

LINE DIV02

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION	AC		JG	04.03.21



GRAY PUKSAND

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250 @ A1

SCALE 1:100 @ A1





Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE

DRAWING TITLE

CIVIL ENGINEERING PACKAGE

MINOR STORMWATER LONGITUDINAL SECTIONS - SHEET 04

JOB NUMBER

202025

DRAWING NUMBER	REVISION
DAC04.25	01

DRAWING SHEET SIZE = A1









900 SQUARE CAST-IRON SOLID  
TOP ACCESS COVER SUPPLIED  
LOOSE  
(OR CAST INTO LID IF  
REQUIRED)

SECTION A-A

DRAWN: C. PASKE      DESIGNED: J. GRINSELL      JOB MANAGER: J. GILLIGAN      VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT		PROJECT	DRAWING TITLE	JOB NUMBER
01	ISSUED FOR INFORMATION	TB		JG	04.03.21	  <b>GRAY PUKSAND</b>	 <b>Northrop Sydney</b> Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	<div>ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK &amp; WHITE</div>	<b>TAFE NSW CONSTRUCTION CENTRE OF EXCELLENCE</b>	<b>CIVIL ENGINEERING PACKAGE</b>	<b>202025</b>
						DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED	THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD			<b>STORMWATER MANAGEMENT DEVICES</b>	<div>DRAWING NUMBER <b>DAC04.61</b></div> <div>REVISION <b>01</b></div> <div>DRAWING SHEET SIZE = A1</div>






LEGEND	
	EXISTING BOUNDARY LINE
	PROPOSED KERB
	EXISTING KERB
	FUTURE KERB
	SAWCUT AND PAVEMENT INFILL
	KERB AND GUTTER
	VEHICULAR CROSSING
	EXISTING CONTOURS
	STORMWATER PIPE
	GRADED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	JUNCTION PIT (NEW / EXTG)
	GRADED TRENCH DRAIN
	PROPOSED FLEXIBLE PAVEMENT
	PROPOSED DRIVEWAY PAVEMENT


01	ISSUED FOR INFORMATION	TB	JG	02.03.20
02	ISSUED FOR INFORMATION	TB	JG	03.03.20

CLIENT




ARCHITECT





ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.  
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.  
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:200@A1





Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email [sydney@northrop.com.au](mailto:sydney@northrop.com.au) ABN 81 094 433 100

TAFE - WESTERN SYDNEY  
CONSTRUCTION HUB

CIVIL ENGINEERING PACKAGE


PROPOSED ACCESS WAY

202025

SKC01.21 02



DRAWN: M. MAI  
DESIGNED: J. GILLIGAN  
JOB MANAGER: J. GILLIGAN  
VERIFIER:



LEGEND	
	EXISTING BOUNDARY LINE
	PROPOSED KERB
	EXISTING KERB
	FUTURE KERB
	SAWCUT AND PAVEMENT INFILL
	KERB AND GUTTER
	VEHICULAR CROSSING
	EXISTING CONTOURS
	STORMWATER PIPE
	GRADED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	JUNCTION PIT (NEW / EXTG)
	GRADED TRENCH DRAIN
	PROPOSED FLEXIBLE PAVEMENT
	PROPOSED DRIVEWAY PAVEMENT

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR INFORMATION	TB		JG	02.03.20

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ARCHITECT

**GRAY PUKSAND**

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

**NORTHROP**  
Sydney  
Level 11 345 George Street, Sydney NSW 2000  
Ph (02) 9241 4188 Fax (02) 9241 4324  
Email sydney@northrop.com.au ABN 81 094 433 100

SCALE 1:200@A1

PROJECT

**TAFE - WESTERN SYDNEY CONSTRUCTION HUB**

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE**

**PROPOSED ACCESS WAY**

JOB NUMBER

**202025**

DRAWING NUMBER

**SKC01.22**

REVISION

**01**

DRAWING SHEET SIZE = A1