



LEGEND - CEILING MATERIAL TYPES

REFER TO A001 INTERNAL MATERIALS & FINISHES SCHEDULE FOR SPECIFIC TYPES & DETAIL/PROPRIETARY DESCRIPTION

CAI	INSULATION
CEX	EXISTING CEILING/SOFFIT TO REMAIN
CNC	METAL CLADDING
CNC	NO CEILING
CRB	PLASTERBOARD
CTV	TIMBER VENEER
FW	PAINT & APPLIED COATING TYPES
US	US OF EXPOSED CONCRETE SOFFIT
0	'ANYTHING PREFIXED WITH 0 DENOTES EXISTING'
C.O.S	CONFIRM ON SITE
TBC	TO BE CONFIRMED
RL	REDUCED OR RELATIVE LEVEL
AFFL	ABOVE FINISHED FLOOR LEVEL
FFCL	EXISTING FINISHED CEILING LEVEL
FFCL X XXX	FINISHED CEILING LEVEL
XXX	EXISTING RETAINED ARCHITECTURAL ELEMENT TO BE RE-INSTATED TO ORIGINAL SITE CONDITIONS
SE:	'ANYTHING PREFIXED WITH SE: REFER TO STRUCTURAL ENGINEERS' DRAWINGS
ME:	'ANYTHING PREFIXED WITH ME: REFER TO MECHANICAL ENGINEERS' DRAWINGS
FE:	'ANYTHING PREFIXED WITH FE: REFER TO FIRE ENGINEERS' DRAWINGS
EE:	'ANYTHING PREFIXED WITH EE: REFER TO ELECTRICAL ENGINEERS' DRAWINGS
HE:	'ANYTHING PREFIXED WITH HE: REFER TO HYDRAULIC ENGINEERS' DRAWINGS
TS:	'ANYTHING PREFIXED WITH TS: REFER TO THEATER SPECIALISTS' DRAWINGS

LEGEND - CEILING FIXTURES & FITTINGS

FOR MECHANICAL LEGEND REFER TO M0001	FOR FIRE PROTECTION SERVICES LEGEND REFER TO F001
FOR ELECTRICAL SERVICES LEGEND REFER TO E0001	FOR THEATER SPECIALIST LEGEND REFER TO T0001
'SPECIALIST LIGHTING TO BE CONFIRMED IN SCOPE	'ALL FINAL LOCATION TO COORDINATE WITH SERVICES DRAWINGS
EXISTING FIXTURE & FITTING LOCATION TO BE C.O.S	SMOKE DETECTOR
EXIT SIGN INCLUDING LED LIGHT	WALL MOUNTED EXIT SIGN INCLUDING LED LIGHT
EXIT SIGN INCLUDING LED LIGHT WITH DIRECTIONAL ARROW	EMERGENCY LIGHTING
SECURITY CAMERA	SPRINKLERS
FIRE HYDRANT POINT	FIRE HOSE REEL
WALL MOUNT OCCUPANCY SENSOR	CEILING MOUNT OCCUPANCY SENSOR
DOWNLIGHT	PENDANT LINEAR LIGHT - LED
FLOURESCENT LIGHT FIXTURE	PEOPLE COUNTER
CEILING ACCESS HATCH	SPEAKER
VISUAL ALARM DEVICE	RIGGING POINT
CEILING MOUNTED RETURN, EXHAUST OR TRANSFER GRILLE	CEILING MOUNTED SUPPLY AIR DIFFUSER
AIR GRILLE	

NOTE: LIGHTING SPECIFICATION, REFER ELECTRICAL DRAWINGS, SPECIFICATION & LUMINAIRE SCHEDULE.

LEGEND - CEILING SYSTEM CODES

CODE	DESCRIPTION
C.S1+0-01-99	HANGING - SUSPENDED CEILINGS
C.S1+0-01-99	STEEL FRAMED CEILINGS
C.T1+0-01-99	TIMBER FRAMED CEILINGS
C.G1+0-01-99	GLAZED CEILING SYSTEMS
C.L1+0-01-99	LININGS (CEILINGS SUPPORTED BY OTHER CEILINGS)

SCHEDULE (CEILING)	DESCRIPTION
CXXX	CATEGORY (CEILING)
F S A	TYPE (CEILING)
F S A	SPECIFIC (CEILING)
F S A	CEILING TYPE
F S A	FSR TYPE
F S A	ACOUSTIC CEILINGS TO ACOUSTIC ENGINEERS REQUIRED RATING
F S A	FIRE RATED CEILINGS

CEILING TYPE TAG:

REFER TO DWG A0412 FOR DETAILS & DESCRIPTION
NOTE: CEILINGSS MARKED 'A' REQUIRING ACOUSTIC INSULATION ADDITIONAL TO DOCUMENTED EXTENT TO BE CONFIRMED BY ACOUSTIC ENGINEER

LEGEND - CH CEILING

COLOUR	DESCRIPTION
NEW	NEW CEILING PENETRATION FOR THEATER EQUIPMENT
CTV40	TIMBER VENEER - WHITE BRUSH
W.L.	W.L. TO EXISTING PENETRATIONS NO LONGER IN USE

GENERAL NOTES

1. CONTRACTOR & SUB-CONTRACTORS TO CO-ORDINATE BETWEEN ARCHITECTURAL, STRUCTURAL & SERVICES DOCUMENTATION, WITH ARCHITECTURAL DOCUMENTATION TO TAKE PRECEDENT FOR SETOUT.
2. CONTRACTOR & SUB-CONTRACTORS TO VERIFY ALL DIMENSIONS & CONFIRM ON SITE CONDITIONS RELATING TO ALL DIMENSIONS PRIOR TO COMMENCEMENT - DO NOT SCALE FROM DRAWING
3. SHOP DRAWINGS ARE TO BE SUPPLIED TO THE RELEVANT PARTIES & CONSULTANTS FOR REVIEW & APPROVAL PRIOR TO THE COMMENCEMENT OF ANY WORKS
4. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ASSOCIATED SPECIFICATIONS, SCHEDULES & CONTRACT DOCUMENTS
5. MAKE GOOD ALL AFFECTED SURFACES & FINISHES INCLUDING ITEMS MARKED FOR REMOVAL &/OR RELOCATION
6. THE CONTRACTOR IS TO ALLOW TO SAND AND RE-FINISH ALL BRUSHBOX NOMINATED TO BE RE-USED THE WORKS. THIS BRUSHBOX IS TO BE INCORPORATED WHEREVER POSSIBLE WHERE WTM-02 IS NOMINATED

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

ARM
ARCHITECTURE
LEVEL 11/522 KUNDELL LANE MELBOURNE VICTORIA 3000 AUS
T 03 8613 1888 F 03 8613 1889
mail@armarchitecture.com.au
ADV 2 275 292 290
www.armarchitecture.com.au

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Issue	Description	Dwn	Appl	Date
0	0A ISSUE	0A	0A	06/10/2018

Sydney Opera House Trust GPO Box 4274 Sydney NSW Australia 2001 Phone: +61 2 9250 7541 email: info@sydneyoperahouse.com	 © Sydney Opera House Trust
---	---

Location	Drawing No:	Sheet:	Rev:	B1
CHVA	49-BR-ARM01	DA1511	D	