

ATTACHMENT A

| |
|-------------------------------|
| RECOMMENDED CONDITIONS |
|-------------------------------|

(1) ALIGNMENT LEVELS – MINOR DEVELOPMENT

- (a) Where ground floor levels of existing buildings are being retained, alignment levels for the buildings and site frontages of those buildings must be submitted to and approved by Council prior to a Construction Certificate being issued for public domain works or above ground building works, whichever is earlier. The submission must be prepared by a Registered Surveyor or suitably qualified engineer and must be submitted with a completed Alignment Levels checklist (available in the *Public Domain Manual*) and Footpath Levels and Gradients Approval Application form (available on the City's website).
- (b) If a *Public Domain Plan* condition applies to the development consent the *Public Domain Plan* submission must incorporate the approved Alignment Levels. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.

(2) PUBLIC DOMAIN PLAN

- (a) A detailed Public Domain Plan must be prepared by a suitably qualified architect, urban designer, landscape architect or engineer and must be lodged with Council's Public Domain Section and be approved by Council prior to a Construction Certificate being issued for public domain work or above ground building work, whichever is later. The Public Domain Plan must be submitted with a completed Public Domain Plan checklist (available in the City of Sydney's *Public Domain Manual*).
- (b) The Public Domain Plan must document all works required to ensure that the public domain complies with the City of Sydney's *Public Domain Manual*, *Sydney Streets Design Code* and *Sydney Streets Technical Specification*, including requirements for road pavement, traffic measures, footway pavement, kerb and gutter, drainage, vehicle crossovers, pedestrian ramps, lighting, street trees and landscaping, signage and other public domain elements. If an Alignment Levels condition applies to the development, the Public Domain Plan submission must incorporate the approved Alignment Levels. If the proposed detailed design of the public domain requires changes to any previously approved Alignment Levels, then an amended Alignment Levels submission must be submitted to and approved by Council to reflect these changes prior to a Construction Certificate being issued for public domain work.
- (c) The works to the public domain are to be completed in accordance with the approved Public Domain Plan and Alignment Levels plans and the

Public Domain Manual before any Occupation Certificate is issued in respect of the development or before the use commences, whichever is earlier.

- (d) A Public Domain Works Deposit will be required for the public domain works, in accordance with the City of Sydney's adopted fees and charges and the *Public Domain Manual*. The Public Domain Works Deposit must be submitted as an unconditional bank guarantee in favour of Council as security for completion of the obligations under this consent.
- (e) Council's Public Domain section must be contacted to determine the guarantee amount prior to lodgement of the guarantee. The guarantee must be lodged with Council prior to a Construction Certificate being issued.
- (f) The Bank Guarantee will be retained in full until all Public Domain works are completed and the required certifications, warranties and works-as-executed documentation are submitted and approved by Council in writing. On satisfying the above requirements, 90% of the total securities will be released. The remaining 10% will be retained for the duration of the specified Defects Liability Period.

(3) PUBLIC DOMAIN WORKS - HOLD POINTS AND HANDOVER

- (a) Prior to a Construction Certificate being issued for public domain work, including civil, drainage and subsurface works, , a set of hold points for approved public domain, civil and drainage work is to be determined with and approved by the City's Public Domain section in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*.
- (b) Prior to a Certificate of Completion being issued for public domain works and before the issue of any Occupation Certificate for the development or before the use commences, whichever is earlier, electronic works-as-executed (as-built) plans and documentation, certified by a suitably qualified, independent professional must be submitted to and accepted by Council for all public domain works. Completion and handover of the constructed public domain works must be undertaken in accordance with the City of Sydney's *Public Domain Manual* and *Sydney Streets Technical Specification*, including requirements for as-built documentation, certification, warranties and the defects liability period.

(4) DEFECTS LIABILITY PERIOD – PUBLIC DOMAIN WORKS

All works to the City's public domain, including rectification of identified defects, are subject to a [insert time frame, typically 12] month defects liability period

from the date of final completion. The date of final completion will be nominated by Council on the Certificate of Completion for public domain works.

(5) PROTECTION OF STONE KERBS

- (a) The existing stone kerbs on the [Street Name/s] frontage[s] of the site are to be retained and properly protected during excavation and construction works.
- (b) To avoid damage to stone kerbs during excavation and construction works for the development, temporary removal and storage of the stone kerbs may be approved by Council. Removed, serviceable stone kerbs (i.e. those that are in good condition as agreed by Council officers) must be re-installed in accordance with the City of Sydney's standard details and specifications after the construction works have been completed.
Note: A temporary concrete kerb will need to be constructed to retain the footpath until the stone kerbs can be reinstalled. The removed stone kerbs are to be reinstalled prior to the issue of an Occupation Certificate.
Note: all costs associated with the works are to be at no cost to the Council.
- (c) Damaged kerbs are to be replaced to match existing to Council's satisfaction or as otherwise advised by Council officers.
- (d) Where new crossings or temporary crossings are to be constructed to access the property, the affected kerb stones should be salvaged and reused wherever possible.
- (e) All new driveway laybacks and kerbs are to be constructed with stone kerbs to match existing stones or as specified by City officers. All unused stone kerbs are to be salvaged and returned to the City's store.
- (f) Council approval is required before kerbs are removed.
- (g) Council approval is required prior to the cutting of existing stone kerbs for stormwater kerb outlets.

(6) PUBLIC DOMAIN DAMAGE DEPOSIT

A Public Domain Damage Deposit calculated on the basis of 4 lineal metres of asphaltic concrete site frontage must be lodged with Council in accordance with the City of Sydney's adopted Schedule of Fees and Charges. The Public Domain Damage Deposit must be submitted as an unconditional bank guarantee in favour of Council as security for repairing any damage to the public domain in the vicinity of the site.

The guarantee must be lodged with Council prior to an approval for demolition being granted or a Construction Certificate being issued, whichever is earlier.

The Bank Guarantee will be retained in full until the final Occupation Certificate has been issued and any rectification works to the footway and Public Domain are completed to Council's satisfaction. On satisfying the above requirements 90% of the total securities will be released, with the remaining 10% to be retained for the duration of the 12 months Defect Liability Period.