





Development Application – Structural, Civil and Maritime Design Report

26th September 2019



Mott MacDonald 383 Kent Street Sydney NSW 2000 PO Box Q1678, QVB Sydney, NSW 1230 Australia

T +61 (0)2 9098 6800 F +61 (0)2 9098 6810 mottmac.com

Infrastructure NSW MLC Centre Level 12 Sydney NSW 2000

The new Sydney Fish Market

Development Application – Structural, Civil and Maritime Design Report

26th September 2019

Issue and Revision Record

Revision	Date	Originator	Checker	Approver	Description
Α	22/02/18	JP	GB	SG	For Comment
В	26/07/18	JP	GB	SG	For Comment
С	04/09/18	JP	GB	SG	For Comment
D	05/11/18	JP	GB	SG	For Comment
E	07/11/18	JP	GB	SG	For Comment
F	09/11/18	JP	GB	SG	For Comment
G	02/04/19	KH	GB	SG	For Comment
Н	03/04/19	KH	GB	SG	DA Submission
J	26/09/19	KH	GB	SG	DA Submission

Document reference: 385951 | RP02 | J

Information class: Standard

This document is issued for the party which commissioned it and for specific purposes connected with the abovecaptioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

Contents

Exe	ecutive	summ	ary	1
1	Intro	oduction	1	2
	1.1	Descrip	otion of Project	2
	1.2		of Report	2
	1.3	Project	•	2
	1.4	-	ions of this Report	2
2	Site	Data &	Constraints	3
	2.1	Geotec	chnical & Contamination conditions	3
		2.1.1	Geotechnical	3
		2.1.2	Contamination	3
	2.2	Bathym	netric Survey Information	4
	2.3	Overla	nd Flow & Stormwater	4
	2.4	Existing	g services	5
	2.5	Existing	g Structures	5
		2.5.1	Fig Trees	5
	2.6	Traffic		5
3	Stai	ndards		6
4	Per	formand	ce Criteria	7
	4.1	Design	Life	7
	4.2	Durabil		7
		4.2.1	Concrete Cover	7
		4.2.2	Allowable Crack Widths	7
	4.3	Materia	al Properties	8
		4.3.1	Concrete	9
		4.3.2	Reinforced Steel	9
		4.3.3	Structural Steel	9
		4.3.4	Stainless Steel	9
	4.4	Movem	nents & Tolerances	9
		4.4.1	Vertical Deflection Limits	9
		4.4.2	Horizontal Deflection Limits	9
	4.5	1.5 Differential Settlement		9
	4.6	Therma	al Movements	9
4.7 Joints			10	
	4.8 Fire Resistance			10
4.9 Progressive Collapse			ssive Collapse	10

5	Load	dings		11
	5.1	Gravity	/ Loading	11
		5.1.1	Dead Loads	11
		5.1.2	Construction loads	11
	5.2	Barrier	s and Handrails	11
	5.3	Water	Pressures	11
		5.3.1	Current Sea Level Pressures	11
		5.3.2	Future Sea Level Pressures	11
	5.4	Wind L	Loads	12
	5.5	Seismi	ic Loads	12
	5.6	Earth F	Pressure	12
	5.7	Therma	12	
6	Stru	ctural S	Scheme	13
	6.1	Introdu	uction	13
	6.2	Tempo	orary Sheet Piled Wall	13
	6.3	Founda	ations	14
		6.3.1	Piles	14
		6.3.2	Typical piles and pile caps	14
	6.4	Sea wa	all	14
	6.5	Sedime	ent Adjustment	16
	6.6	Basem	nent	16
		6.6.1	Basment pits	17
	6.7	Lower	& Upper Ground	17
	6.8	6.8 Feature stairs		18
	6.9	9 Mezzanine		18
	6.10	0 Stability system		18
	6.11			18
	6.12	2 Promenade structure		19
	6.13	Wharf	Structures	20
7	Civil	Design	า	21
	7.1	Bridge	Road	21
	7.2	Overland Flow		21
	7.3	Site sto	ormwater	21
		7.3.1	Roof water	21
		7.3.2	Promenade and Plaza	21
		7.3.3	Lower Ground Floor	21
		7.3.4	External Stairs	22
	7.4		Quality Modelling	22
	7.5		Revetment	22

8	Appendices	0
A.	Safety in Design - Designers Hazard Elimination and Management Reco	rd1
B.	Civil Design Documentation	2
C.	Temporary Sheet Pile Wall Reference Design	3
D.	Rock Revetment Design	4

Executive summary

Mott MacDonald with partners Arcadis and Royal Haskoning DHV are providing Structural, Civil and Maritime Engineering Design Services to support the development of the new Sydney Fish Markets. The vision for the new development is that of a world class facility designed to accommodate future growth and establish itself as an icon of the Bays District.

This report summarises the designs that have been developed during the concept phase to feed into the SSDA submission.

UrbanGrowth NSW Development Corporation (UrbanGrowth NSW) was abolished on 1 July 2019 with all functions transferred to Infrastructure NSW. Any reference to UrbanGrowth NSW throughout the report is interchangeable with Infrastructure NSW.

1 Introduction

1.1 Description of Project

Infrastructure NSW have engaged Mott MacDonald with partners Arcadis and Royal Haskoning DHV to provide structural, civil and maritime Engineering Design Services to support the development of the new Sydney Fish Markets. The vision for the new development is that of a world class facility designed to accommodate future growth and establish itself as an icon of the Bays District.

The new facility will be situated in Blackwattle Bay, adjacent to Pyrmont Bridge Road, adjacent to the existing Fish Markets site, as indicated in Figure 1-1 below.




Figure 1-1 - Site Layout (3XN)

1.2 Scope of Report

This report covers the design philosophy, key design parameters and constraints and assumptions that have been made in developing the engineering scheme for the new facility.

Options explored during concept design phase have been rationalised into a single scheme that will be developed into a detailed design. The process of rationalisation has occurred through coordination with the design team, cost consultant, constructability considerations and operational requirements.

1.3 Project Team

Mott MacDonald are providing structural, civil and maritime engineering services, supported by Royal Haskoning DHV and Arcadis as sub-consultants. They supplement the team's capabilities with their proven expertise in delivering world class civil foreshore and maritime design.

1.4 Limitations of this Report

This report has been prepared to support the project DA submission. Therefore, there remain many unknowns regarding the functional and architectural requirements of the project that will be developed as the design progresses.

This report summarises the design decisions that have been made in forming a base scheme and preliminary cost estimate. Specific details of large areas of the design are yet to be developed.

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

3

2 Site Data & Constraints

A detailed list of constraints, developed as part of the constraints and opportunity register for the three parking options considered through the concept design phase, is included in Appendix A. The main issues are summarised below.

2.1 Geotechnical & Contamination conditions

2.1.1 Geotechnical

The new facility will be located in Blackwattle Bay, adjacent to Pyrmont Bridge Road, adjacent to the existing Fish Markets site.

The site was previously part of the Blackwattle Bay Cove or Blackwattle Swamp Cove and was reclaimed between 1835 and 1891 (exact date unknown).

There are a number of existing geotechnical reports that have been prepared as part of previous studies to the site that describe the geotechnical conditions.

- Coffey Geosciences Pty Ltd Statement of Geotechnical Conditions (Ref: S20790/2 dated 28 May 2001)
- Golder Associates' Geotechnical Investigation and Assessment of Rozelle & Blackwattle Bay Wharves (Ref: 9862337/E dated March 1999)
- Douglas Partners' Report on Geotechnical Investigation Wharf Repair, Blackwattle Bay (Ref: 29094 July 2000)

The subsurface conditions between Pyrmont Bridge Road as taken from the boreholes shown in Figure 2-2 are summarised in Figure 2-1 below.

Material	Description		Inferred Depth to Top of Unit (m)	
		Northern Building	Southern Building	
Fill	SAND, clayey SAND, gravely SAND with sandstone cobbles and boulders, poorly compacted, moist to wet.	0	0	
Marine Sediments	Clayey SILT or silty CLAY with layers of peaty SILT in places, soft to firm, overlying heterogeneous mix of SAND, silty SAND, clayey SAND and gravely SAND, loose to medium dense.	7 to 7.5	5 to 6	
Alluvium	CLAY, medium to high plasticity.	8.8 to 9	8.2 to 8.6	
Residual Soil	Clayey SAND and sandy CLAY, medium dense to very dense, stiff to very stiff (absent in places).	may not exist	16 to 21	
Hawkesbury Sandstone	Extremely low strength to low strength (Class IV and V)* Hawkesbury Sandstone, grading to medium strength (Class III)* within about 0.3 to 3m of the top of the unit.	17 to 20	17 to 21	

^{*} Sydney Sandstone Rock Class according to Reference 1.

Figure 2-1 - Typical Subsurface Conditions

385951 | RP02 | J | 26th September 2019




Figure 2-2 - Summary of Borehole Locations

There is therefore evidence of poorly compacted fill overlying soft marine sediment. Any works or support of structure located within the zone is recommended to be supported on piles driven to rock

The top of rock level takes the form of a buried incised valley floor, with its axis running approximately SE to NW, with the deepest rock levels ~ 21m to 22m below existing ground level.

During the detailed design phase, further geotechnical investigations will be required to validate the design assumptions and confirm those investigations undertaken previously.

2.1.2 Contamination

Environmental Investigation Services undertook a contamination investigation (ref: E29245Klet_SP1 - April 2017). The investigation found the presence of heavy metals and PAHs (Polycyclic Aromatic Hydrocarbons) in the fill and natural sediment samples however noted this is not unusual given the legacy of a large number of former industries historically based on the water front. Reference should also be made to the JBS&G Acid Sulphate Soil Management Plan and a Remedial Action Plans. These reports give recommendations to how these contaminants should be treated once encountered.

The presence of such contamination has been a key consideration in the options explored, with the aim being to minimise the amount of disruption or removal.

2.2 Bathymetric Survey Information

A full bathymetric survey of the bay is available and has been used to understand sea bed levels relative to the underside of structure and the sea wall. The survey plot and typical section is shown in Figure 2-3. This has been combined with the site survey data of the existing wharfs and Pyrmont Bridge Rd to give a full understanding of the relative levels of each.




Figure 2-3 - Bathymetric Survey

2.3 Overland Flow & Stormwater

The proposed site has significant overland flow challenges, with Wentworth Park, Wentworth Park Road and Wattle St acting as conduits in the event of severe storms.

The catchment area is large, extending south to Central Station, east to the City and west towards Glebe. Since Wentworth Park is raised ~ 1m above the surrounding streets with a

boundary wall around much of the perimeter, the adjacent Wentworth park Rd and Wattle St arteries carry significant volumes of water down to the bay, as indicated in Figure 2-4.

Currently there exists a series of walls and obstructions along the northern edge of Pyrmont Bridge Road that result in the greater depths as shown on the plot below.




Figure 2-4 – Overland Flow Plot

There are several existing stormwater culverts that run under Wentworth Park, discharging into Blackwattle Bay, see Figure 2-5. Since the new facility will be placed directly in front of these outlets, the design must account for their location and not impact their operation. Treatment of the existing sea walls and their interaction with the culverts will require careful assessment, in consultation with Sydney Water.

At this stage, no allowance has been made in the project for amplification to the existing network. One of the culverts is heritage listed and will require the appropriate protection during construction. Baffles are proposed to capture detritous / material that flows out from the pipes under the facility. Access hatches will be provided to these baffles to allow for inspection and removal of material.




Figure 2-5 - Existing Stormwater Culverts

2.4 Existing services

The existing stormwater culverts, together with the other existing services indicated along Pyrmont Bridge Road will all need to be considered during the construction of the new facility.

The degree and extent of services diversions will depend on the scale of works to be undertaken along Pyrmont Bridge Road. As the results of the new Bridge Road, it is anticipated the existing electrical including street lighting, telecommunication and gas services located on the northern side of the road reserve will be require to be adjusted and/or relocated. The new Bridge Road generally will tie back to existing road layout at both the intersection. This may be limited adjustments of the existing intersections at Wentworth Park Road and Wattle St, or may include re-profiling of the road for overland flow considerations, or adjusting pavement and kerb lines for site entrances and exits and bus drop off zones.

Existing services adjacent to Pyrmont Bridge Road are sshown in Figure 8-1 in the Appendix of this report.

2.5 Existing Structures

2.5.1 Fig Trees

The large Fig Trees that line the northern edge of Wentworth Park Road are important Heritage items to the City of Sydney. The civil works associated with Bridge Road accounts for the presence of the fig tree roots, by limiting the height to which bridge road is raised to that of the adjacent masonry wall. The roots therefore remain unaffected.



Figure 2-6 - View of Heritage Listed Figs Trees from Heritage Listed Viaduct

2.6 Traffic

The proposed site sits adjacent to some of the main arteries of Sydney, with significant volumes of traffic accessing the Western distributer and Harbour Bridge from Wattle St and Pyrmont Bridge Road.

Traffic studies have been undertaken to assess the impact of changing the access point of the markets from Bank St to Pyrmont Bridge Road on the main intersections at Wattle St and Wentworth Park Road.

Reference should be made to the TIA undertaken by ARUP for a full description of the impacts of the facility on the local and wider reaching network.

3 Standards

The following engineering standards have been used in the design of the Sydney Fish Markets:

National Construction Code (NCC), previously the Building Code of Australia

AS/NZS1170.0 - 2002	Structural Design Actions Part 0: General principles
AS/NZS1170.1 - 2002	Structural design actions Part 1: Permanent, imposed and other actions
AS/NZS1170.2 - 2002	Structural design actions Part 2: Wind actions
AS/NZS1170.4 - 2002	Structural design actions Part 4: Earthquake actions in Australia

AS/NZS 2890 - 2014	Parking facilities
--------------------	--------------------

AS 1314 – 2003	Pre-stressing anchorages
AS 1379 – 2007	Specification and supply of concrete

AC 04E0 400E	Dilian Daning and installation
AS 2159 – 1995	Piling - Design and Installation
/\C 2100 1000	Piling - Design and installation

AS 3600 – 2009	Design of Concrete Structures
AS 5100 – 2017	Design of Bridge Structures

	J	3
AS 3735 – 2001	Concrete Str	uctures for Retaining Liquids

AS 4654 – 2012 Waterproofing membrane systems for exterior use - Above ground level

AS 4997 – 2005 Guidelines for the design of maritime structures

AS 3962 – 2001 Guidelines on the Design of Marinas

BS EN 1992-1 – 2004 Eurocode 2 Design of Concrete structure

The following guides will also be used for reference:

Water-resisting basement construction – a guide – UK CIRIA Guide

ICE (Institute of Consulting Engineers) - Reducing the Risk of Leaking Substructure

- A Clients Guide

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

7

4 Performance Criteria

Reference should be made to the project specification for a full description of the project requirements.

4.1 Design Life

The design life of the new Sydney Fish Markets facility is stated within the functional brief as 50 years.

Table 6.1 of AS4997 Design Life of Structures states that a design life of 50 years is appropriate for normal commercial structures, category 3.

TABLE 6.1
DESIGN LIFE OF STRUCTURES

Facility category	Type of facility	Design life (years)
1	Temporary works	5 or less
2	Small craft facility	25
3	Normal commercial structure	50
4	Special structure/residential	100

Table 4-1 - Design Life of Structures - AS4997.

4.2 **Durability**

4.2.1 Concrete Cover

The Sydney Fish Market (SFM) is designed considering the marine environment within which it is situated. Exposure and classification environments for each area are as per Table 4-2 below These are based on the requirements stated in AS3600 and AS4997.

Location	Surface & Exposure environment	Exposure Classification	Concrete strength (MPa)	Cover (mm)
Precast basement beams, slabs & walls (to AS3600)	Surfaces of maritime structures in water – In tidal splash zone	C2	50	60
In-situ basement slab and walls (to AS3600)	Surfaces of members in interior environments. Industrial buildings subject to repeat wetting and drying	B1	40	30
Above ground insitu slabs	Surfaces of members in above-ground exterior environments - Coastal and any climatic zone:	B2	40	45
(to AS3600)	Surfaces of members in interior environments. Industrial buildings subject to repeat wetting and drying	B1 A2	40	20
	Surfaces of members in interior environments. Fully enclosed, non residential			

Table 4-2 – Exposure and cover classification

4.2.2 Allowable Crack Widths

The crack widths nominated are to prevent water ingress in the basement structure. This will be augmented with the use of high performance membranes and potentially admixtures such as Xypex. In addition, the scheme will provide falls, localised sumps and drains in the event leakages through the basement waterproofing systems do occur.

Crack widths will be controlled by limiting the stress within the reinforcement under serviceability conditions in accordance with AS3735 - Concrete structures for retaining liquids.

The nominal limiting stress in steel reinforcement to limit cracking is 130 MPa assuming N20 bar is adopted in the concrete structure. A minimum reinforcement ratio of 0.8% is adopted to both precast and In-situ concrete structures to control cracking with the use of N20 steel bar, refer to Table 4-4.

Whilst Australian standards do not have a mechanism for calculating crack widths, the design of water retaining elements will also be undertaken in accordance with BS EN 1992-1 – 2004 Eurocode 2 Design of Concrete structure, that allows the maximum crack widths to be estimated.

Table 4-3 – Allowable crack widths indicates the maximum crack widths each area of the proposed facility will be designed to.

Location	Design Max. crack width (mm)
Water retaining structures –	0.2
Precast & in-situ basement slabs & walls	
In-situ slab – external & Auction Hall & areas subject to repeated wetting and drying	0.2
In-situ slab – internal	0.3

Table 4-3 – Allowable crack widths

Bar diameter (mm)	8-12	16	20	24	28
Stress limit (MPa)	150	140	130	120	110
Minimum reinforcement ratio	0.48	0.64	0.80	0.96	1.12

Table 4-4 - Bar stress limits & reinforcement ratios

4.3 Material Properties

Basic material properties for the most commonly used materials are provided below, which are used as the basis for derived material properties as required in appropriate design standards.

For concrete, the specific mix design of each section will be investigated further during detailed design phase, for example, the use of low shrinkage mixes for the hydrostatic slabs.

Material	Density in kg/m ³
Concrete (mass, reinforcement < 1.5%)	2400
Concrete (reinforcement ≥ 1.5%)	2480
Cementitious Structural Grout	2100
Steel	7850
Concrete Block	2400
Timber - GL17 Glulam	650

Table 4-5 - Material Densities

Material	Strength (MPa)
Concrete (fc) – precast elements	50
Concrete (fc) – internal structural elements	32
Concrete (fc) – exposed concrete elements / columns	40
Concrete (fc) – interior/secondary elements	32
Concrete (fc) – foundations	32
Concrete (fc) – blinding concrete	15
Reinforcement (fsy) – plain to AS/NZS 4671 (250N)	250
Reinforcement (fsy) – deformed	500
Reinforcement (fsy) – wire fabric to AS/NZS 4671 (500L)	450
Prestressing (fp) – 12.7 mm, 7 wire super strand to AS 1311	1840
Prestressing (fp) – 15.2 mm, 7 wire super strand to AS 1311	1750
Timber - GL17 Glulam	33

Table 4-6 - Material Strengths

Material	Modulus of Elasticity (MPa)	
Concrete – 50 MPa	34,800	
Concrete – 40 MPa	32,800	
Concrete – 32 MPa	30,100	
Concrete – 15 MPa	19,580	
Reinforcement	200,000	
Pre-stressing	195,000	
Structural Steel	200,000	
Timber - GL17 Glulam	16,700	

Table 4-7 - Material Modulus of Elasticity

Material	Poisson's Ratio
Concrete	0.2
Steel	0.25

Table 4-8 - Material Poisson's Ratio

Material	Coefficient of Thermal Expansion (x 10 ⁻⁶ / °C)
Concrete	11.0
Reinforcement	12.0
Structural Steel	11.7
Timber - GL17 Glulam	5.0

Table 4-9 - Material Coefficient of Thermal Expansion

4.3.1 Concrete

Concrete shall comply with the requirements of AS1379. The average compressive strength at the completion of curing of not less than 75% of the specified concrete strength. Other material requirements shall comply with AS3735 Clause 4.3.

4.3.2 Reinforced Steel

Reinforced steel bar shall comply with the requirement of AS3600 concrete structure Clause 3.2. Yield strength of 500 MPa for reinforcement is adopted in the design.

Where galvanised reinforcement is adopted, galvanizing shall be as per AS3735 CI 5.3.

4.3.3 Structural Steel

A variety of steel grades and section types will be used in the design of the new facility. A summary of standards and grades for each type is shown in Table 4-10 – Typical Steel Grades.

Type of steel	Australian Standard	Grade
Universal beams & columns, parallel flange channels & large angles	AS/NZS 3679.1	300
Welded sections	AS/NZS 3679.2	300
Hot milled plates, flats, floor plates, Small angles and slabs	AS/NZS 3678	250
Hollow sections - square & rectangular	AS 1163	C350 or C450 according to Section designation
Circular hollow sections	AS 1163	C350 or C250 according to Section designation
Cold formed purlins and girts	AS 1397	G450 Z350

Table 4-10 - Typical Steel Grades

All workmanship and material shall be in accordance with AS4100. Fabrication shall be carried out in accordance with section 15 of AS4100. All welding shall comply with AS 1554.

4.3.4 Stainless Steel

Stainless steel cast in angles are proposed for the basement precast structure to provide a watertight barrier prior to laying the membrane and in-situ slab.

Marine grade SS Grade 316 (L) is proposed for these angles as this grade is suitable for heavy gauge welding. It should be noted it is critical that the welding material should match the base grade.

It should also be noted that any granules or powder of carbon steel should not contaminate the stainless steel as it can be a corrosion initiator. The use of non-carbon reinforcing tying the precast to the in-situ slab can help to mitigate this risk. Composite reinforcing systems such as V-Rod are being investigated.

The use of lean duplex (LDX) stainless steel is also being investigated for the basement slabs to achieve the required design life.

4.4 Movements & Tolerances

4.4.1 Vertical Deflection Limits

Deflections under serviceability loads will be limited with due regard to the type of structure under consideration and the impact these deflections will have on supported elements, line of sight, finishes (brittle and non-brittle) and perceptible movement.

The deflection limits proposed in AS/NZS1170.0 Table C1 have been adopted for design as a guideline.

Tolerances for construction inaccuracies and vertical deflections on clearance heights will be accounted for in the design, specifically in areas of constrained clearances such as the basement car park and loading dock.

4.4.2 Horizontal Deflection Limits

Lateral movements under a service wind will be typically limited to H/500.

Inter storey drifts under earthquake loads will be in accordance with AS1170.4.

The structure and associated connections supporting facades and moveable partitions will take account of lateral movements under wind and earthquake.

The interaction between adjacent structures, such as the wharf structures and the main facility will be investigated under lateral actions, with due account taken for differential movements with articulation provided as required.

4.5 Differential Settlement

All structures will be designed so that settlement and heave during all stages of construction and throughout the design life of the structure are kept to within acceptable limits.

4.6 Thermal Movements

Movements due to changes in temperature will be considered during the detailed design phase using the thermal coefficients stated in Tale 4-9.

The sensitivity of each area of the structure to changes in temperature and their impact on adjoining elements will be considered in turn.

4.7 Joints

The use and location of temporary and permanent joints will be investigated during detailed design phase. It is expected that temporary pour strips will be provided in the in-situ basement and RL3.1 slab to allow it to shrink unrestrained and minimise the risk of early age cracking.

Permanent joints in the RL9.0 slab are likely to be provided with the joints running through into the finishes and facades.

Joints within the roof structure will be determined as the design progresses dependant on the materials adopted and the movements expected.

4.8 Fire Resistance

The fire resistance levels for structural elements will be governed by the requirements of the certifying authority and any fire engineered solutions. Reference should be made to the DLA BCA Report.

For concrete elements, fire resistance will typically be achieved by providing the required cover to reinforcement. For steel elements, either protection measures such as fire board, intumescent paint or sprinklers will be assessed. For timber elements, either the inherent fire capacity or systems such as sprinklers will be used following consultation with the BCA Consultant and the fire brigade.

4.9 Progressive Collapse

The structures will be designed to ensure that the failure of a single element will not cause a catastrophic and continued collapse. This will typically be addressed by ensuring the tie requirements specified within the relevant codes are met, with reinforcement or steel connections detailed accordingly.

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

11

5 Loadings

5.1 Gravity Loading

5.1.1 Dead Loads

Self-weights have been accounted for in the design by adopting the material densities as shown in Table 4-5.

Where falls within concrete slabs are formed as part of the cast in-situ slab, the additional weight has been accounted for in the slab thickness. Where falls are created via an in-situ topping, the weight has been accounted for in the superimposed dead loads.

5.1.2 Construction loads

An estimation of the expected construction loads will be made and compared to the design live loads. Crane locations, storage of materials, construction traffic vehicles will be considered.

5.2 Barriers and Handrails

Barriers and handrails will be designed for the loads as specified in Table 3.3 of AS1170.1. Table 5-4 summarises the various areas and barrier types that are expected to be required for Sydney Fish Markets.

Area	Design Loading	Top Edge Horizontal Load (kN/m)
Areas subject to overcrowding – (Inc. feature stairs)	C5	3.0
Areas with tables or fixed seating adjacent balustrades	C1/C2	1.5
Areas not subject to overcrowding	C3	0.75
Pedestrian zones in car park	F/G	1.5

Table 5-1 - Barrier Loads

5.3 Water Pressures

5.3.1 Current Sea Level Pressures

Water pressure for 2017 design is based on the current mean sea level plus high tide and high wave. Water levels are taken from the IPCC Sea Level Rise Scenarios Chart for Sydney, which is detailed in appendix 1, Figure 8-2 – (values assume full reflection).

•	Current sea level –	0.000	AHD
•	Mean High Water Springs (High Tide) -	0.620	AHD
•	Highest Astronomical Tide (HAT) -	1.100	AHD
•	Lowest Astronomical Tide (LAT) -	-0.900	AHD
•	Highest recorded Tide Sydney	1.500	AHD
•	Expected peak wave action in Bay -	0.600m	ı
•	Design addition of half the wave height	0.300m	ı

Peak transient highwater level 2017 - 1.220 AHD
Peak design water level 2017 1.800 AHD

Water pressures for 2017 design scenario will therefore be calculated based on the relative depth of water from 1.220 AHD to the soffit of the structure.




Figure 5-1 - IPCC Sea Level Rise Scenarios - Sydney Tides

5.3.2 Future Sea Level Pressures

Water pressure for the full 50 year design is based on the current mean sea level plus expected sea level rise, plus high tide and high wave, (values assumes full reflection). The initial value presented is for the serviceability design. This is based on a 50 year sea level rise being applied the maximum recorded tide in Sydney:

AHD
AHD
1

For the ultimate design case, the scenario the structure is designed to resist is based on the relative level of the surrounding flood plains.


•	Level of flood plain	2.200	AHD
•	Depth of floodwater	0.300m	ı
•	Top of floodwater level	2.500	AHD
•	Design ultimate load factor	1.2	

Therefore, for serviceability design, a level of 2.200mAHD has been utilised. For the ultimate limit state design, it is assumed the surrounding land has been overtopped and thus this level of 2.500m AHD is assumed with an ultimate load factor of 1.2.

5.4 Wind Loads

Terrain categories vary from the site depending on wind direction. Open water and parkland are present from the NW and SE directions, however, given the height of the development, ~ 20m, and the presence of TC3 and TC4 within the terrain development length and in all other directions, a terrain category of 2.5 has been adopted for all directions at this stage.

This will be refined during detailed design phase for the design of the overall stability and individual elements such as the façade support structure and roof.



Region	A2
Negion	AZ

Structural Importance Level - BCA - part B1	3
$V_{r,Ult}$	46 m/s
V _{r,Serv}	37 m/s
Terrain Category (20m building height)	2.5
Terrain height multiplier Mz Cat	1.01
Shielding Multiplier Ms	1
Direction Multiplier Md	1
Topographic Multiplier Mt	1
Hill Shape Multiplier Mh	1
q (uls) (kPa)	1.30
q (sls) (kPa)	0.84

Table 5-2 - Wind Loads

5.5 Seismic Loads

The structure sits within the bay on steel piles driven into the rock layer. Water depths are approximately 2-10m deep. As per Figure 2-1 – Typical Subsurface Conditions, immediately below the water is a layer of fill over marine sediments and clay over sand over rock. The structure has been designed as a braced frame with raking piles socketed in the rock taking the lateral load. Given the nature of the fill over the rock, for the purposes of seismic design the fill is ignored and the structure designed with the piles modelled as columns socketed into sandstone. For this reason, a site soil sub class of $B_{\rm e}$ has been chosen.

Although AS1170.4 designates an EDC of II, a full dynamic analysis of the structure will be undertaken at detailed design stage in accordance with EDC III.

Structural Importance Level - BCA - part B1	3
Probability Factor kp	1.3
Hazard Factor Z	0.08
Site sub-soil class	Be
kpZ	<0.17
Structure Height	<50m (relative to rock level)
Earthquake Design Category	II

Table 5-3 - Seismic Loads

5.6 Earth Pressure

There is nominal interaction from earth pressures from the existing sea wall that may eventually bear against the side of basement structure following failure of the sea wall over the design life of the facility. The lower ground floor slab typically spans over the top of the existing sea wall, therefore nominal surcharge loads will be applied, refer to Figure 6-5 – Typical section through proposed & existing sea wall.

The magnitude of these loads are not significant compared to the seismic and wind lateral loads imposed on the structure.

5.7 Thermal Loads

Thermal loads will be considered as part of the detailed design phase. Appropriate reinforcement will be provided in the concrete elements together with the necessary allowance for movement and tolerance within the steel connetions.

6 Structural Scheme

6.1 Introduction

The following section outlines the proposed scheme for the construction of the foundations, basement, sea wall, superstructure, lateral stability system and roof.

A single story basement is positioned between mean to low tide level to balance operational requirements including number of car parks & accessibility, site constraints including the maximum height of the facility in relation to adjacent heritage classified fig trees and structural constraints such as buoyancy. Over the basement sits the ground level operational zone, with the retail area at the level above. Discrete areas of mezzanine are provided over that retail zone, with a roof canopy covering the entire floor plate. A typical section is shown in Figure 6-1.



Figure 6-1 – Typical cross sectionional perspective through facility

6.2 Temporary Sheet Piled Wall

A temporary steel sheet pile wall is to be constructed to allow the construction of the basement to proceed unimpeded by water levels. The installation of the sheet pile wall can be done in conjunction with the installation of the main building piles.

The reference design of the sheet pile wall is indicated in Figure 6.2. Sheet piles are driven to rock to achieve cut off before props and wailer beams are installed to provide the required lateral resistance. A number of construction methods for the sheet pile wall have been investigated, including the use of a Giken silent piling technology. The exact method to be adopted will be driven by the marine contractor and their method to achieve cut off to allow dewatering of the coffer dam once complete.

A combination of raking and cantilevered props have been adopted based on the underlying soil profile.

Where both the overburden and rock is shallow, large diameter steel piles bored into the rock cantilever to provide restraint. Where the rock and overburden is deep, raking props are adopted, with the corresponding tension force developed in the sheet pile wall resisted by the friction between the sheet piles and the overburden and rock.

To the southern boundary, the sheet piles are driven from land behind the existing sea wall as required to achieve the necessary cut off.

Once the sheet pile wall is complete, the site is dewatered to a level of -2.3 AHD to allow the building steel piles to be cut to the required height and the precast installed.




Figure 6-2 - Plan & 3D view showing extent of sheet pile wall




Figure 6-3 - Typical section of sheet pile wall

Disturbance to the sea bed will be minimised during removal of the sheet pile wall and the piles associated with the existing wharf. A methodology and mitigation strategy will be developed during the detailed design phase.

6.3 Foundations

The facility is located within Blackwattle Bay. The geotechnical conditions of the site from the existing boreholes are fill, over marine sediments, over clays and sandstone, with the sandstone located between 5 and 20m below 0.0 AHD, refer to Figure 2-1 – Typical Subsurface Conditions.

6.3.1 Piles

The lowest basement level is just below mean sea level. Uplift pressures are therefore driven by rise in sea level caused by a combination of tides, wave action and future sea level rise. As discussed in section 5.3 Water Pressures, it is anticipated this would be approximately 2.8m, equivalent to 28kPa of uplift approximately equivalent to the self-weight of the basement, ground and retail structure.

Given this represents an ultimate condition, and with the additional weight from the upper mezzanine levels and roof, there will not be any residual uplift on the structure in the permanent serviceability case, with the exception of columns with transfers over.

In the temporary case, the hydrostatic uplift pressure will be greater than the self-weight of the precast structure. Whilst the piles have a tension capacity, it would be uneconomical to design the piles for the full uplift pressure, and thus it is assumed that basement and ground in-situ slabs will be installed prior to the stopping of dewatering works.

The foundations will comprise steel CHS piles driven to a specified set and minimum penetration into Class III sandstone. The initial piles together with a sample would be tested with CAPWAP to check end bearing and skin friction capacity.

Following dewatering of the coffer dam, the piles will be cut to the correct level, with a capping plate fixed to accept the precast beams that may be fixed into place via a cast in plate welded to the top of the pile.

Raking piles are proposed to transmit the lateral forces from wind and earthquake actions to the rock. These are located discretely under the building cores and against the temporary cofferdam to provide the necessary lateral resistance. Tension loads may be experienced in the ultimate earthquake case, the magnitude of these loads will be determined during detailed design phase, with the pile size and embedment adjusted as necessary.

All steel piles will require a protective coating against corrosion, with a 1000-micron dry film thickness epoxy finish currently envisaged along the full length of the pile. Cathodic protection in the form of zinc anodes clamped to the piles would also be provided together with a denso tape type wrapping applied above and below the water line in the tidal and splash zone.

6.3.2 Typical piles and pile caps

Figure 6-4 – Typical pile cap detail shows the typical primary beam to pile connection. It is formed with the introduction of a fabricated pile cap that bears onto the pile that has been cut to the correct level. The pile cap ensures the precast element has adequate bearing on the pile and allows for sufficient tolerance in the pile and precast beam installation.




Figure 6-4 - Typical pile cap detail

6.4 Sea wall

An existing sea wall runs along the boundary between Pyrmont bridge road and Blackwattle Bay as shown in Figure 8-3 in the Appendix of this report.

Several options for the construction of a new sea wall were explored during concept phase, considering a new wall either in-front, behind or in line with the existing.

Key constraints considered during the design process included

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

- Existing structure type and method of retention
- Implications of failure of existing wall on adjacent structures
- Ability of existing and proposed wall to resist vertical and lateral loads
- Residual design life of existing structure
- Cost to retain or replace existing wall
- In ground obstructions (dead man anchors)
- Location of known and unknown existing services
- Geotechnical conditions
- Contaminated land
- Relative water levels current and future
- Vermin nuisance

It was concluded that:

- The existing wall is unlikely to have significant residual capacity and should not be relied upon to provide ongoing support for the life of the facility.
- The new wall should be separated from the new facility and not be required to resist lateral and vertical loads as this would require it to be piled due to the poor ground conditions.
- Lateral movements of the wall should only be sensitive to the soil it is retaining
- Any rock revetment should finish at max 0.0 AHD to mitigate the risk of vermin feeding on food scraps lodged within the rocks
- The amount of soil removal and associated contaminated land treatment should be minimised
- The wall should be designed for a full head of water in conjunction with low tide.
- The wall should be kept clear of in ground obstruction and services where possible
- The wall and design should take due account of the existing stormwater culverts.

In June 2018, a condition assessment of the existing sea wall was undertaken by Royal Haskoning DHV and detailed within report PA1518M&AR001F01. Reference should be made to that report for a more detailed understanding of the form and existing condition of the wall. In summary the report highlighted that the majority of the wall is of a Monier type construction, i.e. precast L-shaped gravity wall sitting on a rock revetment. The condition of the wall is poor and not considered adequate for a further 50 year design life.

Proposed Sea Wall remediation

The intent is to place the new facility directly infront of the existing sea wall to minimise the amount of remediation works required, wall as shown in Figure 6-5. To prevent undermining of the existing retaining wall revetment, a shallow precast beam section is proposed along this perimeter.

Where the existing sea wall is not covered by the new facility, it is proposed a new rock revetment wall be placed infront with the stormwater culvert extended as necessary, as indicated by Royal Haskoning DHV in the document PA1518-MA-Revetment Concept_20180718, included in Appendix D.




Figure 6-5 - Typical section through proposed & existing sea wall

The existing stormwater culverts will be locally given sufficient space to discharge into the bay (see Figure 6-6) and the new basement wall can be constructed hard up against the existing sea wall, effectively becoming the new sea wall. A baffle will be provided infront of the stormwater pipe to collect any discharge from the pipe. An access panel to this baffle will be provided from groud level via a removeable preast section. The gap between the two can be filled up with gravel infill, with the precast swing slab that supports ground floor entrance area spanning between a precast corbel on the basement wall and a ground beam (potentially supported off piles pending geotechnical information).




Figure 6-6 - Typical Section Through Culvert that discharges centrally into the facility

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

6.5 Sediment Adjustment

Two sources of information have been used to assess the volume of silt/fill that is required to be adjusted in order to install the basement precast structure and prevent disturbance of flow at stormwater outlets. The first of which is a hydrographic survey that gives a 3D plot of the seabed surface. However, the reliability of this hydrographic survey is questionable in some areas as it indicates very low levels at the base of the Monier Trestle wall. These potential errors may be due to the difficulties in performing the survey beneath the existing wharf structure. The second source is a historical detail of a rock revetment, see Figure 6-7. For the purpose of this analysis the sea bed level has been taken as the maximum of the hydrographic survey and the level of the rock revetment. The regions identified in the hydrographic survey that are above the designated rock revetment level are assumed to be a build of up silt.




Figure 6-7 - Historic Rock revetment detail

A gap of at least 1m will be provided under the structure to allow the hydraulic performance of the stormwater culvert to remain unaffected. A detailed investigation of the hydraulic performance of the culvert with this revised arrangement has been undertaken by Cardno.

To provide this 1m clearance, approximately 55m³ of silt and 335m³ of rock revetment requires removal / relocating, see Figure 6-8. Along the remaining length a buffer zone of 500mm will be required to ensure the basement precast can be installed. This equates to the relocation of 135m³ of rock revetment. Therefore the total volume of silt to be adjusted is 55m³ and the total volume of rock is 470m³.




Figure 6-8 – Approximate extent of silt dredging and revetment adjustment

The likely construction methodology would be the use of a long armed excavator mounted on a barge, scraping the material along the sea bed to an adjacent area. The use of a sediment curtain would be a minimum requirement to control the turbidity, together with some water quality modelling outside of the curtain to ensure it is provide the required control.

Again, the uncertainty surrounding the material being adjusted must be considered in any future analysis. It is recommended to perform a revised survey to confirm these volumes following demolition of the wharf structure above.

6.6 Basement

The basement level structure is typically fully submerged below the water line. The SSL of the basement is -0.3AHD, with low & high tides typically ranging from -0.5 to +0.5 AHD.

The basement structure is formed using highly repetitive precast elements comprising of primary u-shaped culvert beams that span between the piles and secondary T-beams that span onto the primaries. **Figure 6-9 – Basement precast types** gives an indication of the degree of repition.

An insitu topping is then cast directly onto the precast, (precast is formed with a rough broomed finish), this in conjunction with the precast forms the primary basement waterproofing layer. At the precast joints, hydrophilic strips will be provided to mitigate the risk of water tracking along the joint between precast and insitu.




Figure 6-9 - Basement precast types

Above the insitu layer, a 20mm cavidrain system with a wearing slab is laid to prevent any leakage that may occur over time becoming visible. Figure 6-10 shows a typical section through the primary and secondary beams.




Figure 6-10 - Basement precast details

6.6.1 Basment pits

A large number of pits are present in the basement structure in which various pumps, sumps, lift pits and other plant is situated as required for a facility of this type. Due to the nature of the basement construction, each of the pits require an alternate method of support rather than just an additional excavation that would be typical of most buildings.

Whereever possible, lift pits, pits and hoists have been located in the four main building cores since the basement level has been reduced over the entire grid in these locations. This helps to minimise the number of additional local reductions and associated complexity. Elsewhere, the pit types have been standardised wherever possible to limit the number of bespoke precast elements. Figure 6-12 - Bespoke precast pit shows one of these precast pits.




Figure 6-11 – Bespoke precast pit

6.7 Lower & Upper Ground

The lower and upper ground floor structures are comprised of post tensioned banded slabs. Bands are typically 2400mm wide ranging from ~500-600mm in dept and the slabs typically 200mm.

Transfer structures have been limited wherever possible to maximise the efficiency of the structure. They are present only above the loading dock to allow sufficient clearance for truck turning paths and in discrete areas where mezzanine columns do not align.

Column sizes have been standardised to simplify formwork and maximise construction efficiency. Columns are typically square within the operational zone and circular where exposed to view.

6.8 Feature stairs

The feature stairs to the north, south, east and west provide a key architectural feature to the facility as well as vertical access and egress to the main retail level at upper ground. A number of options for the support structure were developed during the design phase, with a significant focus on constructability whilst maintaining the architectural intent. The design is currently for a Steel and bondek system on the North, West and East stairs, and a precast concrete system on the South stairs.

All stairs require a degree of precambering of the steel elements to keep dead and superimposed deflections within allowable limits. The ability to shim and raise specific beams has also been factored into the design to allow for construction tolerances and ensure targt RL's can be achieved.

A consistent feature of the stairs is the spandrel that runs continuously around the perimeter of the building. Structure depths and details have therefore been carefully controlled in this area to maintain this approach.

Due to their nature, a dynamic footfall analysis will been undertaken for each stair to ensure it complies with the limits. Fire protection will be provided in accordance with the fire rating requirements.

6.9 Mezzanine

The mezzanine structure comprises composite metal decking slab on steel beams. This has been driven by the irregular nature of the slab outline and the associated lack of continuity, refer to Figure 6-12 & Figure 6-13 – Mezzaine steel . Studs are shot fired to the top of the beams after the metal decking is laid.




Figure 6-12 - Mezzaine steel layout




Figure 6-13 – Mezzaine steel typical section

6.10 Stability system

Lateral stability to the facility is provided by the four concrete cores that extend up to the roof which are in turn supported on raking piles, highlighted in Figure 6-14 – Building Stability Cores. Significant tie forces are developed in the raking pile to lift core connection. The detailing in this area together with finalising the magnitude of the tension forces within the piles will be developed during detailed design phase.




Figure 6-14 - Building Stability Cores

6.11 Roof Structure

A number of options were investigated for the primary roof structure during the design process. Long span glulam timber beams have been adopted as they aligned with the architectural intent and provided advantages from a corrosion perspective.

The current prefered option comprises timber beams arranged in a defined primary and secondary arrangement. Discussions with timber suppliers and manufacturers are ongoing to determine the schemes feasibility, with a focus on fabrication, erection and joints.

Columns are provided on every second grid, with the structure depth governed by a combination of the longer main spans and the longest cantilever.




Figure 6-15 - Roof concept (3XN)





Figure 6-16 - Roof concept (3XN)

Due to the form of the roof, there are few locations available for the inclusion of rainwater overflows. The sensitivity of the long spanning roof however makes it uneconomical to allow for the pooling of large amounts of water on the roof. As a result, various options are being explored to dissipate the water using bunding, secondary siphonic systems and possibly large sumps over the lift cores.

Where possible, elements of the roof are prefabricated or constructed on ground then lifted into place to limit the amount of work performed on site and/or at height. All timber members are prefabricated with steel plates that either bolt to other members and columns or receive roof pods. Roof pods have been modularised to 4 variations of diamond shapes and designed for the temporary case of crane lifting, again with only bolted connections at height to the timber. The variation in size of pods and oversized bolt holes at connections caters for manufacture and






Figure 6-17 - Roof concept (3XN)

6.12 Promenade structure

The promenade structure will be independent to the main building, with permenant joints. The promenade structure is braced using raking piles. The approximate extent can be seen in **Figure 6-18**.




Figure 6-18 – Promenade structure extent

The structure comprises precast beams and double T-slabs with an insitu topping. Steps in the precast level is achieved by bearing primary precast beams on top of one another over a common pile.

6.13 Wharf Structures

Wharf structures will be required to facilitate a number of functions including fishing operations, public and private vessels, charter boats and ferries as indicated in Figure 6-19 – Preliminary wharf berthing plan (3XN). Currently the wharfs are envisaged to be proprietary systems like those provided by a supplier such as Bellingham or Superior Jetties.

The specific wharf type adopted will be developed during the design process as the functional brief better informs the design.

The wharf piles will likely be similar in nature to those of the main facility, i.e. steel hollow section driven to rock. The piles and the wharf structure will be designed for the relevant lateral loads imposed by tide, wave, and impact from various marine vessels via energy absorption of either the vessels, deck, or fenders.




Figure 6-19 – Preliminary wharf berthing plan (3XN)

7 Civil Design

The civil design has focused on four key areas of the project:

- Bridge Road
- Overland Flow
- Site stormwater
- Rock Revetment

7.1 Bridge Road

Initial traffic studies undertaken by Mott MacDonald, followed by a detailed TIA by ARUP have informed the traffic demands of the new facility on the surrounding road network and the associated intersections at Wattle St and Wentworth Park Road. Reference should be made to the Traffic Impact Assessment undertaken by ARUP for a broader understanding of the facilities impact on the surrounding road network.

The existing lane widths on PBR are non-compliant with current RMS standards. Since the road is being reconfigured for the new facility, and being brought up in level, there is a requirement to bring it up to current standard. The new lanes widths inform the pedestrian concourse and available space for drop off zones, bike paths etc.

The proposed layout is indicated below in Figure 7-1. A central reservation has been provided to maintain straight sections of road and consistent lane widths. The final layout has been developed in conjunction with RMS following several interactive sessions, comments and design revisions.




Figure 7-1 – Bridge Road Layout

The strategic concept design drawings and design report have been issued to RMS for initial commentary with the intent to receive RMS in-principal agreement of the concept design layout and extent of proposed works. For more detailed information relating to the Bridge Road design refer the Bridge Road design report (separate to this report).

7.2 Overland Flow

Flood modelling for the precinct has been undertaken by Cardno. Mott MacDonald have provided Cardno with the civil levels against which the modelling is undertaken. The geometry of Bridge road and the two intersections have been modified to allow the upstream catchment overland flow into the bay without adversely affecting the new facility and the surrounding developments. In order to avoid any adverse impact to the surrounding areas, the western and eastern plaza have been designed to ensure an overland flow route is formed as part of the public domain design.

The full flooding assessment including the overland flow route has been documented in Cardno's flood report.

7.3 Site stormwater

The site has been separated to two catchment areas, the roof and the external hardstands such as water front promenade, plaza's and Bridge Road promenande.

7.3.1 Roof water

The rainwater from the roof will be harvested in a tank inside the building for re-use. The external building drainage system has been designed to allow connection to roof downpipes and overflow pipes. The flow from this drainage system is generally clean roof water which will discharge directly into the bay.

7.3.2 Promenade and Plaza

The runoff from the external areas such as the waterfront promenade and the eastern and western plazas will be captured by the site stormwater drainage system which comprises pits and trench drains. The captured stormwater from these areas is piped to a localised stormwater quality treatment device placed within the site and treated prior to discharging into the harbour. Some of the areas in the western and eastern plaza will flow into an on-grade biofiltration swale where the surface runoff is treated prior to discharging into the harbour.

7.3.3 Lower Ground Floor

Any surface runoff from the loading dock will be captured by a separate building hydraulic system which will be piped to the localised quality treatment devices to remove/reduce hydrocarbons in the runoff prior to discharging into the trade waste system. A section of the lower ground floor area adjacent to the loading dock and wharves is located beyond the roofline as illustrated in Figure 7-2. Trench drains will be provided along the edge of this area to intercept and capture any surface flow.




Figure 7-2 - Lower Ground Floor

7.3.4 External Stairs

Analysis has been undertaken to identify any drainage requirements for the external stairs. Australia Rainfall and Runoff have specific requirements regarding hazardous flow for pedestrians. The standard requirement is for D (depth of flow) multiplied by V (velocity) to be less than 0.4. There are four (4) external stairs located around the building connecting upper ground floor to the Western Plaza, Eastern Plaza, Waterfront promenade and Bridge Road promenade.

DRAINS models have found the DV values at all the four stairs to be below 0.4. Therefore, there is no requirement to provide drainage to capture surface runoff in between landings and only a trench drain at the bottom of the stairs will be provided.

7.4 Water Quality Modelling

A detailed water quality assessment has been undertaken by Cardno using MUSIC software and the results of the assessment are documented in the Water Quality, Soils and Contamination report prepared by Cardno.

7.5 Rock Revetment

A sea wall condition assessment has been undertaken by Royal Haskoning DHV. The assessment identified two (2) sections of the the existing sea wall to have deteriotiate beyond repair and require replacement (See Figure 7-3 for locations).




Figure 7-3 - Location of New Sea Wall

The new sea wall will be formed using rock revetment. Figure 7-4 shows a typical section detail of the rock revetment and Figure 7-5 shows a typical section with drainage outlet.




Figure 7-4 - Typical Section




Figure 7-5 - Typical Section With Drainage Outlet

Mott MacDonald | The new Sydney Fish Market Development Application – Structural, Civil and Maritime Design Report

8 Appendices




Figure 8-1 – Existing Service adjacent Pyrmont Bridge Road




Figure 8-2 – IPCC Sea Level Rise Scenarios – Sydney Tides




Figure 8-3 – Plan showing location of existing sea wall

A. Safety in Design - Designers Hazard Elimination and Management Record

Safety in Design - Designers' Hazard Elimination and Management Record



Projec	ct Title & Brief Description		Project Num	nber			Pro	jec	t Ma	anager						
Sydn	ey Fish Markets (new structu	re)	385951						Graham Babcock							
			Division or Sub-Division						Design Safety Co-ordinator							
			SYD				Alex Been									
Scope		Demolition of existing structures,	design and	cons	stru	ction of new fish market with basement level(s) below water		m ľ	No /	Revision						
Desig	n	table.					В									
(1)	(2)	(3)	(4)	(5	,	(6)		(7)		(8)	(9)	(10)	(11)			
Haz Ref	Activity/Process/ Material/Element	Hazard	Stage of Work	Initial	l Ris vel ¹	Risk Control Measures: Design action taken, record of decision process	_	Residual Is there a		If answer to (8)	Person responsible	Status Within MM				
Нах	Waterial/ Lierrient			Lev	vei	including option considered, design	IXION	isk Level 'significant'2 residual risk			is Yes,	for control of	(Active /			
				lity	7	constraints and justification for	lity	,	Level	to be	information	hazard	Closed)			
				Probability Severity		options/actions not having been taken.	Probability	Severity	, Le	passed on? (Y/N)	flow: D/R/F ³					
				Pro	Diek	(Eliminate, Reduce, Inform, Control)	Pro	Sev	Risk	(1/14)	D/IV/I					
						Prior to undertaking demolition works, Contractor to understand loading capacity	f									
						existing structure. This is currently a combination of the Hanson concrete factory and the Blackwattle Marina. Since concrete trucks currently regularly use the										
						Hanson site. It can be assumed this area has adequate capacity to continue to										
						support construction vehicles. It is likely the Blackwattle Marina will have the sam	:									
		Collapse of structure during demolition,				capacity however this may need to be verified. Any failure would likely be in the form of localised cracking of the wearing surface and therefore not represent a										
	Demolition of existing structure	including any parts to be retained	Demolition	A 2	2 I	significant risk.	Α	2	L	Υ	N/A	Contractor	Active			
						Demolition of marine structures is a specialist skill that should be undertaken by a compentant contractor with significant, proven experience in this area. Selection of	.									
	Demolition of existing marine					appropriate contractor should account for a proven track record of the safe										
2	2 structure	Drowning, injury during demolition	Demolition	B 4	4 H	demolition of marine structures. Demolition plan to be provided.	Α	4	M	Υ	N/A	Owner	Active			
						Temporary works designs to be supplied by the contractor. Temoprary propping of	:									
						retaining walls to consider adjacent in-ground services which may be affected by										
						wall deflections and subsequent ground settlement. Currently, deep excavations are not expected to form part of the design of the facility since it is constructed										
	Basement excavations - Deep					primarily over water. There may be excavations associated with in ground										
3	excavations	Collapse of excavations	Construction	В	4 H	detention pits, in this case the above should apply.	Α	4	M	Υ	D and R	Contractor	Active			
						Ground investigation highlighted presence of contaminated ground. Contractor to										
	Excavation / ground works	Exposure to contaminated ground	Construction	C 2	2 H	prepare safe work method statement for work to and for safe treatment and disposal of contaminated ground.	В	2	М	Y	D and R	Contractor	Active			
			Conoci dollori			aropessa. S. Somanimatou ground.	-	-	141	'	Danuix	Johnaciol	, 101170			
						Existing services survey has been undertaken and will be provided to the										
						contractor. Contractor to undertake detailed review of existing in-ground services,										
	5 Excavation / ground works	Contact with existing services, electrocution	Construction	C 4	4	and follow proper procedure in exposing and removing/moving existing services, informing all construction persons of existing services locations.	В	4	ш	Y	D and R	Contractor	Active			
F ,	Excavation/ ground works	Contact with existing services, electrocution	Construction	C 2	4	milorning all construction persons of existing services locations.	В	4		ī	D and K	Contractor	Active			
		Injury from contact with equipment casued by				Contractor to determine and incorporate the required work area and safe access procedures with operator										
		congested and busy areas.				Contractor to ensure all site personal and those visiting site have had the required										
						inductions and are wearing the correct PPE. Contractor to ensure correct storage										
	Construction - Worker Safety	Fatality on wharf apron due to collision with operations vehicles and construciton vehicles	Construction	C 4	4	of materials. Consultants to consider staged design such that different elements are incorporated at different times so as not to cause congested areas.	В	4	ш	Y	D and R	Contractor	Active			
	Journal deligit - worker Salety	operations verifices and construction verifices	CONSTRUCTION	U 4	7	are moorperated at different times so as not to cause congested areas.	ם	4	-11	ſ	D allu K	Contractor	VCIIA6			

Safety in Design - Designers' Hazard Elimination and Management Record



<u> </u>	Project Title & Brief Description Project Number Project Manager																
	ct Title & Brief Description ey Fish Markets (new structi	uro)	Project Number						Project Manager Graham Babcock								
Syund	ey Fish Markets (Hew Structt	ne)	385951 Division or Sub-Division														
			SYD	Տան-ւ	וועוכ	SIOTI	Design Safety Co-ordinator										
Soone	of .	Demolition of evicting structures	_	laan		action of new fish market with basement level(s) below water	Alex Been Form No / Revision										
Scope of Demolition of existing structures, Design table.			uesign and	COII	Sur	iction of new fish market with basement lever(s) below water	B	111	INU	/ IXEVISION							
			(4)	,	· - \	(0)							(4.4)				
(1)	(2) Activity/Process/	(3) Hazard	(4) Stage of Work	,	(5) Il Ris	(6) k Risk Control Measures: Design action		(7) sidu		(8) Is there a	(9) If answer	(10) Person	(11) Status				
Haz Ref	Material/Element				vel ¹	taken, record of decision process	Ris			'significant'2	to (8)	responsible	Within MM				
Ξ̈́				_	Τ-	including option considered, design constraints and justification for	_		I —	residual risk to be	is Yes, information	for control of hazard	(Active / Closed)				
				Probability	≨ €	options/actions not having been taken.	Probability	iŧ	Level	passed on?	flow:	nazara	Olosca)				
				roba	Seventy	(Flimingto Bodyno Inform Control)	roba	ever	Risk Lev	(Y/N)	D/R/F ³						
				ه ر	Ď o		۵	Ø	22								
						Liaise with operator and harbourmaster to determine safe work arrangements at berth locations and avoid clashes with the potential to form an exclusion zone											
						around the site perimeter.											
						Occupated to Private 1th Occupation and bank are accepted to the form											
						Operator to liaise with Contractor and harbour master to confirm berth arrangement to avoid clashes											
						Ť											
		Diver fatality from collision with vessels at				Document requirement for liaison between operator and Contractor in technical speification											
7	Construction - Worker Safety	berth	Construction	В	5	S	Α	5	L	Υ	N/A	Contractor	Active				
		Collapse or failure of structural system or	:			Design will consider temporary construction loads in the permanent design of the											
3	Temporary Works	integrity of temporary supports.	Construction	В	4 I	structure where appropriate. Contractor to appoint temporary works engineers to ensure all temp works are	В	4	Н	Y	N/A	Contractor	Active				
		Collapse or failure of structural system or				safely and properly designed to standard requirements, ensuring all load bearing											
9	Temporary Works	integrity of temporary supports.	Construction	В	4 I	requirements are met.	В	4	Н	Υ	N/A	Contractor	Active				
						Design to consider future water levels due to sea level rise. This will be based of											
						IPCC data. Initial design to consider impact of wave height in conjunction with high tides for extreme peak uplifts.											
10	Design - Hydrostatic pressure	Tidal lag unknown	Construction	С	3 H	Sea wall structures will be designed for a full head of water.	Α	3	L	N	D	Designer	Active				
						Avoid designing structure extending below the water table. If structure is designed for under-water basement, water-retaining structure must be designed suitably for											
						the hydrostatic pressure imposed by sub-marine location. Use of a membrane to											
						ensure water does not leak through walls, also walls are to be designed to contain											
						reinforcement sufficient to act as a water retaining structure.											
						Current prefered design results in structure located at or below water level. Three											
						lines of protection are currently proposed. Precast concrete design as water											
						retaining structure with pour strips between panels + membrane + Insitu concrete slab and walls design as water retaining structure.											
		Flooding of underground basement(s) due to				Contractor and designer to ensure any alternate solutions provide adequate / equivalent protection. Contractor to ensure all stainless steel is kept free from non											
		leak(s) in structure. Potential to cause				stainless corrosion inducing contaminants to prevent failure of first line of defence.											
		significant structural damage / failure which				Contractor to ensure all membranes are installed in accordance with manfacturers											
11	Basement construction	may lead to injury and loss of life.	Construction	В	4 H	recommendations and have the relevant warranties following installation.	Α	4	M	Υ	R and F	Contractor	Active				

Safety in Design - Designers' Hazard Elimination and Management Record



Desia	at Title 9 Drief Decemention		Dualast Nivo				Desi	:4	4 N / A				1				
	ct Title & Brief Description ey Fish Markets (new structu	re)	Project Number 385951						Project Manager Graham Babcock								
Jun	oy i ion markete (non en acta	. 5,	Division or Sub-Division						Design Safety Co-ordinator								
			SYD	Jub 1	J1V10		Alex Been										
Scop	e of	Demolition of existing structures.		con	strı	ction of new fish market with basement level(s) below water	Form No / Revision										
Design table.						(0, 2000)	B										
(1)	(2)	(3)	(4)	(5)	(6)		(7)		(8)	(9) (10)	(11)					
. Sef	Activity/Process/	Hazard	Stage of Work	Initia	l Ris	Risk Control Measures: Design action	Res	sidu		Is there a	If answer	Person	Status				
Haz Ref	Material/Element			Le	vel ¹	taken, record of decision process including option considered, design	Risk	sk Level		'significant' ² residual risk	to (8) is Yes,	responsible for control of	Within MM (Active /				
-				ξį	3	constraints and justification for	Ξź		ē	to be	information	hazard	Closed)				
				Probability		options/actions not having been taken. (Eliminate, Reduce, Inform, Control)	Probability	Severity	Level	passed on?	flow:						
				Prok	Sev Pick	(Eliminate, Reduce, Inform, Control)	Prok	Seve	Risk	(Y/N)	D/R/F ³						
1.	2 Basement construction	Failure of the pumps causing hydrostatic uplift in excess of design cases on the piles prior to installation of ground floor	Construction	В	4 1	The design has been undertaken such that the piles have an uplift capacity in them; this is sufficient for most cases, with the exception being the exteme king tide and storm surge. The contractor is to ensure they have multiple duty and standby pumps with several lines of redundancy to cater for pump failures. The contractor should ensure there are sufficient back up power generation methods on site to cater for a grid black out. Pumps are to have continuous network linked monitors to send warning text messages to contractors should an out of hours failure occur.		4	M	Υ	R and F	Contractor	Active				
1.	3 Basement construction	Failure of cofferdam causing flooding of site during construction	Construction	В	5 1	Cofferdam to be designed and installed by specialist subcontractor in accordance with australian standards. Design to be reviewed and approved by clients maritme engineer to confirm adequate. Installation to be inspected by clients maritime engineer. The contractor is to develop an adequate evactuation strategy as the last line of defence, ensuring there are multiple exit points.		5	M	Υ	F	Contractor	Active				



	ct Title & Brief Description ey Fish Markets (new structu	re)	Project Nun 385951	nber				Project Manager Graham Babcock						
			Division or S	Sub-l	Divi	isio	on	Design Safety Co-ordinator						
			SYD					Alex Been						
Scope			g (-, (-,					Form No / Revision						
Desig	T	table.	<u> </u>					В				T		
(1)	(2) Activity/Process/	(3) Hazard	(4) Stage of Work		(5) al Die	ck	(6) Risk Control Measures: Design action	Þ	(7)) dual	(8) Is there a	(9) If answer	(10) Person	(11) Status
Haz Ref	Material/Element	riazaiu	Stage of Work		vel ¹		taken, record of decision process			_eve		to (8)	responsible	Within MM
Ξ							including option considered, design				residual risk	is Yes,	for control of	(Active /
				oility		evel	constraints and justification for options/actions not having been taken.	Jility		evel	to be passed on?	information flow:	hazard	Closed)
				Probability	Severity	S L		Probability	evi	Risk Level	(Y/N)	D/R/F ³		
				<u> </u>	Š	œ.	(Eliminate, Reduce, Inform, Control)	4	Š	i z				
							Mitigate direction of over-ground flow and design accordingly a system by which							
		Ground water flow running into new structure					this water is diverted elsewhere (such as a grated walkway into new structure such							
14	Stormwater design	causing flooding which may cause drowning.	Construction	Α	4		that runoff water flows through and down into existing marine body.	Α	4	. M	N	N/A	Contractor	Active
							Implement measures at design stage which allow the structure to meet durability requirements. Including selection of materials and design of individual							
							components.							
		Premature corrosion of structural elements leading to inadequate structural capacity in					This may include cathodic protection of steel elements that may require ongoing							
15	Operation - Durability of structure	future	Operation	С	3		maintenance.	Α	3	L	N	D	Designer	Active
							Design and construct appropriate railings around the perimieter of the structure							
		Workers or pedestrians falling into water					above water. Architect to consider signage warning people not to stay too close to							
16	Use of facility	from new structure.	Operation	В	3	M	the perimeter of the structure.	В	3	M	N	N/A	Designer	Active
							Use best marine contractors to minimise risk to workers and public.							
							Marine works as far as possible should be from the water to avoid having to							
							transport large piles or precast elements along busy city arteries. That is, all piles							
						<u>'</u>	etc barged to site. Minimising traffic hazard and risk.							
							All lifts to be with single floating crane. Multiple crane lifts on floating gear is							
							uninsurable risk. Need large crane.							
							Piling installation wherever possible to be early morning 5 to 7 am, ie before							
							Harbour traffic to avoid disturbance to floating gear.							
		General construction risks associated with a					Maximise elevation of concrete work and steel fabrication to avoid tidal delays and							
17	Construction of basement	marine environment	Construction	С	3	Н	risks.	В	3	M	Y	D and R	Contractor	Active



,	ect Title & Brief Description		Project Number					Project Manager						
Sydi	ney Fish Markets (new structu	re)	385951					Graham Babcock Design Safety Co-ordinator						
			Division or	Sub-l	Divi	sior			-	•	ordinator			
			SYD					Alex						
Scop			, design and construction of new fish market with basement level(s) below water					Form No / Revision						
Desi	gn	table.						В						
(1)	(2)	(3)	(4)			,	7)	(8)	(9)	(10)	(11)			
Haz Ref	Activity/Process/ Material/Element	Hazard	Stage of Work				Risk Control Measures: Design action aken, record of decision process	Res Risk	idual			Person responsible	Status Within MM	
Наz	Material/Element			Le	vel ¹		ncluding option considered, design	KISK	Leve	l 'significant residual ris		for control of	(Active /	
-				iţ	-	<u>a</u> c		Ξź	<u>a</u>	to be	information		Closed)	
				Probability	Severity	_	ptions/actions not having been taken.	Probability	Seventy Risk Level	passed on				
				cop	eve :	조 (I 종	Eliminate, Reduce, Inform, Control)	g	sk eve	(Y/N)	D/R/F ³			
				ш,	ו נט	<u>r</u> (.	Eliminate, reduced, mierri, centreri	ш (<i>n</i>					
						c	Contractor to ensure all works associated with the construction of the basement							
							vhilst it is not in a water tight condition are undertaken by team members pecifically trained in working in that environment.							
							The design has been developed on the ability to construct the majority of lowest							
							pasement structure whilst the tide is out such that the water level is below the top forecast beams & slab.							
						to	The piles after being driven into the sandstone will ned to be cut to the correct level to accept the precast beams. Contractor to ensure cutting of piles is undertaken by pecialist divers with all appropriate safety measures and support staff in place.							
						p	The precast beams can be placed directly onto the piles before being grouted into osition. Contractor to ensure this is undertaken in a controlled manner, with staff upervising precast lift from barges with adequate protection.							
						p b	The precast slabs have been designed such that they can be lifted and fixed into blace with minimal labour, i.e. stainless steel anchors are provided to fix planks to learns so that they can remain in place temporarily until fixed permanently via velding.							
						th C	All welding of stainless steel is to be undertaken by specifally trained contractors hat have a proven track record of undertaking thius work in a marine environment. Contractor to ensure all measures are put in place to ensure the safety of thier staff luring this and all other operations.							
	18 Construction of basement	Crushing of limbs during installation of precast. Slips trips and falls, drowning, electrocution due to water inflow from bay during construction of basement.	Construction	С	3	a	f contractor employs temporary measures to maintain a level of water tightness to illow the waterproofing works to commnce early, this will be under the agreement of all parties responsible for ensuring the water tightness.	В	3 N	1 Y	D and R	Contractor	Active	
	19 Storage of construction materials	Overloading the structure with materials and machinery	Construction	В	2	е	Ensure that the construction load does not exceed the design load. Consult design engineer prior to placing machinery on the structure. Provide temporary propping is required.	В	2 N	1 N	N/A	Contractor	Active	



Droio	ct Title & Brief Description		Drainat Nua	ha				Dr	oio	o+ N	longger			
	ct Title & Brief Description ey Fish Markets (new structu	re)	Project Nun 385951	ibei	Γ			Project Manager Graham Babcock						
Oyun	cy i isii markets (new structu	,	Division or S	Sub	Di	vici	20	Design Safety Co-ordinator						
			SYD	Jub	וטיי	VISI	JII	Alex Been						
Coop	o of	Demolition of evicting structures	_				tion of now fish monket with hooment level(a) helew water							
Scop		table.	9 9					Form No / Revision B						
	1	1	(1)								1 (-)	(=)	1 (1.5)	
(1)	(2) Activity/Process/	(3) Hazard	(4) Stage of Work		(5) ial E	Risk	(6) Risk Control Measures: Design action	D.	(7) esid		(8) Is there a	(9) If answer	(10) Person	(11) Status
Haz Ref	Material/Element	riazaiu	Stage of Work		.eve		taken, record of decision process			iuai evel		to (8)	responsible	Within MM
Ha							including option considered, design				residual risk	is Yes,	for control of	(Active /
				ility	>	Ne.	constraints and justification for	iit	_	Ne Ve	to be	information	hazard	Closed)
				Probability	erity	⟨ Le√	options/actions not having been taken.	Probability	erit	Risk Level	passed on? (Y/N)	flow: D/R/F ³		
				Pro	Severity	Risk	(Eliminate, Reduce, Inform, Control)	Pro	Severity	Ris	(1/14)	D/IV/I		
							Design to maximise use of prefabrication simplification of connections to minimise							
							manual handling at height. Timber elements to have steel plates embeded offsite where possible to allow simple steel to steel connections on site. Pods to be]	
							modularised as far as possible to minimise working at height. lifting lugs on pods							
							could be retained and utilised as fall restraint.							
							Contractor to provide scaffolding and appropriate fall arrest systems as required.							
		lle edite e of stool/timb on other store or d					Contractor to provide scandiding and appropriate rail arrest systems as required.							
2	Steel Erection	Handling of steel/timber structure and connections - fallilng from height	Construction	D	3	S		В	3	м	N	N/A	Contractor	Active
		l l l l l l l l l l l l l l l l l l l		_	Ŭ	Ť	Design to be in accordance with manfucaturers recommendations.	<u> </u>	Ť		.,	1471	oondoto.	7.00.70
		Failure of machanical and chemical anchors.												
2	Structural elements fixed via anchors	Injury as a result of anchor installation.	Construction	С	4	S	Follow installation specification by anchor manufacturer.	Α	4	М	N	N/A	Contractor	Active
							Shoring engineer to ensure the shoring design includes the loading effect from adjacent structures.							
							adjacon chadaros.							
							Surveys of existing structures to understand latent conditions to be undertaken.							
							Contractor to follow construction sequence and requirements on shoring							
							documentation.							
2	2 Excavation	Undermine adjacent structures.	Construction	С	2	н		В	2	М	N	N/A	Contractor	Active
		Large moving crowds (particularly in an	_										_	
		emergency event) can cause a crush,					Barriers in emergency escape pathways and as designated by the BCA consultant]	
2	Movement of people and materials	resulting in injury or even death.	Operation	С	4	S	to be designed for crowd loading.	Α	4	М	N	N/A	Designer	Active
							Structure to consider vehicle impact loading as appropriate to the functional space]	
							and vehicle type. Loading docks may require large impact loading compared to standard car park structure.							
							·]	
							Risk of IED explosive or vehicle explosive to be addressed in design with]	
							appropriate mitigation strategies employed. Vehicle barriers or structural strengthening.							
]	
		Vehicular impact with new structure both												
		accidental and deliberate, can cause												
2	Movement of people and materials	structural failure and thus injury and death.	Operation	Α	4	M		Α	1	L	N	N/A	Designer	Active
							Saparation of nedgetrian and vehicular accessible areas, correct signers to							
							Separation of pedestrian and vehicular accessible areas, correct signage to indicate passenger/vehicle directions, implement speed limits for vehicles. Design							
							to ensure as far as reasonably practicable that fish market vehicles (forklifts,							
_	Managed of a conference of a conference of	Vehicular impact with pedestrians, can cause	0	_			delivery trucks, etc) have their own delivery bay with exclusive access to fish	_	١.		.,		D	A - 12 -
2	Movement of people and materials	injury or death.	Operation	С	4	S	market sales floors.	В	4	Н	Y	D	Designer	Active



	ct Title & Brief Description ey Fish Markets (new structur		Project Nun 385951	nber				Project Manager Graham Babcock						
			Division or	Sub-	Divis	isior	n	Des	ign	Sa	afety Co-ord	dinator		
			SYD					Alex Been						
Scop	e of	Demolition of existing structures,	design and	con	stru	ucti	ion of new fish market with basement level(s) below water	Form No / Revision						
Desig	Design table.					В								
(1) e	(2) Activity/Process/	(3) Hazard	(4) Stage of Work		(5) al Ris		(6) Risk Control Measures: Design action	Res	7) sidua		(8) Is there a	(9) If answer	(10) Person	(11) Status
Haz Ref	Material/Element			Le	vel ¹		aken, record of decision process ncluding option considered, design	Risk	Lev	/el	'significant' ² residual risk	to (8) is Yes.	responsible for control of	Within MM (Active /
				Probability		<u>o</u> c	constraints and justification for options/actions not having been taken.	Probability	ııty .	Level	to be passed on?	information flow:	hazard	Closed)
				Prob	Severity	XiS (I	Eliminate, Reduce, Inform, Control)	Prob	Seventy	Risk	(Y/N)	D/R/F ³		
						S	Signage to be provided around fish market marine area, enforcing a speed limit for ressels, implementing tie-up/docking areas for boats.							
2	6 Movement of people and materials	Vehicular (boat) impact with new structure	Operation	D	3		Wharf structures to be designed for impact loads from marine equipment as would normally be required for a facility of this type.	В	3	M	Υ	R and F	Contractor	Active
2	Installation/maintenance/replacement of building services plant and quipment	Injury sustained from manual handling/lifting of plant and equipment to plantroom.	Maintenance	С	3 H		Allowances for access hatches to be provided in design for lifting/lowering plant equipment, and clear horizontal routes provided to plantrooms.	A	3	L	N	N/A	Contractor	Active
2	Installation/maintenance of plant 8 equipment on roof	Falling from height	Maintenance	В	4 H	p	Parapet or fence to be provided around all roof level plant, stair access to be provided for all rooftop plantroom areas. Lifting eyelets for modular roof could potentially be utilised for static lines.	А	4	M	Ν	N/A	Contractor	Active
2	9 Plant maintenance	Injury resulting from replacement of equipment in tight/confined/difficult to access spaces	Maintenance	С	2 H		Plantroom layouts to allow for sufficient space for maintenance and replacement of plant.	А	2	L	N	N/A	Designer	Active



	Project Title & Brief Description Sydney Fish Markets (new structure)			,				Project Manager Graham Babcock				
							Design Safety Co-ordinator					
			SYD			Alex Be						
_				construc	ction of new fish market with basement level(s) below water	Form No / Revision						
Desigi	Design table.					В						
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)		
Ref	Activity/Process/	Hazard	Stage of Work		Risk Control Measures: Design action	Residual	Is there a	If answer	Person	Status		
Haz Ref	Material/Element			_0.0.	taken, record of decision process including option considered, design	Risk Leve	'significant'2	to (8) is Yes,	responsible for control of	Within MM (Active /		
I					constraints and justification for	<u>Fi</u>	residual risk to be	information	hazard	Closed)		
				robability severity tisk Level	options/actions not having been taken.	abili erity	passed on?	flow:				
				Prob Seve Risk	(Eliminate, Reduce, Inform, Control)	Probability Severity Risk Level	(Y/N)	D/R/F ³				

Checked	and	api	orov	/ed	bv ((see	note	4):

Name: Graham Babcock Signature: Date: 26/07/2018

Notes

- 1 Use Hazard Quantification Tables
- 2 Significant risks are not necessarily those that involve the greatest risks, but those, including health risks that are: (a) not likely to be obvious to a competent contractor or other designers; (b) unusual; or (c) likely to be difficult to manage effectively.
- 3 Information codes: D = Information detailed on drawings (add drawing nos); R = Information for Safety in Design Report; F = Information for Health and Safety File
- 4 Project Manager (or Design Team Leader, as appropriate) to check and approve Record unless the design work has been carried out directly by the Project Manager (or Design Team Leader) in which case the Record is to be checked and approved by the Project Director (or Sub-Project Director, as appropriate).



,	Project Title & Brief Description Sydney Fish Markets (new structure)			, ·				Project Manager Graham Babcock					
				Division or Sub-Division				Design Safety Co-ordinator					
			SYD			Alex Bee	en						
Scope of Demolition of existing structures.			design and	construc	tion of new fish market with basement level(s) below water	Form No	/ Revision						
Design table.						В							
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)			
Ref	Activity/Process/	Hazard	Stage of Work	Initial Risk	Risk Control Measures: Design action	Residual	Is there a	If answer	Person	Status			
Z F	Material/Element				taken, record of decision process	Risk Level	'significant'2	to (8)	responsible				
Η̈́					including option considered, design		residual risk	,	for control of	`			
				ye ii	constraints and justification for	vel ##	to be	information	hazard	Closed)			
				ا تا ه	options/actions not having been taken.	ability erity Level	passed on?	flow:					
				Prob Seve	(Eliminate, Reduce, Inform, Control)	Probabili Severity Risk Lev	(Y/N)	D/R/F ³					

Likelihood	
Probability of Occurrence	Probability Index
So unlikely that probability is close to zero	А
Unlikely to occur, though conceivable	В
Likely to occur sometime	С
Occurrence not surprising. May occur more than once	D
Occurrence inevitable. May occur many times	E

Severity	
Potential Maximum	Hazard
Consequence (Hazard	Severity
Severity)	Index
Minor injury/illness resulting	1
in lost time of 3 days or less	
Injury/illness causing lost time	2
more than 3 days	
Major illness/injury to one or	
more persons not causing	3
permanent disability	
Single fatality or	
single/multiple permanent	4
disability	
Multiple fatality	5
wantplo latality	

Risk Level					1
Hazard Severity Index	Pro	babili	ity Ind	ex	
muex	Α	В	С	D	E
1	L	L	М	Ι	Н
2	J	М	Ι	Ι	Н
3	Ш	M	Ι	S	S
4	М	Н	S	S	S
5	М	Н	S	S	S


Risk Lev	el Action	
Risk Level	Description	Action by Designer
L	Low	Check that risks cannot be
М	Medium	further reduced by simple design changes
н	High	Amend design to reduce risk, or seek alternative option. Only accept option
S	Severe	if justifiable on other grounds.

B. Civil Design Documentation



CITY OF SYDNEY MR 00000 - BRIDGE ROAD

SYDNEY FISH MARKET BRIDGE ROAD UPGRADE FROM WATTLE STREET TO WENTWORTH PARK ROAD CONCEPT DESIGN



PART INDEX

PART NUMBER	SHEET CODE	NAME
	GE	GENERAL
DADT 4	RD	ROAD ALIGNMENT AND DETAIL
PART 1	UT	PUBLIC UTILITIES
	PV	PAVEMENT DESIGN

MM DRAWING SHEET SHEET TITLE NUMBER NUMBER

GENERAL
CI-GE0-A00 GE-0001 GE-0001 COVER SHEET AND INDEX SHEET

GENERAL ARRANGEMENT AND ROAD DESIGN (RD)

 CI-RD1-D10 RD-0011
 RD-0011
 TYPICAL CROSS SECTIONS

 CI-RD3-B20 RD-0301
 RD-0301
 ROADWORKS PLAN SHEET 1 OF 3

 CI-RD3-B20 RD-0302
 RD-0302
 ROADWORKS PLAN SHEET 2 OF 3

 CI-RD3-B20 RD-0303
 RD-0303
 ROADWORKS PLAN SHEET 3 OF 3

 CI-RD3-D20 RD-0401
 RD-0401
 ROADWORKS LONGITUDINAL SECTIONS SHEET 1 OF 3

RD-0402

CI-RD3-D20 RD-0403 UTILITIES (UT)

CI-RD3-D20 RD-0402

CI-UT1-B20 UT-0011 UT-0011 EXISTING UTILITIES LEGEND
CI-UT1-B20 UT-0301 UT-0301 DRAINAGE AND PUBLIC UTILITIES PLAN SHEET 1 OF 3
CI-UT1-B20 UT-0302 UT-0302 DRAINAGE AND PUBLIC UTILITIES PLAN SHEET 2 OF 3
CI-UT1-B20 UT-0303 UT-0303 DRAINAGE AND PUBLIC UTILITIES PLAN SHEET 3 OF 3

PAVEMENT (PV)

 CI-PV1-B20 PV-0301
 PV-0301
 PAVEMENT PLAN SHEET 1 OF 3

 CI-PV1-B20 PV-0302
 PV-0302
 PAVEMENT PLAN SHEET 2 OF 3

 CI-PV1-B20 PV-0303
 PV-0303
 PAVEMENT PLAN SHEET 3 OF 3

NOT FOR CONSTRUCTION

ROADWORKS LONGITUDINAL SECTIONS SHEET 2 OF 3

ROADWORKS LONGITUDINAL SECTIONS SHEET 3 OF 3

3	NOT TO SCALI				
	DRAWING FILE LOCATION / NAME \mottmac\project\Sydney\Projects\38xxxx\385951 Sydney Fish Markets\04 Working\01 Drafting\Civil\Drawings\CI-GE0-A00 GE-000	d dun	LINEAR REFERENCING		PLOT DATE / TIME PLOT BY
-			START: END:		9/25/2019 5:22:45 PM JED64037
ì	PREPARED BY Level 10, 383 Kent Street	DESIGNED	REVIEWED	VERIFIED	RMS PROJECT MANAGER
	Sydney, NSW 2000 Australia				NAME -
-	PO Box Q1678, QVB Sydney	SIGNED -	SIGNED -	SIGNED -	TITLE -
:	NSW 1230, Australia T +61 (0)2 9098 6800	NAME MATTHEW JEDNIUK	NAME ANDREW LEE	NAME BOON SOO	VALIDATION AND ACCEPTANCE OF THESE
	MACDONALD W www.mottmac.com	TITLE PROJECT DESIGNER	TITLE PRINCIPAL HIGHWAY DESIGNER		DRAWINGS AND THE DESIGN SHOWN
	MM DRAWING NUMBER	40.00.00	DATE 14.02.2018	45.00.0040	THEREON IS TO BE CARRIED OUT UNDER
	CI-GE0-A00 GE-0001	DATE 13.02.2018	DATE 14.02.2016	DATE 15.02.2018	SEPARATE PROCESS

UrbanGrowth NSW
Development Corporation

MR 00000 - BRIDGE STREET SYDNEY FISH MARKET BRIDGE ROAD UPGRADE FROM WATTLE STREET TO WE

FROM WATTLE STREET TO WENTWORTH PARK ROAD COVER SHEET

PREPARED FOR URBAN GROWTH

RMS REGISTRATION No.


DS2018/XXXXX


ISSUE STATUS
CONCEPT DESIGN


EDMS No.
SHEET No.
GE-0001


ULTIMO - CITY OF SYDNEY

© Roads and Maritime Services









Sag CH 32.641 RL 2.308

	50mm ON A3 SIZE ORIGINAI
	50mm ON
2	42
720077	40 45
	_

NOT FOR CONSTRUCTION

R-1948.314

0.8%

DRAWING FILE LOCATION / NAME Northmac/project/Sydney/Project/SJ38xxxx385951 Sydney Fish Markets/04 Working/01 Drafting/Civil/Drawings/CI-RD3-D20 RD-0401.dwg DESIGN LOT CODE DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING PLOT BY DATE / TIME PLOT	A3
HORIZONTAL SCALE 1:500 Australia DRG CHECK B.SOO 25,09.19 Australia Development Corporation FROM WATTLE STREET IC) WENTWORTH PARK ROAD
S S I DESIGN JAPACIDEN 2019/19 TROMOVORNS CONSTITUTION LONGITUDINAL SECTION CAPACIDEN 2019/19 TROMOVORNS CONSTITUTION LONGITUDINAL SECTION CAPACIDEN 2019/19 LONGITUDINAL SECTION LONG	ONS SHEET 1 OF 3
VERTICAL SCALE 1:100 MACDONALD T +61 (0)2 9086 6800 Www.mothmac.com DESIGN CHECK V.SOFREVSKI 25,09,19 Www.mothmac.com DESIGN CHECK V.SOFREVSKI 25,09,19 Www.mothmac.com DESIGN CHECK V.SOFREVSKI 25,09,19 WRBAN GROWTH DESIGN CHECK V.SOFREVSKI 25,09,19 WRBAN GROWTH	2018/XXXXXX PART 01
CO-ORDINATE SYSTEM HEIGHT DATUM MM DRAWING NUMBER DESIGN MNGR B.SOO 25,09,19 UNBAN GROWTH ISSUE STATUS	EDMS No. SHEET No. ISSUE
王。 MGA ZONE 56 AHD CI-RD3-D20 RD-0401 PROJECT MIGR G.BABCOCK 25.09.19 CONCEPT DESIGN	RD-0401 1

WATTLE STREET INTERSECTION

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED


O 15 110 115 120 125 130 135 140 145 150mm ON A3 SIZE ORIGINAL

Horizontal Curve 100m VC Vertical Curve -0.8% Grade Datum RL -5.0 Proposed Level 3.1 Existing Level 3.11 Chainage 140.000 140.310 144.272 240.000 1:500 Hor - 1:100 Ver

Longitudinal Section - MC00

NOT FOR CONSTRUCTION

	DRAWING FILE LOCATION / NAME \text{\mottmac\project\Sydney\Projects\38xxxx\385951 Sydney Fish Markets\04 W}	/orking\	\01 Drafting\C	ivil\Drawings\CI-RD3-D20 RD-0402.dwg	DESIGN L	OT CODE	DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF TH		25/9/2019 5:3		PLOT BY PAC82679		ULTIMO - CITY OF SYDNE' MR 00000 - BRIDGE ROAD)	A3]
	EXTERNAL REFERENCE FILES	REV	DATE	AMENDMENT / REVISION DESCRIPTION	WVR No.	APPROVAL	SCALES ON A3 SIZE DRAWING	DRAWINGS / DESIGN PREPARED BY	TITLE	NAME	DATE	-3864- I	SYDNEY FISH MAR	RKET		
₹	(ISSUED FOR CONCEPT DESIGN		B.S00	0 5 10 15 20	Level 10, 383 Kent Street	DRAWN	GA.PACIBEN	25.09.19	UrbanGrowth NSW	BRIDGE ROAD UPO	GRADE		
5 F		1	25.09.2019	RE-ISSUED FOR CONCEPT DESIGN		B.S00	HORIZONTAL SCALE 1:500	Sydney, NSW 2000 Australia	DRG CHECK	B.S00	25.09.19	NSW Development Corporation	FROM WATTLE STI	REET TO WENTWO	ORTH PARK ROAD	
9							0 1 2 3 4	Australia PO Box Q1678, QVB Sydney NSW 1230, Australia	DESIGN	GA.PACIBEN	25.09.19		ROADWORKS LONGITUDII	NAL SECTIONS	SHEET 2 OF 3	,
3							VERTICAL SCALE 1:100	MACDONALD T +61 (0)2 9098 6800 W www.mottmac.com	DESIGN CHECK	V.SOFREVSKI	20.00.10	The state of the s	RMS REGISTRATION No.	DS2018/XX	XXXX PART	1
ر ت							CO-ORDINATE SYSTEM HEIGHT DATUM	MM DRAWING NUMBER	DESIGN MNGR	B.S00	25.09.19	URBAN GROWTH	ISSUE STATUS	EDMS No.	SHEET No. ISSUE	4
É							MGA ZONE 56 AHD		PROJECT MNGR	G.BABCOCK	25.09.19		CONCEPT DESIGN	25mo No.	RD-0402 1	
														0.5		-



WENTWORTH PARK ROAD

NOT FOR CONSTRUCTION

OPIED		260.0	278.5	293.6 298.0 300.0	312.7 320.0 322.7	332.7 340.C	355.0	388.0
INCOMPLETE IF CK	1:500 Hor - 1:100 Ver Longitudinal Section - MC	C00						
K AND MAY BE IT 45 Sommon A3 SIZ								
								NOT FOR CONSTRUCTION
DRAWING FILE LOCATION / NAI	IE 38xxxx\385951 Sydney Fish Markets\04 Working\01 Drafting\Civil\Drawings	s\CI-RD3-D20 RD-0403.dwg	DESIGN LOT CODE	DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF TH	IIS DRAWING	PLOT DATE / TIME 25/9/2019 5:33:33 PM	PLOT BY CLIENT PAC82679	ULTIMO - CITY OF SYDNEY MR 00000 - BRIDGE ROAD
EXTERNAL REFERENCE FILES	0 9.10.2018 ISSUED F	IENT / REVISION DESCRIPTION FOR CONCEPT DESIGN	WVR No. APPROVAL B.SOO	SCALES ON A3 SIZE DRAWING 0 5 10 15 20	DRAWINGS / DESIGN PREPARED BY Level 10, 383 Kent Street	TITLE NAME DRAWN GA.PACIBEN	25.09.19 25.09.19 25.09.19	SYDNEY FISH MARKET ISW BRIDGE ROAD UPGRADE
7ING M.	1 25.09.2019 RE-ISSUE	ED FOR CONCEPT DESIGN	B.SOO	HORIZONTAL SCALE 1:500	Sydney, NSW 2000 Australia PO Box Q1678, QVB Sydney NSW 1230, Australia	DRG CHECK B.SOO DESIGN GA.PACIBEN	25.09.19 Development C	FROM WATTLE STREET TO WENTWORTH PARK ROAD ROADWORKS LONGITUDINAL SECTIONS SHEET 3 OF
DRAW				VERTICAL SCALE 1:100 CO-ORDINATE SYSTEM HEIGHT DATUM	MACPONALD T +61 (0)2 9098 6800 W www.mottmac.com	DESIGN CHECK V.SOFREVSKI DESIGN MNGR B.SOO	25.09.19 PREPARED FOR 25.09.19 URBAN GROWTH	RMS REGISTRATION No. DS2018/XXXXXX PAR 01
SH o				MGA ZONE 56 AHD	CI-RD3-D20 RD-0403	PROJECT MNGR G.BABCOCK	25.09.19	ISSUE STATUS EDMS No. SHEET NO. ISSU RD-0403 1

POLE - LIGHT \oslash STAY POLE ELEC. CABLE JUNCTION BOX □^{E JB} DISTRIBUTION FUSE POINT STAY ANCHOR POLE POLE - POWER POLE - POWER AND LIGHT Q POLE - POWER AND TRANSFORMER DISTRIBUTION FUSE POINT ELEC. CABLE MARKER GARDEN LIGHT \boxtimes HIGH TENSION PYLON ELEC UNDERGROUND LINE — eeu – ELEC UG LINE - DIGITISED – eez – ELEC - HOUSE CONNECTION – eeh – ELECTRICITY CONDUIT - eec -MAJOR TRANSMISSION LINE <u>v</u> ee ____ MINOR TRANSMISSION LINE

EXISTING PUBLIC UTILITIES LEGEND

TELECOMMUNICATIONS SUMP						
TELECOMMUNICATIONS SINGLE CONCRETE PIT						
TELECOMMUNICATIONS TWIN CONCRETE PIT						
OPTICAL FIBRE CABLE MARKER						
TELECOMMUNICATIONS DISTRIBUTION PILLAR						
	OTPL					
TELECOMMUNICATIONS LINE ———— e						
TELECOMMUNICATIONS - DIGITISED ————————————————————————————————————						
	I PILLAR					

WATER MAIN MARKER	₩M	
WATER HYDRANT	□WH	
STOP VALVE		
WATER METER	M	
WATER TAP		
AIR VALVE		
WATER - HOUSE CONNECTION	——еw	h
WATER MAIN	/	
WATER MAIN - DIGITISED	z	

SEWER VENT PIPE	O ₂ /
SEWER LAMPHOLE	OSI
SEWER MANHOLE COVER	$\overline{}$
SEWER MAIN	es
	•
EXISTING STORMWATER LINE	esw —
GAS MAIN	———elg —
	•
RMS TRAFFIC SIGNAL CONDUIT	rms
	•
EXISTING UTILITY LINE TO BE DECOMMISSIONED	* * * *

UTILITY DISCLAIMER


UTILITY DISCLAIMER


UTILITY INFORMATION SHOWN ON THE PLANS DOES NOT DEPICT
ANY MORE THAN THE PRESENCE OF A SERVICE, BASED ON
AVAILABLE DOCUMENTARY EVIDENCE. THE PRESENCE OF A
UTILITY SERVICE, ITS SIZE AND LOCATION SHOULD BE
CONFIRMED BY FIELD INSPECTION, PRIOR TO THE
COMMENCEMENT OF ROADWORKS AND THE RELEVANT UTILITY
PLANS OBTAINED BY DIALLING PH 1100 OR FAX 1300 652 077
(DIAL BEFORE YOU DIG). CAUTION SHOULD BE EXERCISED WHEN WORKING IN THE VICINITY OF ALL UTILITY SERVICES.





NOT FOR CONSTRUCTION


	DRAWING FILE LOCATION / NAME \text{\mothmac\project\Sydney\Projects\38xxxx\385951 Sydney Fish Markets\04 \text{\tin}\text{\texit{\texicr{\texi\text{\text{\texi}\text{\text{\text{\t	Vorking	g\01 Drafting\C	Civil\Drawings\CI-UT1-B00 UT-0011.dwg	DESIGN LO	OT CODE	DESIGN MODEL FILE(S) USED F	OR DOCUMENTATION OF TH	IS DRAWING		25/9/2019 5:3		PLOT BY PAC82679		ULTIMO - CITY OF SYDNEY MR 00000 - BRIDGE ROAD		А	١3
ᆲᇶ	EXTERNAL REFERENCE FILES	REV	DATE	AMENDMENT / REVISION DESCRIPTION	WVR No.	APPROVAL	SCALES ON A3 SIZE DRAWING		DRAWINGS / DESI	GN PREPARED BY	TITLE	NAME	DATE	ا علاقه ا	SYDNEY FISH MARKE	ĒΤ		
ĕ			9.10.2018			B.S00			N/I	Level 10, 383 Kent Street	DRAWN	GA.PACIBEN	25.09.19	UrbanGrowth NSW	BRIDGE ROAD UPGR	ADE		
3 M		1	25.09.2019	RE-ISSUED FOR CONCEPT DESIGN		B.S00			MI	Sydney, NSW 2000 Australia	DRG CHECK	B.S00	25.09.19	UrbanGrowth NSW Development Corporation	FROM WATTLE STRE	ET TO WENTWORT	H PARK ROAD	
ĕ₽									MOTT IVI	PO Box Q1678, QVB Sydney NSW 1230. Australia	DESIGN	GA.PACIBEN	25.09.19		EXISTING UTILITIES LEGEND			
⋛┛									MACDONALD	T +61 (0)2 9098 6800 W www.mottmac.com	DESIGN CHECK	V.SOFREVSKI	25.09.19		RMS REGISTRATION No.	DS2018/XXXX	XX PA	RT 11
- P							CO-ORDINATE SYSTEM	HEIGHT DATUM	MM DRAWING NU		DESIGN MNGR	B.S00	25.09.19	URBAN GROWTH	ISSUE STATUS	EDMS No.	SHEET No. ISS	SUE
≝。							MGA ZONE 56	AHD	CI-UT1-B00 U		PROJECT MNGR	G.BABCOCK	25.09.19		CONCEPT DESIGN		UT-0011	1
_																	114 0 .	_


















New Sydney Fish Market

Bridge Road Upgrade - Strategic Concept Design Report

31 May 2019

Mott MacDonald 383 Kent Street Sydney NSW 2000 PO Box Q1678, QVB Sydney, NSW 1230 Australia

T +61 (0)2 9098 6800 F +61 (0)2 9098 6810 mottmac.com

19 Martin Place, Sydney NSW 2000

New Sydney Fish Market

Bridge Road Upgrade - Strategic Concept Design Report

31 May 2019

Issue and Revision Record

Revision	Date	Originator	Checker	Approver	Description		
Α	05.10.2018	Brian Soo	Vlad Sofrevski	Graham Babcock	Issue for RMS review		
В	31.05.2019	Brian Soo	Vlad Sofrevski	Graham Babcock	Re-issue for RMS review		

Document reference: 385951-Bridge Road Concept Design Report

Information class: Standard

This document is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose.

We accept no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from us and from the party which commissioned it.

Contents

Exe	ecutive	e summary	1
1	Intro	oduction	2
	1.1	Description of Project	2
	1.2	Scope of Report	2
	1.3	Project Team	3
	1.4	Limitations of this Report	3
2	Roa	ad Design	4
	2.1	Design Speed	4
	2.2	Typical Cross Section	4
	2.3	Road Geometry	4
		2.3.1 Horizontal Geometry	4
	2.4	Design Departures	5
3	Stormwater Drainage		6
	3.1	Transverse Drainage	6
	3.2	Pavement Drainage	6
		3.2.1 Layout	6
		3.2.2 Stormwater Modelling	6
		3.2.3 Water Quality	6
4	Stru	7	
	4.1	Wentworth Park Boundary Retaining Wall	7
	4.2	Existing Blackwattle Bay Sea Wall	7
	4.3	Major Traffic Sign Structure	7
5	Pav	vements	8
6	Public Utilities		
	6.1	Ausgrid	9
	6.2 Telstra and Optus		9
	6.3 Sydney Water		9
	6.4 Jemena		9

1

Executive summary

Mott MacDonald with partners Arcadis and Royal Haskoning DHV are providing Structural, Civil and Maritime Engineering Design Services to support the development of the new Sydney Fish Markets. The vision for the new development is that of a world class facility designed to accommodate future growth and establish itself as an icon of the Bays District.

The new Sydney Fish Market is located along Bridge Road in between Wentworth Park Road and Wattle Street. The existing Bridge Road will be upgraded to support the new market and also to improve the safety and performance of the intersection with Bridge Road, Wattle Street and Wentworth Park Road as part of increased traffic from the new fish market including ongoing growth and development.

This report summarises the designs that have been developed during the concept phase to feed into the State Significant Assessment Development Application (SSA-DA) submission.

1 Introduction

1.1 Description of Project

UrbanGrowth NSW Development Corporation (UrbanGrowth NSW) have engaged Mott MacDonald with partners Arcadis and Royal Haskoning DHV to provide structural, civil and maritime Engineering Design Services to support the development of the new Sydney Fish Markets. The vision for the new development is that of a world class facility designed to accommodate future growth and establish itself as an icon of the Bays District.

The new facility will be situated in Blackwattle Bay, adjacent to Pyrmont Bridge Road, adjacent to the existing Fish Markets site, as indicated in Figure 1 below.




Figure 1: Site Layout

1.2 Scope of Report

Source: 3XN

This report covers the design philosophy, key design parameters and constraints and assumptions that have been made in developing the engineering scheme for the new facility.

The New Sydney Fish Market project requires upgrade of the existing Bridge Road to support the new vehicle access to the new market. The upgrade is also required to improve the safety and performance of the intersection with Bridge Road, Wattle Street and Wentworth Park Road as part of increased traffic from the new fish market including ongoing growth and development.

1.3 Project Team

Mott MacDonald are providing structural, civil and maritime engineering services, supported by Royal Haskoning DHV and Arcadis as sub-consultants. They supplement the team's capabilities with their proven expertise in delivering world class civil foreshore and maritime design.

1.4 Limitations of this Report

This report has been prepared to support the project DA submission. Therefore, there remain many unknowns regarding the functional and architectural requirements of the project that will be developed as the design progresses.

This report summarises the design decisions that have been made in forming a base scheme and preliminary cost estimate. Specific details of large areas of the design are yet to be developed.

4

2 Road Design

2.1 Design Speed

The strategic concept design was based on design speed of 60 km/h for all roads and intersections. The existing roads are posted with a 60 km/h speed limit.

2.2 Typical Cross Section

The typical cross section for Bridge Road consists of following configurations:

- Variable width verge/footpath along the westbound carriageway, reflecting the existing conditions
- Westbound Two through lanes with 3.0m centre through lane and 3.5m kerbside lane;
- 3.1m wide median island; and
- Eastbound Two 3.0m through lanes and 3.5m bus drop off lane.
- Verge/footpath along the eastbound carriageway, integrated with the new development.

The proposed road formation is wider than the existing configuration and cannot be accommodated within the existing road corridor. To this, the design retains the existing road boundary on the southern (park) side of Bridge Road and therefore the required widening is occurring on the northern (development) side of the road corridor.

The typical cross sections for Bridge road at the approach to the intersections are:

- Wattle Street Intersection
 - Westbound Two through lanes with 3.0m centre through lane and 3.5m kerbside through lane; and
 - Eastbound 3.1m right turn lane with 3.0m shared through and right turn lane and 3.5m kerbside through lane.
- Wentworth Park Road
 - Westbound 3.1m right turn lane with 3.0m centre through lane and 3.5m kerbside shared through and left turn lane

2.3 Road Geometry

The horizontal and vertical geometry for the proposed works was prepared using Austroads guidelines and RMS supplements as appropriate.

2.3.1 Horizontal Geometry

The proposed horizontal geometry for Bridge Road between Wattle Street and Wentworth Park Road is maintains existing as much as possible.

The Wattle Street intersection has been modified to accommodate the dual right turns from Bridge Road and from Wattle Street.

The Wentworth Park Road intersection has been modified to now include a new intersection leg connecting the development. Also, a new right turn lane from Bridge road into the new development has been added. Vertical Geometry

The vertical geometry for Bridge Road between Wattle Street and Wentworth Park Road was raised by 900mm for the new development levels and then tied back to existing levels at the two intersections.

2.4 Design Departures

Following is a summary of the elements of this design, identified at this strategic stage, that present potential departures from the relevant design standards.

These departures will need to be further reviewed and investigated during next stages of the design with consideration also given to the reasons for departure and, if not rectified, ultimately will need to be accepted and approved by the Approval Authority for the road (assumed RMS).

- At the western Wattle Street intersection leg, Bridge Road eastbound through lane, eastbound right turn lane and westbound through lane widths are less than 3.0m. This is due to the fact that the Bridge Rd upgrade ties in with existing conditions at the intersection within the limits of the existing road corridor.
- At the eastern Wentworth Park Ave intersection leg, Bridge Road eastbound through lane and westbound right turn lane widths are less than 3.0m. This is due to the fact that the Bridge Road upgrade ties in with existing conditions at the intersection within the limits of the existing road corridor.

3 Stormwater Drainage

3.1 Transverse Drainage

There is multiple transverse drainage infrastructure located across Bridge Road which formed part of the main drainage system servicing the upstream catchment. This drainage infrastructure is mainly Sydney Water Corporation assets and the table below provides a brief summary of the infrastructure

Table 1: Existing Major Drainage Infrastructure

Road Chainage	Size	Remarks
60.0	DN 1.25m RCP	
60.0	1.015m x 0.915m box culvert	
72.0	2 x 1.98 x 1.525 box culvert	
102.0	DN 1830 RCP	Junction pit is located on westbound footpath where the upstream heritage oviform pipe connects
180.0	3.73 x 1.675m box culvert	
323.0	3.2 x 1.07m box culvert	

Source: SWC DBYD and Hydra Plans

All the major drainage infrastructure listed above will be retained and no works have been proposed except modification/adjustment to several junction pits within the road reserved to raise the pit covers to suit the new finished road levels.

3.2 Pavement Drainage

3.2.1 Layout

The stormwater design for the project consists of upgrade works as follows:

- New kerb inlet pits along the new kerb and gutter on Bridge Road;
- Adjustment to existing kerb inlet and junction pits to suit the new road finished level;

3.2.2 Stormwater Modelling

A preliminary modelling of the proposed stormwater system was undertaken using the DRAINS software package. The design was undertaken in accordance with Road and Maritime Services (RMS) requirements for a local/collector road with a design recurrence internal of the 10 year ARI storm event.

3.2.2.1 Flow Width Analysis

In accordance with Austroads Guide to Road Design Part 5A states that the flow width shall not exceed 1.0m for the design recurrence interval of the 10 year ARI for local/collector road. An analysis was undertaken to calculate the flow width in each of the kerbs and position the pits accordingly, which form part of these works.

3.2.3 Water Quality

No water quality measures are proposed as part of these works

4 Structures

4.1 Wentworth Park Boundary Retaining Wall

The existing Wentworth Park boundary retaining wall adjacent to Bridge Road reserved will be retained and part of the existing wall will be buried under the new westbound footpath. Any existing pedestrian access between the park and the footpath will be retained.

4.2 Existing Blackwattle Bay Sea Wall

The existing sea wall along the northern edge of Bridge road will be retained except a short section of the wall adjacent to Wentworth Park Road intersection and approximately 45m of the existing sea wall between Road Chainage 55.0 to 100.0 will be replaced with new sea revetment wall.

4.3 Major Traffic Sign Structure

There is an existing major traffic sign structure as shown in Figure 1 that will be impacted by the new works. This sign structure will be relocated to new eastbound kerbside.



Figure 2: Existing traffic sign structure on eastbound lane

Source: Photo by Brian Soo

5 Pavements

The pavement designs for the project have not been undertaken at this stage of the project. Mott Macdonald expect the pavement design and profile will be provided by RMS in subsequent stage to enable Mott MacDonald to document in the design drawings.

As part of the strategic concept design submission, Mott MacDonald has identified the extent of new pavement works and mill and re-sheet/corrective overlay.

6 Public Utilities

6.1 Ausgrid

The existing Ausgrid electrical infrastructure on the site has been identified based on Dial Before You Dig (DBYD) records. Electrical assets within Bridge Road are located behind eastbound kerb line and the assets consists of overhead and underground High Voltage (HV) electrical cables.

The exact depths and positions of the existing reticulation mains are unknown thus further investigation are required to determine the exact existing layout.

It is expected that all existing aerial infrastructure along the Bridge Road would be abandoned or relocated underground. Furthermore, City of Sydney will likely require undergrounding of existing aerial infrastructure in the streets bounding the site. In addition, it is expected the existing underground assets to be relocated into the new road services corridor.

Existing street lighting along the eastbound kerbside will be relocated to suit the new eastbound kerb line.

6.2 Telstra and Optus

The existing Telstra and Optus communication infrastructure is located along behind the eastbound kerb line and it is expected the existing infrastructure would be abandoned and will be relocated into the new road services corridor.

The exact depths and positions of the existing communication cables are unknown thus further investigation are required to determine the exact existing layout.

6.3 Sydney Water

The existing Sydney Water infrastructure on the site has been identified based on Dial Before You Dig (DBYD) records. These records indicate the presence of the following infrastructure:

- A DN 200 DICL potable water main along the eastbound kerbside lane;
- A DN 375 CI sewerage main along the westbound kerbside lane;
- Numerous major drainage infrastructure across Bridge Road. Details are described in previous section.

It is expected the existing potable and sewerage mains underneath Bridge Road would be remained untouched/undisturbed. It has been identified that several potable water surface fixtures (e.g. valve & hydrant) and sewerage manhole will require adjustment to the new Bridge Road finishes surface level.


6.4 Jemena

The existing Jemena gas infrastructure on the site has been identified based on Dial Before You Dig (DBYD) records. Gas assets within Bridge Road is located behind eastbound kerb line and the assets consists of an DN 110 Nylon gas main.


The exact depths and positions of the existing gas main is unknown thus further investigation are required to determine the exact existing layout. It is expected the existing infrastructure would be abandoned and will be relocated into the new road services corridor.



C. Temporary Sheet Pile Wall Reference Design




0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 If this drawing is printed or plotted at a size other than A0 - DO NOT SCALE DIMENSIONS FROM DRAWING Always take fluured dimensions in orderence to scaling.





0 10 20 30 40 50 60 70 80 99 100 110 120 120 130 150 If this drawing is printed or plotted at a size other than A0 - DO NOT SCALE DIMENSIONS FROM DRAWING
Almays take figured dimensions in preference to scaling.

D. Rock Revetment Design



Royal HaskoningDHV Enhancing Society Together







PA1518 - SYDNEY FISH MARKETS


SAVED: 18-Jul-18

Royal HaskoningDHV



Royal HaskoningDHV






NOT FOR CONSTRUCTION

AUSTRALIAN HEIGHT DATUM

1:100 (A3) 1:50 (A1)

Royal HaskoningDHV



NOT FOR CONSTRUCTION

AUSTRALIAN HEIGHT DATUM

1000 0 1000 2000 3000 4000 5000mm 1:100 (A3) 1:50 (A1)

