

Loreto Normanhurst

Car Parks + Site Through Link SSDA Report

Project Number: S18-031
Project Address: Pennant Hills

Revision	Issue	Date	Ву	Checked
А	SSDA Final	10.12.20	AK	RB

O C U L U S Landscape Architecture Urban Design PO BOX 307 p. 02 9557 5533

Acknowledgement of Country

We acknowledge the Darug people of the Darug nation who are the traditional owners of the land of which the project site lies on. We also acknowledge the Gadigal people of the Eora nation who are the traditional owners of the land on which we wor. We would like to pay our respects to the Elders past and present of the Darug and Gadigal people.

Contents

Master Plans		5	4.2	Section 1- Osbourn Rd Interface
1.1	Current Site Context	6	4.3	Section 2 - Pennant Hills Rd Interface
1.2	Revised Stage 1 Master Plan	7	4.4	Section 3 - Car Park to Mt Pleasnat Ave
1.3	Final Master Plan	8	4.5	Section 4 - Basketball Bleachers
1.4	Proposed Works	9		
1.5	Access Strategy	10	Materials + Planting	
			5.1	Indicative Material Palette
Site Analy	/sis	11	5.2	Indicative Planting Palette
2.1	Site Photos	12		
2.2	Tree Removal + Retention Osbourn Rd Entrance	13	ADDEND	UM
2.3	Tree Retention + Removal Car Park 1A	14		
2.4	Tree Retention + Removal Car Park 4A	15		
Concept Design		16		
3.1	Landscape Zones	17		
3.2	Landscape Zoning - Design Intent	18		
3.3	Osbourn Rd Entrance	19		
3.4	Osbourn Rd - Corner Retaining Wall Concept	20		
3.5	Ceremonial Grand Pedestrian Way	21		
3.6	Car Park 1A - Tennis Courts	22		
3.7	New Open Space/Indigenous Garden	23		
3.8	Shade Shelter Concept	24		
3.9	Link to Mt Pleasant Ave	25		
3.10	Car Park 4A - Basketball Court	26		
3.11	Car Park 3A - PUDO	27		

28

29

30

3.12

4.1

Sections

Shade Shelter Concept

Osbourn Rd - Corner Updgrade Section


31 32

33

34

35 36 37

38



1.1 Current Site Context



1.2 Revised Stage 1 Master Plan



1.3 Final Master Plan



1.4 Proposed Works

Stage 1 Works

As part of the revised Stage 1 SSDA application the proposal includes the original submission of Boarding House along Mt Pleasant Ave and upgrades to the Mary Ward courtyard which have been documented in a separate package. The additional works in this package include the proposal to reconsider the use, layout and capacity of the car parking across the school campus.

Car Park + Site Through Link

The key intervention as part of these upgrades is to provide efficient movement of vehicles through the campus with minimal conflict between vehicles and students. With the inclusion of 4 Mt Pleasant Ave a site through link connecting Osbourn Rd to Mt Pleasant Ave will provide this safe movement route through with a new dedicated pick up and drop off area. Associated upgrades with this new link include:

- + Osbourn Rd Entrance:
- + A grand ceremonial entrance and pathway
- + Re-distribution of Year 12 car parking
- + Creation of a new open space to Pennant Hills Rd
- + Car Park 1A under existing Tennis courts + newv pick up/drop off area
- + Car Park 4A under existing basketball courts
- + Car Park 3A car park expansion with relocated pick up/drop off area

All of these upgrades aim to allow for adequate parking for future growth without losing valuable active outdoor facilities for the students.




1.5 Access Strategy



1.6 Tree Canopy Cover





2.1 Site Photos

Existing conditions



Existing slip roadExisting slip road from car park



Existing pedestrian crossingConnection from Pennant Hills Rd bridge crossing



Driveway to 1897 buildingDriveway to be converted to pedestrian ceremonial pathway



Existing tennis courtCourt level to be raised for car parking beneath



View towards 4 Mt Pleasant AveRoute for site through link to side of heritage building.



Road between tennis and basketball courts

Large existing trees and planting to be retained



Basketball court access path

Courts to be raised with new pathway between ELC



Existing walls and bleachersTo be replaced around existing trees to be retained

2.2 Tree Removal + Retention Osbourn Rd Entrance

Observations:

- Blackbutt (T40) and Hoop Pine (T39)to be retained and protected during works.
- Firewheel Tree (T48a) to be removed.
- Any retaining wall structures to be carefully placed around tree root protection zone under supervision of an Arborist.
- Trees adjacent to road upgrade to be protected with installation of trunk protection fences in accordance with Section 10.5 and 10.6 of Arborist Report.
- Excavations for footings and pavements sub-grade to be undertaken in accordance with Section 10.9 of Arborist Report.
- Demolition works within TPZ's to be undertaken in accordance with Section 10.8 of Arborist Report.

LEGEND

Highly Significant Trees

 \bigcirc

Trees to be retained

 C

Trees to be removed

_ _ _

Extent of Works



^{*} To be read in conjunction with Arborist Report

2.3 Tree Retention + Removal Car Park 1A

Observations:

- Norfolk Pine (T13) is High value and High significance
- Himalayan Cedars (T32 & T35), Canary Island palm (T22) and Plum Pine (T23) to be protected during new pathway works.
- Golden Robinia (T20), Blackbean (T86), Blueberry Ash (T87 & T97a), Red Oak,
- Any retaining wall structures to be carefully placed around tree root protection zone under supervision of a qualified Arborist
- Trees adjacent to road upgrade to be protected with installation of trunk protection fences in accordance with Section 10.5 and 10.6 of Arborist Report.
- Excavations for footings and pavements sub-grade to be undertaken in accordance with Section 10.9 of Arborist Report.
- Demolition works within TPZ's to be undertaken in accordance with Section 10.8 of Arborist Report.

To be read in conjunction with Arborist Report

LEGEND

Highly Significant Trees




Trees to be retained



Trees to be removed

Extent of Works



2.4 Tree Retention + Removal Car Park 4A

Observations:

- Brushbox (T95), Hoop Pine (T96) and Camphor Laurel (T141)to be retained and protected during works.
- T106, T14 and T116 are high significance trees which sit outside the site boundary which should be protected and retained during works.
- Any retaining wall structures to be carefully placed around tree root protection zone under supervision of a qualified Arborist
- Trees adjacent to road upgrade to be protected with installation of trunk protection fences in accordance with Section 10.5 and 10.6 of Arborist Report.
- Excavations for footings and pavements sub-grade to be undertaken in accordance with Section 10.9 of Arborist Report.
- Demolition works within TPZ's to be undertaken in accordance with Section 10.8 of Arborist Report.

To be read in conjunction with Arborist Report

LEGEND

Highly Significant Trees

0


Trees to be retained

C

Trees to be removed

_ _ _

Extent of Works



2.5 Tree Retention + Removal Site Through Link (4 Mt Pleasant Ave)

Observations:

- Trees to be removed for site through link to Mt Pleasant Ave.
- All trees to be removed are of low significance value.
- Port Jackson Fig (T86a) is a High significance tree to be retained and protected.
- Any retaining wall structures to be carefully placed around tree root protection zone under supervision of a qualified Arborist
- Trees adjacent to road upgrade to be protected with installation of trunk protection fences in accordance with Section 10.5 and 10.6 of Arborist Report.
- Excavations for footings and pavements sub-grade to be undertaken in accordance with Section 10.9 of Arborist Report.
- Demolition works within TPZ's to be undertaken in accordance with Section 10.8 of Arborist Report.

To be read in conjunction with Arborist Report


LEGEND

Highly Significant Trees

Trees to be retained

Trees to be removed

Extent of Works



2.6 Tree Retention + Removal Car Park 3A

Observations:

- Row of trees to be removed for expansion of car parking.
- Sydney Blue Gum (T480), Grey Ironbark (T485), Sydney Blue Gum (T489) to be retained and protected.
- Trees adjacent to road upgrade to be protected with installation of trunk protection fences in accordance with Section 10.5 and 10.6 of Arborist Report.
- Excavations for footings and pavements sub-grade to be undertaken in accordance with Section 10.9 of Arborist Report.
- Demolition works within TPZ's to be undertaken in accordance with Section 10.8 of Arborist Report.

To be read in conjunction with Arborist Report

LEGEND

Highly Significant Trees


Q


Trees to be retained

 \bigcirc

Trees to be removed

Extent of Works






3.1 Landscape Zones

Aim

The provision of additional carparking and site through link with drop off and pick up areas for the safe movement of pedestrians and vehicles within the school campus.

Key Areas:

- 01. Osbourn Rd Entrance
- 02. Main Pedestrian Pathway
- 03. Car Park 1A- Tennis Courts
- 04. New Pick Up/Drop Off Area (PUDO)
- 05. Link to Mt Pleasant Ave
- 06. Car Park 4A Basketball Courts
- 07. Car Park 3A Pick Up/Drop Off Area



3.2 Landscape Zoning - Design Intent



01. Osbourn Rd EntranceFeature entrance signage on the corner of Pennant Hills Rd.



04. New Open SpaceIncorporation of Indigenous garden



02. Main Pedestrian PathwayFeature paving and clear sight lines through the campus



05. Link to Mt Pleasant AveFormal buffer planting along the new road link



03. Car Park 1A - Tennis courtsTerraced planters with cascading planting



06. Car Park 4A - Basketball courtsTerraced bleachers with natural materials

3.3 Osbourn Rd Entrance

(5)

6



Key Plan



Legend

- Upgrade to corner retaining wall
- 2 Slope stabilisation with planting
- Replacement of slip road with gravel pathway
- Additional planting around car park
- Retaining walls sensitive to existing tree
- Planting along upgraded roadway





3.4 Osbourn Rd - Corner Retaining Wall Concept


Design Moves

Proposed upgrades to the corner treatment of Osbourn Rd and Pennant Hills would improve the public domain interface and edge condition.

These are the proposed changes:

- Sandstone wall to replace delapidated timber retaining wall to match into surround edge treatment of the school
- Extension of retaining wall to retain edge to pathway to prevent soil erosion and maintain a clear path of travel
- Upgraded planting with large shrubs retained and additional groundcover planting.
- Digital signage integration for School on Boundary line subject to separate approval.






3.5 Main Pedestrian Entrance + Accessible Path




Key Plan



Legend

- Ceremonial entrance with retained heritage gate
- Pedestrian link to pick up and drop off area
- Pedestrian crossing with removable bollards
- Accessible route to raised tennis courts
- Retention of high value existing tree
- **(6)** Re-paving of pathway
- Regrading of car parking area to become open plaza space
 - Accessible raised pathway through garden around existing

3.6 Car Park 1A - Tennis Courts



Key Plan








Legend

- Pick Up/Drop Off Area with 2 x Shade shelters
- 2 Car Park entrance
- 3 Existing Norfolk Pine Tree to be retained and protected
- (4) Raised Tennis courts x 2
- Existing kerb and sandstone walls retained, planting upgraded
 - Retaining garden walls with re-use of heritage sandstone
- (7) Entrance to tennis courts
- Accessible path link from tennis courts to main plaza area
- Path access from car park below
- (10) Make good with existing path
- Feature planting around existing Norfolk Pine tree


3.7 New Open Space/Indigenous Garden



Key Plan



3.8 Shade Shelter Concept



Legend


- (1) Steel Structural Frame
- 2) Translucent Roof Sheeting
- (3) Louvres
- Sandstone block seat
- Steel cables with climbing plants







Section - Shelter through PUDO



Elevation - Shelter towards open space