



4 DARLING STREET MARSDEN PARK STORMWATER MANAGEMENT PLAN



Disclaimer

This report has been prepared on behalf of and for the exclusive use of Sydney Business Park and is subject to and issued in accordance with the agreement between Sydney Business Park and Northrop Consulting Engineers. Northrop Consulting Engineers accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this report by any third party. Copying this report without the permission of Sydney Business Park and Northrop Consulting Engineers is not permitted.

Document Control

Prepared for Sydney Business Park
Project Name 4 Darling Street, Marsden Park
File Reference S172938-CR01-C
Date 28/03/18

Document Control**S172938-CR01-C Stormwater Management Strategy Report**

Rev	Description	Prepared by	Reviewed by	Issue Date	Client App	Approval Date
A	Draft Issue	CP	SF	13.03.18		
B	Issued for Development Application	CP	SF	28.03.18		
C	Re-issued for Development Application	CP	SF	28.08.18		

Contents

1. Introduction.....	5
2. Related Reports and Documents	5
3. The Development Site	6
3.1. Site Description	6
3.2. Proposed Development	7
4. Erosion and Sediment Control	8
4.1. Sediment Basin	8
4.2. Construction Measures	8
5. Bulk Earthworks.....	9
5.1. Construction Sequence	9
6. Stormwater Management Objectives and Controls	10
6.1. Development Control Plan Objectives.....	10
6.2. Stormwater Management Controls	10
7. Stormwater Quantity Management	11
7.1. Existing Catchment.....	11
7.2. Stormwater Quantity Management Strategy	11
7.3. Hydrological Modelling.....	12
8. Stormwater Quality Management.....	13
8.1. Adopted Water Quality Objectives	13
8.2. Stormwater Quality Management Scheme.....	13
8.3. Rainwater Tanks.....	13
8.4. Rainfall Data.....	14
8.5. Methodology	15
8.6. Model Results.....	16
8.7. Proposed Stormwater Treatment Train	17
8.8. Stream Erosion Index	18
9. Conclusion.....	19
Appendix A – Civil Engineering Plans	20
Appendix B – Site Survey Plan	21
Appendix C – Maintenance Schedule	22

Figures

Figure 1 - Site Locality (Department of Planning and Infrastructure, 2013)	6
Figure 2 - Site Plan (NEARMAP, 2018)	7
Figure 3 - Pre-Development Catchment Plan.....	11
Figure 4 - Catchment Areas	12
Figure 5 – Rainwater Reuse Graph.....	14
Figure 6 - MUSIC Link and Node Diagram.....	15

Tables

Table 1 - Concept Sediment Basin Volumes.....	8
Table 2 - Concept Earthworks Volumes.....	9
Table 3 - Flow Width Analysis Results	13
Table 4 - Water Quality Targets	13
Table 5 - Rainfall Runoff Parameters	15
Table 6 - Water Quality Parameters for MUSIC Source Nodes	16
Table 7 - MUSIC Model Results.....	16
Table 8 - SEI Flow Music Results	19

Appendices

Appendix A – Civil Engineering Plans	20
Appendix B – Site Survey Plan	21
Appendix C – Maintenance Schedule	22

1. Introduction

Northrop Consulting Engineers Pty Ltd (Northrop) have been engaged by Sydney Business Park to prepare civil engineering design and documentation in support of a Development Application (DA) submission to Blacktown City (Council) for the proposed warehouse development at 4 Darling Street, Marsden Park (the site).

This report covers:

- Erosion and sediment control;
- Bulk earthworks;
- Stormwater quantity and quality management; and
- Water Sensitive Urban Design.

2. Related Reports and Documents

This report is to be read in conjunction with the following documents:

- a. Development Application Documentation prepared by Northrop (refer Appendix A):
 - 172938-DAC01.01 Cover Sheet, Drawing Schedule and Locality Plan;
 - 172938-DAC02.01 Concept Sediment and Soil Erosion Control Plan;
 - 172938-DAC02.11 Sediment and Soil Erosion Control Details;
 - 172938-DAC03.01 Bulk Earthworks Cut and Fill Plan;
 - 172938-DAC04.01 Siteworks and Stormwater Management Plan – Sheet 01;
 - 172938-DAC04.02 Siteworks and Stormwater Management Plan – Sheet 02;
 - 172938-DAC04.03 Siteworks and Stormwater Management Plan – Sheet 03;
 - 172938-DAC04.04 Siteworks and Stormwater Management Plan – Sheet 04;
 - 172938-DAC05.11 Stormwater Longitudinal Section – Sheet 01;
 - 172938-DAC05.12 Stormwater Longitudinal Section – Sheet 02;
 - 172938-DAC05.13 Stormwater Longitudinal Section – Sheet 03;
 - 172938-DAC05.14 Stormwater Longitudinal Section – Sheet 04;
 - 172938-DAC05.15 Stormwater Longitudinal Section – Sheet 05;
 - 172938-DAC05.20 Stormwater Analysis Results;
 - 172938-DAC08.01 Catchment Plan;
 - 172938-DAC09.01 Typical Details – Sheet 01.
- b. Marsden Park Industrial Precinct – Post Exhibition Water Cycle Management Strategy Report prepared by J. Wyndham Prince, 2011;
- c. Road, Drainage and Basin Design: Marsden Park Industrial Stage 1.02B, prepared by Calibre;
- d. NSW Department of Housing Manual – Managing Urban Stormwater Soil & Construction 2004; and
- e. Developer Handbook for Water Sensitive Urban Design prepared by Blacktown City Council 2013.

3. The Development Site

3.1. Site Description

Sydney Business Park is situated on the western side of Bells Creek between South Street and Castlereagh Freeway, which separates it from the suburbs of Hassall Grove and Bidwill. The subject site is within Blacktown City Council local government area and is part of the Marsden Park Industrial Precinct in the North West Growth Centre as presented in Figure 1.




Figure 1 - Site Locality (Department of Planning and Infrastructure, 2013)

The site occupies approximately 5.72 hectares and is situated:

- West of Richmond Road;
- Near an existing regional on-site detention basin to the south east; and
- Adjacent to a vacant lot to the north, and a commercial development to the west.





Figure 2 - Site Plan (NEARMAP, 2018)

3.2. Proposed Development

The proposed development involves construction of a warehouse with associated office, loading dock, truck turning areas, car parking, a separate showroom building and landscape areas.

Refer to the architectural drawings prepared by Reid Campbell and Northrop's civil drawing package for more detailed site description.

The site currently falls to the south east corner. A portion of the site falls to the north. All surface runoff will be directed to the southern and eastern boundary. Stormwater runoff will be collected by a below ground pit and pipe stormwater drainage network.

The development will comprise of roof catchments, hardstand catchments (car parking, loading dock and driveways) and landscaped areas. A portion of the roof catchment will be directed to a rainwater reuse tank. Any overflow from the rainwater tank will be discharged to the pit and pipe network. The rainwater tank will pre-treat captured runoff. Gross pollutant and coarse sediment traps at each surface inlet pit will provide pre-treatment to runoff from paved areas. Prior to discharging to Council's stormwater drainage network all surface runoff will be treated by a proprietary filtration system which is located at the downstream end of the drainage system.

On-site stormwater detention is not provided within the site. Stormwater quantity control is provided by a regional on-site detention basin located south east of the site.

4. Erosion and Sediment Control

Erosion and sedimentation control has been designed in accordance with Council requirements and the NSW Department of Housing Manual, "Managing Urban Stormwater Soil & Construction" 2004 prior to any earthworks commencing on site. The concept sediment and erosion control measures are documented in Northrop's Development Application drawing 172938-DAC02.01.

4.1. Sediment Basin

A sediment basin has been designed to capture site runoff during construction and has been located towards the eastern side of the site, in the lowest point. The construction of the basin will be done in stages to enable maximum runoff capture assisted by the diversion of swales to capture and direct runoff to the basins.

Calculations to determine concept design basin sizes have been based on available geotechnical information regarding soil types and through the use of the Soils and Construction Volume 1 Manual.

To ensure the sediment basins are working effectively they are to be maintained throughout the construction works. Maintenance includes water removal by pumping to reach the minimum storage volume at the lower level of the settling zone. The settling zone will be identified by pegs to clearly show the level at which design storage capacity is available.

The pumped water from the sediment basins will be reused to irrigate areas of hydro-mulch and for dust control during construction.

Weirs are to be provided to control overflow for rainfall events in excess of the 100 year ARI storm event.

Below is the concept sediment basin sizing table.

Table 1 - Concept Sediment Basin Volumes

Basin	Catchment Area (Ha)	Volume Required (m ³)	Volume Provided (m ³)
South East	5.71	1228.57	1230

4.2. Construction Measures

Prior to any earthworks commencing, erosion and sediment control measures will have to be implemented in accordance with the approved drawings. The measures shown on the drawings describe the minimum treatment requirements. The contractor will be required to modify the erosion and sedimentation control measures to suit the construction program, sequencing and techniques. Erosion and sediment control measures include:

- A fence around the site.
- A security fence surrounding the site office area and the proposed sediment basins;
- Sediment fencing downstream of all disturbed areas, and any topsoil stockpiles;
- Installation of silt arrestors to collect site runoff and retain suspended particles;
- Dust control measures which includes covering stockpiles, maintain site fences and watering exposed areas;
- Placement of hay bales or mesh and gravel filters along proposed catch drains and around stormwater inlets pits; and
- The construction of temporary sediment basins as noted above in Section 4.1

5. Bulk Earthworks

The proposed works will consist of earthworks cut and fill operations to establish design levels. The levels have been designed to optimise cut to fill across the site and minimise the need to import or export material from the site. The existing site has a natural fall which runs throughout the site from North West side to the Eastern side. The majority of the cut will come from western side and used to fill the eastern side. This is represented on Northrop's Bulk Earthworks Drawing 172938-DAC03.01.

The bulk earthworks quantities are summarised in Table 2.

Table 2 - Concept Earthworks Volumes

Earthworks	Volume (m ³)
Cut	27,509
Fill	28,804
Balance	1,295 Import

Any stockpiled material, including topsoil, shall be located as far away as possible from any associated natural watercourses. Sediment Fences shall be installed on the downstream side of stockpiles and the embankment formation. All stockpiles and embankment formations shall be stabilised by hydro-seeding or hydro-mulching on formation.

The bulk earthworks cut/fill volumes provided are conceptual only and are subject to change pending final coordination and detailed design. It should be noted the above mentioned cut/fill operations have been calculated based on the following assumptions.

- No allowance for soil bulking factors;
- No allowance for spoil generated from utility service and stormwater drainage trenching;
- No allowance for spoil generated from water quality media; and
- A 330mm pavement depth

5.1. Construction Sequence

Bulk earthworks sequencing is as follows:

- Provision of site erosion and sediment control measures outlined in Section 4;
- Clearing of vegetation from the development site. Cleared vegetation will be either removed from site or mulched;
- Stripping and stockpiling of topsoil suitable for reuse;
- Inspection of exposed underlying material to ensure conformity with design assumptions and requirements;
- Placement of fill in layers not greater than 200mm in thickness and compacted to not less than 98% Standard Maximum Dry Density (SMDD) in accordance with the geotechnical report; and
- Spread topsoil to a maximum depth of 200mm and hydro-seed or hydro-mulch disturbed areas.

6. Stormwater Management Objectives and Controls

6.1. Development Control Plan Objectives

The stormwater management strategy for Sydney Business Park has been developed in accordance with the Water Sensitive Urban Design and Integrated Water Cycle Management, prepared by Blacktown City Council.

Blacktown City Council Integrated Water Cycle Management DCP (Ref. 6) states the following objectives:

- (a) Protect and enhance natural watercourses and their associated ecosystems and ecological processes
- (b) Minimise potable water demand and wastewater generation
- (c) Minimise stream erosion by matching the post development runoff regime to the pre development or natural water runoff regime
- (d) Mitigate the impacts of development on water quality and quantity;
- (e) Mitigate the impacts of development on groundwater, particularly in saline groundwater environments;
- (f) Ensure any changes to the existing groundwater regime do not adversely impact upon any other properties and the environment;
- (g) Integrate water cycle management measures into the landscape and urban design to maximise amenity;
- (h) Minimise the potential impacts of development and other associated activities on the aesthetic, recreational and ecological values of receiving waters;
- (i) Minimise soil erosion and sedimentation resulting from site disturbing activities;
- (j) Ensure the principles of ecologically sustainable development are applied in consideration of economic, social and environmental values in water cycle management.

The stormwater quantity and quality management for the subject site have been developed at a precinct planning level outlined in the “Marsden Park Industrial Precent- Post Exhibition Water Cycle Management Strategy Report” (J. Wyndham Prince, Feb 2011).

6.2. Stormwater Management Controls

Marsden Park Industrial Precent- Post Exhibition Water Cycle Management Strategy Report states that the sites catchment area will drain into the regional Basin I to ensure that peak post development discharges are restricted to pre development discharges and that the quality of the post development stormwater discharges meet the requirements of the NSW Department of Planning and Blacktown City Council.

A water quality treatment strategy proposed for the site has been designed to achieve the objectives (stated above) and controls as outlined below:

Controls are as follows:

- Rainwater tanks on each allotment, installed during building construction;
- Proprietary GPT units upstream of each stormwater discharge point to trunk drainage channels;
- On-lot water quality devices for commercial/industrial and medium/high density residential catchments;

- Precinct based bio-retention/filtration raingarden systems.

Stormwater quantity and quality management measures will be discussed in sections 7 and 8 of this report respectively.

7. Stormwater Quantity Management

7.1. Existing Catchment

The existing catchment for 4 Darling Street is approximately 5.64ha in size and is within the Bells Creek catchment area. The area generally drains from the West to East, with the site low point located in the south-eastern corner. The run off from the site area drains towards the regional Basin I which will discharge to culverts under Richmond Road and into tributaries of Bells Creek.

Figure 3 below shows the pre-development catchment plan for Sydney Business Park area.



Figure 3 - Pre-Development Catchment Plan

Permissible site discharge rates (PSD) for each storm event were not calculated as the proposed Basin I is designed to restrict post development peak discharges from the site, to predevelopment levels for the 5 year and 100 year ARI storms events.

7.2. Stormwater Quantity Management Strategy

The stormwater quantity management strategy has been designed so that the run off from the various catchments will discharge to the external (road) stormwater drainage network, which discharges into the precinct based detention basin.

The site has been divided into catchments which can be referred in Figure 4.



Figure 4 - Catchment Areas

7.3. Hydrological Modelling

The Hydrology of the existing catchment and bio-retention raingarden sizes were modelled using DRAINS software. The existing slopes of the catchments were calculated based on site survey prepared by Freeburn Surveying (refer Appendix B).

In order to initialise the DRAINS model tail water levels were adopted from the hydraulic grade levels as documented in the construction certificate documentation for Marsden Park Stage 1.02B by Calibre Consulting.

A stormwater analysis of the network drainage system for a 20 and 100 year ARI indicated the Flow Depth and Velocity were all in accordance with council requirements. Refer to DRAINS Model and Longsection Results Drawing DAC05.11 to DAC05.15.

A gutter flow with analysis was prepared to support the modification of two existing pits that are located within the south-western driveway for the development. The proposed stormwater strategy includes converting these kerb inlet pits to v-grate pits and introducing kerb inlet pits downstream of the driveway. The flow width analysis results are included in Table 3 below and compare flow widths along the gutter under existing and proposed conditions. The existing conditions have been extracted from the construction certificate documentation for Marsden Park Stage 1.02B by Calibre Consulting.

Table 3 - Flow Width Analysis Results

Pit Number	Gutter Flow Width (m)	
	Existing	Proposed
Existing pit - 11/2 (as documented by Calibre)	1.61	0.78
Existing pit - 11/3 (as documented by Calibre)	1.78	1.01
Existing pit - 11/4 (as documented by Calibre)	1.76	1.27
Existing pit - 11/5 (as documented by Calibre)	1.94	1.55

8. Stormwater Quality Management

8.1. Adopted Water Quality Objectives

The main objectives for stormwater quality are indicated in Developer Handbook for Water Sensitive Urban Design V1.1 November 2013 and are presented in Table 4 below:

Table 4 - Water Quality Targets

Pollutant	% Reduction Post-Development Average Annual Load Reduction
Gross Pollutants	90
Total Suspended Solids (TSS)	85
Total Phosphorous (TP)	65
Total Nitrogen (TN)	45

8.2. Stormwater Quality Management Scheme

The first stage of the stormwater treatment train is pit inlet filter baskets (trash baskets). The filter baskets will provide pre-treatment by capturing gross pollutants and the coarser suspended solids. The secondary treatment is provided by proprietary filter cartridges and will remove nutrients such as nitrogen and phosphorous.

8.3. Rainwater Tanks

The rainwater tank will collect approximately one third of the roof water from the development which will pass through a first flush system prior to capture. The rainwater tank will be located adjacent beneath the carpark and incorporate a 100 year overflow to the external stormwater drainage network.

The collected water will be used for toilet flushing and landscape irrigation only. The tank will be equipped with the following:

- Solid access lid and step irons;
- High level overflow to external stormwater drainage network;
- Duty and standby pump configured for alternative operation;
- Mains water top-up; and
- Associated float valves and control panels.

A water balance model was created to determine the reduction in runoff days as a result of the rainwater tank. The following inputs were adopted:

- Rainfall and catchment data as per parameters discussed above;
- Roof area draining to tank approximately = 8,000 m²
- Initial tank volume = 230,000L.

The water usage was estimated using both Blacktown City Council's Developer Handbook for Water Sensitive Urban Design and Water by Design Draft Stormwater Harvesting Guidelines (by property type) guide.

- Development Type: Industrial Warehouse
- Total Roof Area: 8,000 m²
- Total Bathrooms: 24
- Flushing Demand (kL/day/toilet): 0.1
- Total Average Daily Demand (kL/day): 2.4
- Total Landscape Area to be Irrigated by Rainwater Tank: 5,400 m²
- Landscape Demand (kL/year/m²): 0.4
- Total Average Daily Demand (kl/year): 2160

The results of the water balance model are shown in Figure 5 below.




Figure 5 – Rainwater Reuse Graph

The results show that with a 230,000L tank the re-use demand met is 80.4%.

Due to the standard usage of non-potable water in the proposed development the 80% target required by Council is able to be achieved. The tank size has therefore been taken at a point where the demand/tank size relationship reaches 80% demand resulting in the 230,000L rainwater tank.

8.4. Rainfall Data

For the analysis of the MUSIC modelling, historical rainfall records were obtained from the Bureau of Meteorology for Station No. 067035 at Liverpool (Whitlam Centre). The MUSIC analysis was undertaken using a 6 min time step for year 1967 to 1976 of historical data.

The mean annual rainfall for the modelled data was 857mm.

The evapotranspiration values have been entered from the default data provided by the MUSIC software for the Sydney area.

8.5. Methodology

The water quality modelling software MUSIC v6 was used to analyse the performance of the treatment train. Figure 6 shows the MUSIC node and link diagram used to describe the proposed treatment train. The model has been built to assess the adequacy of the Stormwater treatment measure proposed and to ensure that the quality of stormwater meets the objectives prior to stormwater runoff leaving the site.




Figure 6 - MUSIC Link and Node Diagram

The following rainfall and runoff parameters shown in Table 5 have been utilised.

Table 5 - Rainfall Runoff Parameters

Parameter	Recommended Values
Rainfall Threshold (mm/day)	1.4
Soil Storage Capacity (mm)	170
Initial Storage (% of Capacity)	30
Field Capacity (mm)	70
Infiltration Capacity Coefficient – a	210
Infiltration Capacity Exponent – b	4.7
Initial Depth (mm)	10
Daily Recharge Rate (%)	50
Daily Base flow Rate (%)	4
Daily Deep Seepage Rate (%)	0

The pollutant concentration parameters used in the model were based on information provided in “Using MUSIC in Sydney’s Drinking Water Catchment”, Sydney Catchment Authority, 2012. The parameters are listed in table below:

Table 6 - Water Quality Parameters for MUSIC Source Nodes

Land- Use Category		Log TSS (mg/L)		Log TP (mg/L)		Log TN (mg/L)	
		Storm Flow	Base flow	Storm Flow	Base Flow	Storm Flow	Base Flow
Roof Areas	Mean	1.30	1.20	-0.89	-0.85	0.30	0.11
	Std Dev	0.32	0.17	0.25	0.19	0.19	0.12
Road Areas	Mean	2.43	1.20	-0.30	-0.85	0.34	0.11
	Std Dev	0.32	0.17	0.25	0.19	0.19	0.12
Other Impervious Areas	Mean	2.15	1.20	-0.60	-0.85	0.30	0.11
	Std Dev	0.32	0.17	0.25	0.19	0.19	0.12
Pervious Areas	Mean	2.15	1.20	-0.60	-0.85	0.30	0.11
	Std Dev	0.32	0.17	0.25	0.19	0.19	0.12

8.6. Model Results

The results of the analysis showed the treatment train will achieve the water quality targets set out in Council’s DCP. Table 7 below displays the effectiveness of the treatment train for the primary and secondary treatment.

The water quality model created using MUSIC software provides an indication of the pollutant removal rates expected when a treatment train of water quality measures is applied to the proposed layout of the development.

Table 7 - MUSIC Model Results

Pollutant	Before Treatment	After Treatment	% Reduction	% Objective	Compliance
Total Suspended Solids (kg/yr)	6800	621	90.9	85	OK
Total Phosphorus (kg/yr)	12.6	3.92	68.9	65	OK
Total Nitrogen (kg/yr)	81.2	35.2	56.6	45	OK
Gross Pollutants (kg/yr)	905	67.3	92.6	90	OK

8.7. Proposed Stormwater Treatment Train

In order to achieve the reduction targets the following treatment devices are required as part of the treatment train:

- Jellyfish Stormwater treatment

A total of six (6) cartridges, (2x) JF2250 and (2x) JF3250 are to be introduced to the design as a major filter device located at the end of the treatment train to treat all sub-catchments. This stormwater quality treatment technology incorporates a pre-treatment with light-weight membrane filtration and removes a high level and a wide variety of stormwater pollutants. The capture rates provided by the TARP- Field Study, 2012 and MRDC Floatables Testing, 2008:

○ TSS	89%
○ TN	51%
○ TP	59%
○ Litter	99%

- Bio-Swales

Bio Retention Swales (Bio-Swales) will act as secondary treatment for stormwater by detaining flows and promoting sedimentation. The media beds of the bio – retention system will be designed to 500mm deep with an average particle size of 0.5 mm and a hydraulic conductivity of 100 mm/hr with a minimum depth of storage above the media of 150mm. Direct filtration of particulate matter and nutrient stripping by bio films are established within the media bed and gravel layer.

The expected sediment and nutrient removal performance of the bio - retention systems was determined using the default parameters and equations provided in the MUSIC Blacktown City Council Nodes. Water quality reduction mechanisms in MUSIC are based on an exponential decay equation

- Stormwater360 Enviropod 200 Inserts

Enviropod 200 inserts will be used as a pre-treatment for stormwater runoff to capture litter and coarse sediment surface flows on the site. Enviropod inserts are to be installed on all surface inlet pits across the site. The following capture rates have been adopted for the MUSIC model, based on information provided by Stormwater360:

○ TSS	54%
○ TN	21%
○ TP	30%
○ Litter	100%

- 230kL Rainwater Tank

A 230kL rainwater tank will be implemented to capture stormwater runoff generated off the roof. The collected rainwater will be used for irrigation of the landscaped areas across the site and for toilet flushing.

8.8. Stream Erosion Index

As per Councils Development Control Plan 2015, Part J, Section 4.4, the development ensures that post development duration of stream forming flows are no greater than 3.5 times the pre-developed duration of stream forming flows.

Calculations of the Stream Erosion Index (SEI) have been completed as per Council's Developer Handbook for Water Sensitive Urban Design, adopted from the Draft NSW MUSIC Modelling Guide (Aug 2010). MUSIC v6 software has been used to estimate the SEI.

Estimating the critical flow

Step 1

$$t_c = 0.76A^{0.38} \quad (A(km^2 = Ha/100), t_c(hour))$$

Total Area = 5.715 ha

$$t_c = 0.76 \times \frac{0.05715^{0.38}}{100}$$

$$t_c = 0.26 \text{ hrs}$$

$$t_c = 15.4 \text{ mins}$$

Step 2

With reference to the Rainfall Intensity Chart in the Engineering Guide for Development based on the 2 year ARI and calculated t_c in minutes.

$$I_2 = 64 \text{ mm/hr}$$

Step 3

$$C_2 = C_{10} \times FF_2$$

$$C_2 = 0.6 \times 0.74$$

$$C_2 = 0.444$$

Step 4

Rational Method

$$Q_2 \left(\frac{m^3}{s} \right) = 0.278 \times C_2 \times I_2 \times A$$

$$Q_2 \left(\frac{m^3}{s} \right) = 0.278 \times 0.444 \times 64 \times \frac{5.715}{100}$$

$$Q_2 \left(\frac{m^3}{s} \right) = 0.452$$

Step 5

$$Q_{crit} \left(\frac{m^3}{s} \right) = 0.25 \times 0.452$$

$$Q_{crit} \left(\frac{m^3}{s} \right) = 0.113$$

Table 8 - SEI Flow Music Results

	Inflow Pre-development	Inflow Post-development
Flow (ML/yr)	1.76	5.40

Council's target for SEI is a value less than 3.5. The SEI for the development has been calculated using the following equation as per Council's guideline.

$$SEI = \sum(Q_{post} - Q_{critical}) / \sum(Q_{pre} - Q_{critical})$$

$$SEI = \frac{5.40 - 0.113}{1.76 - 0.113}$$

The resultant SEI for the proposed development = **3.086**

After modelling, it was found that the Council's target for the SEI value less than 3.5 was achieved which demonstrates that the proposed waterway will be stable.

9. Conclusion

Based on investigations, analyses and designs, it is anticipated that there Blacktown City Council's stormwater quantity and quality measures will be met by the management measures proposed as part of the industrial development at 4 Darling Street, Marsden Park.

The Water Management Plan herein, proposes a series of individual elements arranged in a treatment train consisting of on-lot treatment, street level treatment and precinct based public domain infrastructure treatment measures. Suggested structural elements for the development include:

- Stormwater pit filter inserts
- Bio-Swales
- Proprietary filter cartridge systems downstream
- Rainwater reuse tank - 230,000L Tank.

The stormwater assessment report has been prepared to conform to the requirements of the Council's Growth Centre Precincts Development Control Plan (DCP) 2010 and Council's Engineering Guide for Development, 2005.

Appendix A – Civil Engineering Plans

4 DARLING STREET, MARSDEN PARK

CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION




SOURCE : NEARMAP.COM.AU (©2018)

DRAWING SCHEDULE	
DRG No.	DRAWING TITLE
DAC01.01	COVER SHEET, DRAWING SCHEDULE AND LOCALITY PLAN
DAC02.01	CONCEPT SEDIMENT AND SOIL EROSION CONTROL PLAN
DAC02.11	SEDIMENT AND SOIL EROSION CONTROL DETAILS
DAC03.01	EARTHWORKS CUT AND FILL PLAN
DAC04.01	SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 01
DAC04.02	SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 02
DAC04.03	SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 03
DAC04.04	SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 04
DAC05.11	STORMWATER LONGITUDINAL SECTIONS - SHEET 1
DAC05.12	STORMWATER LONGITUDINAL SECTIONS - SHEET 2
DAC05.13	STORMWATER LONGITUDINAL SECTIONS - SHEET 3
DAC05.14	STORMWATER LONGITUDINAL SECTIONS - SHEET 4
DAC05.15	STORMWATER LONGITUDINAL SECTIONS - SHEET 5
DAC05.20	STORMWATER ANALYSIS RESULTS
DAC06.01	BOUNDARY ALIGNMENT PLAN
DAC06.11	BOUNDARY LONGITUDINAL SECTION - SHEET 1
DAC06.12	BOUNDARY LONGITUDINAL SECTION - SHEET 2
DAC06.13	BOUNDARY LONGITUDINAL SECTION - SHEET 3
DAC08.01	CATCHMENT PLAN
DAC09.01	TYPICAL DETAILS - SHEET 01

DRAWN: C. PASKE
DESIGNED: M. SANTIAGO
JOB MANAGER: J. GILLIGAN
VERIFIER:

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT	PROJECT		DRAWING TITLE	JOB NUMBER	
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18			 Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	4 DARLING STREET, MARSDEN PARK	CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION	172938	
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18							
						DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED	THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD	SCALE 1:2500@A1 				
										DRAWING NUMBER	REVISION	
										DAC01.01	02	
										DRAWING SHEET SIZE = A1		



LEGEND

BOUNDARY LINE

EASEMENT LINE

EASEMENT LINE

EXISTING CONTOURS

SEDIMENT FENCE

SECURITY FENCE

WIRE MESH AND GRAVEL SEDIMENT FILTER

STRAW BALE FILTER

DROP INLET SEDIMENT TRAP

DRAINAGE SWALE

STABILISED SITE ACCESS

STOCKPILE

SEDIMENT BASIN

4. Volume of Sediment Basins, Type D and Type F Soils

Basin volume = settling zone volume + sediment storage zone volume

Settling Zone Volume

The settling zone volume for Type F and Type D soils is calculated to provide capacity to contain all runoff expected from up to the y-percentile rainfall event. The volume of the basin's settling zone (V) can be determined as a function of the basin's s

$$V = 10 \times C_v \times A \times R_{x\text{-day}, y\text{-tile}} \text{ (m}^3\text{)}$$

where:

10 = a unit conversion factor

C_v = the volumetric runoff coefficient defined as that portion of rainfall that runs off as stormwater over the x-day period

$R_{x\text{-day}, y\text{-tile}}$ = is the x-day total rainfall depth (mm) that is not exceeded in y percent of rainfall events. (See Sections 6.3.4(d), (e), (f), (g) and (h)).

A = total catchment area (ha)

Sediment Storage Zone Volume

In the detailed calculation on Soil Loss Classes 1 to 4 lands, the sediment storage zone can be taken as 50 percent of the settling zone capacity. Alternately designers can design the zone to store the 2-month soil loss as calculated by the RUSLE (Section

Place an "X" in the box below to show the sediment storage zone design parameters used here:

50% of settling zone capacity,

☒ X 2 months soil loss calculated by RUSLE

Total Basin Volume

Site	C_v	$R_{x\text{-day}, y\text{-tile}}$	Total catchment area (ha)	Settling zone volume (m ³)	Sediment storage volume (m ³)	Total basin volume (m ³)
1	0.65	32.2	5.641	1171.57929	57	1228.57929
2						
3						
4						
5						
6						

DESIGNED: M. SANTIAGO

JOB MANAGER: J. GILLIGAN

VERIFIER:

DRAWN: C. PASKE

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18	sydney business park
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18	

ARCHITECT

REID CAMPBELL

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:500 @ A1

0 5 10 15 20 25m

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

PROJECT

4 DARLING STREET, MARSDEN PARK

NORTHROP

Sydney

Level 11 345 George Street, Sydney NSW 2000

Ph (02) 9241 4188 Fax (02) 9241 4324

Email sydney@northrop.com.au ABN 81 094 433 100

DRAWING TITLE

CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION

CONCEPT SEDIMENT AND SOIL EROSION CONTROL PLAN

JOB NUMBER

172938

DRAWING NUMBER

DAC02.01


REVISION

02

DRAWING SHEET SIZE = A1

REVISION		DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT		ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COLORED TO BLACK & WHITE.	PROJECT	DRAWING TITLE	JOB NUMBER									
01		ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18			 Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	NOT TO SCALE	4 DARLING STREET, MARSDEN PARK	CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION	172938									
02		ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18								DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED.	THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD	SEDIMENT AND SOIL EROSION CONTROL DETAILS	DAC02.11	02				
													DRAWING SHEET SIZE = A1									

DRAWN: C. PASKE
DESIGNED: M. SANTIAGO
JOB MANAGER: J. GILLIGAN
VERIFIER:



LEGEND	
	BOUNDARY LINE
	EASEMENT LINE
	EXISTING OVERHEAD TRANSMISSION LINE
	EXISTING TRANSMISSION TOWER
	PROPOSED KERB
	SAWCUT AND PAVEMENT INFILL
	KERB ONLY
	KERB AND GUTTER
	RETAINING WALL - TYPE 1
	EXISTING RETAINING WALL
	CONCRETE EDGING
	CREST
	DIRECTION OF GRADE
	VEHICULAR CROSSING
	KERB RAMP
	WHEEL STOP
	BOLLARD
	ANTI-RAM BOLLARD
	KERB TAPER TO 0
	PROPOSED FINISHED FLOOR LEVEL
	PROPOSED BATTERS
	PROPOSED SPOT HEIGHT
	EXISTING SPOT HEIGHT
	PROPOSED CONTOURS
	EXISTING CONTOURS
	PROPOSED STORMWATER PIPE
	EXISTING STORMWATER PIPE
	GRATED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	PROPOSED RAINWATER TANK
	PROPOSED WATER QUALITY TANK
	VEHICULAR CONCRETE PAVEMENT - TYPE '1'
	ASPHALT PAVEMENT - TYPE '2'
	CONCRETE PAVEMENT - TYPE '3'
	FIRE-TRAIL PAVEMENT - TYPE '4'
	LANDSCAPING

FOR CONTINUATION REFER TO SHEET 02

FOR CONTINUATION REFER TO SHEET 03

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18
03	ISSUED FOR INFORMATION	JO		TB	04.07.18
04	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18
05	ISSUED FOR COUNCIL APPROVAL	CP		TB	28.08.18
06	RE-ISSUED FOR COUNCIL APPROVAL	CP		TB	29.08.18

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

THE COPYRIGHT OF THIS DRAWING REMAINS WITH
NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE
COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS
TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250@A1

Sydney

Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

4 DARLING STREET,
MARSDEN PARK

DRAWING TITLE

CIVIL ENGINEERING WORKS
DEVELOPMENT APPLICATION

SITeworks AND STORMWATER
MANAGEMENT PLAN - SHEET 01

JOB NUMBER

172938

DRAWING NUMBER

DAC04.01

REVISION

06


DRAWING SHEET SIZE = A1

FOR CONTINUATION REFER TO SHEET 01

VERIFIER: J. GILLIGAN

JOB MANAGER: M. SANTIAGO

DESIGNED: C. PASKE



LEGEND	
	BOUNDARY LINE
	EASEMENT LINE
	EXISTING OVERHEAD TRANSMISSION LINE
	EXISTING TRANSMISSION TOWER
	PROPOSED KERB
	SAWCUT AND PAVEMENT INFILL
	KERB ONLY
	KERB AND GUTTER
	RETAINING WALL - TYPE 1
	EXISTING RETAINING WALL
	CONCRETE EDGING
	CREST
	DIRECTION OF GRADE
	VEHICULAR CROSSING
	KERB RAMP
	WHEEL STOP
	BOLLARD
	ANTI-RAM BOLLARD
	KERB TAPER TO 0
	PROPOSED FINISHED FLOOR LEVEL
	PROPOSED BATTERS
	PROPOSED SPOT HEIGHT
	EXISTING SPOT HEIGHT
	PROPOSED CONTOURS
	EXISTING CONTOURS
	PROPOSED STORMWATER PIPE
	EXISTING STORMWATER PIPE
	GRATED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	PROPOSED RAINWATER TANK
	PROPOSED WATER QUALITY TANK
	VEHICULAR CONCRETE PAVEMENT - TYPE '1'
	ASPHALT PAVEMENT - TYPE '2'
	CONCRETE PAVEMENT - TYPE '3'
	FIRE-TRAIL PAVEMENT - TYPE '4'
	LANDSCAPING

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18	
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18	
03	ISSUED FOR INFORMATION	JO		TB	04.07.18	
04	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18	
05	ISSUED FOR COUNCIL APPROVAL	CP		TB	28.08.18	
06	RE-ISSUED FOR COUNCIL APPROVAL	CP		TB	29.08.18	

sydney business park

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT

REID CAMPBELL

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250@A1

0 2 4 6 8 10 12m

NORTHROP

Sydney

Level 11 345 George Street, Sydney NSW 2000

Ph (02) 9241 4188 Fax (02) 9241 4324

Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

4 DARLING STREET, MARSDEN PARK

DRAWING TITLE

CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION

SITeworks AND STORMWATER MANAGEMENT PLAN - SHEET 02

JOB NUMBER

172938

DRAWING NUMBER

DAC04.02

REVISION

06

DRAWING SHEET SIZE = A1

FOR CONTINUATION REFER TO SHEET 01

PROPOSED WAREHOUSE

FFL35.75

"LOT 306"
DP 1213756
(EXISTING AUS REO SITE)

LEGEND

- BOUNDARY LINE
- EASEMENT LINE
- EXISTING OVERHEAD TRANSMISSION LINE
- EXISTING TRANSMISSION TOWER
- PROPOSED KERB
- SAWCUT AND PAVEMENT INFILL
- KO
- KG
- RW
- RETAINING WALL - TYPE 1
- eRW
- EXISTING RETAINING WALL
- CE
- CONCRETE EDGING
- CREST
- DIRECTION OF GRADE
- VC
- VEHICULAR CROSSING
- KR
- KERB RAMP
- WHEEL STOP
- B
- BOLLARD
- ANTI-RAM BOLLARD
- KERB TAPER TO 0
- FFLXX.XX
- PROPOSED FINISHED FLOOR LEVEL
- PROPOSED BATTERS
- RLXX.XX
- eRLXX.XX
- PROPOSED SPOT HEIGHT
- EXISTING SPOT HEIGHT
- PROPOSED CONTOURS
- EXISTING CONTOURS
- PROPOSED STORMWATER PIPE
- EXISTING STORMWATER PIPE
- GRATED INLET PIT (NEW / EXTG)
- KERB INLET PIT (NEW / EXTG)
- RWT
- PROPOSED RAINWATER TANK
- WQT
- PROPOSED WATER QUALITY TANK
- VEHICULAR CONCRETE PAVEMENT - TYPE '1'
- ASPHALT PAVEMENT - TYPE '2'
- CONCRETE PAVEMENT - TYPE '3'
- FIRE-TRAIL PAVEMENT - TYPE '4'
- LANDSCAPING

FOR CONTINUATION REFER TO SHEET 04

NOT FOR CONSTRUCTION

DRAWN: C. PASKE
DESIGNED: M. SANTIAGO
JOB MANAGER: J. GILLIGAN
VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18	
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18	
03	ISSUED FOR INFORMATION	JO		TB	04.07.18	
04	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18	
05	ISSUED FOR COUNCIL APPROVAL	CP		TB	28.08.18	
06	RE-ISSUED FOR COUNCIL APPROVAL	CP		TB	29.08.18	

sydney business park

ARCHITECT
REID CAMPBELL

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250@A1

NORTHROP
Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT
4 DARLING STREET,
MARSDEN PARK

DRAWING TITLE
CIVIL ENGINEERING WORKS
DEVELOPMENT APPLICATION

SITeworks AND STORMWATER
MANAGEMENT PLAN - SHEET 03


JOB NUMBER
172938

DRAWING NUMBER
DAC04.03

REVISION
06

DRAWING SHEET SIZE = A1

FOR CONTINUATION REFER TO SHEET 02



LEGEND	
	BOUNDARY LINE
	EASEMENT LINE
	EXISTING OVERHEAD TRANSMISSION LINE
	EXISTING TRANSMISSION TOWER
	PROPOSED KERB
	SAWCUT AND PAVEMENT INFILL
	KERB ONLY
	KERB AND GUTTER
	RETAINING WALL - TYPE 1
	EXISTING RETAINING WALL
	CONCRETE EDGING
	CREST
	DIRECTION OF GRADE
	VEHICULAR CROSSING
	KERB RAMP
	WHEEL STOP
	BOLLARD
	ANTI-RAM BOLLARD
	KERB TAPER TO 0
	PROPOSED FINISHED FLOOR LEVEL
	PROPOSED BATTERS
	PROPOSED SPOT HEIGHT
	EXISTING SPOT HEIGHT
	PROPOSED CONTOURS
	EXISTING CONTOURS
	PROPOSED STORMWATER PIPE
	EXISTING STORMWATER PIPE
	GRADED INLET PIT (NEW / EXTG)
	KERB INLET PIT (NEW / EXTG)
	PROPOSED RAINWATER TANK
	PROPOSED WATER QUALITY TANK
	VEHICULAR CONCRETE PAVEMENT - TYPE '1'
	ASPHALT PAVEMENT - TYPE '2'
	CONCRETE PAVEMENT - TYPE '3'
	FIRE-TRAIL PAVEMENT - TYPE '4'
	LANDSCAPING

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT	PROJECT	DRAWING TITLE	JOB NUMBER
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18			4 DARLING STREET, MARSDEN PARK	CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION	172938
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18					
03	ISSUED FOR INFORMATION	JO		TB	04.07.18					
04	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18					
05	ISSUED FOR COUNCIL APPROVAL	CP		TB	28.08.18				SITWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 04	DAC04.04
06	RE-ISSUED FOR COUNCIL APPROVAL	CP		TB	29.08.18					06

sydney business park

REID CAMPBELL

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.

SCALE 1:250@A1

0 2 4 6 8 10 12m

NORTHROP

Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

DRAWING SHEET SIZE = A1

DRAWN: C. PASKE DESIGNED: M. SANTIAGO JOB MANAGER: J. GILLIGAN VERIFIER:

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18
03	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18
04	ISSUED FOR COUNCIL APPROVAL	JO		TB	29.08.18



sydney
business
park

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED

ARCHITECT



REIDCAMPBELL

THE COPYRIGHT OF THIS DRAWING REMAINS WITH
NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE
BEGINNING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS
TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE



NORTHROP

Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

**4 DARLING STREET,
MARSDEN PARK**

DRAWING TITLE

**CIVIL ENGINEERING WORKS
DEVELOPMENT APPLICATION**

**STORMWATER LONGITUDINAL
SECTIONS - SHEET 1**

JOB NUMBER

172938


DRAWING NUMBER

DAC05.11

REVISION

04

DRAWING SHEET SIZE = A1



LINE 01

NOT FOR CONSTRUCTION

DRAWN: C. PASKE
DESIGNED: M. SANTIAGO
JOB MANAGER: J. GILLIGAN
VERIFIER:

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	24.0					
H.G.L. (20yr)	32.634 32.634 32.274					31.036
FINISHED SURFACE	33.488					32.963
NATURAL SURFACE	33.425					32.963
PIPE INVERT LEVEL	32.066 31.755					30.950 30.870
DEPTH TO INVERT	1.422 1.733					2.013 2.093
CO-ORDINATED SETOUT	E299753.264 N6267791.482					E299773.556 N6267783.733
CHAINAGE	322.191					349.021

LINE 01

0.000	E299671.120					
	N6267723.146					
42.485	E299710.706					
	N6267781.839					
84.174	E299753.264					
	N6267791.482					

LINE 03

-13.735	E299783.084					
	N6267798.818					
16.974	E299753.264					
	N6267791.482					

LINE 04

0.000	E299698.779					
	N6267367.216					
23.433	E299701.400					
	N6267743.929					
49.193	E299708.073					
	N6267719.049					

LINE 05

0.000	E299757.386					
	N6267330.332					
10.062	E299717.595					
	N6267728.015					

LINE 06

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18
03	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18
04	ISSUED FOR COUNCIL APPROVAL	JO		TB	29.08.18



sydney
business
park

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED



REIDCAMPBELL

ARCHITECT

THE COPYRIGHT OF THIS DRAWING REMAINS WITH
NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE
COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE
USABILITY, COMPLETENESS OR SCALE OF DRAWINGS
TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR,
AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.



NORTHROP

Sydney

Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

4 DARLING STREET,
MARSDEN PARK

DRAWING TITLE

CIVIL ENGINEERING WORKS
DEVELOPMENT APPLICATION

STORMWATER LONGITUDINAL
SECTIONS - SHEET 2

JOB NUMBER

172938

DRAWING NUMBER

DAC05.12

REVISION

04

DRAWING SHEET SIZE = A1

DRAWN: C. PASKE
DESIGNED: M. SANTIAGO
JOB MANAGER: J. GILLIGAN
VERIFIER:

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	22.0									
H.G.L. (20yr)	31.853	31.730	31.654	31.621	31.598	31.558	31.438	31.395	31.395	31.289
FINISHED SURFACE	32.270	31.836	31.698	31.694	31.694	31.816	31.816	31.816	31.816	31.582
NATURAL SURFACE	31.916	31.771	31.788	31.817	31.950	31.882	31.950	31.896	31.933	31.582
PIPE INVERT LEVEL	30.938	30.738	30.601	30.337	30.317	30.180	29.969	29.679	29.540	29.460
DEPTH TO INVERT	1.332	1.098	1.118	1.097	1.210	1.536	1.619	1.848	2.463	2.122
CO-ORDINATED SETOUT	E29971.553	E299800.057	E299806.783	E299806.783	E299806.783	E299806.783	E299806.783	E299806.783	E299806.783	E299806.783
CHAINAGE	-21.614	6.948	23.624	45.209	64.792	83.108	105.117	119.866	124.966	152.833

LINE 10

DATUM RL	22.0	
H.G.L. (20yr)	31.087	31.084
FINISHED SURFACE	31.985	31.907
NATURAL SURFACE	32.171	31.975
PIPE INVERT LEVEL	30.855	30.735
DEPTH TO INVERT	1.130	1.172
CO-ORDINATED SETOUT	E299882.272	E299888.841
CHAINAGE	-6.510	5.436


LINE 11

DATUM RL	23.0		
H.G.L. (20yr)	31.914	31.680	31.552
FINISHED SURFACE	32.691	32.806	31.940
NATURAL SURFACE	32.014	32.017	32.001
PIPE INVERT LEVEL	31.283	31.163	30.845
DEPTH TO INVERT	1.408	1.643	1.095
CO-ORDINATED SETOUT	E299820.754	E299830.832	E299845.853
CHAINAGE	-38.040	-26.065	-1.111

LINE 12

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT		PROJECT	DRAWING TITLE	JOB NUMBER	
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18			 Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	4 DARLING STREET, MARSDEN PARK	CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION STORMWATER LONGITUDINAL SECTIONS - SHEET 3	172938	
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18							
03	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18							
04	ISSUED FOR COUNCIL APPROVAL	JO		TB	29.08.18							
						DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED		THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD		DRAWING NUMBER DAC05.13		
										REVISION 04		
										DRAWING SHEET SIZE = A1		



NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT	ARCHITECT	ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE	PROJECT	DRAWING TITLE	JOB NUMBER	
01	ISSUED FOR DEVELOPMENT APPLICATION	CP	MS	13.03.18				 Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100	4 DARLING STREET, MARSDEN PARK	CIVIL ENGINEERING WORKS DEVELOPMENT APPLICATION	172938	
02	ISSUED FOR DEVELOPMENT APPLICATION	CP	MS	28.03.18							DRAWING NUMBER	REVISION
03	STORMWATER DRAINAGE AMENDMENT	CP	TB	16.07.18							DAC05.14	04
04	ISSUED FOR COUNCIL APPROVAL	JO	TB	29.08.18							DRAWING SHEET SIZE = A1	
						DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED	THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD					

Drawn: C. PASKE Designed: M. SANTIAGO Job Manager: J. GILLIGAN Verifier:

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 21	
H.G.L. (20yr)	31.731	31.472
FINISHED SURFACE	32.200	31.985
NATURAL SURFACE	31.889	31.933
PIPE INVERT LEVEL	31.154	31.067
DEPTH TO INVERT	1.046	0.919
CO-ORDINATED SETOUT	E299891.452	E299891.580
CHAINAGE	0.000	8.693

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 23	
H.G.L. (20yr)	35.049	34.848
FINISHED SURFACE	35.750	35.551
NATURAL SURFACE	37.916	37.831
PIPE INVERT LEVEL	34.782	34.587
DEPTH TO INVERT	0.968	0.964
CO-ORDINATED SETOUT	E299615.389	E299614.196
CHAINAGE	0.000	5.500

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 24	
H.G.L. (20yr)	35.051	34.850
FINISHED SURFACE	35.750	35.551
NATURAL SURFACE	37.154	37.098
PIPE INVERT LEVEL	34.782	34.587
DEPTH TO INVERT	0.968	0.964
CO-ORDINATED SETOUT	E299639.368	E299638.097
CHAINAGE	0.000	5.500

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 25	
H.G.L. (20yr)	35.054	34.854
FINISHED SURFACE	35.750	35.551
NATURAL SURFACE	36.906	36.849
PIPE INVERT LEVEL	34.782	34.587
DEPTH TO INVERT	0.968	0.964
CO-ORDINATED SETOUT	E299663.218	E299661.997
CHAINAGE	0.000	5.500

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 26	
H.G.L. (20yr)	35.044	34.842
FINISHED SURFACE	35.750	35.551
NATURAL SURFACE	36.826	36.770
PIPE INVERT LEVEL	34.782	34.587
DEPTH TO INVERT	0.968	0.964
CO-ORDINATED SETOUT	E299687.301	E299685.898
CHAINAGE	0.000	5.500

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 27	
H.G.L. (20yr)	35.013	34.813
FINISHED SURFACE	35.750	35.501
NATURAL SURFACE	36.796	36.724
PIPE INVERT LEVEL	34.757	34.512
DEPTH TO INVERT	0.993	0.989
CO-ORDINATED SETOUT	E299710.875	E299709.798
CHAINAGE	0.000	5.502

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 28	
H.G.L. (20yr)	34.988	34.790
FINISHED SURFACE	35.750	35.451
NATURAL SURFACE	34.993	34.992
PIPE INVERT LEVEL	34.734	34.439
DEPTH TO INVERT	1.016	1.012
CO-ORDINATED SETOUT	E299734.934	E299733.699
CHAINAGE	0.000	5.500

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 29	
H.G.L. (20yr)	35.015	34.815
FINISHED SURFACE	35.750	35.500
NATURAL SURFACE	34.697	34.691
PIPE INVERT LEVEL	34.757	34.512
DEPTH TO INVERT	0.993	0.988
CO-ORDINATED SETOUT	E299758.942	E299757.600
CHAINAGE	0.000	5.502

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 30	
H.G.L. (20yr)	35.075	34.880
FINISHED SURFACE	35.750	35.500
NATURAL SURFACE	34.472	34.481
PIPE INVERT LEVEL	34.757	34.512
DEPTH TO INVERT	0.993	0.988
CO-ORDINATED SETOUT	E299782.336	E299781.500
CHAINAGE	0.000	5.513

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE 31	
H.G.L. (20yr)	35.096	34.902
FINISHED SURFACE	35.750	35.500
NATURAL SURFACE	34.482	34.474
PIPE INVERT LEVEL	34.757	34.512
DEPTH TO INVERT	0.993	0.988
CO-ORDINATED SETOUT	E299805.738	E299804.425
CHAINAGE	0.000	5.501

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE EX01	
H.G.L. (20yr)	32.541	32.416
FINISHED SURFACE	34.020	33.927
NATURAL SURFACE	34.020	33.927
PIPE INVERT LEVEL	32.230	32.010
DEPTH TO INVERT	1.790	1.917
CO-ORDINATED SETOUT	E299661.349	E299670.415
CHAINAGE	0.000	9.306

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE EX02	
H.G.L. (20yr)	32.416	32.331
FINISHED SURFACE	33.927	33.712
NATURAL SURFACE	33.927	33.712
PIPE INVERT LEVEL	32.230	32.010
DEPTH TO INVERT	1.790	1.932
CO-ORDINATED SETOUT	E299661.349	E299670.415
CHAINAGE	0.000	9.306

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE EX03	
H.G.L. (20yr)	32.416	32.331
FINISHED SURFACE	33.927	33.712
NATURAL SURFACE	33.927	33.712
PIPE INVERT LEVEL	32.230	32.010
DEPTH TO INVERT	1.790	1.932
CO-ORDINATED SETOUT	E299661.349	E299670.415
CHAINAGE	0.000	9.306

PIPE GRADE (%)
PIPE SIZE (mm)
Vf - FULL PIPE VELOCITY (m/s)
Q20 - PIPE FLOW (L/s)
DRAINAGE LINE

DATUM RL	LINE EX04	
H.G.L. (20yr)	32.416	32.331
FINISHED SURFACE	33.927	33.712
NATURAL SURFACE	33.927	33.712
PIPE INVERT LEVEL	32.230	32.010
DEPTH TO INVERT	1.790	1.932
CO-ORDINATED SETOUT	E299661.349	E299670.415
CHAINAGE	0.000	9.306

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE
01	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	13.03.18
02	ISSUED FOR DEVELOPMENT APPLICATION	CP		MS	28.03.18
03	STORMWATER DRAINAGE AMENDMENT	CP		TB	16.07.18
04	ISSUED FOR COUNCIL APPROVAL	JO		TB	29.08.18



sydney business park

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD



REID CAMPBELL

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK. NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY. THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE.



NORTHROP

Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

PROJECT

4 DARLING STREET,
MARSDEN PARK

DRAWING TITLE

CIVIL ENGINEERING WORKS
DEVELOPMENT APPLICATION

STORMWATER LONGITUDINAL
SECTIONS - SHEET 5

JOB NUMBER

172938

DRAWING NUMBER

DAC05.15

REVISION

04

DRAWING SHEET SIZE = A1



NOT FOR CONSTRUCTION

[illegible]


DRAWN: C. PASKE	JOB MANAGER: J. GILLIGAN	VERIFIER: M. SANTIAGO	12d Model Dynamic Drainage Results																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
			Negative Flow Values Indicate Reverse Flows																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
DATA																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
Pit	Pit	Surface	Pit	Pipe																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															

Appendix B – Site Survey Plan

- NOTES:
- THE POSITION OF FEATURES ARE INDICATIVE ONLY.
 - SERVICES SHOWN HEREON HAVE BEEN LOCATED WHERE POSSIBLE BY FIELD SURVEY. PRIOR TO ANY EXCAVATION OR CONSTRUCTION ON THE SITE, THE RELEVANT AUTHORITY SHOULD BE CONTACTED FOR POSSIBLE LOCATION OF ANY OTHER SERVICES INCLUDING THOSE WHICH MAY BE UNDERGROUND.
 - INDICATES EXISTING SURFACE LEVEL.
 - CONTOURS SHOWN DEPICT THE GENERAL TOPOGRAPHY. THEY DO NOT REPRESENT EXACT LEVELS OTHER THAN AT SPOT LEVELS SHOWN.
 - RELATIONSHIP OF IMPROVEMENTS TO BOUNDARIES IS DIAGRAMMATIC ONLY. WHERE OFFSETS ARE CRITICAL THEY SHOULD BE CONFIRMED BY FURTHER SURVEY.
 - ONLY THE INDIVIDUAL STREET TREES WITHIN THE ROAD RESERVE ARE SHOWN. FURTHER FIELD INSPECTION SHOULD BE CARRIED OUT WHERE TREE DETAILS ARE CONSIDERED TO CRITICALLY AFFECT DESIGN. NO INDIVIDUAL TREES APART FROM AREAS OF TREES & BUSHLAND HAVE BEEN SHOWN.

NOTE:

THESE PLANS SHOULD BE READ IN CONJUNCTION WITH DIGITAL DATA ISSUED TO CLIENT. THE DIGITAL DATA CONTAINS NUMEROUS LAYERS OF INFORMATION WHICH ARE NOT SHOWN ON THESE PLANS FOR THE SAKE OF CLARITY.



Client: Marsden Park Developments	Project: PLAN OF LEVELS & CONTOURS OVER PROPOSED LOT 3005, BEING PART OF LOTS 303-305 IN DP 1213756 DARLING STREET, MARSDEN PARK	FREEBURN W E SURVEYING	MATTHEW FREEBURN LAND, ENGINEERING & MINING SURVEYOR SUITE 2, FIRST FLOOR, "SURVEYOR HOUSE" 2 CASTLEREAGH STREET PENRITH 2750	Telephone 02 4721 2289 Fax 02 4721 5646 email a.dean@freeburnsurveyors.com or matthew@freeburnsurveyors.com	Scale 1:500	Datum: AHD	Contour: 0.5m
					Surveyor: CR/AF	Drawn By: LJMc	Checked: AF
					Date of Survey: April 2017 & Dec 2017		Sheet 1 of 1
					AUTOCAD	REVISION 01	33 444 - LOT 3005

Appendix C – Maintenance Schedule

4 Darling Street, Marsden Park



Stormwater Maintenance Schedule

Prepared on 28.08.18

Site Description: The site is located on the eastern end of Darling Street

Site Area: 57,120 m2

Site Access: Direct access to the site via Darling Street

Inspected by:

Date of Inspection:

Next Inspection:

Items to be Inspected	Frequency	Performed by	Inspected		Maintenance		Maintenance Procedure	Initial
			Yes	No	Yes	No		
General								
Stormwater surface inlet pits	Four Monthly/Aftermajor Storm	Owner/Maintenance Contractor					Remove grate and inspect internal walls and base, repair where required. Remove any collected sediment, debris, litter and vegetaion. (eg. Vacuum/ eductor truck) Inspect and ensure grate is clear of sediment, debris, litter and vegetation. Ensure flush placement of grate on refitment.	
General inspection of complete stormwater drainage system (that's visible - including roof gutters)	Bi-annually	Owner/Maintenance Contractor					Inspect all drainage structure noting any dilapidatin, carry out required repairs.	
Rainwater Tank								
First flush Device	6 monthly	Owner/Maintenance Contractor					Inspect first flush device to ensure correct operation. Remove accumulated litter and debris. If device is not functioning properly repair or replace.	
Internal inspection	6 monthly	Owner/Maintenance Contractor					Check for evidence of access by animals, birds or insect including the presence of mosquito larvae. If present, identify access point and close. If evidence of algae growth, find and close points of light entry.	
Tank and Lids	6 monthly	Owner/Maintenance Contractor					Check structural integrity of tank including roof and access covers. Any dilapidation including holes or gaps are to be noted and repaired.	
Depth of Sediment within Tank	Every 2 Years	Owner/Maintenance Contractor					De-sludge tank(s) by engaging professional cleaner	
Bio-retention Basin								
Basin and contributing areas are clean of debris and domestic litter	6 Monthly	Owner / Maintenance Contractor					Remove litter and debris within basin and in areas that is obstructing flows into basin.	
Inflow points - sediment accumulation / sediment erosion	6 Monthly	Maintenance Contractor					Replace any top soil in eroded area and grade accordingly. Remove any sediment and debris accumulation if present.	
Embankments	6 Monthly	Maintenance Contractor					Inspect embankments show no visible deformity. Repair and regrade embankments. Replace any plants / vegetation if required.	
Basin vegetation condition	3 Monthly	Maintenance Contractor					Ensure vegetation is still in place. Remove and replace any plants that are dead or beyond a reasonable level of rehabilitation. Trim vegetation to a height that is suitable for the plant type.	
Pond Lining	3 Monthly	Maintenance Contractor					Inspect pond lining for any visible damage. Remove and replace with new lining if required.	
Check vegetation is fertilised	6 Monthly	Maintenance Contractor					Where required fertilise plants with appropriate fertiliser for plant type.	
Enviropod								
Enviropod Pit Inserts	Refer Manufacturers Manual	Maintenance/ Specialised Contractor					Refer to manufacturers operation and maintenance manual.	
Jellyfish Cartridge Filters								
Filter Cartridge sump	Refer Manufactures Manual	Maintenance / Specialised Contractor					Refer to manufactures operation and maintenance manual.	
Chamber filter screen, weir, lid, diversion chamber	Refer Manufactures Manual	Maintenance / Specialised Contractor					Refer to manufactures operation and maintenance manual.	