
LIGHTSOURCE DEVELOPMENT SERVICES WEST WYALONG SOLAR FARM CIVIL WORKS

DRAWING LIST

18-583-C000 COVER SHEET AND LOCALITY PLAN NOTES AND LEGENDS GENERAL ARRANGEMNT PLAN TYPICAL DETAILS SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 3 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 4 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 7 18-583-C018 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 8 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 9 18-583-C019 18-583-C020 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 10 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 11 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 12 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 13 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 14 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 15 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 16 18-583-C027 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 17 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 18 18-583-C028 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 19 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 20 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 21 18-583-C032 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 22 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 23 18-583-C033 18-583-C034 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 24 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 25 18-583-C035 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 26 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 27 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 28 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 29 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 30 18-583-C040 18-583-C041 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 31 SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 32

OVERALL PROPOSED STORMWATER CATCHMENT PLAN



LOCALITY PLAN

Date Plotted: 9 Jan 2019 - 04:39PM File Name: F:\18-583 West Wyalong Solar Farm\6.0 Drgs\Civil\Final\18-583-C000.dwg

			Bar Scales	Key Plan	Client	Scales	D	Orawn	DM	Project	Civil Engineers and Project Managers	
					lightsourcebo		D	Designed	DM	WEST WYALONG	Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au	
						Grid MG/	SA C	Checked	АТ	SOLAR FARM		
						Height Datum AHI	ID A	Approved		That .		
					ingintocaroop				Titt	Title	FOR APRROVAL A1	
		09-01-19 05-12-18				THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FOR OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALL INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L			HAT ORIGINALLY		NOT TO BE USED FOR CONSTRUCTION	
Issue	Description	Date				INTENDED WITE	IIIOOI IHE WRII	THEN FEMILISSION OF AIRL		LOCALITY PLAN	Project - Drawing No. Issue P2	

SURVEY NOTES

THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY T.J. HINCHCLIFFE & ASSOCIATES PTY LTD, BEING REGISTERED SURVEYORS. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. AT&L

DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS.

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT AT

THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM THE ORIGINAL SURVEY DOCUMENTS:

- 1. ALL BENCHMARKS ARE STAR PICKETS NEAR FENCE LINES DRIVEN INTO THE GROUND IN A SHALLOW DEPRESSION.
- 2. THIS PLAN IS DRAWN TO NATURAL SCALE.
- 3. CO-ORDINATES OF POINTS IN THE DIGITAL VERSION OF THIS PLAN ARE NOT M.G.A. CO-ORDINATES.
- 4. PLEASE CONTACT T.J. HINCHCLIFFE & ASSOCIATES IF YOU REQUIRE SHIFTS, SWINGS OR SCALE FACTORS TO ACHIEVE M.G.A. CO-ORDINATES
- THIS DETAIL SURVEY IS NOT A SURVEY AS DEFINED BY THE SURVEYING AND SPATIAL INFORMATION ACT, 2002.IF ANY CONSTRUCTION OR DESIGN WORK WHICH RELIES ON CRITICAL SETBACKS FROM THE STREET OR BOUNDARIES IS PLANNED WE RECOMMEND THAT SUCH A SURVEY BE CARRIED OUT TO MORE ACCURATELY DEFINE THE BOUNDARIES AND ANY ENCROACHMENTS BY OR UPON THE LAND. THE BOUNDARIES SHOWN HAVE NOT BEEN MARKED ON THE GROUND & HAVE BEEN DETERMINED BY BOTH PLAN DIMENSIONS & FIELD MEASUREMENT SERVICES SHOWN ARE THOSE THAT WERE VISIBLE AT THE TIME OF SURVEY, SERVICE LOCATIONS SHOULD BE INVESTIGATED WITH THE RELEVANT SERVICE AUTHORITY BEFORE THE COMMENCEMENT OF ANY EARTHWORKS OR CONSTRUCTION

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE. AT & L CAN NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION

AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER. CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING

HAND EXCAVATION WHERE NECESSARY.

ISSUED FOR DEVELOPMENT APPLICATION

ISSUED FOR DEVELOPMENT APPLICATION

Description

CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.

CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

STORMWATER DRAINAGE NOTES

1. STORMWATER DESIGN CRITERIA: (A) AVERAGE RECURRENCE INTERVAL:
1:100 YEARS ROOFED AREAS TO SURCHARGE PIT 1:20 YEARS EXTERNAL PAVEMENTS (B) RAINFALL INTENSITIES:

TIME OF CONCENTRATION: 5 MINUTES 1:100 YEARS= 229 mm/hr 1:20 YEARS= 179 mm/hr

(C) RUNOFF COEFFICIENTS: ROOF AREAS: EXTERNAL PAVEMENTS: C20 =1.0

- 2. PIPES 300 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '3' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O.
- 3. PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC WITH SOLVENT
- WELDED JOINTS.

4. EQUIVALENT STRENGTH VCP OR FRC PIPES MAY BE USED.

- 5. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE upvc pressure pipe grade 6. Ensure all verticals and DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN HEIGHT.
- 6. PIPES TO BE INSTALLED TO TYPE HS3 (ROAD) HS2 (LOTS) SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 7. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 (2006) AND AS/NZS 3500 3.2
- 8. PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO
- APPROVAL BY AT & L. P. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 10. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED.
- 11. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL

Bar Scales

09-01-1

05-12-1

Date

- 12. GRATES AND COVERS SHALL CONFORM TO AS 3996. 13. ALL INTERNAL PIT DIMENSIONS TO CONFORM TO AS3500.3 TABLE 7.5.2.1
- 14. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 5. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.

SITEWORKS NOTES

- 1. ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO AT & L.
- 3. MAKE SMOOTH CONNECTION WITH EXISTING WORKS.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO RMS. SPECIFICATION R116.
- 8. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIFD MATERIAL TO COMPLY WITH RMS. FORM 3051 (UNBOUND), RMS. FORM 3052 (BOUND) COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF BASECOURSE MATERIAL PLACED.
- 9. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH RMS. FORM 3051, 3051.1 AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH RMS. FORM 3051 AND 3051.1 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF AT & L.
- 11. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THIS SHALL BE CLEARLY INDICATED IN THEIR TENDER AND THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.
- 12. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

BULK EARTHWORKS NOTES

- 1. ORIGIN OF LEVELS: REFER SURVEY NOTES
- STRIP ALL TOPSOIL/ORGANIC MATERIAL FROM CONSTRUCTION AREA AND REMOVE FROM SITE OR STOCK PILE AS DIRECTED BY SUPERINTENDENT.
- B. EXCAVATED MATERIAL TO BE USED AS STRUCTURAL FILL PROVIDED THE PLACEMENT MOISTURE CONTENT OF THE MATERIAL IS +/- 2% OF THE OPTIMUM MOISTURE CONTENT.
- 4. COMPACT FILL AREAS AND SUBGRADE TO NOT LESS THAN: LOCATION STANDARD DRY DENSITY
- (AS 1289 E 5.1.1.) UNDER BUILDING SLABS
- ON GROUND 98% UNDER ROADS AND CARPARKS LANDSCAPED AREAS UNLESS NOTED OTHERWISE 98%
- 5. FOR NON COHESIVE MATERIAL, COMPACT TO 75% DENSITY INDEX.
- 5. BEFORE PLACING FILL, PROOF ROLL EXPOSED SUBGRADE WITH AN 8 TONNE (MIN) DEADWEIGHT SMOOTH DRUM VIBRATORY ROLLER TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER).
- 7. FREQUENCY OF COMPACTION TESTING SHALL BE NOT LESS THAN :-(A) 1 TEST PER 200m³ OF FILL PLACED PER 300 LAYER OF FILL. (B) 3 TESTS PER VISIT (C) 1 TEST PER 1000m² OF EXPOSED SUBGRADE TESTING SHALL BE "LEVEL 1" TESTING IN ACCORDANCE WITH AS 3798
- 8. FILLING TO BE PLACED AND COMPACTED IN MAXIMUM 150mm LAYERS 9. NO FILLING SHALL TAKE PLACE TO EXPOSE SUBGRADE UNTIL THE AREA HAS BEEN PROOF ROLLED IN THE PRESENCE OF AT & L AND APPROVAL GIVEN IN WRITING THAT FILLING CAN PROCEED.

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- 1. THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- 2. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS b. EPA REQUIREMENTS
- c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH
- 3. MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.
- 4. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.
- 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- (A) INSTALL A WIND FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (B) INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (C) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL.
- (D) INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- (E) INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN.
- (F) UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 10. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- I. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES PAINTS ACID WASHINGS LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
- (A) PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- (B) ENSURING THAT NOTHING IS NAILED TO THEM
- (C) PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS.
- (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE
- AND THE TRUNK, WHICH EVER IS THE GREATER (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

Project

Title

DM

DM

ΑT

WORKS LEGEND

___<___

EXISTING

FENCE TREES

EXISTING OVERLAND FLOW PATH

EXISTING BOUNDARY

PROPOSED

VEHICLE ACCESS TRACKS SOLTEC TRACKERS

SECURITY FENCING $\overline{}$

──> ──> ─ STORMWATER DRAINAGE SWALE

STORMWATER DRAINAGE CULVERT



CONTRACTOR SHALL CALL; DIAL BEFORE YOU DIG 1100 PRIOR TO COMMENCEMENT OF WORK TO OBTAIN ALL CURRENT SERVICE AUTHORITY PLANS

Civil Engineers and Project Managers

WEST WYALONG SOLAR FARM

NOTES AND

North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au

Level 7, 153 Walker Street

FOR APRROVAL NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 18-583-C001

THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L.

Checked

MGA


AHD


LEGENDS

Date Plotted: 8 Jan 2019 - 09:46AM File Name: F:\18-583 West Wyalong Solar Farm\6.0 Drgs\Civil\Final\18-583-C001.dwg 100mm on Original

Client


Key Plan





TYPICAL SECTION - ACCESS TRACK

SCALE 1:25



		Bar Scales	Key Plan	Client	Scales		Drawn	DM	Project	Civil Engineers and Project Managers	
					AS S	AS SHOWN	Designed	DM	WEST WYALONG	Level 7, 153 Walker Stree North Sydney NSW 2060	
		0 500 1000 1500 2000mm					Cl. l. l	DIVI			
					Grid M	MGA	Checked	AT	SOLAR FARM	ABN 96 130 88 Tel: 02 9438	
		1:20 @ A1 1:40 @ A3	·		Height ^	ALID.	Approved		1	Fax: 02 9923 1055 www.atl.net.au	
				lightsourcebp	Datum A	AHD			Title	info@atl.net.au	
		0 0.5 1 1.5 2 2.5m 1: 25 @ A1 1: 50 @ A3			THIS DRAWING CANNOT BE					Status	
ISSUED FOR DEVELOPMENT APPLICATION	09-01-19					CANNOT BE COP	OPIED OR REPRODUCE	D IN ANY FORM	TYPICAL	FOR APRROVAL	
ISSUED FOR DEVELOPMENT APPLICATION	05-12-18				OR USED FOR ANY OTHER PURPO INTENDED WITHOUT THE V				DETAILS	NOT TO BE USED FOR CONSTRUCTION	
Description	Date				II. (IEI.)	WILLIOUT THE W	, WITTE, TERMIDOTC	ar or mul	DETAILS	Project - Drawing No. 18-583-C005	

