

Sydney Metro City & South West: Crows Nest Over Station Development

North Sydney Development Control Plan 2013 Assessment

Applicable to:	Sydney Metro City & Southwest
Author:	Ethos Urban
Owner	Sydney Metro Authority
Status:	Final
Version:	1
Date of issue:	09.11.2018
Review date:	09.11.2018
© Sydney Metro 2018	

1.0 Introduction

This document supports a concept State Significant Development (SSD)application (concept SSD Application or concept proposal) submitted to the Department of Planning and Environment pursuant to Part 4 of the *Environmental Planning and Assessment Act 1979* (EP&A Act). The concept SSD Application is made under Section 4.22 of the EP&A Act.

Sydney Metro is seeking to secure concept approval for a building above the Crows Nest metro station, otherwise known as over station development (OSD). The concept SSD Application seeks consent for the broad development concept for the future development including the maximum building envelopes, maximum gross floor areas, minimum non-residential floor area, land uses, pedestrian and vehicle access, car parking, signage zones, future subdivision of part of the OSD footprint (if required) and structural, servicing and space provisioning integration with Crows Nest Station which was approved as Critical State Significant Infrastructure (SSI 15_7400) by the Minister for Planning on 9 January 2017 (as modified).

This document has been prepared to assess the concept proposal's consistency with key relevant controls within *North Sydney Development Control Plan 2013* (NSDCP 2013). Clause 11 of *State Environmental Planning Policy (State and Regional Development) 2011* states that development control plans do not apply to SSD. Accordingly, NSDCP 2013 does not apply to this concept proposal. Also, the Secretary's Environmental Assessment Requirements (SEARs) for the project do not list NSDCP 2013 as a relevant document. Nonetheless, the underlying objectives of NSDCP 2013 have informed and influenced this application, as demonstrated in the assessment below.

2.0 Assessment against NSDCP 2013 controls

The table below provides an assessment of the concept proposal against key relevant controls contained in the NSDCP 2013.

Section	Provision	Concept proposal
Part B, Section 2 – Commercial and Mixed Use Development		
2.4.3 Setbacks	P1 Provide a setback for public space at ground level where indicated in the relevant character statement (refer to Part C of the DCP)	Refer to Part C assessment below.
	P2 New development must give consideration to the setbacks of adjacent buildings and heritage items	Complies The proposed building envelopes have various setbacks to several frontages. The setbacks consider the existing setbacks of adjacent buildings and heritage items.



Section	Provision	Concept proposal
		Site A has a setback of between 1.5 metres and 3 metres from Pacific Highway in response to the design of the station box approved under SSI 15_7400.
		The building envelopes are setback along Hume Street to allow for a 24 metre building separation between the buildings on Site A and Site B.
		Site A and B are setback 2-2.8 metres and 1.2-2.6 metres respectively along Clarke Lane to allow for future street widening. Site A is also set back approximately 1.5 metres along Oxley Street to align with the St Leonards Centre heritage item across Clarke Lane.
	Front	Refer to Part C assessment below.
	P3 A zero metre setback must be provided, unless an alternative setback is identified within the relevant character statement (refer to Part C of the DCP)	
	P4 That part of the building located above the podium must be setbackin accordance with the relevant area character statement (refer to Part C of the DCP)	Refer to Part C assessment below.
	Side & Rear	Refer to Part C assessment below.
	P5 A zero metre setback, unless an alternative setback is identified within the relevant character statement (refer to Part C of the DCP)	
	P6 Despite P5 above, buildings containing non-residential activities must be	Not applicable
	setback a minimum of 3m from the property boundary where the adjoining site has balconies or windows to the main living areas of dwellings or serviced apartments located at the same level	The adjoining developments to Site A, B and C do not contain residential uses, or where they do, are not adjacent to areas of the concept SSD Application proposing non-residential activities.
2.3.7 Solar access	P1 Development within the North Sydney Centre must comply with the height and overshadowing requirements contained within cl. 4.3, and cl. 6.3 of NSLEP 2013	Generally Complies The proposed building envelope exceeds maximum height shown on the Height of Buildings Map under clause 4.3 of NSLEP 2013.

Page 3 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
		In October 2018, the Department of Planning and Environment (DPE) publicly exhibited a Rezoning Proposal Report to support a proposal to amend the NSLEP 2013. The Rezoning Proposal applies to the Crows Nest Sydney Metro site only. As a proposed instrument, this Rezoning Proposal is a matter for consideration under Section 4.15(1)(a)(ii) of the EP&A Act. Compliance with the Rezoning Proposal Report and the associated proposed controls are provided as an Addendum to this EIS at Appendix JJ. In summary, the concept proposal is generally consistent with the height of buildings in the Rezoning Proposal.
		Clause 6.3 of the NSLEP 2013 is not relevant to the subject development as it is not located within, nor will it have any impact on, the North Sydney Centre.
2.3.8 Views	P1 Where appropriate, the opening up of views should be sought to improve the legibility of the area. P4 Maintain and protect views identified in the relevant character statement (refer to Part C of the DCP) from future development.	Complies
		The proposal is visually prominent from certain local viewpoints, in particular from Ernest Place, Hume Street Park and Willoughby Road. However, even in these instances, the development appropriately responds to local contexts. The proposed building envelope for Site C, being 8 stories, provides a transitional foreground view to the 27 storey buildings in the background from these locations.
		From Willoughby Road/Ernest Place, large expanses of sky remain visible and the legibility of pedestrian reading and appreciation of the single storey shopfronts on Willoughby Road remains.
		Complies
		The proposed development is partly contained within the Crows Nest Town Centre and partially within the St Leonards Town Centre. Within the St Leonards Town Centre precinct, the NSDCP (2013) identifies the below view point:
		 Slot views to the sky and between higher buildings are to be provided

Page 4 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
		Within the Crows Nest Town Centre precinct, the NSDCP (2013) identifies the below view points:
		Vista north along Willoughby Road and Pacific Highway
		• District views from the upper levels of taller buildings.
		The proposed development does not infringe upon these views, and provides slots between buildings to allow for views of the sky, with the exception of district views from the upper levels of 545 Pacific Highway. Refer to Section 8.3.2 of the EIS.
2.4.9 Through- site pedestrian links	P1 Provide linkages through sites to other streets and laneways as identified in the relevant area character statement (refer to Part C of the DCP) applying to the site or where enhancing pedestrian movement to public transport infrastructure.	Complies Refer to Part C assessment below.
2.4.10 Streetscape	P3 Where practical, the building's ground level façade to a laneway should be provided as an active frontage (e.g. has a retail or commercial premises fronting the laneway).	Not applicable The ground level facades are being dealt with under the terms of the CSSI Approval and will be resolved through the preparation of the Station Design and Precinct Plan required under that approval.

Part B, Section 10 – Car parking and Transport

10.2 Parking	Non residential	Generally Complies
Provision	 P7 Provide on-site car parking at the maximum rate specified below: (a) B4 Mixed Use – Crows Nest, Neutral Bay, Cremorne – 1 space / 60m² non residential GFA 	The indicative OSD design (refer to Appendix D of the EIS) provides for 150 parking spaces, including 125 spaces in Site A (for residential uses) and 25 spaces in Site B (for tourist and visitor accommodation uses or commercial uses).
	 (b) B4 Mixed Use – North Sydney Centre, Milsons Point, St Leonards – 1 Space / 400m² non-residential GFA Residential 	The proposed parking spaces are supplemented by 138 existing on street and off-street parking spaces, 26 proposed motorcycle spaces and 198 bicycle spaces.

© Sydney Metro 2018

Page 5 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	 (a) Residential flat buildings, shop top housing – B4 Mixed Use (St Leonards Precinct 2 & 3) i. Studio, 1 bedroom – 0.25 space/dwelling ii. 2 or more bedrooms – 0.5 space/dwelling iii. Motorcycle parking – 1 space/10 car spaces 	The traffic report provided at Appendix AA of the EIS identifies that while this is a reduction in the number of parking spaces provided on the site compared to what was previously provided, there is a change in the nature of the use of the parking. The previously existing spaces were likely to be used primarily for car trips to work at Crows Nest, while the proposed car spaces will now be used by residents travelling from home at Crows Nest. It is also expected that due to the high level of public transport connectivity from the site, week day peak period car trips will be minimised, with residents expected to take advantage of the public transport options available on and near the site.
		The traffic assessment takes into consideration the location of the proposed residential buildings above an operational metro station and with excellent public transport links to numerous employment and retail areas.
		The provision of 0.25 parking spaces per one-bedroom apartment and 0.5 parking spaces per two-bedroom and three-bedroom apartment follows the trend of apartment parking allocation in the area. This is consistent with the North Sydney DCP maximum rate of 0.25 parking spaces per one bedroom and 0.5 parking spaces per two bedroom and above.
	P9 On-site car parking provision significantly below maximum rates specified above will generally only be considered if the proposed development has good access to public transport due to the impact that unmet on-site parking demand may have on surrounding residential streets, if viable alternative transport modes are not available	Complies The proposed development has excellent public transport links to numerous employment and retail areas, due to the close proximity of the metro.
	P12 Parking for motor cycles must be provided at the minimum rate of 1 space per 10 cars or part thereof.	Complies The development provides 26 motorcycle parking spaces, which complies with the one space per 10 car spaces ratio.

Part B, Section 9 – Advertising and signage

© Sydney Metro 2018

Page 6 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
9.4 General Controls – Design, Scale and Size	P1 Signage attached to a building is to be designed, scaled and sized having regard to a façade grid analysis.	Complies The proposed indicative signage zones are appropriately placed so as to
	P2 Where practical signage not attached to buildings must be designed to have regard to the size, height and scale of nearby buildings and their elements.	not obstruct views, cause overshadowing or dominate the building. Details of the signage would be provided as part of the future detailed SSD
	P3 Signage should be visually interesting and integrated with the architecture of the building.	Application(s) and would have regards to the provisions of this DCP. Signage Zones are proposed in the Built Form and Urban Design Report at Appendix F to the EIS.
	P4 Lettering, materials and colours should be used that complement the existing building or place.	
	P5 Signage must not dominate the building or site to which it is attached.	
	P6 Do not locate signage where it will obstruct views, vistas or cause significant overshadowing.	
	P7 Signage must not dominate the skyline or protrude above any parapet or eaves.	
	P8 Signage must not cover any window, other opening or significant architectural features of the building.	
	P9 The proposed means of fixture to the building or any support structure for freestanding signs must be consistent with the relevant character statement is Section 9.2.	
9.5 Location	P1 Where relevant, signage should be located to take account of a façade-grid analysis.	Complies

Page 7 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	P2 The preferred location for signage is identified in the relevant character statement in Section 9.2.	The application seeks concept approval for future business and building identification signage. The Built Form and Design Report (Appendix F of the EIS) details concept proposals for indicative signage locations on all
	P3 Signage should be located such that they do not unreasonably obstruct accessible paths of travel for pedestrians.	buildings. The specific signage to be located within the signage zones would be subject to separate approval and would be refined as part of the future detailed SSD Application(s).
	P4 Signage should be located such that they do not obscure a driver's or pedestrian's sightlines, especially in the vicinity of intersections, traffic control devices or driveways.	
	P5 Provide signs that respect the viewing rights of other advertisers.	
9.6 Restrictions	P3 Must not provide more than one large building and/or business identification sign per building, allocated to a major tenant of that building.	Generally Complies The indicative signage zones for building naming rights and tenants are integrated into the building design and are appropriately placed to avoid visual clutter. The proposed indicative signage zones are similar to the signage of commercial towers in nearby St Leonards in terms of size and scale.
	P4 Avoid advertising products that are not sold on the premises.	
	P5 Maximum of one directory board per multiple-occupancy buildings.	
	P6. Where provided, the name or logo of the person who owns or leases an advertisement must be integrated into the advertising display area and no exceed 0.25m ² in area.	
	P7 Any consent granted by Council for advertising signs (i.e. not building identification or business identification signs) is valid for a maximum of three (3) years.	
9.8 Pedestrian and Road Safety	P1 Signage should be designed in accordance with the provisions contained within the NSW Roads and Traffic Authority Policy for Advertising on RTA infrastructure (1999).	Complies

Page 8 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	result in a pedestrian or driver being confused with messages contained within road traffic signs, signals or other traffic information device.	The proposed signage zones are appropriately placed and would not adversely affect driver and pedestrian safety. Any signage proposed under a future detailed SSD Application would include additional assessment under this provision.
	P3 The proposed sign does not obscure a road hazard, traffic warning or directional sign or signal, oncoming vehicles or pedestrians.	
	P5 Signs must not be located where drivers and pedestrians require a higher level of concentration (e.g. major intersections)	

Part C3.1 St Leonards Town Centre (Site A, C)

3.1.1 Significant Elements	Land Use P1 Predominantly mixed commercial and residential development. P2 Commercial development. P3 Community facilities. P4 Passive and active recreation spaces	Complies The concept proposal provides a variety of mixed commercial and residential development, as well as a variety of community facilities and open spaces, such as a childcare centre and public roof garden.
	Topography P5 Slight falls to the east and north east from the Pacific Highway which generally follows the ridgeline	Complies The building envelope reflects this fall to the north east, with a reduction in the height of the proposed Site B building, reflecting the change in topography.
	Identity / Icons P7 St Leonards Station as a major transport interchange hub. P8 Pacific Highway, a major sub-arterial thoroughfare	Complies The proposed development does not impact upon the identity of these areas.

© Sydney Metro 2018

Page 9 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	Streetscape	Not Applicable
	P10 Wide fully paved footpaths along Pacific Highway and other commercial and mixed use buildings.	The ground level public interface details are being dealt with under the terms of the CSSI Approval and will be resolved through the preparation of
	P12 Awnings provided along the Pacific Highway and for other commercial and mixed use buildings.	the Station Design and Precinct Plan required under that approval.
	P13 Irregular planting of street trees.	
	Public transport	Complies
	P14 Development is to take advantage of high levels of access to high frequency public train and bus services	The concept proposal takes advantage of the accessibility provided by the Crows Nest Station by locating significant commercial, tourist and visitor
	P15 Public transport, cycling and walking are the main forms of transport to the Centre.	accommodation and residential floor space directly above the station.
3.1.2 Desired	Diversity of activities, facilities, opportunities and services	Complies
Future Character	 P1 Predominantly medium-rise, mixed commercial and residential development. P2 Provision of a variety of different sized commercial office, business, retail, recreation (indoor and outdoor) community, entertainment, food and drink and other active non-residential uses at the street level in the Commercial Core and Mixed Use zones P5 High density residential accommodation within mixed use buildings is concentrated closest to the railway station. 	The concept proposal provides mixed commercial, tourist and visitor accommodation and residential development, with a variety of commercial office, business, retail, recreation, entertainment and food and drink uses within the B4 Mixed Use Zone. The proposal also provides a concentration of residential accommodation above the future Crows Nest Metro Station.
	Public spaces and facilities	Complies
	P7 Outdoor dining to be concentrated along widened footpaths to Atchison, Mitchell and Oxley Streets.	The CSSI Approval provides the opportunity for public spaces and facilities. The increased setback of Site A by 1.5 metres to Oxley Street allows for a widened footpath for future public uses.

Page 10 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	P11 Artworks and water features are integrated into design of the plaza – artworks and other features act as windbreaks, particularly at the Pacific Highway end of Mitchell Street.	As identified in the Built Form and Urban Design Report (Appendix F of the EIS), the provision of Public Art at all stations and associated Over Station Developments must aim to:
	P12 Plazas incorporate space for public entertainment and expression of community identity, large enough to hold an open air performance or market. P13 Roof top gardens and public facilities that allow public access to district views from higher floors.	 Elevate the customer's travel experience; Create a benchmark in national transit art; and Engage and expand diverse audiences for contemporary art. The OSD Public Art Strategy will be further developed for the Stage 2 detailed SSD Application(s) to align with the broader approach to Public Art to align with the further Sydney Metro plan. The Built Form and Urban Design Report also outlines the provision of a rooftop garden and public facility for shared community engagement opportunities, and to allow public access to district views from higher floors.
	Accessibility and permeability P16 New through site links are to align as best as possible with existing through site links to maximise permeability.	Not Applicable The ground level public interface details are being dealt with under the terms of the CSSI Approval and will be resolved through the preparation of the Station Design and Precinct Plan required under that approval.
3.1.3 Desired Built Form	Subdivision P1 Maintain a frontage of 20m – 40m, which equates approximately to the amalgamation of two or three original allotments. P2 Development on consolidated allotments with a frontage wider than 20m – 40m frontage is to be broken down by articulation, design and detailing, change in materials and colours.	Not Applicable The ground level facades and articulation are being addressed under the terms of the CSSI Approval and will be resolved through the preparation of the Station Design and Precinct Plan required under that approval.
	Form, massing and scale	Generally Complies

Page 11 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -




Section	Provision	Concept proposal
	 P3 Buildings should generally step down in height from the tallest buildings, being the Forum (201-207 Pacific Highway) down to the surrounding areas and the lower scale development on Chandos Street, Willoughby Road, Crows Nest Town Centre, the Upper Slopes Neighbourhood and Crows Nest Neighbourhood. P4 Roof design presents a varies, composed and interesting skyline when viewed from a regional context. P5 Architectural detailing and ornamentation provides a rich visual texture and a symbolic reference to the history of the place, the building's use or occupant. P6 Developments on land greater than 1,000m² should consider the incorporation 	The concept SSD Application proposes a built form that considers the context of the site, including the existing development, the transitional nature of the local area and the proximity to public transport. The scale of the proposal will strengthen the streetscape and is in line with the desire to situate prominent buildings at major entrances or above train stations. While the tallest buildings in the precinct are located closer towards St Leonards, it remains appropriate to provide a notable locational marker at the site as an identifier of the new station in accordance with the height and density proposed in the 2036 Draft Plan.
	of internal courtyards adjacent to laneways and through site links to broaden the range and form of open space in the locality.	in built form and prevents the repetitive orientation of buildings and roof lines which can result in the perception of greater density.
		The three sites have a total area of more than 1000m ² , and therefore the indicative OSD design has included opportunities for future social infrastructure on Site A or Site C.
	Setbacks	Not Applicable
	P7 Zero setback to all street frontages, with the exception of the setbacks on the Building Setbacks Map (refer to Figure C $-$ 3.2)	The station building dictates the street level setbacks.

Page 12 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -





Page 13 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	Podiums	Partially complies
	P8 Podiums are to be provided in accordance with the Building Podiums Map (refer to Figure C-3.3) P9 Despite P8, corner sites are to maintain a consistent podium height to all street frontages to achieve consistent built form.	The articulation of the proposed design at Site A seeks to demarcate between the podium and the building above and relates to the existing scale of Crows Nest by providing a podium which preserves the street character along the Pacific Highway. The podium is largely dictated by the station box. Above the podium, the indicative design has sought to relate to the existing built form along the streetscape either through increased setbacks, or materiality changes to demarcate between the podium and the areas above.

Page 14 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -





Page 15 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -




Section	Provision	Concept proposal
	Above podium setbacks	
	P10 All buildings are to be designed to provide setbacks above the podium in accordance with the Above Podium Setbacks Map (refer to Figure C-3.4). Setbacks above the podium are to be measured from the outer wall of the podium.	
	P11 Despite P10, increased setbacks above the podium may be required to achieve adequate building separation in accordance with SEPP 65.	

Page 16 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -





Page 17 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	Awnings	Not Applicable
	P12 Awnings are to be provided along all street frontages in the B3 Commercial Core and B4 Mixed Use zones	The ground level awning details are being dealt with under the terms of the CSSI Approval and will be resolved through the preparation of the Station Design and Precinct Plan required under that approval.
	Solar Access	Complies
	P14 Development should not increase overshadowing of the existing or proposed public open space area at Hume Street Park bounded by Pole Lane, Oxley Street, Clarke Street and Hume Street between the hours of 9am – 3pm.	No areas of Hume Street Park will be affected by overshadowing caused by the OSD prior to 3.00pm at any time of year.
	Noise	Capable of compliance
	P15 Elevations of buildings fronting Pacific Highway and Chandos Street are to be designed and incorporate features to minimize traffic noise transmission (e.g. the use of cavity brick walls, double glazing, minimal glazing, solid core doors, concrete floors, enclosed balconies etc).	This concept SSD Application seeks approval for building envelopes only. Features and materiality that would minimise traffic noise transmissions are able to be addressed as part of a future detailed SSD Application(s).
	Views	Complies
	P16 Slot views to the sky and between higher buildings are to be provided.	The concept proposal allows for separation in the building envelope of Site
	(Note Provision P17 – P22 do not apply to the proposed development)	A to allow for slot views to the wider district skyline.
	Car accommodation	Complies
	P23 Where a property has a frontage to a laneway, vehicular access must be provided from the laneway	The concept proposal provides all OSD parking and loading dock access off Clarke Lane in Site A and Site B. The use of public transport, due to the accessibility of the Crows Nest Metro Station, is promoted, and the proposed parking provision reflects this.
	P24 All off-street car parking must be provided underground	
	P25 Pick up and drop off points for public transport and taxi ranks should be located close to public spaces and activities, and main building entries.	

Page 18 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	P26 Short stay (ten minute) parking spaces should be located close to meeting places.	
	P27 The amount of long stay commuter parking is minimized P28 Non-residential parking is minimised	

3.2 Crows Nest Town Centre (Site B)

3.2.1 Significant elements	Land Use	Complies
	P1 Predominantly mixed commercial and residential development.	The concept proposal provides a variety of mixed commercial, residential, tourist and visitor accommodation development in addition to social infrastructure
	P2 Public parking facilities.	
	P3 Community facilities.	
	P4 Medium density residential accommodation	
	P5. Passive and active recreation spaces.\	
	Topography	Complies
	P6 Slight falls to the east and north east from the Pacific Highway which generally follows the ridgeline.	The building envelope reflects this fall to the north east, with a reduction the height of the proposed Site B building, reflecting the change in
	Natural Features	topography.
	P7 Ridge line following the alignment of Pacific Highway.	
	Views	Complies
	P8 The following views and vistas are to be preserved and where possible enhanced:	The proposed development does not infringe upon the views listed in the NSDCP. The proposal is visually prominent form certain local viewpoints, in particular from Ernest Place, Hume Street Park and Willoughby Road. However, the design responds to the local context in this sense by ensuring a large expanse of sky remains visible and the legibility of a
	(a) Vista north along Willoughby Road and Pacific Highway.	
	(b) District views from the upper levels of taller buildings.	

© Sydney Metro 2018

Page 19 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
		pedestrian reading and appreciation of the single storey shopfronts on Willoughby Road remains.
	Identity / Icons	Complies
	P9 Crows Nest five ways intersection	The proposed development does not impact upon the identity of these
	P10 Formalised outdoor dining on Willoughby Road, Burlington, Ernest and Holtermann Streets.	areas and promotes the importance of the Pacific Highway as a major sub- arterial thoroughfare.
	P11 Pacific Highway and Falcon Streets, major sub-arterial thoroughfares	
	P12 Hume Street Park	
3.2.2 Desired Future Character	Diversity of activities, facilities, opportunities and services	Generally complies
	P2 Remainder of the Centre medium rise, mixed used development, boundary to boundary with setbacks a laneway, public spaces and above podium – shops at ground level, non-residential/residential on the first floor, residential above.	The mixed commercial and residential use of the concept proposal allows for setbacks on laneways and public spaces. The above podium setbacks are varied, but read similarly to traditional podiums
3.2.3 Desired	Setbacks	Not Applicable
Built Form	P3 Zero setback to all street frontages	The proposed building envelope sits above the approved station building (CSSI Approval) and therefore has no bearing on street level setbacks.
	P4 1 1.5m setback to all laneways.	
	Podiums	Partially Applies
	P5 A podium of 13m (4 storey) to all streets with a setback of 3m above the podium level, with the following exceptions:	There is no podium element on Site B, however the proposal provides distinct articulation of materiality to relate to the streetscape of the Pacific Highway heights. The first three levels are proposed to be a more solid element in comparison to the levels above, providing a lower built form which reads similarly to a traditional podium.
	(a) A podium of 8.5m (2 storey) with a setback of 3m above the podium to:	
	i. Pacific Highway, between Shirley Road and Hume Street	
	(b) A podium of 10m (3 storey) to all laneways, with a setback of 3m above the podium.	

Page 20 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



Section	Provision	Concept proposal
	Building design	Complies
	P6 Consistent parapet façade heights are provided along Willoughby Road and the Pacific Highway.	The building parapets will be resolved as part of future detailed SSD Application(s).
	P7 Off street car parking must be provided underground except when owned and operated by Council as a public car park.	Off street car parking will be provided above ground in Site A and Site B, with access available via Clarke Lane.
	Noise	Capable of compliance
	P8 Elevations of buildings fronting Falcon Street and Pacific Highway are to be designed and incorporate design features to minimize traffic noise transmission (e.g. the use of cavity brick walls, double glazing, minimal glazing, solid core doors, concrete floors, enclosed balconies etc.)	This concept SSD Application seeks approval for building envelopes only. Features and materiality that would minimise traffic noise transmissions are able to be addressed as part of a future detailed SSD Application (s).
	Awnings	Not Applicable
	P9 Awnings must be provided to all street frontages, except laneways.	The ground level awning details are being dealt with under the terms of the CSSI Approval and will be resolved through the preparation of the Station Design and Precinct Plan required under that approval.
	Car Accommodation	Complies
	No vehicular access is permitted to:	Vehicular access will be provided to Site B via Clarke Lane to redirect
	Pacific Highway between Shirley Road and Hume Street	traffic entry away from Pacific Highway.

Page 21 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -



3.0 Conclusion

Overall, it has been found that the concept proposal generally complies with relevant controls within the NSDCP 2013, with sufficient justification for any variation.

The concept proposal aligns with the Council's desired future character and built form for Crows Nest and St Leonards by capitalising on the transport benefits of Sydney Metro, delivering significant commercial, tourist and visitor accommodation and residential floor space, providing for activation and respecting surrounding heritage items.

© Sydney Metro 2018

Page 22 of 22

Sydney Metro City & Southwest | Crows Nest Over Station Development EIS -