

Overland Flow Assessment & Stormwater Management Report 2B-6 Hassall Street Parramatta

Issue: A- Development Application

3rd April 2019

Prepared For: CHARTER HALL LIMITED

Project No.: 18570C

Document No.: 18570-CH RPT-SWMP-190403



Report Amendment Register

Issue	Section & Page No.	Issue / Amendment Details	Author	Reviewer	Date
Α	All	DEVELOPMENT APPLICATION	S.S/Z.J	C.R	03.04.19
		T T			
				•	
		- A		-	
		5 1			

ISSUE / AMENDMENT AUTHOR:

Author of Issue / Amendment Signing for and on behalf of Robert Bird Group Pty Ltd

Reviewer of Issue / Amendment Signing for and on behalf of Robert Bird Group Pty Ltd

REVIEWER:



Table of Contents

1.0	Introd	duction	1
	1.1	Executive Summary	. 1
	1.2	Site Description	. 1
	1.3	Standards and Design reference information	. 2
2.0	Flood	ling and Freeboard levels	2
3.0	Propo	osed Stormwater Quantity Strategy	3
	3.1	Existing Catchment Analysis	. 3
	3.2	Proposed Stormwater Catchment Analysis	. 3
	3.3	Proposed On-site Detention	. 3
4.0	Storn	nwater Quality Management	4
	4.1	Water Quality Train Performance	. 4
5.0	Erosi	on and Sediment Control	5
	ndix A	·	
	ndix B ndix C		
	ndix D	G	

This report has been prepared on behalf of and for the exclusive use of the Client, and is subject to and issued in accordance with the agreement between the Client and Robert Bird Group Pty Ltd. Robert Bird Group Pty Ltd accepts no liability or responsibility whatsoever for any use of or reliance upon this report by any third party. Any copying of this report to external parties requires the permission of the Client and Robert Bird Group Pty Ltd.

1.0 Introduction

1.1 Executive Summary

This report has been prepared by Robert Bird Group (RBG) and is submitted to the City of Parramatta Council. This report is to accompany a Development Application (DA) for a mixed-use tertiary educational and commercial development at 2B-6 Hassall Street, Parramatta.

This stormwater management report summarises the stormwater drainage design for the proposed development site and its connections to existing networks for point of discharge. Stormwater Quality management and Stormwater Management Strategy has also been incorporated within this report. All design of stormwater infrastructure including detention tanks and treatment devices has been carried out by Floth Pty.Ltd.

Other associated reference information, standards and inputs, a description of the existing site and the proposed works, discussion on the pre- and post- development catchment analysis has also been discussed within this report.

1.2 Site Description

The site is located at 2B-6 Hassall Street, in the City of Parramatta locality. The proposed development area is currently occupied by three allotments of land that comprises of a two-storey structure, a three-storey low residential apartment and a vacant lot in between the two lots to provide a partition. The site is approximately 62m long and 48m wide, is located between Hassall Street to the south and Station Street to the west. The project area is on a flat topography at the crest of Hassall Street.



Figure 1-1: Project Extents

1.3 Standards and Design reference information

The project team has consulted with City of Parramatta Council during Pre-DA stage. City of Parramatta Council require that the stormwater design is carried out in accordance with the City of Parramatta Development Control Plan (DCP) 2011, Interim Floodplain Management Plan and Stormwater Drainage Guideline.

Other reports from City of Parramatta which have been reviewed in the preparation of this reports are:

- Stormwater and OSD documentation DA checklist
- Development Engineering Design Guidelines 2018
- Upper Parramatta River Catchment Trust (UPRCT) On Site Detention Handbook 2005
- Upper Parramatta River Catchment Trust (UPRCT) Calculation Sheet V9
- Stormwater Disposal Policy
- AS 3500 National Plumbing Code Part 3 Stormwater Drainage
- Australian Rainfall and Runoff 2016
- Blue Book (Landcom 2004)

2.0 Flooding and Freeboard levels

Based on City of Parramatta flood maps, (Refer to Appendix D), the subject site is not located within any of the Low, Medium and High flood zones.

Consultation with council's Senior Development Engineer (Andrew Rofail) has occurred and we have been advised that freeboard is not required as the development is outside of the floodplain. This advice also appears consistent with neighbouring properties such as 10 Hassall street.




Figure 2-1 10 Hassall Street Basement entrance, with no freeboard

RBG have completed an upstream and local catchment review along Hassall street to assess whether any external overland flow paths may impact the development. It was found that the proposed development is located at the crest of Hassall Street and that the adjoining roads (Station Street and Charles Street) fall away from the development. Hence the project is not impacted by any significant external overland flow paths.

Based on the above RBG the design provides a minimum vehicle clearance of 225mm between kerb invert and property line. This effective freeboard consists of a 150mm kerb and a 2.5% cross fall along the pedestrian footpath.

3.0 Proposed Stormwater Quantity Strategy

3.1 Existing Catchment Analysis

Based on the survey it is evident that the existing structures within the site are currently discharging into the kerb inlets on Hassall Street. No stormwater pits have been detected on site from the survey information provided.

3.2 Proposed Stormwater Catchment Analysis

The majority of the runoff from the development is to be captured and detained by an onsite detention (OSD) system using gravity flow. This system is comprised of rainwater gutters, inlets, pipes and pits.

In accordance with Council standards, Floth has designed the OSD system to cater for all storm durations up to and including the 1% Annual Exceedance Probability (AEP).

This section aims to summarise the approach implemented within the project.

Total Catchment area	2647m ²	
Area of Site Draining to OSD	2456m ²	
Residual Site Area (lot Area – Roof Area)	880m²	
Area Bypassing Storage	191m²	
Area Bypassing / Residual Site Area %	21.7%	

3.3 Proposed On-site Detention

The proposed OSD design follows the City of Parramatta guidelines. The OSD sizing has been calculated using the "On-Site Detention Calculation Sheet for Upper Parramatta River Catchment HED Secondary Outlet" Spreadsheet, provided by the City of Parramatta.

A key set up to this design has been implementing the City of Parramatta's recent approach to combined OSD's and WSUD devices. That is by designing a separate chamber for the WSUD device, capable of treating and holding the flow from a 3-month storm. Refer to Appendix C for drawings by Floth.

A summary of the design is shown below.

WSUD chamber volume	9.58m³
OSD Total Volume	120m³
Site Discharge	28.21L/s

4.0 Stormwater Quality Management

A proprietary water quality treatment system has been utilised to ensure that the development improves the quality of stormwater leaving the site the project. Floth has modelled the proposed treatment Train performance using the computer software "MUSIC". Refer to Appendix C for MUSIC model provided by Floth.

The projects approach to water quality urban design has been summarised below.

4.1 Water Quality Train Performance

The Stormwater 360 StormFilter Cartridges system has been proposed and can be installed in the detention tank. The system is effective at removing total suspended solids, total phosphorus, and total nitrogen to reach the reduction targets.

As per Council's recent approach the StormFilter Cartridges have been installed into a separate chamber within the OSD capable of treating a 3-month flow.

A summary of the performance is shown below.

Pollutant	Objective Target	Design Reduction
Gross Pollutant (GP)	90%	95%
Total Suspended Solids (TSS)	85%	85%
Total Phosphorus (TP)	60%	86.9%
Total Nitrogen (TN)	45%	80%




Figure 4-1 MUSIC Modelling Performance

5.0 Erosion and Sediment Control

To maintain the water quality during the construction stage, erosion and sediment control measures will be installed. Soil management measures shall follow the Landcom guidelines Managing Urban Stormwater Runoff: Soils and Construction ("Blue Book"), City of Parramatta DCP and Drainage Standards.

The footprint of the basement and above ground structure is such that disturbed soil will only be exposed during excavation of the basement. As such the majority of RBG's erosion and sediment control strategy takes places during the early works and preparation of the site.

RBG's proposed basement drainage strategy during construction consists of the following;

- 1. The basement rain and groundwater is to be stored and inspected prior to being pumped off site. This is to verify that the water is free of contamination, so its disposal should not contribute to water pollution.
- 2. To remove water from the work area, the pump intake should be kept as close to the surface of the pool as possible. Floating intakes should be used when the depth of water is sufficient. Care will be taken to avoid pumping from the bottom of ponds, and constant supervision is required during pumping operations to ensure this does not happen.

The following additional erosion and sediment control measure for the development are also required throughout the duration of the project to protect downstream infrastructure.

- Sediment fences around stockpiles and construction zones where soils are exposed;
- Sediment basin with sediment storage volume;
- Sediment protection devices on existing and proposed inlet pits i.e. filter socks; and
- Truck Wash/Shaker Grid at all site access/egress points.

Refer to drawing C-1-00 in Appendix B for further information.

Stormwater Management Report 2B-6 Hassall Street, Parramatta Issue: A

Appendix A

City of Parramatta Council Stormwater and OSD documentation DA checklist.



STORMWATER & OSD **DOCUMENTATION DA CHECKLIST**

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

- The purpose of this form is to confirm that your stormwater design and OSD drawings (where necessary) have been prepared in line with Council requirements.
- It will ensure that quality submissions are lodged with necessary and correct information to prevent delay of the assessment of the development application
- A correctly completed form is required to enable lodgement of your DA/s96.
- It is essential that the Design Engineer carefully reads this checklist as any inaccurate or incomplete checklists will prevent the lodgement of your application.
- N/A shall be indicated adjacent to any details or information that are not relevant.

PROPERTY DETAILS

1.	Pro	nerty	Details	
_	FIV	DC: LA	DCrail2	

Unit No: 2,4,6

House No:

26 - 6

Address

Street: HASSAVV STREET

Suburb: PARRAMATTA

Postcode: 2150

Lot/DP/SP etc

Lot: 22,62,7

DP/SP etc: DP608861, DP100 6215

DP 128820

DA Number: (office use only)

TYPE OF DEVELOPMENT

MINOR **DEVELOPMENTS** NO OSD

May include single and secondary dwellings, alterations and additions with No OSD.



PAGE 2

MAJOR **DEVELOPMENTS** with OSD

May include duplexes, townhouses, residential flat buildings, commercial premises, major developments.



PAGE 3-7

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

Minor Developments - No OSD

Stormwater Drainer/ Plumber (or Engineer's) Details & Declaration

This form is to be completed by a Licensed Drainer/Plumber (or a Registered Stormwater Engineer).

Company Details	Company & ABN:	
Engineering Details:	Registered Engineer Reference (NPE	ER) if held:
	Licence no & ABN:	
Family Name:	Full Given Name(s):	
Engineering Details: Registered Engineer Reference (NPER) if held: Licence no & ABN: Family Name: Full Given Name(s): Postal Address Suburb: Postcode:	Postcode:	
Contact Details	Office phone:	Mobile:
	Fax:	Email:

I confirm that:

- A true diagram or drawing of the stormwater system is attached.
- I am the Licensed Stormwater Drainer /Plumber (or Engineer) responsible for designing the stormwater system associated with this development proposal AND
- I certify that this proposal will meet accepted standards of good stormwater practice, Council and Australian Standards and will not cause nuisance or adversely affect this or other properties, AND
- There is no Council drainage line within or adjacent to this property, AND
- in my opinion, the existing stormwater drainage system is adequate to receive the stormwater from this new development OR I have proposed a new stormwater drainage system which will be adequate for the total site drainage needs from the existing and new development.

Stormwater Drainer / Plumber or Engineer's Signature:

date:

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

Major Developments - OSD required

This portion of the form is to be completed by a registered and practising stormwater engineer.

R	egi	istered	Sto	rmwat	er D	esian	Ena	ineer's	Details
	_								

Company & ABN: 67 010 580 248

Registered Stormwater Design Engineer Reference (NPER): 4155 632

Is the Engineer accredited to carry out Design of Stormwater & OSD Systems:

(Y)N

Full Given Name(s): COLIN DAVID ROPE

Suburb: BELROSE

Postcode: NSW

Office phone: +61(0)2 82463200

Mobile: 0437 008 375

Registered Stormwater Design Engineer's Checklist

	ITEMS	Yes (✓)	No N/A (✓)
1	Registered Stormwater Design Engineer Name, Signature, and Registration of the Stormwater Design Engineer are clearly indicated on the submitted design documentation.	/	
2.	Flood Prone Land The site is (wholly or partly) affected by flood as indicated on a current s149 planning certificate AND: Flood Level information has been obtained from Council by completing a Flood Enquiry Application form. This is attached. 20 year and 100 year ARI flood inundation extent line and levels (to m AHD) are clearly indicated on submitted Plan No	>	\ \ \
	There is a Council stormwater pipe, channel or watercourse traversing the site or within close proximity to the site AND an upstream catchment Overland Flow Assessment Report is attached for a 1 in 20 and 1 in 100 year ARI storm event flow running through site (including hydrological and hydraulic calculations). This information is attached as Attachment - B Overland flow paths within the site are identified on Plan No		

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

3.	Private Easements	155	
	Existing easement - drainage is proposed through adjoining private properties.		
	The site already benefits from an existing drainage easement AND an up to date Certificate of Title has been provided to confirm this benefit. AND an engineer or licensed plumber has certified that the proposed system (including connection to Council's stormwater system) is adequate and operational. Written confirmation of this is attached.		
	OR, New easement - drainage proposed through adjoining private properties.		
	A new easement(s) over downstream property/ies is required to enable the site and/or the OSD system to be drained by gravity AND this is indicated on submitted Plan No		/
	The permission of all affected downstream property owners has been obtained for such easement(s) AND written approval of this is attached.		/
	An engineer (or licensed plumber) has certified that the proposed system (including connection to Council's stormwater system) is adequate and operational. Written confirmation of this is attached.		/
4.	Stormwater Design Preparation and Documents:		
	A site inspection was undertaken in preparation of the stormwater system design.	V	10
	A survey by a Registered Surveyor has been prepared to AHD and is attached.	1	
	The stormwater system and OSD system are designed in accordance with:		
	 Councils Stormwater Disposal Policy (2015) and other relevant Policies Council's Development Design Guidelines (2015), Policies and Engineering Specifications and DCP 2011. 	>>>	
	 Upper Parramatta River Catchment Trust On Site Detention Handbook (Ed 3 or 4) (unless overridden by Council's Policies) Australian Standards and National Construction Codes (2015). 	/	
	 Stormwater designs are consistent with architectural and landscape designs for the development and correspond with levels, building locations, requirements of any Flood/Overland Flow Assessment, trees to be retained or planted, utilities, services and easements. 	~	
	 Stormwater designs adequately incorporate Water Sensitive Urban Design Principles and are generally in accordance with Council's DCP 2011, Development Design Guidelines (2015) and WSUD Technical Guidelines for Western Sydney (2004), and/or other approved reference. 	~	
	The submitted stormwater plans:		NT N
	 are based on a Survey Plan prepared by a registered surveyor provide spot levels to mAHD and contours (with extensions into adjoining prop- 	/	
	erties) • provide location of any existing easements	/	
	 provide locations of existing trees and structures are to a 1:100 scale @ (INTERNA) 1:200 (WHOLE SITE) 	~	
5.	On Site Retention (OSR) and Water Sensitive Urban Design (WSUD):		
	The site is greater than 2000m ² and WSUD/OSR requirements of Council's DCP 2011 have been addressed.		
	Full details of the OSR/WSUD system are attached.	/	

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

6.	The site immediately drains to a Council Reserve or other Council land and Council does not accept a piped drainage line across this land. As a result OSD is not proposed and an OSR/WSUD system is proposed instead. Full details of the OSR/WSUD system are attached.		/
7.	The site immediately drains to a floodway and OSD here is predicted to adversely affect mainstream flooding. A demonstration of this is attached. As a result OSD is not proposed and an OSR/WSUD system is proposed instead. Full details of the OSR/WSUD system are attached.		/
8.	For Development Requiring OSD		
	Residential Development (Duplexes) The OSD system comprises below ground tanks as required for residential development.		×
	Non residential development only: The depth of above ground detention basins does not exceed 300mm in landscaped areas and 150mm over impervious surfaces. TANK PROV PROPOSED ABOVE GROUND AND WITHIN BUILDING STRUCTURE	/	~
9.	OSD Design # OA - HO6 The OSD design (DWG Nos DA: 10.4) is generally consistent with the requirements of the Upper Parramatta River Catchment Trust On Site Detention Handbook (Ed 3 or 4).	/	
	 and showing the following details: Site layout showing all buildings, pathways, roadways and landscaped areas; Areas to be drained to OSD Location, levels and extent of all detention tanks, pits and pipes Location and levels of all collecting stormwater system including downpipes, surface collection pits, grated drains and Water Sensitive Urban Design (WSUD) and OSR features Areas of the site that by-pass detention system/s Location of any other constraints, e.g. easements, Sydney Water Assets (water/sewer pipes) & Electricity Overhead Cables; 	111111	
	OSD storage tank detail designs (or OSD storage basins for non-residential development) and surface collection pits include:		
¥9	 All design dimensions including levels and inverts to AHD and OSD volumes Cross-Sectional details Discharge Control Pit/s Safe and practical maintenance access 	1111	
	The above details are shown on A1 or A3 size plans with a scale of 1:100 and/or 1:50	/	
	The OSD storage volume has been calculated using the Upper Parramatta River Catchment Trust On Site Detention Handbook (3rd or 4th edition) calculation sheet.	/	
	The completed Design Summary Calculation Sheet has been signed by the Stormwater Design Engineer and attached as Attachment - C .	/	
	The areas of the site (including roofs) to be drained to any rainwater collection system and to the OSD system have been determined and are clearly indicated on Plan No.	/	
			2007

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

		$\overline{}$	
9.	OSD Design (continued)		
	The remaining percentage of the total site area not drained to the roofwater and OSD systems is 3:2% (to be not more than 15%).	/	50
	This is <u>not</u> a 'drowned outlet'.		~
	Because the designed discharge flow rate is greater than 30l/s, a connection to the nearest Council stormwater pit has been shown with associated levels.		~
	Overland flow from adjacent properties has been intercepted and disposed separately without discharging into any proposed OSD system.		/
Register	ed Stormwater Design Engineer's Declaration		
tem asso	that, as the Registered Stormwater Design Engineer responsible for designing the st ciated with this development proposal, that I have done so with a full understanding equirements and have read, understood and completed this checklist accurately.	ormwate	er sys- elevant
Registere	ed Stormwater Design Engineer's Signature:	date:	
	73	64/2	0101
	cgc 03	104/2	2()
Council	Development Engineer's Notes	131	4 , 3
Developme	ent Engineer Name:		
- 1-77			
Signature:	date:		

STORMWATER & OSD DOCUMENTATION DA CHECKLIST

Disclaimer: The information provided by you on this form will be used by Parramatta City Council or its agents to process this application. Once collected by Council, the information can be accessed by you in accordance with Council's Access to Information Policy and Privacy Management Plan or in special circumstances, where Commonwealth legislation requires or where you give permission for third party access.

PART 4 - Applicant Declaration

6. Declaration

I confirm that as the design engineer/project designer responsible for designing the stormwater system associated with this development proposal that I have done so with a full understanding of the relevant Council requirements and have read, understood and completed this checklist accurately.

Cler CROPE

Engineer's signature

Engineer's name

date: 03/04/2019

PART 5 - Council's Officers Sign-off

7. Declaration

Council Officers signature

date:

Council Officers name



You can log onto www.parracity.nsw.gov.au/development to track the progress of any application lodged after 30 June 2005. The information you supply on this form and any related documentation will be publicly available on this Council website.

Parramatta City Council 30 Darcy Street, Parramatta 2150 PO Box 32, Parramatta 2124


DX 8279 Parramatta phone: 9806 5524 9806 5917 fax:

Appendix BCivil Engineering Drawings




2B-6 HASSAL ST MAIN WORKS PARRAMATTA, NSW 2150 CIVIL ENGINEERING DRAWINGS ISSUED FOR DEVELOPMENT APPLICATION

	Sheet List Table
Sheet Number	Sheet Title
C-0-00	COVER SHEET, LOCATION MAP AND SHEET INDEX
C-0-01	GENERAL NOTES
C-1-00	EROSION AND SEDIMENT CONTROL
C-1-10	EROSION AND SEDIMENT CONTROL DETAILS
C-2-01	BULK EARTHWORKS PLAN
C-2-10	BULK EARTHWORKS SECTIONS
C-3-00	GENERAL ARRANGEMENT PLAN
C-3-10	CIVIL DETAILS
C-4-10	PAVEMENT DETAILS
C-6-50	STORMWATER PRE CATCHMENT ANALYSIS
C-6-51	STORMWATER POST CATCHMENT ANALYSIS



LOCALITY MAP SCALE NTS



GENERAL NOTES

- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER ENGINEERING DRAWINGS AND CITY OF PARRAMATTA COUNCIL AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT.
- 2. THESE ENGINEERING PLANS ARE TO BE READ IN CONJUNCTION WITH PROJECT SPECIFICATIONS AND OTHER CONSULTANTS DOCUMENTATION ON THE PROJECT.
- 3. THESE ENGINEERING PLANS HAVE BEEN PREPARED FROM INFORMATION AVAILABLE AT THE TIME OF ISSUE. AS THIS INFORMATION MAY BE THE SUBJECT OF CHANGE PRIOR TO OR DURING CONSTRUCTION THE CONTRACTOR IS TO ADVISE THE ENGINEER WHERE DISCREPANCIES OCCUR.
- 4. THESE DRAWINGS SHALL NOT BE USED FOR FINAL SETOUT OF THE PROJECT UNLESS SPECIFICALLY STATED.
- 5. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH PARRAMATTA CITY COUNCIL STANDARDS, GUIDELINES AND TECHNICAL MANUALS.
- 6. ALL WORKS SHALL HAVE SMOOTH JUNCTIONS WITH EXISTING.
- 7. ALL SURFACES SHALL BE EVEN GRADED AT MINIMUM 1% TO PREVENT SURFACE WATER PONDING.
- 8. WHERE CERTIFICATION IS REQUIRED, INSPECTIONS ARE TO BE PERFORMED BY A DULY APPOINTED INSPECTOR FROM 'ROBERT BIRD GROUP'. THESE INSPECTIONS ARE TO BE PERFORMED IN ACCORDANCE WITH THE INSPECTION & TEST PLANS PREPARED BY 'ROBERT BIRD GROUP.' THE INSPECTOR IS TO BE GIVEN A MINIMUM NOTICE AS DETAILED IN THE SPECIFICATIONS.
- 9. ALL MATERIALS SHALL COMPLY WITH WHAT IS SHOWN ON THE PROJECT DRAWINGS AND IN THE
- 10. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL EXISTING SERVICES WITH ALL RELEVANT SERVICE AUTHORITIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. A COPY OF THE LOCATIONS OF THE EXISTING SERVICES IS TO BE PROVIDED TO THE MANAGING CONTRACTOR BY THE SERVICES ENGINEER. CONTRACTOR TO NOTIFY MANAGING CONTRACTOR OF ANY POTENTIAL
- 11. THE CONTRACTOR SHALL VERIFY OFFSET PEGS AND BENCHMARK LEVELS, AND ADVISE THE MANAGING CONTRACTOR OF ANY DISCREPANCY PRIOR TO COMMENCING CONSTRUCTION.
- 12. THE CONTRACTOR SHALL VERIFY THE EXISTING LEVELS WHERE NEW WORKS ARE TO JOIN TO EXISTING WORKS, AND ADVISE THE MANAGING CONTRACTOR OF ANY DISCREPANCY PRIOR TO COMMENCING CONSTRUCTION.
- 13. THE CONTRACTOR SHALL CHECK OR OBTAIN ALL DIMENSIONS RELEVANT TO SETTING OUT OF
- 14. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STABILITY OF THE WORKS AND ENSURE NO PART IS OVERSTRESSED. THE DESIGN AND CERTIFICATION OF ALL FORMWORK AND BACKPROPPING IS TO BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 15. THE CONTRACTOR IS TO OBTAIN DESIGN ADVICE FROM A SUITABLY QUALIFIED ENGINEER REGARDING DEMOLITION, RETROFITTING, TEMPORARY WORKS, HEALTH & SAFETY AND NUISANCE. THIS HAS BEEN REFERRED TO AS THE "CONTRACTORS ENGINEER" THROUGHOUT THE REMAINING NOTES.
- UNLESS SPECIFIED OTHERWISE IN THE PROJECT DOCUMENTATION, MINIMUM STRIPPING TIMES FOR IN-SITU CONCRETE FORMWORK SHALL COMPLY WITH SECTION 5.4.3 (TABLE 5.4.1) OF AS3610-'FORMWORK FOR CONCRETE'.
- 17. WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CURRENT AUSTRALIAN STANDARDS AND BCA STATUTORY REQUIREMENTS, EXCEPT WHERE VARIED BY THE CONTRACT
- 18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT SUFFICIENT TOLERANCES ARE PROVIDED AND INTEGRATED THROUGHOUT ALL ELEMENTS OF THE WORKS.
- 19. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- 20. ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (A.H.D.)
- 21. DESIGN LEVELS AND SETOUT DETAILED HEREIN ARE DERIVED SURVEY, LANDSCAPE AND ARCHITECTURAL PLANS. CONTRACTOR SHALL CONFIRM LEVELS ARE COORDINATED PRIOR TO COMMENCING WORKS. EXISTING LEVELS ARE DERIVED FROM SURVEY DATA. CONTRACTOR TO CONFIRM ALL ON SITE PRIOR TO COMMENCING WORKS.

HEALTH & SAFETY

- 1. THE CONTRACTOR SHALL DEVELOP, IMPLEMENT AND ADMINISTER A WORKPLACE HEALTH AND SAFETY PROGRAM THAT WILL ENSURE THAT ALL CONSTRUCTION ACTIVITIES ARE PERFORMED TO THE RELEVANT WORKPLACE HEALTH AND SAFETY REQUIREMENTS AND ANY OTHER RELEVANT STATUTORY REQUIREMENTS.
- 2. THE WORKPLACE HEALTH AND SAFETY PROGRAM MUST BE CO-ORDINATED WITH ADJOINING PROPERTY OWNERS AND ALL RELEVANT PARTIES AS NECESSARY TO ENSURE A SAFE BUILDING ENVIRONMENT AT ALL TIMES.

NUISANCE

- THE CONTRACTOR SHALL DEVELOP. IMPLEMENT, AND ADMINISTER A PLAN THAT WILL ENSURE THE MANAGEMENT OF NOISE AND VIBRATION RESULTING FROM CONSTRUCTION WORKS. REFER TO SPECIFICATIONS FOR REQUIRED LIMITS, OTHERWISE, CONTACT ENGINEER FOR GUIDANCE.
- 2. THE CONTRACTOR WILL NEED TO ENSURE ALL ADJOINING PROPERTY REQUIREMENTS RELATING TO NOISE AND VIBRATION ARE MET.
- 3. IF IT IS ESTABLISHED THAT THERE ARE NO SITE SPECIFIC REQUIREMENTS, THEN THE CONTRACTOR SHALL REFER TO MINIMUM REQUIREMENTS FOR ABATEMENT OF NOISE AND VIBRATION NOMINATED BY RELEVANT STATUTORY REQUIREMENTS
- 4. THE CONTRACTOR WILL NEED TO PREPARE AND ADVISE ON MONITORING AND MANAGEMENT OF NOISE AND VIBRATION BASED ON PROFESSIONAL ADVICE FROM SUITABLY QUALIFIED PERSON OR PERSONS.

SURVEY NOTES

1. THE SURVEY INFORMATION SHOWN ON ROBERT BIRD GROUP DRAWINGS HAS BEEN OVERLAID FROM INFORMATION PROVIDED IN THE DETAILED SURVEY BY USHER & COMPANY, SURVEYING AND LAND DEVELOPMENT CONSULTANTS FILE REF: 6083-DET ISSUE 3, DATED 25.09.2018. ROBERT BIRD GROUP DOES NOT GUARANTEE THAT THE SURVEY INFORMATION IS ACCURATE, AND ACCEPTS NO LIABILITY FOR

SEDIMENT AND EROSION CONTROL NOTES

- 1. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PROVIDED IN ACCORDANCE WITH SPECIFICATION AND EPA "MANAGING URBAN STORMWATER CONSTRUCTION ACTIVITIES" 1998. ALL WORKS SHALL BE COMPLETED PRIOR TO CONSTRUCTION COMMENCING.
- 2. REFER TO ROBERT BIRD GROUP'S DRAWING SHEETS C-1-00 AND C-1-10 FOR EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.

EARTHWORKS NOTES

- 1. REFER TO THE GEOTECHNICAL ENGINEERING REPORT.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL, COMPACTION AND DISPOSAL OF ALL EXCAVATED MATERIAL.
- 3. ALL EARTHWORKS AREAS ARE TO BE LEFT IN A FREE DRAINING STATE.
- 4. PROOF ROLL SUBGRADE TO REVEAL SOFT SPOTS. SOFT SPOTS TO BE REMOVED AND BACKFILLED. ALL NATURAL SUBGRADE IS TO BE COMPACTED TO IN ACCORDANCE WITH AS1289 PRIOR TO PLACEMENT OF
- 5. MATERIAL WON FROM THE SITE TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER FOR APPROVAL PRIOR TO USE AS FILL. ALL FILL TO BE COMPACTED TO MIN. 98% STANDARD COMPACTION IN 200mm MAXIMUM THICK LAYERS IN ACCORDANCE WITH AS1289.
- 6. TEST CERTIFICATES ON THE FILL MATERIAL SHALL BE SUPPLIED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO THE USE OF THE FILL MATERIAL.

TEMPORARY WORKS

- 1. THE CONTRACTOR SHALL ALLOW FOR THE DESIGN, SUPPLY, INSTALLATION AND REMOVAL OF ALL TEMPORARY BACK PROPPING, SAFETY SCREENS, SCAFFOLDING AND OTHER REQUIREMENTS OF THE CONSTRUCTION PROCESS. THE CONTRACTOR SHALL ENGAGE SUITABLY QUALIFIED ENGINEER REFEREED TO AS "CONTRACTORS ENGINEER". TO DESIGN INSPECT AND CERTIFY ALL TEMPORARY WORKS, AND DEMOLITION WORKS.
- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THE OVERALL STABILITY OF THE STRUCTURES WHILST UNDER CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ADVICE FROM THE CONTRACTORS ENGINEER.

CONCRETE NOTES

- CONCRETE WORK SHALL BE IN ACCORDANCE WITH AS3600 AND WITH THE PROJECT SPECIFICATIONS.
- 2. CONSTRUCTION JOINTS SHALL BE PROPERLY FORMED AND USED ONLY WHERE SHOWN ON SUPERINTENDENT DRAWINGS OR SPECIFICALLY APPROVED BY SUPERINTENDENT.
- 3. ALL THICKNESSES SHOWN ARE MINIMUM STRUCTURAL REQUIREMENTS, NO REDUCTION IN THICKNESS DUE TO FALLS OR TOPPING IS PERMITTED.
- 4. UNLESS A GROOVE LINE ALLOWANCE HAS BEEN NOTED ON THE DRAWINGS, NO GROOVE LINES ARE PERMITTED, EXCEPT AT SLAB LINES. ALL GROOVE LINES ARE TO BE SUBMITTED TO 'ROBERT BIRD GROUP' FOR APPROVAL.
- 5. THE FACE OF ALL CONCRETE AGAINST WHICH NEW CONCRETE IS TO BE CAST IS TO BE THOROUGHLY MECHANICALLY SCABBLED, FULLY EXPOSING THE AGGREGATE MATRIX.

CONCRETE

- 1. THE CHARACTERISTIC COMPRESSIVE STRENGTH (I'c) AT 28 DAYS OF IN PLACE CONCRETE SHALL BE AS
- NOTED IN THE SPECIFICATION OR OTHERWISE NOTED ON THE DRAWINGS
- MAXIMUM AGGREGATE SIZE.....20mm
- SLUMP....
- 4. ALL CONCRETE SHALL BE VIBRATED.
- 5. ALL CONCRETE SHALL BE CURED IN ACCORDANCE WITH THE SPECIFICATION
- 6. ALL CONCRETE SHALL BE SAMPLED AND TESTED IN ACCORDANCE WITH AS1012 AND THE PROJECT
- SPECIFICATION. 7. ALL FORM WORK SHALL COMPLY WITH AS3610
- 8. REFER STRUCTURAL ENGINEER'S SPECIFICATIONS FOR CONCRETE REQUIREMENTS.

- 1. REINFORCEMENT IS TO BE MANUFACTURED IN ACCORDANCE WITH AS4671 AND SHALL BE FIXED AS SHOWN ON DRAWINGS.
- 2. MATERIAL IS INDICATED BY THE FOLLOWING SYMBOLS:-
 - Y DEFORMED BAR GRADE 400 N DEFORMED BAR GRADE 500 (NORMAL DUCTILITY)
 - R PLAIN ROUND BAR GRADE 250
 - W PLAIN WIRE GRADE 450 SL SQUARE FABRIC GRADE 500
 - RL RECTANGULAR FABRIC GRADE 500
- 3. THE BAR SIZE IS INDICATED BY A NUMBER AFTER THE SYMBOL, WHICH INDICATES THE BAR DIAMETER IN MILLIMETRES.
- 4. REINFORCEMENT SPACING NOMINATED ON DRAWINGS IS TO ASSIST SCHEDULER AND STEEL FIXER TO ASSESS TOTAL NUMBER OF BARS REQUIRED. WHERE BARS PLACED IN ACCORDANCE WITH SPACING NOMINATED FOUL WITH OTHER STRUCTURAL REQUIREMENTS, PREFERENCE IS TO BE GIVEN TO RELOCATING BARS BY LOCALLY ADJUSTING SPACING TO ENABLE ASSEMBLY OF REINFORCEMENT TO BE COMPLETED. ENGINEER IS TO BE CONTACTED IN THE EVENT THAT REINFORCEMENT IS NEEDED TO BE CUT ON SITE PRIOR TO CONTINUING.
- 5. LAP LENGTHS TO REINFORCEMENT BARS TO BE AS NOTED ON THE RELEVANT DRAWINGS.
- 6. WELDING OF REINFORCEMENT BARS IS NOT PERMITTED UNLESS APPROVED.

CONCRETE NOTES CONTINUED REINFORCEMENT CONTINUED

- 7. COVER SHALL BE AS NOTED ON THE RELEVANT DRAWINGS.
- 8. CONCRETE COVERS NOTED ARE MEASURED FROM THE FORM WORK OR GROUND FACE TO THE OUTERMOST REINFORCEMENT COMPONENT. i.e., IN COLUMNS AND BEAMS TO THE OUTSIDE OF TIES OR
- 9. COVER TO BE MAINTAINED DURING POURING BY THE USE OF PLASTIC CHAIRS OR PLASTIC TIPPED METAL CHAIRS.
- 10. WHERE NO REINFORCEMENT IS SHOWN ON THE DRAWING AT RIGHT ANGLES TO THE MAIN REINFORCEMENT DISTRIBUTION REINFORCEMENT IS TO BE PROVIDED.
- 11. BENDING & STRAIGHTENING
 - COLD BENDING: BARS CANNOT BE COLD BENT WITHOUT PRIOR APPROVAL FROM THE PROJECT STRUCTURAL ENGINEER. CORRECT MINIMUM DIAMETER FORMERS ARE TO BE USED IN ACCORDANCE WITH AS3600.
 - HOT BENDING: HOT BENDING MAY ONLY BE CONDUCTED WITH THE APPROVAL OF THE PROJECT STRUCTURAL ENGINEER. HOT BENDING CAN ONLY BE PERFORMED BY A CERTIFIED WELDER. TEST CERTIFICATE OF AFFECTED AREA TO BE OBTAINED.
 - STRAIGHTENING: WHEN RE-STRAIGHTENING PARTIALLY EMBEDDED BARS, DO NOT BEND OVER FORMERS OF SMALLER DIAMETER THAN PERMITTED IN AS 3600. DO NOT SUBJECT REINFORCEMENT BARS TO IMPACT IN ORDER TO STRAIGHTEN.

SLAB ON GROUND NOTES

- 1. SLAB ON GROUND TO BE POURED ON A LAYER OF POLYETHYLENE SHEETING 200 µm THICK ON TOP OF 50mm OF BEDDING SAND. JOINTS TO BE TAPED
- 2. FABRIC TO BE PLACED ON CHAIRS AT 800 x 800 CENTRES AND CHAIRS TO BE PLACED ON STEEL
- 3. LAP FABRIC REINFORCEMENT THUS:



4. WHERE BEDDING SAND IS REQUIRED UNDER SLAB, THIS SHALL BE COMPACTED SUFFICIENTLY TO SUPPORT REINFORCEMENT PLUS 100kg/CHAIR WITHOUT VERTICAL DISPLACEMENT EXCEEDING 5mm.

ROADS AND PAVEMENT NOTES

GENERAL

PAVEMENT SHALL BE BOXED OUT TO THE DEPTHS AS SHOWN ON THE PAVEMENT DRAWINGS, AND SUBGRADE TESTING IS TO BE UNDERTAKEN. SUBGRADE TESTING RESULTS ARE TO BE FORWARDED TO THE ENGINEER (ROBERT BIRD GROUP) FOR DETERMINATION OF FINAL PAVEMENT DEPTH. PAVEMENT CONSTRUCTION IS TO HOLD UNTIL FINAL PAVEMENT DEPTH HAS BEEN DETERMINED BY THE ENGINEER, AND APPROVED BY THE RELEVANT AUTHORITY.

PREPARATION OF SELECT SUBGRADE LAYERED

- THE SELECT SUBGRADE LAYER IS DEFINED AS THE UPPER 300MM OF THE FORMATION UPON WHICH THE ROAD PAVEMENT IS TO BE CONSTRUCTED. THE UPPER SURFACE OF THE SUBGRADE LAYER IS DEFINED AS THE DESIGN SUBGRADE LEVEL.
- THE SELECT SUBGRADE LAYER SHALL BE FREE FROM ALL POCKETS OF SOFT COMPRESSIBLE MATERIAL, FREE FROM STONE WITH A MAXIMUM DIMENSION LARGER THAN 50MM, AND HAVE A MINIMUM SOAKED CBR AS SPECIFIED ON
- 4. ANY UNSUITABLE LAYER SHALL BE COMPACTED TO A FIELD DRY DENSITY OF NOT LESS THAN 100% AS DETERMINED IN ACCORDANCE WITH RTA TEST METHOD T111 - STANDARD COMPACTION (FOR A COHESIVE SOIL) OR A MINIMUM DENSITY INDEX OF 80% WHEN TESTED IN ACCORDANCE WITH AS.1289.5.6.1 (FOR A COHESIVE LESS
- 5. TESTS FOR COMPACTION OF SELECTED SUBGRADE LAYER SHALL BE CARRIED OUT BY THE CONTRACTOR AT LOCATION APPROVED BY THE SUPERINTENDENT AT A RATE AS SPECIFIED.

PLACEMENT OF PAVEMENT MATERIALS

- 1. THE PAVEMENT SHALL BE CONSTRUCTED TO THE THICKNESS AS SHOWN ON THE DRAWINGS. PAVEMENT COURSES LESS THAN 150mm IN COMPACTED THICKNESS SHALL BE SPREAD AND COMPACTED IN TWO OR MORE LAYERS OF NOT LESS THAN 75MM OR MORE THAN 150MM IN COMPACTED THICKNESS.
- 2. SPREADING SHALL BE UNDERTAKEN BY A METHOD THAT WILL ENSURE THAT SEGREGATION DOES NOT OCCUR.
- 3. MIXING OR BLENDING OF PAVEMENT MATERIALS WILL NOT BE ALLOWED ON THE ROAD FORMATION. PAVEMENT MATERIAL SHALL NOT BE SPREAD ON A WATERLOGGED SUBGRADE NOR BROKEN ON THE SUBGRADE. WHEN SPREADING AND/OR MIXING PAVEMENT MATERIAL. CARE SHALL BE TAKEN TO ENSURE THAT THE SUBGRADE SHALL NOT BE DISTURBED. BECOME RUTTED OR MIXED WITH THE PAVEMENT MATERIALS.
- 4. IF, AT ANY TIME ANY PART OF SUBGRADE AND PAVEMENT MATERIALS BECOME MIXED, THE CONTRACTOR SHALL, AT ITS COST, REMOVE THE MIXTURE AND RESHAPE THE SUBGRADE WITH APPROVED MATERIAL COMPACTED UNIFORMLY WITH THE SURROUNDING SURFACE.
- 5. WHEN EACH LAYER OF PAVEMENT MATERIAL HAS BEEN SPREAD, WATERING SHALL BE CARRIED OUT AS NECESSARY TO MAINTAIN THE MATERIAL AT A MOISTURE CONTENT DURING ROLLING AS CLOSE TO BUT NOT EXCEEDING ITS OPTIMUM MOISTURE CONTENT.
- WHERE THE MOISTURE CONTENT OF PAVEMENT MATERIAL IS INSUFFICIENT, WATER SHALL BE ADDED BY APPROVED WATERING EQUIPMENT AND SHALL BE MIXED UNIFORMLY WITH THE MATERIAL BY AN APPROVED MECHANICAL DEVICE.
- WHERE THERE IS EXCESS MOISTURE IN THE PAVEMENT MATERIAL, IT SHALL BE DRIED TO THE REQUIRED MOISTURE CONTENT BY LOOSENING AND AERATING.

PO Box A2309

Sydney South, NSW 1235

ydney NSW 2000

COMPACTION OF PAVEMENT MATERIALS

- 1. AS EACH LAYER IS BROUGHT TO IT OPTIMUM MOISTURE CONTENT, IT SHALL BE IMMEDIATELY COMPACTED BY
- COMPACTION SHALL BE CARRIED OUT USING APPROVED EQUIPMENT OF ADEQUATE CAPACITY TO ACHIEVE THE DEGREE OF COMPACTION SPECIFIED.
- 3. ANY DEFICIENCIES MADE BY THE SINKING OF THE COMPACTOR WHEN COMPACTING MATERIAL SHALL AT ONCE BE MADE GOOD BY SCARIFYING THE SURFACE AND ADDING ADDITIONAL MATERIAL AT THE CONTRACTOR 'S
- 4. ON THE SECTION OF PAVEMENT HAVING A ONE-WAY CROSS FALL, COMPACTION SHALL COMMENCE AT THE LOWER EDGE OF THE BASE AND PROGRESS UPWARDS TO THE HIGHER EDGE.
- 5. ON CROWNED SECTION OF PAVEMENT, COMPACTION SHALL COMMENCE AT THE OUTER EDGES OF THE BASE AND PROGRESS INWARDS TOWARDS THE CROWN.
- 6. EACH PASS OF THE COMPACTION PLANT SHALL BE PARALLEL TO THE CENTRE LINE OF THE PAVEMENT. THE METHOD OF COMPACTION SHALL ALLOW FOR PROGRESSIVE AND UNIFORM OVERLAP BETWEEN PASSES.
- 7. IF NON-VIBRATING SMOOTH-WHEELED ROLLERS ARE USED AS COMPACTION PLANT. THEY SHALL BE

OPERATED WITH THE DRIVING ROLLERS FACING THE UNCOMPACTED MATERIAL DURING THE INITIAL PASS.

- 8. IF VIBRATING ROLLERS ARE USED AS COMPACTION PLANT, THE VIBRATOR SHALL NOT BE ACTIVATED UNTIL A MINIMUM OF TWO "STATIC" PASSES HAVE BEEN MADE. IN ADDITION, THE VIBRATORS SHALL NOT BE ACTIVATED DURING ANY CHANGE IN DIRECTION OF THE ROLLER.
- COMPACTION PLANT AND OTHER ANCILLARY PLANT SHALL NOT BE ALLOWED TO REMAIN STANDING ON THE COMPACTED PAVEMENT WITHOUT THE APPROVAL OF THE SUPERINTENDENT.
- 10. TRAFFIC SHALL NOT BE ALLOWED ON ANY COMPACTED LAYER WITHOUT APPROVAL OF THE SUPERINTENDENT. EACH LAYER IN A MULTI-LAYERED COURSE SHALL BE FULLY COMPACTED IN SEQUENCE. THE SURFACE OF THE COMPACTED LAYER SHALL BE KEPT SUFFICIENTLY MOIST TO MAINTAIN THE REQUIRED FIELD MOISTURE CONTENT THROUGHOUT THE FULL DEPTH OF THE LAYER PRIOR TO PLACEMENT OF SUBSEQUENT LAYERS OR TO THE APPLICATION OF THE SURFACE PRIMER. AS APPLICABLE.
- 11. COMPACTION SHALL CONTINUE UNTIL THE MATERIAL DOES NOT CREEP OR WAVE AHEAD OF THE ROLLER. UNTIL THE SURFACE PRESENTS A SMOOTH UNIFORM APPEARANCE AND UNTIL THE MATERIAL HAS BEEN LEVELED AND COMPACTED TO THE REQUIREMENTS AND TOLERANCES SPECIFIED ELSEWHERE HEREIN.
- 12. TESTS FOR COMPACTION OF ROAD PAVEMENT MATERIALS SHALL BE CARRIED OUT BY THE CONTRACTOR AT LOCATIONS APPROVED BY THE SUPERINTENDENT AT A RATE AS SPECIFIED.

STORMWATER DRAINAGE NOTES

1. THESE NOTES SHALL BE READ IN CONJUNCTION WITH: A. GENERAL NOTES AND DISCLAIMERS FOR THE PROJECT B. ROADWORKS NOTES FOR THE PROJECT

C. SPECIFICATIONS FOR THE PROJECT.

- 2. STORMWATER PIPES 375NB AND GREATER SHALL BE RCP RRJ, U.N.O. CLASSES AS NOTED ON THE DRAWINGS. FRC PERMITTED.
- 3. STORMWATER DRAINAGE PIPES LESS THAN OR EQUAL TO 900mm DIAMETER SHALL BE SPIGOT AND SOCKET AND RUBBER RING JOINTED.
- 4. OUTLET LOCATIONS ARE TO BE CONFIRMED ON SITE BY THE MANAGING CONTRACTOR PRIOR TO THE COMMENCEMENT OF STORMWATER DRAINAGE CONSTRUCTION.
- 5. ALL PROPOSED STORMWATER WORKS DESIGNED IN ACCORDANCE WITH A. AUSTRALIAN RAINFALL AND RUNOFF (1987 EDITION) VOLUMES 1 AND 2. B. AS 3500 NATIONAL PLUMBING CODE PART 3 - STORMWATER DRAINAGE. C. PARRAMATTA CITY COUNCIL'S PUBLIC DOMAIN GUIDELINES.

SERVICE NOTES

1. ALL EXISTING SERVICES LIDS THAT ARE TO REMAIN ARE TO BE RECONSTRUCTED TO MATCH PROPOSED LEVELS AND ALIGNED TO PARRAMATTA CITY COUNCIL STANDARDS.

LANDSCAPING NOTES

REFER TO ASPECT LANDSCAPE ARCHITECTS DRAWINGS FOR LANDSCAPING DETAILS.

HYDRAULICS NOTES

1. REFER TO HYDRAULIC ENGINEERS DRAWINGS FOR SEWER, WATER AND INTERNAL SITE STORMWATER DRAINAGE WORKS

Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the accuracy, currency or completeness of any information or data they supply or transfer by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means matches the information or data on the corresponding PDF or DWF version issued by RBG. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance and reliance transferred by electronic means and the reliance of the supplied or transferred by electronic means and the reliance of the re By App Date | Rev Revision Description By App Date Rev Revision Description ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 04.03.19 Robert**Bird**Group on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirect suffer in connection with your access to or use of that information or data. surrer in connection with your access to or use of that information or acta.

RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferable, fully revocable licence to use the intellectual property rights for the express Member of the Surbana Jurong Group SYDNEY OFFICE lobert Bird Group Pty Ltd

DO NOT SCALE DRAWINGS. USE FIGURED DIMENSIONS

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE

Ph: (02) 8246 3200

Fax: (02) 8246 3201

ACN 010 580 248

Email: sydney@robertbird.com.au

Web: www.robertbird.com



GENERAL NOTES 2B-6 HASSALL STREET

PARRAMATTA

Scale at A1 AS SHOWN 04.03.19

18570C NOT FOR CONSTRUCTION

S.MANANDHAR

Designer

Z.JONES


Drawing Number C-0-01


Design Checker


Approved

C.ROPE

Job Number











SCALE 1:10

REFER C-3-00 FOR PAVEMENT LAYOUT PLAN. ASSUMED SUBGRADE CBR 3% TO BE VERIFIED ON SITE BY INSITU SUBGRADE TESTING, IN ACCORDANCE WITH AS1209.6. TEST INTERVAL TO BE 1 TEST PER 400m².




TRAFFICABLE PAVED FOOTPATH - PV02 (PAVED VEHICULAR CROSSING) TYPICAL DETAILS SCALE 1:10




TYPICAL FOOTPATH JOINTING

1. EJ'S TO ALIGN WITH ADJOINING BAYS 2. JOINT SPACING AROUND CURVES IS TO BE TAKEN TO THE OUTSIDE LENGTH





FOOTPATH TOOLED/SAWN JOINT (F.T.J.) SCALE 1:10

Rev Revision Description




FOOTPATH EXPANSION JOINT (F.E.J.) SCALE 1:10





DOWELLED EXPANSION JOINT (DEJ) DETAIL
SCALE 1:10




MOVEMENT JOINT SEALANT DETAILS (FOR DCJ, EJ, DEJ, KJ & DDJ JOINTS) SCALE 1:10

STEPS:

1. FORM REBATE IN SLAB 2 AGAINST FACE OF SLAB 1.

- 2. AFTER SLAB CURING PERIOD (MIN. 28 DAYS) WASH OUT REBATE USING HIGH PRESSURE WATER. DRY USING HIGH PRESSURE COMPRESSED AIR AND ALLOW ADDITIONAL 16HRS TO DRY THOROUGHLY.
- 3. INSTALL POLYETHYLENE BOND BREAKER TAPE FOR FULL WIDTH 'W'. FOR IJ, EJ AND DEJ JOINTS OMIT BOND BREAKER TAPE.
- 4. PRIME FACES OF SIDES OF REBATE (REFER SEALANT TABLE)
- 5. INSTALL SEALANT AS SPECIFIED (REFER SEALANT TABLE) IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

DOWEL / TIE BAR TABLE						
JOINT DESIGNATION	in incomer / lie i		LENGTH 'L'			
DEJ	10x110 DANLEY DIAMOND	450	155			



SAWN JOINT CUT AND SEALANT DETAILS SCALE 1:10

INITIAL CUT TO DEPTH 'T'/4 ('T'/3 FOR STEEL FIBRE REINFORCED CONCRETE) WITHIN 1 DAY OF POURING CONCRETE. INSERT POLYURETHANE BACKING ROD TO PREVENT INGRESS OF DIRT UNTIL SEALANT APPLIED (MIN 28 DAYS LATER). ROD DIAMETER TO BE MIN. 1.25 x CUT WIDTH.

STEP 2: REMOVE ALL DIRT FROM SAW CUT, USING HIGH PRESSURE COMPRESSED AIR. REPLACE BACKING ROD WITH LARGER DIAMETER IF LOOSE. PUSH BACKING ROD INTO SAW CUT 1mm BELOW DEPTH 'D'. IF NECESSARY, REMOVE AND REPLACE BACKING ROD. WIDEN SAW CUT TO WIDTH 'W' AND DEPTH 'D' WITH ADDITIONAL SAW CUT/CUTS.

REMOVE ALL FOREIGN MATERIAL USING HIGH PRESSURE WATER WASH. DRY USING HIGH PRESSURE COMPRESSED AIR AND ALLOW ADDITIONAL 16 HRS TO DRY THOROUGHLY. INSTALL POLYETHYLENE BOND BREAKER TAPE.

PRIME FACES OF CUT CONCRETE (REFER TABLE BELOW) INSTALL SEALANT AS SPECIFIED (REFER TABLE BELOW) IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.


LOCATION	SEALANT	PRIMER
EXTERNAL PAVEMENTS	EMER-ROAD SEAL SL	FOSROC PRIMER 10

ALTERNATIVE SEALANTS MUST HAVE

- MOVEMENT ACCOMMODATION FACTOR +/- 50%
- PRIMER TO MANUFACTURER'S SPECIFICATION INSTALLATION TO MANUFACTURER'S RECOMMENDATIONS
- PRIOR APPROVAL BY SUPERINTENDENT.

SEAL	ANT DIMENS	IONS
MEAN SLAB LENGTH (m)	SEALANT WIDTH 'W' (mm)	SEALANT DEPTH 'D' (mm)
≤4	7 ± 1	7 ± 1
5	9 ± 2	7 ± 1
6	9 ± 2	7 ± 1
7	10 ± 2	8 ± 1
8	11 ± 2	9 ± 2
9	12 ± 2	10 ± 2
10	13 ± 2	10 ± 2
11	14 ± 2	11 ± 2
12	15 ± 2	12 ± 2
ALL (TSJ)	6	6
ALL (IJ & EJ)	10	8

1. FOR T.S.J. ONLY, CLEAN, PRIME AND SEAL INITIAL SAW CUT ONLY.



EXPANSION JOINT AND ISOLATION JOINT SEALANT DETAIL

- 1. CLOSED CELL POLYURETHANE FILLER (FULL DEPTH)
- CUT HOLES IN FILLER TO FIT CLOSELY AROUND DOWELS 2. FORM GROOVE IN SLAB 2 AND AGAINST FACE OF SLAB 1
- 3. JET WASH AND DRY GROOVE AFTER SLAB CURING PERIOD
- PRIME FACES WITH FOSROC PRIMER 10
- 4. BOND BREAKER TAPE
- 5. INSTALL JOINT SEALANT PARBURY EMER-ROADSEAL OR APPROVED EQUIVALENT WITH MOVEMENT ACCOMMODATION FACTOR +/-50% IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS

DOWEL / HE BAR TABLE						
JOINT DESIGNATION	DOWEL / TIE	SPACING CTR-CTR	LENGTH 'L'			
DEJ	10x110 DANLEY DIAMOND	450	155			

By App Date

Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the accuracy, currency or completeness of any information or data they supply or transferred by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means matches the information or data on the corresponding PDF or DWF version issued by RBG. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance.

Structural, Civil & Construction Engineering Consultant By App Date | Rev Revision Description ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 04.03.19 RobertBirdGroup Charter 2 ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 03.04.19 on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirectly suffer in connection with your access to or use of that information or data. RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a controctual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferable, fully revocable licence to use the intellectual property rights for the express SYDNEY OFFICE Robert Bird Group Pty Ltd

DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE

PO Box A2309

ydney NSW 2000

Sydney South, NSW 1235


Fax: (02) 8246 3201


ACN 010 580 248

Web: www.robertbird.com




Title	Scale at A1 AS SHOWN	Drawn S MANIANDHAD	Design Checker
PAVEMENT DETAILS	Date 03.04.19	S.MANANDHAR Designer Z.JONES	Approved C.ROPE Job Number 18570C
Project 2B-6 HASSALL STREET PARRAMATTA	NOT F Drawing Number C-4-10	OR CONSTRU	








Appendix C Floth OSD and WSUD Drawings

















On-Site Detention Calculation Sheet for Upper Parramatta River Catchment HED Secondary Outlet

Project:	2-6 Hassall St Pari	ramatta						
Site Address	2-6 Hassall St Pari							
		amatta						
Job No:	18255							
Designer:	James Browne							
Telephone:	(02) 9406 4563							
				te Data				
OSD Area:		Upper Parr			ment			
L.G.A		Parramatta	_		2			
Site Area		0.2647	ha	2,647	m ²			
Total Roof Area	000.01	0.1767	ha	1,767	m²	Out to the		
Area of Site draining to	· ·	0.2456	ha	2,456	m ⁻	Satisfactory		
Residual Site Area (Lo	•	0.088 0.0191	ha					
Area Bypassing Storag	=	21.7%	ha			Satisfactory		30% Max
Area Bypassing / Residue No. of Dwellings on Sit		1				Satisfactory Satisfactory		30 % Wax
Site Area per Dwelling		0.265	ha			Saustactory		
Roof Area per Dwelling		0.265						
Rooi Area per Dweiling	g	0.177	ha					
		Ва	sic OS	D Parar	neters			
		Extended D	Detention	1			Detention	
Basic SSR Vols	Ext Detention Storage	300	m ³ /ha			Total Storage	455	m ³ /ha
Basic SRDs	Primary Outlet	40	L/s/ha			Secondary Outlet	150	L/s/ha
			OSD T	ank Byp	ass			
Residual Lot Capture i	n OSD Tank	78%						
Adjusted SRDs		33	L/s/ha				107	L/s/ha
				alculati	ons		- · · ·	
D : 00D // I		Extended [petention m ³	1		o	Detention	m ³
Basic SSR Volume	Ext Detention Storage	79.41	m-			Total Storage		m-
	•		3				120.44	3
Total Rainwater Tank	•	0.64	m ³				0.83	m ³
Total Rainwater Tank (Storage Volume	Credits					Total	0.83 119.61	m ³
Total Rainwater Tank (Storage Volume Storage Volume	Credits Ext Detention Storage	78.77	m ³			Flood Detention Storage	0.83 119.61 40.84	m ³
Total Rainwater Tank (Credits	78.77					0.83 119.61	m ³
Total Rainwater Tank (Storage Volume Storage Volume OSD Discharges	Credits Ext Detention Storage Primary Outlet	78.77 8.86	m ³ L/s			Flood Detention Storage	0.83 119.61 40.84 28.21	m ³ m ³ L/s
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges	Credits Ext Detention Storage Primary Outlet I of Storage	78.77 8.86	m ³ L/s			Flood Detention Storage	0.83 119.61 40.84 28.21	m ³ L/s
Total Rainwater Tank (Storage Volume Storage Volume OSD Discharges	Credits Ext Detention Storage Primary Outlet I of Storage	78.77 8.86	m ³ L/s m m			Flood Detention Storage	0.83 119.61 40.84 28.21	m ³ L/s m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices	Ext Detention Storage Primary Outlet I of Storage	78.77 8.86 0.000 0.000	m ³ L/s	RI		Flood Detention Storage	0.83 119.61 40.84 28.21 15.323 12.302	m³ m³ L/s
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin	Ext Detention Storage Primary Outlet I of Storage ne	78.77 8.86 0.000 0.000 1 9.00	m ³ L/s m m 1.5 yr A		el	Flood Detention Storage Secondary Outlet	0.83 119.61 40.84 28.21 15.323 12.302 1	m ³ m ³ L/s m m 100 yr ARI
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line	78.77 8.86 0.000 0.000 1 9.00 9.00	m m m T 1.5 yr A Raise	RI Orifice Lev		Flood Detention Storage Secondary Outlet	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30	m³ m³ L/s m m 100 yr ARI
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000	m m m 1.5 yr A Raise	Orifice Lev	TWI	Flood Detention Storage Secondary Outlet Satisfactory L Ext Detn Storage - RL Orifice	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302	m³ m³ L/s m m 100 yr ARI m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line	78.77 8.86 0.000 0.000 1 9.00 9.00	m m m T 1.5 yr A Raise		TWI	Flood Detention Storage Secondary Outlet	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30	m³ m³ L/s m m 100 yr ARI
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line e Centre meter	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Flood Detention Storage Secondary Outlet Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302	m³ m³ L/s m m 100 yr ARI m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line e Centre meter	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Flood Detention Storage Secondary Outlet Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302	m³ m³ L/s m m 100 yr ARI m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lir Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line the Centre meter Oble Floor Level	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Flood Detention Storage Secondary Outlet Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM!	m³ m³ L/s m m 100 yr ARI m m m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lir Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar RL of Minimum Habita	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line of Centre meter Dile Floor Level of Floor Level	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM!	m³ m³ L/s m m 100 yr ARI m m m m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar RL of Minimum Habita RL of Minimum Garage Length of Overflow We Site Runoff Coefficient	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line of Centre meter Dele Floor Level eir	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Flood Detention Storage Secondary Outlet Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM! 12.100 0.90 0.75	m³ m³ L/s m m 100 yr ARI m m m m m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar RL of Minimum Habita RL of Minimum Garage Length of Overflow We Site Runoff Coefficient Storm Intensity (5 min	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line of Centre meter Dele Floor Level eir	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM! 12.100 0.90 0.75 206	m³ m³ L/s m m 100 yr ARI m m mm mm m m
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lin Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar RL of Minimum Habita RL of Minimum Garage Length of Overflow We Site Runoff Coefficient Storm Intensity (5 min Peak Flow over Weir	Ext Detention Storage Primary Outlet I of Storage In Flood Level Of Orifice Cente-line I Centre Interest Center Interest Interes	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Orifice Lev Satisfact	TWI ory	Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM! 12.100 0.90 0.75 206 105.4	m³ m³ L/s m m m 100 yr ARI m m m m m L/s
Total Rainwater Tank of Storage Volume Storage Volume OSD Discharges RL of Top Water Level RL of Orifice Centre-lir Number of Orifices Estimated Downstream Downstream FL - RL of Design Head to Orifice Calculated Orifice Diar RL of Minimum Habita RL of Minimum Garage Length of Overflow We Site Runoff Coefficient Storm Intensity (5 min	Ext Detention Storage Primary Outlet I of Storage ne In Flood Level of Orifice Cente-line e Centre meter Oble Floor Level e Floor Level eir 100 yr ARI)	78.77 8.86 0.000 0.000 1 9.00 9.00 0.000 #DIV/0!	m m m T 1.5 yr A Raise m m mm	Satisfact Freeboa	TWI ory	Satisfactory L Ext Detn Storage - RL Orifice #DIV/0!	0.83 119.61 40.84 28.21 15.323 12.302 1 9.00 -3.30 -12.302 #NUM! 12.100 0.90 0.75 206	m³ m³ L/s m m 100 yr ARI m m m m m m m m


Rainwater Tank Calculations (per Dwelling)

OSD Prelim 20190318.xls Version 9 HED

Only Complete th					
The calculations a	ssume that the	same size rainwater tank	is installed on each dwel	ling	
				Min	Max
% of Roof draining to Rainwater Tank	100.0%		Satisfactory	4.6%	100%
Total Rainwater Tank Volume	40.00	kL	Tank Volume OK		
Min Volume that triggers Top-up	0.00	kL	Note - Min Vol in Tank	< 10% Total Tai	nk Vol
Total Tank Vol - Min Top-up Vol	40.00	kL			
		Dedicated Airspace			
Dedicated Airspace	0.00	kL	Satisfactory		
	Extended De	etention		Detention	
Dedicated Airspace Credit	0.00	kL		0.00	kL
Maximum Tank PSD	40	L/s/ha			
Maximum Tank Discharge	0.0	L/s			
Maximum Head to Centre of Tank Orifice	0.000	m	No Dedicated Airspace	9	
Calculated Orifice Diameter	0	mm	No Dedicated Airspace	•	
		Dynamic Airspace			
Maximum Dynamic Storage (Nett Vol)	40.00	kL	Controls minimum % I	Roof to Rainwat	er Tank
Daily Demand on Rainwater Tank	0.657	kL/d	Satisfactory		
Dynamic Airspace at start of Storm	8.59	kL			
	Extended De	etention		Detention	
Dynamic Airspace Credit	0.64	kL		0.83	kL
Combined Rainwater Tank Credit	0.64	kL		0.83	kL
Maximum Rainwater Tank Credit	40.00	kL		40.00	kL
Rainwater Tank Credit per Dwelling	0.64	kL		0.83	kL
Rainwater Tank Credit for the Site	0.64	m ³		0.83	m ³

Signature: James Browne Date: 27/03/201	19
---	----

OSD Prelim 20190318.xls Version 9 HED



Appendix DFlood Enquiry Application





Our Reference: FL/136/2018
Contact: Peter Sirianni
Telephone: 02 9806 8250
Fax: 02 9806 5906

Gary Singh & Andrew Steventon Level 14, 5 Martin Place SYDNEY NSW 2000

24 October 2018

FLOOD ENQUIRY APPLICATION

Property Details

Fioperty	Details
Address	2 Hassall Street, PARRAMATTA NSW 2150, 4 Hassall Street, PARRAMATTA NSW 2150, 6 Hassall Street, PARRAMATTA NSW 2150
	This form applies for up to three adjoining sites relating to the same development. A

Delivery Preference

gary.singh@solutionsconsulting.com.au & andrew.steventon@solutionsconsulting.com.au

separate Flood Enquiry form and fee will be required for more than 3 or separate lots.

Reason for Enquiry

Proposed Re-development of Property

Property Type

** GST not applicable from 1 July 2013**

Flooding Application - Commercial

\$496.45

Disclaimer: Flood levels and flood extent lines are based on current information held by Council. Council does not accept responsibility for the accuracy of this information. Any pipe sizes and location of pits and pipe lines should be confirmed by site investigation.

The flood levels shown on the back of this form are only an approximate guide and have been derived using the current computer simulated model.

The information provided in this document is presented in good faith to assist the public in understanding Council's drainage requirements that apply within the Parramatta Local Government Area. It is the responsibility of each individual using this information to undertake their own checks and confirm this information prior to its use.

City of Parramatta Council, its agents and employees are not liable (whether by reason of negligence, lack of care or otherwise) to any person for any damage or loss whatsoever which has occurred or may occur in relation to that person taking or not taking (as the case may be) action in respect of any representation, statement, or advice referred to above.

Refer to back of this form for level information issued






Flood Enquiry Information Issued - 24 October 2018

Mainst	ream Flooding						
Is thi	s property affected by	mainstream flooding?		Yes			
2-6	Hassall Street,	Parramatta		⊠ No			
	Flood Levels	Closest Cross Sections: (Please re	efer to Flood Study):				
	5% AEP	m AHD	Comments:				
	1% AEP m AHD See Note on Flood / Hazard I						
	PMF	m AHD	oce Note on Flood / Flazard	Wap			
		ovided for detailed flood levels.					
		ed from the following flood study rep					
1	 Lower Parrai 	matta River Floodplain Ri	sk Management Study - Floo	od Study			
	Review, 2005						
		rainage, 1990 (Sinclair K					
Note: F	lood inundation can be	verified by detail survey to AHD un	dertaken by a Registered Surveyor.				
l ocal E	looding						
	<u> </u>			Yes			
		in a Hatched Grey Area? <i>Hatched Grey Area</i> are subjected i	to flooding from the local catchment.	⊠ No			
	e property located with			☐ Yes ⊠ No			
	erties located within a ling in the local catchm		nal site drainage controls to manage	<u> </u>			
		affected by overland stormwater run-	-off from the local catchment?	Yes			
Note	Note: No site inspection conducted for this assessment. Based solely on the information supplied for this flood enquiry application. Subject to Detail Investigation						
			rice Engineer for any details and requiren	nents relating to			
deve	lopment that is affecte	d by local flooding.		-			
Additio	nal Recommended A	ctions					
	The Applicant needs Services Engineer.	to discuss the proposal to re-develo	op this site with Council's Town Planner a	nd Development			
	The Applicant needs to redevelop this prop		and organise a pre-lodgement meeting to	discuss any proposal			
	The Applicant needs land affected by flood		n Risk Management policy for details rela	ating to developing a			

Definitions: (As per NSW Floodplain Development Manual dated April 2005)

- 1. **AHD** a common national surface level datum approximately corresponding to mean sea level.
- 2. **ARI** the long term average number of years between the occurrences of a flood as big as or larger than, the selected event
- 3. **PMF** is the largest flood that could conceivably occur at a particular location, usually estimated from probable maximum precipitation.
- 4. **AEP** Annual Exceedance Probability is the chance of a flood of a given or larger size occurring in any one year, usually expressed as a percentage.







Printed

23/10/2018

City of Parramatta Council Flood Map


1:4,000

DISCLAIMER: Flood levels and flood extent lines are based on current information held by Council. Council does not accept responsibility for the accuracy of this Information. Any pipe sizes and location of pits and pipe lines should be confirmed by site investigation.

The flood levels provided are only an approximate guide and have been derived using the current computer simulated model.

The information provided on this document is presented in good faith. It is the responsibility of each individual using this information to undertake their own checks and confirm this

information prior to its use.





Printed

23/10/2018

1:4,000

and location of pits and pipe lines should be confirmed by site investigation.

The flood levels provided are only an approximate guide and have been derived using the current computer simulated model.

The information provided on this document is presented in good faith. It is the responsibility of each individual using this information to undertake their own checks and confirm this

information prior to its use.

City of Parramatta Council, its agents and employees are not liable (whether by reason of negligence, lack of care or otherwise) to any person for any damage or loss whatsoever which has occurred or may occur in relation to that person taking or not taking (as the case may be) action in respect of any representation, statement, or advice referred to above.



Robert **Bird** Group

Sydney Office


Robert Bird Group Pty Ltd ABN 67 010 580 248 ACN 010 580 248

Level 11, 151 Castlereagh Street Sydney NSW 2000 PO Box A2309 Sydney South NSW 1235 Australia


> P: +61 (0) 2 8246 3200 F: +61 (0) 2 8246 3201

2B-6 HASSAL ST MAIN WORKS PARRAMATTA, NSW 2150 CIVIL ENGINEERING DRAWINGS ISSUED FOR DEVELOPMENT APPLICATION

	Sheet List Table		
Sheet Number	Sheet Title		
C-0-00	COVER SHEET, LOCATION MAP AND SHEET INDEX		
C-0-01	GENERAL NOTES		
C-1-00	EROSION AND SEDIMENT CONTROL		
C-1-10	EROSION AND SEDIMENT CONTROL DETAILS		
C-2-01	BULK EARTHWORKS PLAN		
C-2-10	BULK EARTHWORKS SECTIONS		
C-3-00	GENERAL ARRANGEMENT PLAN		
C-3-10	CIVIL DETAILS		
C-4-10	PAVEMENT DETAILS		
C-6-50	STORMWATER PRE CATCHMENT ANALYSIS		
C-6-51	STORMWATER POST CATCHMENT ANALYSIS		



LOCALITY MAP SCALE NTS



GENERAL NOTES

- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER ENGINEERING DRAWINGS AND CITY OF PARRAMATTA COUNCIL AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT.
- 2. THESE ENGINEERING PLANS ARE TO BE READ IN CONJUNCTION WITH PROJECT SPECIFICATIONS AND OTHER CONSULTANTS DOCUMENTATION ON THE PROJECT.
- 3. THESE ENGINEERING PLANS HAVE BEEN PREPARED FROM INFORMATION AVAILABLE AT THE TIME OF ISSUE. AS THIS INFORMATION MAY BE THE SUBJECT OF CHANGE PRIOR TO OR DURING CONSTRUCTION THE CONTRACTOR IS TO ADVISE THE ENGINEER WHERE DISCREPANCIES OCCUR.
- 4. THESE DRAWINGS SHALL NOT BE USED FOR FINAL SETOUT OF THE PROJECT UNLESS SPECIFICALLY STATED.
- 5. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH PARRAMATTA CITY COUNCIL STANDARDS, GUIDELINES AND TECHNICAL MANUALS.
- 6. ALL WORKS SHALL HAVE SMOOTH JUNCTIONS WITH EXISTING.
- 7. ALL SURFACES SHALL BE EVEN GRADED AT MINIMUM 1% TO PREVENT SURFACE WATER PONDING.
- 8. WHERE CERTIFICATION IS REQUIRED, INSPECTIONS ARE TO BE PERFORMED BY A DULY APPOINTED INSPECTOR FROM 'ROBERT BIRD GROUP'. THESE INSPECTIONS ARE TO BE PERFORMED IN ACCORDANCE WITH THE INSPECTION & TEST PLANS PREPARED BY 'ROBERT BIRD GROUP.' THE INSPECTOR IS TO BE GIVEN A MINIMUM NOTICE AS DETAILED IN THE SPECIFICATIONS.
- 9. ALL MATERIALS SHALL COMPLY WITH WHAT IS SHOWN ON THE PROJECT DRAWINGS AND IN THE
- 10. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL EXISTING SERVICES WITH ALL RELEVANT SERVICE AUTHORITIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. A COPY OF THE LOCATIONS OF THE EXISTING SERVICES IS TO BE PROVIDED TO THE MANAGING CONTRACTOR BY THE SERVICES ENGINEER. CONTRACTOR TO NOTIFY MANAGING CONTRACTOR OF ANY POTENTIAL
- 11. THE CONTRACTOR SHALL VERIFY OFFSET PEGS AND BENCHMARK LEVELS, AND ADVISE THE MANAGING CONTRACTOR OF ANY DISCREPANCY PRIOR TO COMMENCING CONSTRUCTION.
- 12. THE CONTRACTOR SHALL VERIFY THE EXISTING LEVELS WHERE NEW WORKS ARE TO JOIN TO EXISTING WORKS, AND ADVISE THE MANAGING CONTRACTOR OF ANY DISCREPANCY PRIOR TO COMMENCING CONSTRUCTION.
- 13. THE CONTRACTOR SHALL CHECK OR OBTAIN ALL DIMENSIONS RELEVANT TO SETTING OUT OF
- 14. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STABILITY OF THE WORKS AND ENSURE NO PART IS OVERSTRESSED. THE DESIGN AND CERTIFICATION OF ALL FORMWORK AND BACKPROPPING IS TO BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 15. THE CONTRACTOR IS TO OBTAIN DESIGN ADVICE FROM A SUITABLY QUALIFIED ENGINEER REGARDING DEMOLITION, RETROFITTING, TEMPORARY WORKS, HEALTH & SAFETY AND NUISANCE. THIS HAS BEEN REFERRED TO AS THE "CONTRACTORS ENGINEER" THROUGHOUT THE REMAINING NOTES.
- UNLESS SPECIFIED OTHERWISE IN THE PROJECT DOCUMENTATION, MINIMUM STRIPPING TIMES FOR IN-SITU CONCRETE FORMWORK SHALL COMPLY WITH SECTION 5.4.3 (TABLE 5.4.1) OF AS3610-'FORMWORK FOR CONCRETE'.
- 17. WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CURRENT AUSTRALIAN STANDARDS AND BCA STATUTORY REQUIREMENTS, EXCEPT WHERE VARIED BY THE CONTRACT
- 18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT SUFFICIENT TOLERANCES ARE PROVIDED AND INTEGRATED THROUGHOUT ALL ELEMENTS OF THE WORKS.
- 19. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- 20. ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (A.H.D.)
- 21. DESIGN LEVELS AND SETOUT DETAILED HEREIN ARE DERIVED SURVEY, LANDSCAPE AND ARCHITECTURAL PLANS. CONTRACTOR SHALL CONFIRM LEVELS ARE COORDINATED PRIOR TO COMMENCING WORKS. EXISTING LEVELS ARE DERIVED FROM SURVEY DATA. CONTRACTOR TO CONFIRM ALL ON SITE PRIOR TO COMMENCING WORKS.

HEALTH & SAFETY

- 1. THE CONTRACTOR SHALL DEVELOP, IMPLEMENT AND ADMINISTER A WORKPLACE HEALTH AND SAFETY PROGRAM THAT WILL ENSURE THAT ALL CONSTRUCTION ACTIVITIES ARE PERFORMED TO THE RELEVANT WORKPLACE HEALTH AND SAFETY REQUIREMENTS AND ANY OTHER RELEVANT STATUTORY REQUIREMENTS.
- 2. THE WORKPLACE HEALTH AND SAFETY PROGRAM MUST BE CO-ORDINATED WITH ADJOINING PROPERTY OWNERS AND ALL RELEVANT PARTIES AS NECESSARY TO ENSURE A SAFE BUILDING ENVIRONMENT AT ALL TIMES.

NUISANCE

- THE CONTRACTOR SHALL DEVELOP. IMPLEMENT, AND ADMINISTER A PLAN THAT WILL ENSURE THE MANAGEMENT OF NOISE AND VIBRATION RESULTING FROM CONSTRUCTION WORKS. REFER TO SPECIFICATIONS FOR REQUIRED LIMITS, OTHERWISE, CONTACT ENGINEER FOR GUIDANCE.
- 2. THE CONTRACTOR WILL NEED TO ENSURE ALL ADJOINING PROPERTY REQUIREMENTS RELATING TO NOISE AND VIBRATION ARE MET.
- 3. IF IT IS ESTABLISHED THAT THERE ARE NO SITE SPECIFIC REQUIREMENTS, THEN THE CONTRACTOR SHALL REFER TO MINIMUM REQUIREMENTS FOR ABATEMENT OF NOISE AND VIBRATION NOMINATED BY RELEVANT STATUTORY REQUIREMENTS
- 4. THE CONTRACTOR WILL NEED TO PREPARE AND ADVISE ON MONITORING AND MANAGEMENT OF NOISE AND VIBRATION BASED ON PROFESSIONAL ADVICE FROM SUITABLY QUALIFIED PERSON OR PERSONS.

SURVEY NOTES

1. THE SURVEY INFORMATION SHOWN ON ROBERT BIRD GROUP DRAWINGS HAS BEEN OVERLAID FROM INFORMATION PROVIDED IN THE DETAILED SURVEY BY USHER & COMPANY, SURVEYING AND LAND DEVELOPMENT CONSULTANTS FILE REF: 6083-DET ISSUE 3, DATED 25.09.2018. ROBERT BIRD GROUP DOES NOT GUARANTEE THAT THE SURVEY INFORMATION IS ACCURATE, AND ACCEPTS NO LIABILITY FOR

SEDIMENT AND EROSION CONTROL NOTES

- 1. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PROVIDED IN ACCORDANCE WITH SPECIFICATION AND EPA "MANAGING URBAN STORMWATER CONSTRUCTION ACTIVITIES" 1998. ALL WORKS SHALL BE COMPLETED PRIOR TO CONSTRUCTION COMMENCING.
- 2. REFER TO ROBERT BIRD GROUP'S DRAWING SHEETS C-1-00 AND C-1-10 FOR EROSION AND SEDIMENT CONTROL NOTES AND DETAILS.

EARTHWORKS NOTES

- 1. REFER TO THE GEOTECHNICAL ENGINEERING REPORT.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL, COMPACTION AND DISPOSAL OF ALL EXCAVATED MATERIAL.
- 3. ALL EARTHWORKS AREAS ARE TO BE LEFT IN A FREE DRAINING STATE.
- 4. PROOF ROLL SUBGRADE TO REVEAL SOFT SPOTS. SOFT SPOTS TO BE REMOVED AND BACKFILLED. ALL NATURAL SUBGRADE IS TO BE COMPACTED TO IN ACCORDANCE WITH AS1289 PRIOR TO PLACEMENT OF
- 5. MATERIAL WON FROM THE SITE TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER FOR APPROVAL PRIOR TO USE AS FILL. ALL FILL TO BE COMPACTED TO MIN. 98% STANDARD COMPACTION IN 200mm MAXIMUM THICK LAYERS IN ACCORDANCE WITH AS1289.
- 6. TEST CERTIFICATES ON THE FILL MATERIAL SHALL BE SUPPLIED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO THE USE OF THE FILL MATERIAL.

TEMPORARY WORKS

- 1. THE CONTRACTOR SHALL ALLOW FOR THE DESIGN, SUPPLY, INSTALLATION AND REMOVAL OF ALL TEMPORARY BACK PROPPING, SAFETY SCREENS, SCAFFOLDING AND OTHER REQUIREMENTS OF THE CONSTRUCTION PROCESS. THE CONTRACTOR SHALL ENGAGE SUITABLY QUALIFIED ENGINEER REFEREED TO AS "CONTRACTORS ENGINEER". TO DESIGN INSPECT AND CERTIFY ALL TEMPORARY WORKS, AND DEMOLITION WORKS.
- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THE OVERALL STABILITY OF THE STRUCTURES WHILST UNDER CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ADVICE FROM THE CONTRACTORS ENGINEER.

CONCRETE NOTES

- CONCRETE WORK SHALL BE IN ACCORDANCE WITH AS3600 AND WITH THE PROJECT SPECIFICATIONS.
- 2. CONSTRUCTION JOINTS SHALL BE PROPERLY FORMED AND USED ONLY WHERE SHOWN ON SUPERINTENDENT DRAWINGS OR SPECIFICALLY APPROVED BY SUPERINTENDENT.
- 3. ALL THICKNESSES SHOWN ARE MINIMUM STRUCTURAL REQUIREMENTS, NO REDUCTION IN THICKNESS DUE TO FALLS OR TOPPING IS PERMITTED.
- 4. UNLESS A GROOVE LINE ALLOWANCE HAS BEEN NOTED ON THE DRAWINGS, NO GROOVE LINES ARE PERMITTED, EXCEPT AT SLAB LINES. ALL GROOVE LINES ARE TO BE SUBMITTED TO 'ROBERT BIRD GROUP' FOR APPROVAL.
- 5. THE FACE OF ALL CONCRETE AGAINST WHICH NEW CONCRETE IS TO BE CAST IS TO BE THOROUGHLY MECHANICALLY SCABBLED, FULLY EXPOSING THE AGGREGATE MATRIX.

CONCRETE

- 1. THE CHARACTERISTIC COMPRESSIVE STRENGTH (I'c) AT 28 DAYS OF IN PLACE CONCRETE SHALL BE AS
- NOTED IN THE SPECIFICATION OR OTHERWISE NOTED ON THE DRAWINGS
- MAXIMUM AGGREGATE SIZE.....20mm
- SLUMP....
- 4. ALL CONCRETE SHALL BE VIBRATED.
- 5. ALL CONCRETE SHALL BE CURED IN ACCORDANCE WITH THE SPECIFICATION
- 6. ALL CONCRETE SHALL BE SAMPLED AND TESTED IN ACCORDANCE WITH AS1012 AND THE PROJECT SPECIFICATION.
- 7. ALL FORM WORK SHALL COMPLY WITH AS3610
- 8. REFER STRUCTURAL ENGINEER'S SPECIFICATIONS FOR CONCRETE REQUIREMENTS.

- 1. REINFORCEMENT IS TO BE MANUFACTURED IN ACCORDANCE WITH AS4671 AND SHALL BE FIXED AS SHOWN ON DRAWINGS.
- 2. MATERIAL IS INDICATED BY THE FOLLOWING SYMBOLS:-
 - Y DEFORMED BAR GRADE 400 N DEFORMED BAR GRADE 500 (NORMAL DUCTILITY)
 - R PLAIN ROUND BAR GRADE 250
 - W PLAIN WIRE GRADE 450
 - SL SQUARE FABRIC GRADE 500
 - RL RECTANGULAR FABRIC GRADE 500
- 3. THE BAR SIZE IS INDICATED BY A NUMBER AFTER THE SYMBOL, WHICH INDICATES THE BAR DIAMETER IN MILLIMETRES.
- 4. REINFORCEMENT SPACING NOMINATED ON DRAWINGS IS TO ASSIST SCHEDULER AND STEEL FIXER TO ASSESS TOTAL NUMBER OF BARS REQUIRED. WHERE BARS PLACED IN ACCORDANCE WITH SPACING NOMINATED FOUL WITH OTHER STRUCTURAL REQUIREMENTS, PREFERENCE IS TO BE GIVEN TO RELOCATING BARS BY LOCALLY ADJUSTING SPACING TO ENABLE ASSEMBLY OF REINFORCEMENT TO BE COMPLETED. ENGINEER IS TO BE CONTACTED IN THE EVENT THAT REINFORCEMENT IS NEEDED TO BE CUT ON SITE PRIOR TO CONTINUING.
- 5. LAP LENGTHS TO REINFORCEMENT BARS TO BE AS NOTED ON THE RELEVANT DRAWINGS.
- 6. WELDING OF REINFORCEMENT BARS IS NOT PERMITTED UNLESS APPROVED.

CONCRETE NOTES CONTINUED REINFORCEMENT CONTINUED

- 7. COVER SHALL BE AS NOTED ON THE RELEVANT DRAWINGS.
- 8. CONCRETE COVERS NOTED ARE MEASURED FROM THE FORM WORK OR GROUND FACE TO THE OUTERMOST REINFORCEMENT COMPONENT. i.e., IN COLUMNS AND BEAMS TO THE OUTSIDE OF TIES OR
- 9. COVER TO BE MAINTAINED DURING POURING BY THE USE OF PLASTIC CHAIRS OR PLASTIC TIPPED METAL CHAIRS.
- 10. WHERE NO REINFORCEMENT IS SHOWN ON THE DRAWING AT RIGHT ANGLES TO THE MAIN REINFORCEMENT DISTRIBUTION REINFORCEMENT IS TO BE PROVIDED.
- 11. BENDING & STRAIGHTENING
 - COLD BENDING: BARS CANNOT BE COLD BENT WITHOUT PRIOR APPROVAL FROM THE PROJECT STRUCTURAL ENGINEER. CORRECT MINIMUM DIAMETER FORMERS ARE TO BE USED IN
 - ACCORDANCE WITH AS3600. HOT BENDING: HOT BENDING MAY ONLY BE CONDUCTED WITH THE APPROVAL OF THE PROJECT STRUCTURAL ENGINEER. HOT BENDING CAN ONLY BE PERFORMED BY A CERTIFIED WELDER. TEST CERTIFICATE OF AFFECTED AREA TO BE OBTAINED.
 - STRAIGHTENING: WHEN RE-STRAIGHTENING PARTIALLY EMBEDDED BARS, DO NOT BEND OVER FORMERS OF SMALLER DIAMETER THAN PERMITTED IN AS 3600. DO NOT SUBJECT REINFORCEMENT BARS TO IMPACT IN ORDER TO STRAIGHTEN.

SLAB ON GROUND NOTES

- 1. SLAB ON GROUND TO BE POURED ON A LAYER OF POLYETHYLENE SHEETING 200 µm THICK ON TOP OF 50mm OF BEDDING SAND. JOINTS TO BE TAPED
- 2. FABRIC TO BE PLACED ON CHAIRS AT 800 x 800 CENTRES AND CHAIRS TO BE PLACED ON STEEL
- 3. LAP FABRIC REINFORCEMENT THUS:



4. WHERE BEDDING SAND IS REQUIRED UNDER SLAB, THIS SHALL BE COMPACTED SUFFICIENTLY TO SUPPORT REINFORCEMENT PLUS 100kg/CHAIR WITHOUT VERTICAL DISPLACEMENT EXCEEDING 5mm.

ROADS AND PAVEMENT NOTES

GENERAL

PAVEMENT SHALL BE BOXED OUT TO THE DEPTHS AS SHOWN ON THE PAVEMENT DRAWINGS, AND SUBGRADE TESTING IS TO BE UNDERTAKEN. SUBGRADE TESTING RESULTS ARE TO BE FORWARDED TO THE ENGINEER (ROBERT BIRD GROUP) FOR DETERMINATION OF FINAL PAVEMENT DEPTH. PAVEMENT CONSTRUCTION IS TO HOLD UNTIL FINAL PAVEMENT DEPTH HAS BEEN DETERMINED BY THE ENGINEER, AND APPROVED BY THE RELEVANT AUTHORITY.

PREPARATION OF SELECT SUBGRADE LAYERED

- THE SELECT SUBGRADE LAYER IS DEFINED AS THE UPPER 300MM OF THE FORMATION UPON WHICH THE ROAD PAVEMENT IS TO BE CONSTRUCTED. THE UPPER SURFACE OF THE SUBGRADE LAYER IS DEFINED AS THE DESIGN SUBGRADE LEVEL.
- THE SELECT SUBGRADE LAYER SHALL BE FREE FROM ALL POCKETS OF SOFT COMPRESSIBLE MATERIAL, FREE FROM STONE WITH A MAXIMUM DIMENSION LARGER THAN 50MM, AND HAVE A MINIMUM SOAKED CBR AS SPECIFIED ON
- 4. ANY UNSUITABLE LAYER SHALL BE COMPACTED TO A FIELD DRY DENSITY OF NOT LESS THAN 100% AS DETERMINED IN ACCORDANCE WITH RTA TEST METHOD T111 - STANDARD COMPACTION (FOR A COHESIVE SOIL) OR A MINIMUM DENSITY INDEX OF 80% WHEN TESTED IN ACCORDANCE WITH AS.1289.5.6.1 (FOR A COHESIVE LESS
- 5. TESTS FOR COMPACTION OF SELECTED SUBGRADE LAYER SHALL BE CARRIED OUT BY THE CONTRACTOR AT LOCATION APPROVED BY THE SUPERINTENDENT AT A RATE AS SPECIFIED.

PLACEMENT OF PAVEMENT MATERIALS

- 1. THE PAVEMENT SHALL BE CONSTRUCTED TO THE THICKNESS AS SHOWN ON THE DRAWINGS. PAVEMENT COURSES LESS THAN 150mm IN COMPACTED THICKNESS SHALL BE SPREAD AND COMPACTED IN TWO OR MORE LAYERS OF NOT LESS THAN 75MM OR MORE THAN 150MM IN COMPACTED THICKNESS.
- 2. SPREADING SHALL BE UNDERTAKEN BY A METHOD THAT WILL ENSURE THAT SEGREGATION DOES NOT OCCUR.
- 3. MIXING OR BLENDING OF PAVEMENT MATERIALS WILL NOT BE ALLOWED ON THE ROAD FORMATION. PAVEMENT MATERIAL SHALL NOT BE SPREAD ON A WATERLOGGED SUBGRADE NOR BROKEN ON THE SUBGRADE. WHEN SPREADING AND/OR MIXING PAVEMENT MATERIAL. CARE SHALL BE TAKEN TO ENSURE THAT THE SUBGRADE SHALL NOT BE DISTURBED. BECOME RUTTED OR MIXED WITH THE PAVEMENT MATERIALS.
- 4. IF, AT ANY TIME ANY PART OF SUBGRADE AND PAVEMENT MATERIALS BECOME MIXED, THE CONTRACTOR SHALL, AT ITS COST, REMOVE THE MIXTURE AND RESHAPE THE SUBGRADE WITH APPROVED MATERIAL COMPACTED UNIFORMLY WITH THE SURROUNDING SURFACE.
- 5. WHEN EACH LAYER OF PAVEMENT MATERIAL HAS BEEN SPREAD, WATERING SHALL BE CARRIED OUT AS NECESSARY TO MAINTAIN THE MATERIAL AT A MOISTURE CONTENT DURING ROLLING AS CLOSE TO BUT NOT EXCEEDING ITS OPTIMUM MOISTURE CONTENT.
- WHERE THE MOISTURE CONTENT OF PAVEMENT MATERIAL IS INSUFFICIENT, WATER SHALL BE ADDED BY APPROVED WATERING EQUIPMENT AND SHALL BE MIXED UNIFORMLY WITH THE MATERIAL BY AN APPROVED MECHANICAL DEVICE.
- WHERE THERE IS EXCESS MOISTURE IN THE PAVEMENT MATERIAL, IT SHALL BE DRIED TO THE REQUIRED MOISTURE CONTENT BY LOOSENING AND AERATING.

PO Box A2309

Sydney South, NSW 1235

ydney NSW 2000

COMPACTION OF PAVEMENT MATERIALS

- 1. AS EACH LAYER IS BROUGHT TO IT OPTIMUM MOISTURE CONTENT, IT SHALL BE IMMEDIATELY COMPACTED BY
- COMPACTION SHALL BE CARRIED OUT USING APPROVED EQUIPMENT OF ADEQUATE CAPACITY TO ACHIEVE THE DEGREE OF COMPACTION SPECIFIED.
- 3. ANY DEFICIENCIES MADE BY THE SINKING OF THE COMPACTOR WHEN COMPACTING MATERIAL SHALL AT ONCE BE MADE GOOD BY SCARIFYING THE SURFACE AND ADDING ADDITIONAL MATERIAL AT THE CONTRACTOR 'S
- 4. ON THE SECTION OF PAVEMENT HAVING A ONE-WAY CROSS FALL, COMPACTION SHALL COMMENCE AT THE LOWER EDGE OF THE BASE AND PROGRESS UPWARDS TO THE HIGHER EDGE.
- 5. ON CROWNED SECTION OF PAVEMENT, COMPACTION SHALL COMMENCE AT THE OUTER EDGES OF THE BASE AND PROGRESS INWARDS TOWARDS THE CROWN.
- 6. EACH PASS OF THE COMPACTION PLANT SHALL BE PARALLEL TO THE CENTRE LINE OF THE PAVEMENT. THE METHOD OF COMPACTION SHALL ALLOW FOR PROGRESSIVE AND UNIFORM OVERLAP BETWEEN PASSES.
- 7. IF NON-VIBRATING SMOOTH-WHEELED ROLLERS ARE USED AS COMPACTION PLANT. THEY SHALL BE OPERATED WITH THE DRIVING ROLLERS FACING THE UNCOMPACTED MATERIAL DURING THE INITIAL PASS.
- 8. IF VIBRATING ROLLERS ARE USED AS COMPACTION PLANT, THE VIBRATOR SHALL NOT BE ACTIVATED UNTIL A MINIMUM OF TWO "STATIC" PASSES HAVE BEEN MADE. IN ADDITION, THE VIBRATORS SHALL NOT BE ACTIVATED DURING ANY CHANGE IN DIRECTION OF THE ROLLER.
- COMPACTION PLANT AND OTHER ANCILLARY PLANT SHALL NOT BE ALLOWED TO REMAIN STANDING ON THE COMPACTED PAVEMENT WITHOUT THE APPROVAL OF THE SUPERINTENDENT.
- 10. TRAFFIC SHALL NOT BE ALLOWED ON ANY COMPACTED LAYER WITHOUT APPROVAL OF THE SUPERINTENDENT. EACH LAYER IN A MULTI-LAYERED COURSE SHALL BE FULLY COMPACTED IN SEQUENCE. THE SURFACE OF THE COMPACTED LAYER SHALL BE KEPT SUFFICIENTLY MOIST TO MAINTAIN THE REQUIRED FIELD MOISTURE CONTENT THROUGHOUT THE FULL DEPTH OF THE LAYER PRIOR TO PLACEMENT OF SUBSEQUENT LAYERS OR TO THE APPLICATION OF THE SURFACE PRIMER. AS APPLICABLE.
- 11. COMPACTION SHALL CONTINUE UNTIL THE MATERIAL DOES NOT CREEP OR WAVE AHEAD OF THE ROLLER. UNTIL THE SURFACE PRESENTS A SMOOTH UNIFORM APPEARANCE AND UNTIL THE MATERIAL HAS BEEN LEVELED AND COMPACTED TO THE REQUIREMENTS AND TOLERANCES SPECIFIED ELSEWHERE HEREIN.
- 12. TESTS FOR COMPACTION OF ROAD PAVEMENT MATERIALS SHALL BE CARRIED OUT BY THE CONTRACTOR AT LOCATIONS APPROVED BY THE SUPERINTENDENT AT A RATE AS SPECIFIED.

STORMWATER DRAINAGE NOTES

1. THESE NOTES SHALL BE READ IN CONJUNCTION WITH: A. GENERAL NOTES AND DISCLAIMERS FOR THE PROJECT B. ROADWORKS NOTES FOR THE PROJECT

C. SPECIFICATIONS FOR THE PROJECT.

- 2. STORMWATER PIPES 375NB AND GREATER SHALL BE RCP RRJ, U.N.O. CLASSES AS NOTED ON THE DRAWINGS. FRC PERMITTED.
- 3. STORMWATER DRAINAGE PIPES LESS THAN OR EQUAL TO 900mm DIAMETER SHALL BE SPIGOT AND SOCKET AND RUBBER RING JOINTED.
- 4. OUTLET LOCATIONS ARE TO BE CONFIRMED ON SITE BY THE MANAGING CONTRACTOR PRIOR TO THE COMMENCEMENT OF STORMWATER DRAINAGE CONSTRUCTION.
- 5. ALL PROPOSED STORMWATER WORKS DESIGNED IN ACCORDANCE WITH A. AUSTRALIAN RAINFALL AND RUNOFF (1987 EDITION) VOLUMES 1 AND 2. B. AS 3500 NATIONAL PLUMBING CODE PART 3 - STORMWATER DRAINAGE.

C. PARRAMATTA CITY COUNCIL'S PUBLIC DOMAIN GUIDELINES.

SERVICE NOTES

1. ALL EXISTING SERVICES LIDS THAT ARE TO REMAIN ARE TO BE RECONSTRUCTED TO MATCH PROPOSED LEVELS AND ALIGNED TO PARRAMATTA CITY COUNCIL STANDARDS.

LANDSCAPING NOTES

REFER TO ASPECT LANDSCAPE ARCHITECTS DRAWINGS FOR LANDSCAPING DETAILS.

HYDRAULICS NOTES

1. REFER TO HYDRAULIC ENGINEERS DRAWINGS FOR SEWER, WATER AND INTERNAL SITE STORMWATER DRAINAGE WORKS

Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the accuracy, currency or completeness of any information or data they supply or transfer by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means matches the information or data on the corresponding PDF or DWF version issued by RBG. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance and reliance transferred by electronic means and the reliance of the supplied or transferred by electronic means and the reliance of the re By App Date | Rev Revision Description By App Date Rev Revision Description ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 04.03.19 Robert**Bird**Group on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirect suffer in connection with your access to or use of that information or data. surrer in connection with your access to or use of that information or acta.

RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a contractual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferable, fully revocable licence to use the intellectual property rights for the express Member of the Surbana Jurong Group SYDNEY OFFICE lobert Bird Group Pty Ltd

DO NOT SCALE DRAWINGS. USE FIGURED DIMENSIONS

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE

Ph: (02) 8246 3200 Fax: (02) 8246 3201 Email: sydney@robertbird.com.au Web: www.robertbird.com ACN 010 580 248



GENERAL NOTES 04.03.19 2B-6 HASSALL STREET

PARRAMATTA

18570C NOT FOR CONSTRUCTION

S.MANANDHAR

Designer

Z.JONES

Design Checker

Approved


C.ROPE

Job Number

Drawing Number C-0-01

Scale at A1

AS SHOWN



GENERAL NOTES:

- A1. THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT.
- A2. CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE LANDCOM - MANAGING URBAN STORMWATER: SOIL AND CONSTRUCTION, 4th EDITION, MAR
- A3. REFER VEGETATION MANAGEMENT PLAN BY ECOLOGICAL FOR VEGETATION CLEARANCE AND RIPARIAN ZONE MANAGEMENT.
- A4. REFER GEOTECHNICAL REPORT FOR EARTHWORKS AND PARAMETERS.
- A5. ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

SITE MAINTENANCE NOTES:

- SM1. THE CONTRACTOR SHALL INSPECT THE SITE AT LEAST WEEKLY AND AT THE CONCLUSION OF EVERY STORM EVENT TO:
- A) ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT AND NECESSARY REPAIRS.
- B) REMOVED SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.
- C) REMOVED TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURES HAS BEEN EXCEEDED.
- D) ENSURE REHABILITATION LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD TO INITIATE UPGRADING OR REPAIR AS NECESSARY.
- E) CONSTRUCT ADDITIONAL EROSION AND OR SEDIMENT CONTROL WORKS THAT MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS. MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECT TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT.
- F) MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED.
- SM2. THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
 - A) THE VOLUME AND INTENSITY OF ANY RAINFALL EVENTS.
- B) THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS.
- C) THE CONDITION OF VEGETATION AND ANY NEED TO IRRIGATE.
- D) THE NEED FOR DUST PREVENTION STRATEGIES THE LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE SUPERINTENDENT AT THE CONCLUSION OF THE WORKS.

SEDIMENT CONTROL NOTES:

- SC1. SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE.
- SC2. SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES.
- SC3. SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR.

SC4. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METERS OF HAZARD AREAS INCLUDING

- AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND DRIVEWAYS. SC5. WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM
- UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE.
- SC6. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- SC7. ACCESS TO SITES SHOULD BE STABILIZED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT.

LAND DISTURBANCE NOTES:


- LD1. ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METERS THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNIZE THOSE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH A BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- LD2. ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH.
- LD3. WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE:
- A) INSTALL ALL BARRIER AND SEDIMENT FENCING WHERE SHOWN ON THE PLAN.
- B) CONSTRUCT THE STABILISED SITE ACCESS.
- C) CONSTRUCT DIVERSION DRAINS AS REQUIRED.
- D) INSTALL MESH AND GRAVEL INLETS FOR ANY ADJACENT KERB INLETS. E) INSTALL GEOTEXTILE INLET FILTERS AROUND ANY ON-SITE DROP INLET PITS.
- F) CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN LOCATIONS SHOWN ON THE
- G) UNDERTAKE ALL ESSENTIAL CONSTRUCTION WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE.
- H) GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS.
- I) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- LD4. ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING.


SOIL EROSION CONTROL NOTES:

- SE1. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTES, THAN THAT RECOMMENDED BY THE GEOTECHNICAL REPORT.
- SE2. ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- SE3. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70% GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- SE4. STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.1% (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- SE5. ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- SE6. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS. NEWLY PLANTED LANDS WILL BE WATERED REGULARLY UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY. FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED AS NECESSARY.

WASTE CONTROL NOTES:

- WC1. ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY. DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- WC2. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOW PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- WC3. ALL SITE STAFF AND SUBCONTRACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED.
- WC4. ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT
- WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS. WC5. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS.






INSTALLATION


- I. EXCAVATE A TRENCH 200mm DEEP. 2. DRIVE POSTS 500-700mm INTO GROUND AT A MAXIMUM
- SPACING OF 3.0m CENTRES.
- 3. PLACE AND FIX SUPPORT MESH (F52) TO POST. 4. LAY BIDIM GEOFABRIC (SF 2000) AGAINST THE SUPPORT
- MESH AND FIX BY TIE WIRE, STAPLES OR HOG RINGS. 5. PLACE BIDIM IN TRENCH AND BACKFILL WITH SOIL.

POSITION OF SEDIMENT FENCE AS DIRECTED BY

SUPERINTENDENT. FENCE TO REMAIN IN PLACE UNTIL

EXCAVATION IS BELOW FOOTPATH LEVEL.





lobert Bird Group Pty Ltd O Box A2309

Sydney South, NSW 1235


ydney NSW 2000


Fax: (02) 8246 3201

ACN 010 580 248

Email: svdnev@robertbird.com.au

Web: www.robertbird.com





DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE

AS SHOWN EROSION AND SEDIMENT CONTROL **DETAILS** 30.11.18

2B-6 HASSALL STREET PARRAMATTA

S.MANANDHAR Designer Z.JONES

Design Checker


C.ROPE

Approved

C.ROPE

Job Number

18570C **NOT FOR CONSTRUCTION** Drawing Number C-1-10



EARTHWORKS ANALYSIS

THIS PLAN DENOTES THE PROPOSED DEPTH OF BULK EARTHWORKS:

GROSS CUT VOLUME 15,750m³
GROSS FILL VOLUME 0m³
NET VOLUME 15,750m³ (CUT)

SOIL ESTIMATION;

GENERAL SOLID WASTE (GWS) - 1100m³

EXCAVATED NATURAL MATERIAL (ENM)/VIRGIN EXCAVATED NATURAL MATERIAL

 $-14,650 \text{m}^3$

CUT & FILL ANALYSIS ASSUMPTIONS:


- ANALYSIS HAS NOT INCORPORATED

STRUCTURAL FOOTINGS, CONSTRUCTION


ACCESS RAMPS, BASEMENT SERVICE


TRENCHES OR TREES.

- 1:1 TEMPORARY BATTERS HAVE BEEN ALLOWED. FOR SAFE WORKING BATTERS REFER TO GEOTECHNICAL REPORT 86415.03.R.001.Rev0.GEOTECH.
- SHORING ASSUMED TO BE VERTICAL.
 EXISTING LEVELS BASED ON SURVEY
- DATA "6083-DET-2", DATE OF SURVEY 10/01/2019.
- EARTHWORKS ANALYSIS DOES NOT INCLUDE MATERIAL BULKING VALUES THROUGH EXCAVATION.
- BULK EARTHWORKS CALCULATED TO THE UNDERSIDE OF THE RAFT SLAB . NO PAD FOOTINGS OR PILES HAVE BEEN ALLOWED.
- BUILDING LEVELS BASED ON SECTION DRAWING "2B-6 HASSAL STREET PARRAMATTA SCHEMATIC DESIGN DEC 2018, EAST-WEST SECTION.
- VOLUME OF SOIL MATERIAL IS AN ESTIMATION ONLY. THE CALCULATIONS ARE BASED ON THE GEOTECHNICAL REPORT, 86415.03.R.001.Rev0.GEOTECH



Surface Analysis: Elevation Ranges				
Number	Color	Minimum Elevation (m)	Maximum Elevation (m)	
1		-10.700	-10.000	
2		-10.000	-9.500	
3		-9.500	-9.000	
4		-9.000	-8.500	
5		-8.500	-8.000	
6		-8.000	-7.500	
7		-7.500	-7.000	
8		-7.000	-6.500	
9		-6.500	-6.200	
10		-6.200	-5.900	
11		-5.900	-5.600	
12		-5.600	-5.300	
13		-5.300	-5.000	
14		-5.000	-4.700	
15		-4.700	-4.400	
16		-4.400	-4.100	
17		-4.100	0.100	







SECTION B - LONG SECTION


		· — — — — — — — — — — — — — — — — — — —		
	BASEMENT CAR PARK	RAFT SLAB EXCAVATION		BASEMENT CAR PARK
VERT EXAG 1:1 Datum 1.000		HIGH RISE LIFTS OVERUN		
DESIGN LEVELS 99	5.350	1.600	5.350	009:9
EXISTING LEVELS 52.	12.257	11.999	11.627	-4.709 11.309 6.600 -4.688 11.288 6.600
DEPTH 656.5-	-6.907		-6.277	602.7-
CHAINAGE 88	10.000	20.000	30.000	40.000

SECTION A - LONG SECTION

~	- — — — — — — — — — —	BASEMENT CAR PARK			RAFT SLAB
VERT EXAG 1:1 Datum 1.000					HIGH RISE LIFT OVERRUN
DESIGN LEVELS §	009.9	0099	009.9	009.9	4.213
EXISTING LEVELS 20.	12.668	12.500	12.472	12.250	11.996
DEPTH 124.9-	-6.068	-5.900	-5.872	-5.650	-7.783
CHAINAGE 00	0000	0000	0.000	0.000	0.000











SCALE 1:10

REFER C-3-00 FOR PAVEMENT LAYOUT PLAN. ASSUMED SUBGRADE CBR 3% TO BE VERIFIED ON SITE BY INSITU SUBGRADE TESTING, IN ACCORDANCE WITH AS1209.6. TEST INTERVAL TO BE 1 TEST PER 400m².




TRAFFICABLE PAVED FOOTPATH - PV02 (PAVED VEHICULAR CROSSING) TYPICAL DETAILS SCALE 1:10




TYPICAL FOOTPATH JOINTING

1. EJ'S TO ALIGN WITH ADJOINING BAYS 2. JOINT SPACING AROUND CURVES IS TO BE TAKEN TO THE OUTSIDE LENGTH





FOOTPATH TOOLED/SAWN JOINT (F.T.J.) SCALE 1:10

Rev Revision Description




FOOTPATH EXPANSION JOINT (F.E.J.) SCALE 1:10





DOWELLED EXPANSION JOINT (DEJ) DETAIL
SCALE 1:10




MOVEMENT JOINT SEALANT DETAILS (FOR DCJ, EJ, DEJ, KJ & DDJ JOINTS) SCALE 1:10

STEPS:

1. FORM REBATE IN SLAB 2 AGAINST FACE OF SLAB 1.

- 2. AFTER SLAB CURING PERIOD (MIN. 28 DAYS) WASH OUT REBATE USING HIGH PRESSURE WATER. DRY USING HIGH PRESSURE COMPRESSED AIR AND ALLOW ADDITIONAL 16HRS TO DRY THOROUGHLY.
- 3. INSTALL POLYETHYLENE BOND BREAKER TAPE FOR FULL WIDTH 'W'. FOR IJ, EJ AND DEJ JOINTS OMIT BOND BREAKER TAPE.
- 4. PRIME FACES OF SIDES OF REBATE (REFER SEALANT TABLE)
- 5. INSTALL SEALANT AS SPECIFIED (REFER SEALANT TABLE) IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

DOWEL / TIE BAR TABLE				
JOINT DESIGNATION	DOWEL / TIE	SPACING CTR-CTR	LENGTH 'L'	
DEJ	10x110 DANLEY DIAMOND	450	155	



SAWN JOINT CUT AND SEALANT DETAILS SCALE 1:10

INITIAL CUT TO DEPTH 'T'/4 ('T'/3 FOR STEEL FIBRE REINFORCED CONCRETE) WITHIN 1 DAY OF POURING CONCRETE. INSERT POLYURETHANE BACKING ROD TO PREVENT INGRESS OF DIRT UNTIL SEALANT APPLIED (MIN 28 DAYS LATER). ROD DIAMETER TO BE MIN. 1.25 x CUT WIDTH.

STEP 2: REMOVE ALL DIRT FROM SAW CUT, USING HIGH PRESSURE COMPRESSED AIR. REPLACE BACKING ROD WITH LARGER DIAMETER IF LOOSE. PUSH BACKING ROD INTO SAW CUT 1mm BELOW DEPTH 'D'. IF NECESSARY, REMOVE AND REPLACE BACKING ROD. WIDEN SAW CUT TO WIDTH 'W' AND DEPTH 'D' WITH ADDITIONAL SAW CUT/CUTS.

REMOVE ALL FOREIGN MATERIAL USING HIGH PRESSURE WATER WASH. DRY USING HIGH PRESSURE COMPRESSED AIR AND ALLOW ADDITIONAL 16 HRS TO DRY THOROUGHLY. INSTALL POLYETHYLENE BOND BREAKER TAPE.

PRIME FACES OF CUT CONCRETE (REFER TABLE BELOW) INSTALL SEALANT AS SPECIFIED (REFER TABLE BELOW) IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.


LOCATION	SEALANT	PRIMER
EXTERNAL PAVEMENTS	EMER-ROAD SEAL SL	FOSROC PRIMER 10

ALTERNATIVE SEALANTS MUST HAVE

- MOVEMENT ACCOMMODATION FACTOR +/- 50%
- PRIMER TO MANUFACTURER'S SPECIFICATION INSTALLATION TO MANUFACTURER'S RECOMMENDATIONS
- PRIOR APPROVAL BY SUPERINTENDENT.

SEAL	ANT DIMENS	DIMENSIONS		
MEAN SLAB LENGTH (m)	SEALANT WIDTH 'W' (mm)	SEALANT DEPTH 'D' (mm)		
≤4	7 ± 1	7 ± 1		
5	9 ± 2	7 ± 1		
6	9 ± 2	7 ± 1		
7	10 ± 2	8 ± 1		
8	11 ± 2	9 ± 2		
9	12 ± 2	10 ± 2		
10	13 ± 2	10 ± 2		
11	14 ± 2	11 ± 2		
12	15 ± 2	12 ± 2		
ALL (TSJ)	6	6		
ALL (IJ & EJ)	10	8		

1. FOR T.S.J. ONLY, CLEAN, PRIME AND SEAL INITIAL SAW CUT ONLY.



EXPANSION JOINT AND ISOLATION JOINT SEALANT DETAIL

- 1. CLOSED CELL POLYURETHANE FILLER (FULL DEPTH)
- CUT HOLES IN FILLER TO FIT CLOSELY AROUND DOWELS 2. FORM GROOVE IN SLAB 2 AND AGAINST FACE OF SLAB 1
- 3. JET WASH AND DRY GROOVE AFTER SLAB CURING PERIOD
- PRIME FACES WITH FOSROC PRIMER 10
- 4. BOND BREAKER TAPE
- 5. INSTALL JOINT SEALANT PARBURY EMER-ROADSEAL OR APPROVED EQUIVALENT WITH MOVEMENT ACCOMMODATION FACTOR +/-50% IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS

JOINT	DOWEL / TIE	SPACING	LENGTH
DESIGNATION		CTR-CTR	'L'
DEJ	10x110 DANLEY DIAMOND	450	155

By App Date

Disclaimer: Robert Bird Group Pty Ltd ACN 010 580 248 and its related entities (RBG) do not warrant the accuracy, currency or completeness of any information or data they supply or transferred by electronic means. You are responsible for verifying that any information or data supplied or transferred by electronic means matches the information or data on the corresponding PDF or DWF version issued by RBG. RBG will not be liable for any loss or damage you or any other party incurs as a result of acting in reliance.

Structural, Civil & Construction Engineering Consultant By App Date | Rev Revision Description ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 04.03.19 RobertBirdGroup Charter 2 ISSUED FOR DEVELOPMENT APPLICATION ZJ CR 03.04.19 on any information or data supplied or transferred by electronic means and you release RBG from any liability for any loss or damage however caused which you or any other party may directly or indirectly suffer in connection with your access to or use of that information or data. RBG provides this information for the express purpose contemplated by the underlying terms of engagement for the project which must not be used for any other purpose. The information is not a controctual document. Unless otherwise agreed in writing by RBG, all intellectual property rights in any information supplied by RBG are owned by, or licensed to, RBG. RBG only provides you with a non-transferable, fully revocable licence to use the intellectual property rights for the express SYDNEY OFFICE Robert Bird Group Pty Ltd PO Box A2309 Fax: (02) 8246 3201 Sydney South, NSW 1235 Email: sydney@robertbird.com.au

DO NOT SCALE DRAWINGS, USE FIGURED DIMENSIONS

REFER TO GENERAL NOTES UNLESS NOTED OTHERWISE



Web: www.robertbird.com

ACN 010 580 248

ydney NSW 2000

PAVEMENT DETAILS	Scale at A1 AS SHOWN Date 03.04.19	Drawn S.MANANDHAR Designer Z.JONES	Design Checker Approved C.ROPE Job Number 18570C
2B-6 HASSALL STREET PARRAMATTA	NOT F Drawing Number C-4-10	OR CONSTRU	Revision

