


LEGEND				
FT-01	PODIUM GLAZING	CUSTOM VERTICAL ALUMINIUM MULLIONS FROM GROUND TO LEVEL 03. FULL HEIGHT LAMINATED GLASS WITH BLACK HORIZONTAL SILICONE BUTT JOINTS. COLOURLESS LOW IRON GLASS. XIR FILM FOR GLAZING PERFORMANCE TO NORTH FACADE.		
FT-02	TOWER CURTAIN WALL	FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL GLAZING, STRUCTURAL GLAZED IGU WITH BLACK SPACERS AND BLACK SILICON BUTT JOINT. VLT: 45-50% REFLECTIVITY: 20% MAX SHGC: 0.20 MIN BACKPAN: CERAMIC FRIT BACK PAN (FT03A TO SPANDREL ONLY) MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL		
FT-03	PLANT ROOMS CURTAIN WALL	FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL WITH RIGID MESH PANELS FIXED TO BACK OF MULLIONS. MULLIONS TO BE EXPOSED. MESH PERFORATION SIZE TBC, SUBJECT TO FINAL ENGINEERING DESIGN DEVELOPMENT MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL		
FT-03A	SPANDREL PANEL CURTAIN WALL	FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL GLAZING, STRUCTURAL GLAZED IGU WITH BLACK SPACERS AND BLACK SILICON BUTT JOINT. VLT: 45-50% REFLECTIVITY: 20% MAX SHGC: 0.20 MIN BACKPAN: FULL HEIGHT CERAMIC FRIT BACK PAN MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL		
FT-04	CONCRETE WALL SYSTEM	PRECAST CONCRETE PANELS AND/OR OFF FORM CONCRETE COLOUR: NEUTRAL GREY AGGREGATE: 'HOLCIM GEOSTONE' REBATES SHOWN ARE INDICATIVE ONLY		
FT-05	FRAMELESS GLASS BALUSTRADE	LOW IRON CLEAR MONOLITHIC FRAMELESS GLASS BALUSTRADE. GENERALLY 1200MM WIDE WITH 20MM CLEAR VERTICLE GAP BETWEEN GLASS PANELS WITH CONTINUOUS STAINLESS STEEL TOP CHANNEL.		
MW-01	CURTAIN WALL HORIZONTAL SUNSHADE (NORTH FACADE)	ALUMINIUM SLEEVE FINS AT STACK JOINTS. FINS TO BE SOLID EXTRUSION TO CUSTOM SHAPE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.		
MW-02	CURTAIN WALL RECESS (TOWER)	CURTAIN WALL HORIZONTAL RECESS AT SLAB EDGE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.		
MW-03	CURTAIN WALL VERTICAL SUNSHADE (WEST FACADE)	ALUMINIUM SLEEVE FINS AT STACK JOINTS. FINS TO BE SOLID EXTRUSION TO CUSTOM SHAPE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.		



Rev	Description	Consultant	Date	Issued by
K	Issue for Jury Review	BRT	31.07.19	MD
L	RtS Submission	BRT	09.08.19	MD
M	Mod2 Submission	BRT	24.03.19	JM
N	Mod3 Submission	BRT	24.06.20	MD



**Tzannes + BlightRayner**  
Suite 5, 15, 2-12 Foveaux St Level 2, 88 Creek St  
Surry Hills, NSW, 2010 Brisbane, Qld, 4000  
Sydney, Australia W: blightrayner.com.au  
T: 61 7 3905 6500 E: info@blightrayner.com.au  
E: tzannes@tzannes.com.au


Project Name  
**Hassall Street**  
Project Address  
**2-6 Hassall Street Parramatta NSW 2150**

Sheet Name  
**SOUTH ELEVATION**

©BLIGHT RAYNER ARCHITECTURE PTY LTD ACN 614335956  
Use figured dimensions only. Do not scale. Check all dimensions on site prior to fabrication or setout. These designs, drawings and specifications are copyright and must not be used, kept or copied by any means without permission.

Project No.  
**18032**  
Drawing No.  
**30.02**  
Revision  
**N**  
Date  
**24.06.20**  
Drawn by  
**TW**  
Checked by  
**MSK**

SCALE @A3  
As indicated  
0 4 12



LEGEND	
FT-01	<b>PODIUM GLAZING</b> CUSTOM VERTICAL ALUMINIUM MULLIONS FROM GROUND TO LEVEL 03. FULL HEIGHT LAMINATED GLASS WITH BLACK HORIZONTAL SILICONE BUTT JOINTS. COLOURLESS LOW IRON GLASS. XIR FILM FOR GLAZING PERFORMANCE TO NORTH FACADE.
FT-02	<b>TOWER CURTAIN WALL</b> FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL GLAZING, STRUCTURAL GLAZED IGU WITH BLACK SPACERS AND BLACK SILICON BUTT JOINT. VLT: 45-50% REFLECTIVITY: 20% MAX SHGC: 0.20 MIN BACKPAN: CERAMIC FRIT BACK PAN (FT03A TO SPANDREL ONLY) MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL
FT-03	<b>PLANT ROOMS CURTAIN WALL</b> FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL WITH RIGID MESH PANELS FIXED TO BACK OF MULLIONS. MULLIONS TO BE EXPOSED. MESH PERFORATION SIZE TBC, SUBJECT TO FINAL ENGINEERING DESIGN DEVELOPMENT MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL
FT-03A	<b>SPANDREL PANEL CURTAIN WALL</b> FULL HEIGHT ALUMINIUM FRAMED UNITIZED CURTAIN WALL GLAZING, STRUCTURAL GLAZED IGU WITH BLACK SPACERS AND BLACK SILICON BUTT JOINT. VLT: 45-50% REFLECTIVITY: 20% MAX SHGC: 0.20 MIN BACKPAN: FULL HEIGHT CERAMIC FRIT BACK PAN MULLION COLOUR: ANODISED ALUMINIUM - CHARCOAL
FT-04	<b>CONCRETE WALL SYSTEM</b> PRECAST CONCRETE PANELS AND/OR OFF FORM CONCRETE COLOUR: NEUTRAL GREY AGGREGATE: 'HOLCIM GEOSTONE' REBATES SHOWN ARE INDICATIVE ONLY
FT-05	<b>FRAMELESS GLASS BALUSTRADE</b> LOW IRON CLEAR MONOLITHIC FRAMELESS GLASS BALUSTRADE. GENERALLY 1200MM WIDE WITH 20MM CLEAR VERTICLE GAP BETWEEN GLASS PANELS WITH CONTINUOUS STAINLESS STEEL TOP CHANNEL.
MW-01	<b>CURTAIN WALL HORIZONTAL SUNSHADE (NORTH FACADE)</b> ALUMINIUM SLEEVE FINS AT STACK JOINTS. FINS TO BE SOLID EXTRUSION TO CUSTOM SHAPE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.
MW-02	<b>CURTAIN WALL RECESS (TOWER)</b> CURTAIN WALL HORIZONTAL RECESS AT SLAB EDGE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.
MW-03	<b>CURTAIN WALL VERTICAL SUNSHADE (WEST FACADE)</b> ALUMINIUM SLEEVE FINS AT STACK JOINTS. FINS TO BE SOLID EXTRUSION TO CUSTOM SHAPE. RECESSED ALUMINIUM CHANNEL INTEGRATED WITHIN CURTAIN WALL.

Rev	Description	Consultant	Date	Issued by
K	Issue for Jury Review	BRT	31.07.19	MD
L	RtS Submission	BRT	09.08.19	MD
M	Mod2 Submission	BRT	24.03.19	JM
N	Mod3 Submission	BRT	24.06.20	MD