



M1 Pacific Motorway extension to Raymond Terrace

Environmental impact statement

Transport for NSW | July 2021





M1 Pacific Motorway extension to Raymond Terrace

Environmental impact statement

Transport for NSW | July 2021

Prepared by Transport for NSW Publication No.: 21.171

ISBN: 978-1-922549-14-3

Contents

Exe	cutive	summary		E-1
1.	Intro	duction		1-1
	1.1		posed project	
	1.2		ocation	
	1.3	,	e of this environmental impact statement	
2.			rocess	
	2.1	•	l framework	
		2.1.1	Environmental Planning and Assessment Act 1979	
	2.2		gislationgaining and Assessment Act 1975	
		2.2.1	NSW legislation	
		2.2.2	Commonwealth legislation	
3.	Strat	eaic iustif	ication and project need	
	3.1		d Australian strategic planning and policy framework	
	3.1	3.1.1	NSW State Infrastructure Strategy 2018-2038	
		3.1.2	Future Transport Strategy 2056	
		3.1.3	NSW Freight and Ports Plan 2018-2023	
		3.1.4	Road Safety Plan 2021	
		3.1.5	Regional NSW Services and Infrastructure Plan	
		3.1.6	Australian Infrastructure Plan and Priority List	
		3.1.7	National Freight and Supply Chain Strategy	
		3.1.8	National Road Safety Strategy 2011-2020	
		3.1.9	Lower Hunter Regional Strategy 2006-2031	
		3.1.10	Hunter Regional Plan 2036	3-5
		3.1.11	Hunter Regional Transport Plan	3-6
		3.1.12	Greater Newcastle Future Transport Plan	3-6
		3.1.13	City of Newcastle Local Strategic Planning Statement	3-7
		3.1.14	Raymond Terrace and Heatherbrae Strategy 2015-2031	
	3.2	Project r	need	
		3.2.1	Overview	3-7
		3.2.2	National context	
		3.2.3	Pacific Highway upgrade program	
		3.2.4	Existing road network conditions and performance	
		3.2.5	Network freight efficiency and capacity	
		3.2.6	Road safety	
		3.2.7	Future growth	
		3.2.8	Flooding	
	3.3	•	objectives	
	3.4		nt of strategic need	
4.			pment and alternatives	
	4.1		ves	
		4.1.1	Alternative 1: Do nothing (base case)	
		4.1.2	Alternative 2: Do minimum	
		4.1.3	Alternative 3: Rail as an alternative mode of transport and freight	
		4.1.4	Alternative 4: Establishing a primary route to the west	
		4.1.5	Alternative 5: M1 Pacific Motorway extension to Raymond Terrace (the project	-
	4.5	4.1.6	Performance of alternatives against project objectives	
	4.2	Koute of	otions development	4-/

		4.2.1 4.2.2	Route options assessment and identification of preferred option	
	4.3	***	review: alignments	4-11
		4.3.1	Alignment options	4-11
		4.3.2	Alignment 0 – 2010 Preferred Route	4-11
		4.3.3	Alignment 1	4-13
		4.3.4	Alignment 2	4-13
		4.3.5	Evaluation of alignment options	
		4.3.6	Preferred alignment	
	4.4	The pre	eferred option – 2016 concept design	4-19
	4.5	Design	refinements	4-22
		4.5.1	Minimising and avoiding environmental impacts	4-25
	4.6	The pro	pject	4-26
5.	Proie	ect descri	iption	5-1
٥.	-		scope	
	5.1	•	·	
		5.1.1	The project	
	5.2	•	criteria	
		5.2.1	Design standards	
		5.2.2	Urban design objectives and principles	
		5.2.3	Detailed design requirements	
	5.3		mpleted project	
		5.3.1	Operational footprint	
		5.3.2	Main alignment	
		5.3.3	Interchanges, intersections and local road changes	
		5.3.4	New England Highway	
		5.3.5	Bridge structures and viaducts	
		5.3.6	Road cuttings, fill embankments and retaining walls	
		5.3.7	Pavement	
		5.3.8	Drainage infrastructure	
		5.3.9	Water quality management	
		5.3.10	Waterway adjustments	
		5.3.11	Roadside furniture, fencing and lighting	
		5.3.12	Fauna connectivity	
		5.3.13	Emergency service access and traffic management features	
		5.3.14	Noise barriers	
		5.3.15	Utility services	
		5.3.16	Walking and cycling	
		5.3.17	Public transport	
		5.3.18	Oversize overmass vehicles	
		5.3.19	Property acquisition	
		5.3.20	Property access	
	5.4		uction work	
		5.4.1	Construction footprint	
		5.4.2	Overview of construction activities	
		5.4.3	Construction ancillary facilities	
		5.4.4	Plant and equipment	
		5.4.5	Construction resources	
		5.4.6	Bridge work	
		5.4.7	Demolition	
		5.4.8	Waterway adjustments	
		5.4.9	Temporary creek crossings	5-84

		5.4.10	Drainage infrastructure	
		5.4.11	Water quality management	
		5.4.12	Traffic management, transport and access	
		5.4.13	Workforce and construction work hours	
		5.4.14	Construction program and components	
		5.4.15	Project staging	
6.	Cons			
	6.1		ation objectives and strategy	
	6.2	Consult	ation process	6-3
		6.2.1	Consultation overview and background	
		6.2.2	Stakeholders	
		6.2.3	Guidelines, engagement and consultation tools	
		6.2.4	Aboriginal cultural heritage consultation	
		6.2.5	Consultation carried out during route selection	
		6.2.6	Consultation carried out during concept design and environmental assessment	
	6.3	Summa	ry of issues raised during concept design and environmental assessment	6-15
		6.3.1	Summary of key issues raised	6-15
		6.3.2	Issues raised by public authorities and emergency services	
		6.3.3	Issues raised by the community	
		6.3.4	Issues raised by the Aboriginal community	
	6.4	Future	consultation	
		6.4.1	Consultation during public display of the EIS	6-37
		6.4.2	Consultation during construction stages	6-38
7.	Traff	ic and tra	ınsport	7-1
	7.1		and planning setting	
	7.2	-	ment methodology	
	1.2	7.2.1	Overview	
		7.2.2	Study area	
		7.2.3	Traffic model development	
		7.2.4	Sensitivity modelling	
		7.2.5	Assessment criteria	
	7.3		g environment	
	7.0	7.3.1	Road network	
		7.3.2	Land use	
		7.3.3	Existing road performance	
		7.3.4	Road safety and crash history	
		7.3.5	Public transport	
		7.3.6	Freight	
		7.3.7	Walking and cycling	
		7.3.8	Maritime traffic	
		7.3.9	Traffic growth and future land use	
	7.4	Assessi	ment of potential construction impacts	
		7.4.1	Construction traffic	
		7.4.2	Impact on property access	
		7.4.3	Other transport modes	
	7.5		ment of potential operation impacts	
	.	7.5.1	Road network performance	
		7.5.2	Travel time performance	
		7.5.3	Network statistics	
		7.5.4	Intersection performance	
			1	

		7.5.5 7.5.6	Interchange analysisFreight	
		7.5.7	Regional and local community connectivity	
		7.5.8	Road safety	
		7.5.9	Other transport modes	7-43
	7.6	Cumula	ative impacts	7-45
	7.7	Environ	nmental management measures	7-48
8.	Nois	e and vib	oration	8-1
	8.1		and planning setting	
	8.2	•	ment methodology	
	0.2	8.2.1	Study areas and noise catchment areas	
		8.2.2	Noise monitoring	
		8.2.3	Construction noise and vibration assessment methodology	
		8.2.4	Operational noise and vibration assessment methodology	
	8.3	Existing	g environment	
		8.3.1	Noise sensitive receivers and noise catchment areas	8-21
		8.3.2	Existing noise levels	8-25
	8.4	Assess	ment of potential construction impacts	8-27
		8.4.1	Noise management levels	8-27
		8.4.2	Predicted worst-case noise impacts	
		8.4.3	Construction airborne noise impacts	8-30
		8.4.4	Construction ground-borne noise	8-49
		8.4.5	Construction road traffic noise	
		8.4.6	Construction vibration impacts	
		8.4.7	Construction blasting noise and vibration	
	8.5		ment of potential operational impacts	
		8.5.1	Operational road traffic noise predictions – impacts without mitigation	
		8.5.2	Operational road traffic noise predictions – impacts with mitigation	
		8.5.3	Maximum noise level assessment	
	8.6	Environ	nmental management measures	8-65
9.	Biod	iversity		9-1
	9.1	Policy a	and planning setting	9-3
	9.2	Assess	ment methodology	9-4
		9.2.1	Study area	9-4
		9.2.2	Desktop assessment	
		9.2.3	Field surveys	9-7
		9.2.4	Key fish habitat	9-16
		9.2.5	Biodiversity offsets	9-16
	9.3	Existing	g environment	9-16
		9.3.1	Landscape features and values	9-16
		9.3.2	Native vegetation	
		9.3.3	Threatened ecological communities	
		9.3.4	Groundwater dependent ecosystems	
		9.3.5	Threatened species	
		9.3.6	Aquatic habitat	
		9.3.7	Matters of national environmental significance	
	0.1	9.3.8	Weeds, pests and pathogens	
	9.4		ment of potential impacts	
		9.4.1	Avoidance and minimisation of impacts	
		9.4.2	Assessment of potential construction impacts	9-50

		9.4.3	Assessment of potential operational impacts	
	9.5	Environi	mental management measures	
		9.5.1	Habitat connectivity measures	9-87
	9.6	Offsettir	ng requirements	9-87
		9.6.1	Biodiversity offsets	9-87
		9.6.2	Offsets for impacts to aquatic habitats	9-89
10.	Hydro	ology and	d flooding	10-1
	10.1		and planning setting	
	10.2	•	ment methodology	
		10.2.1	Study areas	
		10.2.1	Groundwater survey	
		10.2.3	Flood design criteria and objectives	
		10.2.4	Technical modelling assessment	
		10.2.5	Climate change assessment	
	10.3		environment	
		10.3.1	Catchment overview	
		10.3.2	Sensitive receiving environments	
		10.3.3	Surface water hydrology	
		10.3.4	Groundwater hydrology	
		10.3.5	Flooding	10-24
		Impact a	avoidance	10-38
	10.4	Assessr	ment of potential construction impacts	10-38
		10.5.1	Surface water hydrology	10-38
		10.5.2	Groundwater hydrology	
		10.5.3	Flooding	
		10.5.4	Sensitive receiving environments	10-69
		10.5.5	Site water balance	10-70
		10.5.6	Summary of construction impacts	10-71
	10.5	Assessr	ment of potential operational impacts	10-73
		10.6.1	Surface water hydrology	10-73
		10.6.2	Groundwater hydrology	10-78
		10.6.3	Flooding	
		10.6.4	Sensitive receiving environments	
		10.6.5	Site water balance	
		10.6.6	Summary of operational impacts	
	10.6	Environi	mental management measures	10-109
11.	Surfa		and groundwater quality	
	11.1	Policy a	and planning setting	11-3
	11.2	Assessr	ment methodology	11-3
		11.2.1	Study areas	11-4
		11.2.2	Identification of sensitive receiving environments	11-4
		11.2.3	Site investigations and monitoring	11-5
		11.2.4	Identification of water quality criteria	11-6
		11.2.5	Data analysis	11-11
		11.2.6	Impact assessment methodology	
	11.3	Existing	environment	
		11.3.1	Existing surface water quality	
		11.3.2	Existing groundwater quality	
		11.3.3	Sensitive receiving environments	
	11.4	Impact a	assessment	11-23

		11.4.1 11.4.2	Impacts avoided and minimised Construction impacts	11-23
	11 5	11.4.3	Operational impacts	
	11.5		mental management measures	
		11.5.1	Water quality monitoring program	11-63
12.	Abori	iginal cul	tural heritage	12-1
	12.1		and planning setting	
	12.2	-	ment methodology	
		12.2.1	Overview	
		12.2.2	PACHCI and consultation	
		12.2.3	Study area	
		12.2.4	Review of previous archaeological work	
		12.2.5	Desktop assessment and predictive modelling	
		12.2.6	Archaeological survey	12-1
		12.2.7	Archaeological test excavation	12-2
		12.2.8	Aboriginal cultural values	12-3
		12.2.9	Significance assessment	
		12.2.10		
	12.3	Aborigin	nal community consultation	12-4
	12.4	Existing	environment	12-5
		12.4.1	Landscape context	
		12.4.2	Historical Aboriginal land use	12-6
		12.4.3	Identified sites	12-6
		12.4.4	Areas of cultural significance	
		12.4.5	Significance assessment summary	
	12.5		ment of potential impacts	
		12.5.1	Construction	
		12.5.2	Operation	
	12.6	Environ	mental management measures	12-25
13.	Socio	o-econom	nic	13-1
	13.1	Policv a	and planning setting	13-2
	13.2		ment methodology	
		13.2.1	Study area	
		13.2.1	Data sources	
		13.2.3	Local business surveys	
		13.2.4	Community and stakeholder consultation	
		13.2.5	Evaluation of significance	
	13.3	Existing	environment	
		13.3.1	Regional context	
		13.3.2	Community profile	
		13.3.3	Economic profile	
		13.3.4	Local business and industry	
		13.3.5	Community values	
		13.3.6	Social infrastructure	
		13.3.7	Access and connectivity	13-20
	13.4	Assessr	ment of potential impacts	13-24
		13.4.1	Construction impacts	13-24
		13.4.2	Operational impacts	13-31
		13.4.3	Evaluation of significance	
	13.5	Environ	mental management measures	13-40

14.	Land	use and	property	14-1
	14.1	Policy a	and planning setting	14-2
	14.2	Assessr	ment methodology	14-3
		14.2.1	Study area	
		14.2.2	Data sources	
	14.3	Existing	genvironment	14-5
		14.3.1	Regional land use	14-5
		14.3.2	Property	
		14.3.3	Existing land use	
		14.3.4	Land use zoning	14-11
		14.3.5	Mining	
		14.3.6	Utilities	
		14.3.7	Water users	
		14.3.8	Future land use	
	14.4	Assessr	ment of potential impacts	
		14.4.1	Property	
		14.4.2	Existing land use	
		14.4.3	Land use zoning	
		14.4.4	Mining	
		14.4.5	Utilities	
		14.4.6	Water users	
		14.4.7	Future land use	
		14.4.8	Evaluation of potential land use risk conflicts	
	14.5		mental management measures	
15.	Urbar		landscape and visual amenity	
	15.1	Policy a	and planning setting	15-2
	15.2	Assessr	ment methodology	15-3
		15.2.1	Study area	15-3
		15.2.2	Landscape character assessment	15-4
		15.2.3	Visual impact assessment	15-5
		15.2.4	Mitigation strategy	15-6
	15.3	Urban d	design and landscape strategy	15-6
		15.3.1	Urban design vision	15-6
		15.3.2	Urban design objectives and principles	15-6
		15.3.3	Urban design strategy	
		15.3.4	Urban design and landscape concept	
	15.4	Existing	genvironment	15-19
		15.4.1	Landscape character	
		15.4.2	Existing views	
	15.5	Assessr	ment of potential impacts	15-30
		15.5.1	Construction	15-30
		15.5.2	Operation	
	15.6	Environ	mental management measures	15-49
16.	Soils	and cont	tamination	16-1
	16.1	Policy a	and planning setting	16-2
	16.2	Assessr	ment methodology	16-3
		16.2.1	Desktop assessment	16-4
		16.2.2	Site inspections	16-6
		16.2.3	Identification of areas of potential contamination risk	16-6

	16.3	Existing	g environment	16-7
		16.3.1	Topography, geology and soil landscapes	16-7
		16.3.2	Acid sulfate soils and acid rock	
		16.3.3	Contamination	16-17
		16.3.4	Soil salinity	
		16.3.5	Sensitive receiving environments	
		16.3.6	Areas of potential contamination risk	
	16.4	Assessi	ment of potential impacts	
		16.4.1	Construction impacts	
		16.4.2	Operational impacts	
	16.5		mental management measures	
17.	Non-		al heritage	
	17.1	Policy a	and planning setting	17-3
	17.2	Assessi	ment methodology	17-4
		17.2.1	Assessment approach	17-4
		17.2.2	Study area	
		17.2.3	Site investigations	17-5
		17.2.4	Assessment of significance and impact assessment	17-5
	17.3	Existing	g environmentg	17-6
		17.3.1	Historical context	17-6
		17.3.2	Heritage context	17-7
		17.3.3	Field survey results	17-8
		17.3.4	Assessments of significance	17-16
	17.4	Impact	assessment	17-18
		17.4.1	Alternatives and design options considered	17-18
		17.4.2	Assessment of potential impacts	
	17.5	Environ	mental management measures	17-25
18.	Air qu	uality		18-1
	18.1	Policy a	and planning setting	18-2
	18.2	Assessi	ment methodology	18-3
		18.2.1	Air quality data review	18-3
		18.2.2	Meteorological modelling	
		18.2.3	Construction assessment methodology	18-3
		18.2.4	Operational assessment methodology	18-6
	18.3	Existing	g environment	18-8
		18.3.1	Sensitive receivers	18-8
		18.3.2	Existing air quality conditions	18-10
		18.3.3	Meteorological conditions	18-12
	18.4	Assessi	ment of potential impacts	18-14
		18.4.1	Air quality impacts	18-14
		18.4.2	Construction impacts	18-15
		18.4.3	Operational impacts	
	18.5	Environ	mental management measures	18-41
19.	Wast	e		19-1
	19.1	Policy a	and planning setting	19-2
	19.2	Assessi	ment methodology	19-2
	19.3	Existing	g environment	19-3
	19.4	_	ment of potential impacts	
		19.4.1	Resource use	

		19.4.2	Construction waste		
	10 E	19.4.3	Operational waste		
	19.5		mental management measures		
20.	Sustainability				
	20.1	Policy a	nd planning setting	20-1	
	20.2	Assessment methodology			
	20.3	Assessr	nent of the project	20-2	
	20.4	Environi	mental management measures	20-11	
21.	Clima	ite chang	e risk	21-1	
	21.1	Policy and planning setting			
	21.2	Assessr	ment methodology	21-2	
		21.2.1	Climate change risk assessment	21-2	
		21.2.2	Greenhouse gas assessment	21-4	
	21.3	Existing	environment	21-8	
	21.4	Assessr	ment of potential impacts	21-9	
		21.4.1	Climate change projections	21-9	
		21.4.2	Construction impacts		
		21.4.3	Operational impacts		
	21.5	Environi	mental management measures	21-17	
22.	Safet	y and risl	K	22-1	
	22.1	Policy a	nd planning setting	22-1	
	22.2	Assessr	ment methodology	22-2	
		22.2.1	Public safety risks	22-2	
		22.2.2	Road, pedestrian and cyclist safety	22-2	
		22.2.3	Bushfire risk		
		22.2.4	Flood evacuation risks		
		22.2.5	Storage, handling and use of dangerous goods and hazardous material		
		22.2.6	Contamination hazards		
		22.2.7	Subsidence risk		
	22.2	22.2.8 Existing	Biosecurity risk		
	22.3	22.3.1	environment		
		22.3.1	Public safety risks Road, pedestrian and cyclist safety		
		22.3.2	Bushfire risks		
		22.3.4	Flood evacuation risks		
		22.3.5	Storage, handling and use of dangerous goods and hazardous material		
		22.3.6	Contamination hazards		
		22.3.7	Subsidence risk	22-8	
		22.3.8	Biosecurity risk	22-9	
	22.4	Assessr	ment of potential impacts	22-9	
		22.4.1	Construction impacts	22-9	
		22.4.2	Operational impacts		
	22.5	Environi	mental management measures	22-17	
23.	Cumu	ılative im	pacts	23-1	
		Assessr	ment methodology	23-1	
		Identifie	d developments	23-2	
		Assessr	ment of potential impacts	23-8	
		Environi	mental management measures	23-16	

24.	Sumn	mary of e	nvironmental management measures	24-1
	24.1	-	mental management framework	
		24.1.1	Summary of management measures	
25.	Envir	onmental	I risk analysis	25-1
	25.1	Assessr	ment methodology	25-1
		25.1.1	Identification of environmental risk categories	25-1
		25.1.2	Likelihood and consequence analysis	25-1
	25.2	Environi	mental risk analysis	25-2
	25.3	Risk and	alysis outcomes	25-14
26.	Proje	ct justific	cation and conclusion	26-1
	26.1	Justifica	ation	26-1
		26.1.1	Project justification	26-1
		26.1.2	Objects of the EP&A Act	
		26.1.3	Ecologically Sustainable Development	26-5
	26.2	Conclus	sion	26-8
27.	Proje	ct synthe	esis	27-1
	27.1	Overvie	w of the project	27-1
		27.1.1	The completed project	27-2
	27.2	Constru	ction of the project	27-2
	27.3	Project (uncertainties	27-6
	27.4	Summa	ry of project impacts and management measures	27-10
		27.4.1	Key impact avoidance	
		27.4.2	Key project impacts	
		27.4.3	Environmental management plan framework	27-14
	27.5	Perform	ance outcomes	27-14
	27.6	Project j	justification and conclusion	27-21
		27.6.1	Overview of project need	27-21
		27.6.2	Biophysical, economic and social considerations	27-22
		27.6.3	Ecologically Sustainable Development	
		27.6.4	Cumulative impacts	
		27.6.5	Conclusion	27-24
20	Dofor	onooc		20.4

List of figures

Figure 1-1 Regional context of the project	1-3
Figure 1-2 Project key features	
Figure 2-1 Approval process under Part 5, Division 5.2 of the EP&A Act and the EPBC Act	
Figure 3-1 Existing road and rail infrastructure	3-2
Figure 3-2 Existing traffic volumes	3-11
Figure 3-3 Major freight activity precincts in the vicinity of the project	3-13
Figure 4-1 Project development process	4-2
Figure 4-2 Alternatives to the project	4-3
Figure 4-3 Early stage route options considered for the project	4-9
Figure 4-4 The 2010 Preferred Route and LEP corridor	4-10
Figure 4-5 Alignment options	4-12
Figure 4-6 Interchange options at Tomago	4-14
Figure 4-7 Evaluation criteria	4-15
Figure 4-8 Preferred alignment announced in October 2015	4-18
Figure 4-9 The preferred option – 2016 concept design	4-21
Figure 4-10 The preferred option and design refinements	4-24
Figure 5-1 The project – Key features	5-7
Figure 5-2 Black Hill interchange configuration	5-16
Figure 5-3 Black Hill interchange visualisation	5-16
Figure 5-4 Tarro interchange configuration	5-17
Figure 5-5 Tarro interchange visualisation	5-18
Figure 5-6 Tomago interchange configuration	5-19
Figure 5-7 Tomago interchange visualisation	5-20
Figure 5-8 Raymond Terrace interchange configuration	5-21
Figure 5-9 Raymond Terrace interchange visualisation	5-21
Figure 5-10 Hunter Region Botanic Gardens access	5-22
Figure 5-11 New England Highway upgrade and realignment	5-23
Figure 5-12 Project bridge locations	5-25
Figure 5-13 Indicative drawing of super-T girder bridge structure (B05)	5-28
Figure 5-14 Indicative drawing of a bulb-T girder bridge structure (B12)	5-28
Figure 5-15 Indicative drawing of box girder bridge structure (B05)	5-29
Figure 5-16 Indicative drawing of the voided slab bridge structure (B08)	5-29
Figure 5-17 Indicative drawing of Black Hill section	5-32
Figure 5-18 Indicative drawing of Tarro section	5-33
Figure 5-19 Indicative drawing of Tomago interchange section	5-34
Figure 5-20 Indicative drawing of Heatherbrae section	5-34
Figure 5-21 Indicative drawing of Raymond Terrace interchange section	5-35
Figure 5-22 Tributary of Viney Creek adjustment	5-40
Figure 5-23 Purgatory Creek adjustment	5-42
Figure 5-24 Noise barriers	5-46
Figure 5-25 Construction footprint	5-54
Figure 6-1 Summary of project consultation stages	6-4

Figure 7-1 Traffic and transport study area	7-5
Figure 7-2 Existing road network	7-8
Figure 7-3 Daily traffic volumes of key routes in the study area	7-11
Figure 7-4 Travel time survey routes	7-13
Figure 7-5 Locations of intersections assessed	7-15
Figure 7-6 Operating bus services	7-18
Figure 7-7 Rail network	7-19
Figure 7-8 B-double routes	7-22
Figure 7-9 Modelled peak period traffic volumes (8–9am and 5pm–6pm)	7-32
Figure 7-10 Estimated daily traffic volumes	7-33
Figure 8-1 Study areas and noise monitoring locations	8-5
Figure 8-2 Noise catchment areas	8-23
Figure 8-3 Example of indicative construction noise over a full day	8-29
Figure 8-4 Predicted construction noise impacts – highly noise affected residential receivers	8-47
Figure 8-5 Proposed noise barriers considered for NMG analysis	8-59
Figure 9-1 Biodiversity study area (construction footprint) and landscape buffer	9-6
Figure 9-2 Threatened fauna survey locations	9-11
Figure 9-3 National parks and coastal wetlands	
Figure 9-4 Native vegetation extent and fauna corridors	9-21
Figure 9-5 Plant Community Types, condition and vegetation survey locations	9-25
Figure 9-6 Threatened ecological communities identified within the construction footprint	9-31
Figure 9-7 Recorded threatened species	9-40
Figure 9-8 Aquatic habitat and key fish habitat assessment sites	
Figure 10-1 Surface water and groundwater study areas	
Figure 10-2 Flooding study area	10-8
Figure 10-3 Water sharing plans	10-14
Figure 10-4 Elevation	10-15
Figure 10-5 Key waterways, wetlands and surface water monitoring sites	
Figure 10-6 Groundwater systems in the vicinity of the project	10-22
Figure 10-7 Flood level and depth during April 2015 event	
Figure 10-8 Hunter Valley Flood Mitigation Scheme	
Figure 10-9 Existing flood level and depth (5% AEP)	
Figure 10-10 Existing flood level and depth (1% AEP)	
Figure 10-11 Existing flooding on major roads	10-34
Figure 10-12 Existing flooding at railways	
Figure 10-13 Number of existing lots affected	
Figure 10-14 Number of lots affected by high hazard flooding	
Figure 10-15 Hectares affected by high hazard flooding	
Figure 10-16 Location of stormwater discharge points	
Figure 10-17 Change in flood level during construction (20% AEP)	
Figure 10-18 Change in flood level during construction (10% AEP)	
Figure 10-19 Change in flood level during construction (5% AEP)	
Figure 10-20 Change in flow velocity during construction (20% AEP)	10-57

Figure 10-21 Change in flow velocity during construction (10% AEP)	10-58
Figure 10-22 Change in flow velocity during construction (5% AEP)	10-59
Figure 10-23 Change in flood hazard during construction (20% AEP)	10-61
Figure 10-24 Change in flood hazard during construction (10% AEP)	10-62
Figure 10-25 Change in flood hazard during construction (5% AEP)	10-63
Figure 10-26 Change in duration of inundation during construction (20% A	EP)10-64
Figure 10-27 Change in duration of inundation during construction (10% A	EP)10-65
Figure 10-28 Change in duration of inundation during construction (5% AE	EP)10-66
Figure 10-29 Change in flood level during operation (20% AEP)	10-81
Figure 10-30 Change in flood level during operation (5% AEP)	10-82
Figure 10-31 Change in flood level during operation (1% AEP)	10-83
Figure 10-32 Change in flood level during operation (Probable Maximum F	Flood)10-84
Figure 10-33 Change in flow velocity during operation (20% AEP)	10-86
Figure 10-34 Change in flow velocity during operation (5% AEP)	10-87
Figure 10-35 Change in flow velocity during operation (1% AEP)	10-88
Figure 10-36 Change in flow velocity during operation (Probable Maximun	n Flood)10-89
Figure 10-37 Change in flood hazard during operation (20% AEP)	10-91
Figure 10-38 Change in flood hazard during operation (5% AEP)	10-92
Figure 10-39 Change in flood hazard during operation (1% AEP)	10-93
Figure 10-40 Change in flood hazard during operation (Probable Maximur	n Flood)10-94
Figure 10-41 Change in duration of inundation during operation (20% AEF	P)10-96
Figure 10-42 Change in duration of inundation during operation (5% AEP)	10-97
Figure 10-43 Change in duration of inundation during operation (1% AEP)	10-98
Figure 10-44 Change in duration of inundation during operation (Probable	Maximum Flood)10-99
Figure 11-1 Water quality monitoring locations	11-8
Figure 12-1 Aboriginal cultural heritage study area	12-1
Figure 12-2 Aboriginal sites, PADs and PAS within the study area	12-14
Figure 13-1 Study area used for the socio-economic assessment	13-5
Figure 13-2 Businesses near the project	13-11
Figure 13-3 Social infrastructure within one kilometre of the project	13-22
Figure 14-1 Study area for the land use and property assessment	14-4
Figure 14-2 Land tenure within the study area	14-6
Figure 14-3 Existing land use within the study area	14-9
Figure 14-4 Land use zones within the study area	14-12
Figure 14-5 Mining activities within the study area	14-15
Figure 14-6 Properties impacted by acquisition or temporary lease	14-21
Figure 15-1 Urban design and visual amenity study area	15-4
Figure 15-2 Urban design concept for Type 1 bridges	15-11
Figure 15-3 Urban design concept for Type 2 bridges	15-12
Figure 15-4 Cross section (indicative only) at Black Hill cut, about 700m e. Motorway at Black Hill	15-13
Figure 15-5 Cross section (indicative only) at Tomago Interchange, about Tomago	
Figure 15-6 Landscape character zones within the study area	15-20

Figure 15-7 Visual envelope and viewpoint locations	15-29
Figure 16-1 Soils and contamination study area	16-5
Figure 16-2 Geology	16-9
Figure 16-3 Soil landscapes and soft soils	16-12
Figure 16-4 Acid sulfate soil risk areas	16-15
Figure 16-5 High salinity risk areas	16-23
Figure 16-6 Areas of Potential Contamination Risk	16-32
Figure 17-1 Listed and potential heritage items within or next to the construction project-related work	· · · · · · · · · · · · · · · · · · ·
Figure 18-1 Construction air quality assessment procedure (UK IAQM 2014)	18-5
Figure 18-2 Selected sensitive receiver locations	18-9
Figure 18-3 Annual wind roses for data collected at the DPIE Beresfield Station	18-13
Figure 18-4 Predicted maximum 1-hour average CO	18-21
Figure 18-5 Predicted change in maximum 1-hour average CO	18-22
Figure 18-6 Predicted maximum 8-hour average CO	18-23
Figure 18-7 Predicted change in maximum 8-hour average CO	18-24
Figure 18-8 Predicted maximum 1-hour average NO ₂	18-27
Figure 18-9 Predicted change in maximum 1-hour average NO ₂	18-28
Figure 18-10 Predicted annual average NO ₂	18-29
Figure 18-11 Predicted change in annual average NO ₂	18-30
Figure 18-12 Predicted maximum 24-hour average PM ₁₀	18-33
Figure 18-13 Predicted change in maximum 24-hour average PM ₁₀	18-34
Figure 18-14 Predicted annual average PM ₁₀	18-35
Figure 18-15 Predicted change in annual average PM ₁₀	18-36
Figure 21-1 Risk management process	21-3
Figure 21-2 Sources of GHGs – Adapted from World Business Council for Susta Greenhouse Gas Protocol	•
Figure 21-3 Extent and division of roads within the project scope	21-7
Figure 22-1 Bushfire prone land	
Figure 23-1 Developments considered in the cumulative impact assessment	23-7
Figure 27-1 Project key features	27-4

List of tables

Table 2-1 SEARs (assessment process)	2-1
Table 2-2 NSW legislation applicable to the project	2-4
Table 3-1 SEARs (strategic justification and project need)	
Table 3-2 Existing travel times during peak periods	3-10
Table 3-3 Crashes recorded within the traffic and transport study area during the five year reporting between October 2014 and September 2019	-
Table 3-4 Assessment of the project against the project objectives	
Table 4-1 SEARs (project development and alternatives)	
Table 4-2 Performance of alternatives against project objectives	4-7
Table 4-3 Performance of each option	4-16
Table 4-4 Revisions to the concept design	4-19
Table 4-5 Refinements to the concept design	4-22
Table 5-1 SEARs (project description)	5-1
Table 5-2 Key design criteria	5-3
Table 5-3 Bridges and viaducts	5-26
Table 5-4 Retaining wall summary	5-31
Table 5-5 Drainage criteria for water management structures	5-36
Table 5-6 Operational water quality controls	5-38
Table 5-7 Roadside furniture	5-43
Table 5-8 Fauna crossing and fencing structures	5-44
Table 5-9 Potential utility relocations, adjustments and protection	5-47
Table 5-10 OSOM restrictions to vehicle movements not catered for by the project	5-51
Table 5-11 Construction components and activities	5-63
Table 5-12 Proposed construction ancillary facility locations and uses	5-66
Table 5-13 Assessment of ancillary facilities against standard considerations	5-71
Table 5-14 Relevant mitigation measures for ancillary facilities	5-72
Table 5-15 Indicative construction plant and equipment	5-73
Table 5-16 Approximate total bulk earthwork quantities	5-74
Table 5-17 Approximate quantities of concrete and asphalt	5-76
Table 5-18 Estimated water use during construction	5-77
Table 5-19 Access to ancillary facilities	5-88
Table 5-20 Standard working hours	5-90
Table 5-21 Extended working hours	5-90
Table 5-22 Construction program	5-92
Table 6-1 SEARs (consultation)	6-1
Table 6-2 Community consultation activities carried out during route selection	6-8
Table 6-3 Consultation carried out during concept design and environmental assessment	6-11
Table 6-4 Stakeholders consulted during concept design and environmental assessment	6-14
Table 6-5 Summary of issues raised by public authorities	6-16
Table 6-6 Summary of issues raised by the community – individuals, special interest groups, utilities service providers	
Table 7-1 SEARs (traffic and transport)	7-1

Table 7-2 Modelled scenarios	7-4
Table 7-3 LoS criteria	7-7
Table 7-4 Existing traffic conditions for state roads in the study area	7-9
Table 7-5 Existing travel time	
Table 7-6 Performance of modelled intersections in 2017	7-16
Table 7-7 Total crashes on roads in the study area between October 2014 and September 2019	7-16
Table 7-8 Daily construction traffic movement numbers (in and out)	7-27
Table 7-9 Travel time improvements for key routes across the project (morning peak)	7-34
Table 7-10 Travel time improvements for key routes across the project (evening peak)	7-34
Table 7-11 Network speed for horizon years (2025, 2038, 2048)	7-36
Table 7-12 Performance of modelled intersections in 2028	7-37
Table 7-13 Performance of modelled intersections in 2038	7-38
Table 7-14 Performance of modelled intersections in 2048	
Table 7-15 LoS performance of modelled interchanges	7-39
Table 7-16 Potential cumulative traffic impacts for relevant identified projects	7-46
Table 7-17 Environmental management measures (traffic and transport)	7-48
Table 8-1 SEARs (noise and vibration)	8-1
Table 8-2 Justification for out-of-hours activities	8-8
Table 8-3 Construction scenarios, indicative work durations and periods	8-9
Table 8-4 Noise management levels for residential receivers in accordance with the ICNG	8-11
Table 8-5 NMLs at other noise sensitive land uses	8-11
Table 8-6 Ground-borne noise objectives at residential premises	8-13
Table 8-7 Recommended minimum working distances for vibration intensive plant and equipment	8-13
Table 8-8 Recommended airblast limits for human comfort and structural damage	8-15
Table 8-9 Ground vibration limits for human comfort	8-16
Table 8-10 NCG criteria for residential receivers	8-18
Table 8-11 NCG criteria for non-residential sensitive land uses	8-18
Table 8-12 Traffic noise modelling scenarios	8-19
Table 8-13 Noise catchment areas	8-21
Table 8-14 Summary of background noise monitoring results	8-25
Table 8-15 Monitored road traffic noise levels	8-26
Table 8-16 Construction NMLs and sleep disturbance screening levels for residential receivers	8-27
Table 8-17 NML exceedance bands and corresponding perception of impacts	8-30
Table 8-18 Predicted construction noise exceedances standard daytime – residential receivers	8-31
Table 8-19 Predicted construction noise exceedances morning shoulder – residential receivers	8-34
Table 8-20 Predicted construction noise exceedances daytime out-of-hours – residential receivers	8-36
Table 8-21 Predicted construction noise exceedances evening shoulder – residential receivers	8-38
Table 8-22 Predicted construction noise exceedances evening – residential receivers	8-42
Table 8-23 Predicted construction noise exceedances night time – residential receivers	8-44
Table 8-24 Potential vibration impacts for residential and commercial / industrial structures	8-50
Table 8-25 Heritage items with the potential to be impacted by construction vibration	8-52
Table 8-26 Number of receiver buildings exceeding the NCG noise criteria without mitigation	8-53
Table 8-27 Number of receiver buildings impacted due to the project for design year 2038	8-56

Table 8-28 Summary of NMG noise barrier analysis	8-61
Table 8-29 Number of receiver buildings potentially eligible for at-property noise mitigation treatment	8-63
Table 8-30 Management measures (noise and vibration)	8-65
Table 9-1 SEARs (biodiversity)	9-1
Table 9-2 Targeted threatened flora species	9-8
Table 9-3 Targeted threatened fauna species	9-9
Table 9-4 Biodiversity landscape features and values	9-16
Table 9-5 PCTs identified within the construction footprint	9-23
Table 9-6 TECs present within the construction footprint	9-30
Table 9-7 Potential terrestrial groundwater dependent ecosystems present within the construction for	
Table 9-8 Recorded threatened flora within the construction footprint	
Table 9-9 Listed threatened and migratory fauna species confirmed by surveys or assumed present the construction footprint	
Table 9-10 Waterways identified as KFH within the construction footprint	9-45
Table 9-11 MNES applicable to the project	9-48
Table 9-12 Impacts to PCTs and TECs listed under the TSC Act and EPBC Act	9-51
Table 9-13 Impacts to threatened flora	9-52
Table 9-14 Summary of threatened fauna species impacts	9-54
Table 9-15 Potential impacts associated with proposed bridge construction	9-62
Table 9-16 Potential impacts to aquatic ecosystems during construction of the project	9-65
Table 9-17 Habitat fragmentation impacts	9-72
Table 9-18 Biosecurity duty associated with weeds in the construction footprint	9-74
Table 9-19 Impacts from construction noise, dust, light and contaminants on biodiversity	9-76
Table 9-20 Potential impacts to aquatic ecosystems during operation of the project	9-79
Table 9-21 Impacts from noise, dust, light and contaminants on biodiversity during operation of the p	-
Table 9-22 Environmental management measures (biodiversity)	9-84
Table 9-23 Ecosystem credit requirements	9-87
Table 9-24 Species credit requirements	
Table 10-1 SEARs (flooding, hydrology and climate change)	
Table 10-2 Quantitative flood management objectives	
Table 10-3 Typical existing flood depths	10-25
Table 10-4 Peak flood depths, flow velocities and duration of inundation at key parts of the study are	a 10-31
Table 10-5 Flooding on existing major roads	
Table 10-6 Length of highways and major roads subject to H2 flood hazard in existing case	10-33
Table 10-7 Length of railway flooded in existing case	10-36
Table 10-8 River flow objectives relevant to project construction impacts	10-40
Table 10-9 Estimated groundwater take during construction	10-50
Table 10-10 Change in length of highways and major roads subject to H2 flood hazard, comparison construction phase to existing case	of
Table 10-11 River flow objectives relevant to project operation impacts	
Table 10-12 Change in length of highways and major roads subject to H2 flood hazard, comparison of	
operational phase to existing case	.10-100

Table 10-13 Climate change scenarios and change in flooding at the project	10-103
Table 10-14 Environmental management measures (hydrology and flooding)	10-109
Table 11-1 SEARs (surface water and groundwater quality)	11-1
Table 11-2 NSW Water quality objectives (DGV's) for waterway categories	11-6
Table 11-3 Assigned categories for waterways in the study area from DECCW mapping	11-7
Table 11-4 Water quality indicators and associated default guideline values for water quality objective nominated to waterways within the surface water study area	
Table 11-5 Groundwater sources in groundwater study area and adopted categories	
Table 11-6 Compliance against water quality objectives	
Table 11-7 Summary of existing water quality compliance with recommended ANZG (2018) threshold aquatic ecosystems	ds for
Table 11-8 Summary of existing water quality compliance with recommended ANZG (2018) threshold other relevant values	
Table 11-9 Summary of existing water quality comparison against ANZG (2018) DGVs for aquatic ecosystems	11-19
Table 11-10 Groundwater systems and existing groundwater quality	11-19
Table 11-11 Description of SREs and reasons for determination	11-21
Table 11-12 Waterways and wetlands with the potential to be impacted by construction activities	11-25
Table 11-13 Pollutants relating to construction activities and general impacts on surface water quality	/.11 - 26
Table 11-14 Construction impacts on erosion and sedimentation	11-27
Table 11-15 Annual average TSS loads (kg/yr) discharged from sediment basins under controlled conditions	11-30
Table 11-16 Coastal Management Areas (Coastal Management SEPP) that would be cleared or occi for use during construction	
Table 11-17 Comparisons of calculated turbidity discharged from sediment basins during constructio against existing conditions and guideline values	
Table 11-18 Project impact on water quality objectives during construction	11-36
Table 11-19 Operational water quality risks and waterways that may be impacted	11-45
Table 11-20 Average annual pollutant loads (kg/yr) discharged from water quality basins during oper under controlled conditions	
Table 11-21 Coastal Management Areas (Coastal Management SEPP) that would be cleared or occi	•
Table 11-22 Comparison of modelling water quality during operation with existing water quality and p water quality objectives	-
Table 11-23 Project impact on water quality objectives during operation	11-53
Table 11-24 Environmental management measures (surface water and groundwater quality)	11-61
Table 11-25 Location, frequency and indicators for surface water quality monitoring	11-63
Table 11-26 Location, frequency and indicators for groundwater quality monitoring	11-64
Table 12-1 SEARs (Aboriginal cultural heritage)	12-1
Table 12-2 Consultation activities carried out during each of the PACHCI stages	12-4
Table 12-3 Predictive model based on landscape regions for the identification of areas of high, mode and low archaeological sensitivity	
Table 12-4 Summary of Aboriginal sites, PADs and PAS within the study area	12-9
Table 12-5 Aboriginal cultural values near or within the study area	12-16
Table 12-6 Summary of the significance assessment for Aboriginal sites	12-17

Table 12-7 Impact assessment for Aboriginal sites, PADs and PAS	12-20
Table 12-8 Environmental management measures (Aboriginal cultural heritage)	12-25
Table 13-1 SEARs (socio-economic, land use and property)	
Table 13-2 Summary of impacts on social infrastructure within 400 metres of the project	13-29
Table 13-3 Impacts on directly affected businesses	13-32
Table 13-4 Summary of impacts on social infrastructure within 400 metres of the project	13-37
Table 13-5 Environmental management measures (socio-economic)	13-40
Table 14-1 SEARs (land use and property)	14-1
Table 14-2 Key land uses within the study area	14-8
Table 14-3 Summary of properties to be acquired or leased	14-18
Table 14-4 Properties with access changes during construction and operation	14-29
Table 14-5 Impacts to key land uses during construction and operation	14-32
Table 14-6 Summary of utility impacts	14-35
Table 14-7 Environmental management measures (land use and property)	14-39
Table 15-1 SEARs (urban design and visual amenity)	15-1
Table 15-2 Landscape character and visual impact rating matrix	15-5
Table 15-3 Urban design objectives and principles	15-7
Table 15-4 Proposed urban design treatments for project elements	15-15
Table 15-5 Landscape character zones within the study area	15-21
Table 15-6 Existing viewpoints within the VEM	15-25
Table 15-7 Summary of landscape character impacts during operation	15-32
Table 15-8 Summary of visual amenity impacts during operation	15-34
Table 15-9 Operational visual impacts at each viewpoint	15-38
Table 15-10 Environmental management measures (urban design, landscape and visual amenity).	15-49
Table 16-1 SEARs (soils and contamination)	16-1
Table 16-2 Summary of soil landscapes within the construction footprint	16-10
Table 16-3 Summary of potential contamination issues in the study area as identified from the histo aerial photography review	
Table 16-4 Summary of potential contamination issues within the study area as identified from histomaps and business directories	
Table 16-5 Regulated/notified sites within the study area	16-19
Table 16-6 POEO public record search within the study area	16-20
Table 16-7 Findings of previous contamination investigations	16-21
Table 16-8 Sensitive receiving environments in the study area	16-24
Table 16-9 Areas of potential contamination risk	16-26
Table 16-10 Potential soil erosion impacts resulting from construction activities	16-34
Table 16-11 Environmental management measures (soils and contamination)	16-40
Table 17-1 SEARs (non-Aboriginal heritage)	17-1
Table 17-2 Definitions of levels of impact	17-6
Table 17-3 Areas with potential for heritage items within the construction footprint	17-8
Table 17-4 Description and photographs of listed and potential heritage items identified during field	•
Table 17-5 Summary of significance of heritage items within or next to the construction footprint	17-16
Table 17-6 Summary of potential impacts on heritage items	17-19

Table 17-7 Environmental management measures (non-Aboriginal heritage)	17-25
Table 18-1 SEARs (air quality)	18-1
Table 18-2 Operational air quality impact assessment criteria contained within the Approved M	ethods18-7
Table 18-3 Selected sensitive receivers	
Table 18-4 Summary of measured background CO concentrations	18-10
Table 18-5 Summary of measured background NO ₂ concentrations	18-10
Table 18-6 Summary of measured PM ₁₀ concentrations	18-11
Table 18-7 Summary of measured PM _{2.5} concentrations	18-11
Table 18-8 Assumed project background levels	
Table 18-9 Dust emission magnitude classifications determined for the project	18-16
Table 18-10 Surrounding receiver sensitivity classifications determined for the project	18-16
Table 18-11 Unmitigated construction dust risk values for the project	18-17
Table 18-12 Predicted CO concentrations at selected sensitive receivers	18-20
Table 18-13 Predicted NO ₂ concentrations at selected sensitive receivers	18-26
Table 18-14 Predicted PM ₁₀ concentrations at selected sensitive receivers	18-32
Table 18-15 Predicted PM _{2.5} concentrations at selected sensitive receivers	18-37
Table 18-16 Predicted air toxics concentrations at selected sensitive receivers	18-38
Table 18-17 Environmental management measures (air quality)	18-41
Table 19-1 SEARs (waste)	
Table 19-2 Nearest waste management facilities	19-3
Table 19-3 Indicative construction waste streams and volumes	19-4
Table 19-4 Estimated stockpile volumes	
Table 19-5 Indicative operational waste streams and volumes	
Table 19-6 Environmental management measures (waste)	
Table 20-1 SEARs (sustainability)	20-1
Table 20-2 Sustainability focus areas that relate to the project	
Table 20-3 Environmental management measures (sustainability)	20-11
Table 21-1 SEARs (climate change risk)	
Table 21-2 GHG emission sources	21-5
Table 21-3 Construction GHG emissions	21-11
Table 21-4 Climate change risks with a residual risk of 'medium' or higher	21-13
Table 21-5 CO₂e contribution of traffic to the project emissions	21-15
Table 21-6 Comparison of vehicle kilometres travelled between model scenarios	21-16
Table 21-7 Environmental management measures (climate change risk)	
Table 22-1 SEARs (safety and risk)	
Table 22-2 Flooding on existing major roads	
Table 22-3 Environmental management measures (safety and risk)	22-17
Table 23-1 SEARs (cumulative impacts)	23-1
Table 23-2 Developments considered in the cumulative impact assessment	23-3
Table 23-3 Potential cumulative impacts during construction and operation	23-8
Table 23-4 Environmental management measures (cumulative impacts)	
Table 24-1 SEARs (environmental management measures)	24-1
Table 24-2 Environmental management measures for the project	24-2

Table 25-1 Likelihood of environmental risks	25-2
Table 25-2 Consequence of environmental risks	25-2
Table 25-3 Risk rating matrix	25-2
Table 25-4 Environmental risk analysis	25-3
Table 26-1 SEARs relating to project justification and conclusion	26-1
Table 26-2 Assessment of the project against the project objectives	26-2
Table 26-3 Assessment of the project against the objects of the EP&A Act	26-3
Table 26-4 Inter-generational equity considerations of the project	26-6
Table 27-1 SEARs relating to the synthesis chapter	27-1
Table 27-2 Resolution of project uncertainties	27-7
Table 27-3 Summary of key project impacts and management measures	27-11
Table 27-4 Design performance outcomes and project outcome	27-15

Appendices

Appendix	Appendix name
Appendix A	Secretary's Environmental Assessment Requirements and checklist
Appendix B	Environmental Planning and Assessment Regulation 2000 Checklist
Appendix C	Schedule 4 of the Environment Protection and Biodiversity Conservation Regulations 2000 (Commonwealth) Checklist
Appendix D	Transport Environment and Sustainability Policy
Appendix E	Community Consultation Framework
Appendix F	Environmental Record of Proponent
Appendix G	Traffic and Transport Working Paper
Appendix H	Noise and Vibration Working Paper
Appendix I	Biodiversity Assessment Report
Appendix J	Hydrology and Flooding Working Paper
Appendix K	Surface Water and Groundwater Quality Working Paper
Appendix L	Aboriginal Cultural Heritage Assessment Report
Appendix M	Socio-economic Working Paper
Appendix N	Land Use and Property Working Paper
Appendix O	Urban Design, Landscape Character and Visual Amenity Working Paper
Appendix P	Soils and Contamination Working Paper
Appendix Q	Non-Aboriginal Heritage Working Paper
Appendix R	Air Quality Working Paper
Appendix S	Waste Working Paper
Appendix T	Sustainability Working Paper
Appendix U	Climate Change Risk Working Paper

Certification

Submission of environmental impact statement

Prepared under Division 5.2 of the Environmental Planning and Assessment Act 1979

Environmental impact statement prepared by:

Name: Peter Horn

Qualifications: BAppSci – Environmental Science, MAppSci – Environmental Management and Restoration

Address: Jacobs Group (Australia) Pty Ltd

7/177 Pacific Highway, North Sydney, NSW 2060

Responsible person:

Name: Tony Gant, Project Director, M1 Pacific Motorway extension to Raymond Terrace

Transport for NSW

Address: 6 Stewart Avenue

Newcastle West, NSW, 2302

Proposed development:

M1 Pacific Motorway extension to Raymond Terrace

Address of the land on which the infrastructure to which the statement relates:

Land between Black Hill to the west and Raymond Terrace to the east for a distance of about 15 kilometres, within the City of Newcastle and Port Stephens Council local government areas, as described in the environmental impact statement.

Description of the infrastructure to which the statement relates:

Construction and operation of the M1 Pacific Motorway extension to Raymond Terrace, which would connect the existing M1 Pacific Motorway at Black Hill and the Pacific Highway at Raymond Terrace. The project would comprise a 15 kilometre motorway comprised of a four lane divided road, including; four new interchanges at Black Hill, Tarro, Tomago and Raymond Terrace; a 2.6 kilometre viaduct over the Hunter River flood plain including new bridge crossings over the Hunter River, the Main North Rail Line and the New England Highway; bridge structures over local waterways, and connections and modifications to the adjoining local road network.

Environmental impact statement:

An environmental impact statement is attached addressing all matters in accordance with Division 5.2 of the *Environmental Planning and Assessment Act 1979*.

Declaration: I certify that I have prepared the contents of this environmental impact statement in response to

the Secretary's environmental assessment requirements dated 20 March 2019 and the relevant provisions of Schedule 2 of the Environmental Planning and Assessment Regulation 2000. To the best of my knowledge the information contained in the environmental impact statement is

not false or misleading.

Signature:

Name: Peter Horn

Date: 01 July 2021

Glossary of terms and abbreviations

AADT Average Annual Daily Traffic ABS Australian Bureau of Statistics Abutment An end support of a bridge. Access road A road providing access to a property or another road. ACHAR Aboriginal Cultural Heritage Assessment Report ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Impact Permit AIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Are geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Are geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Are and Potential Contamination Risk APIC Aboriginal Participation in Construction AGIA Air Quality Impact Assessment AGMP Air Quality Management Plan ARI Annual Recurrence Interval ARIC Australian Soil Resources Information System Acid Sulfate Soil	Term / Abbreviation	Definition
ABS Australian Bureau of Statistics Abutment An end support of a bridge. Access road A road providing access to a property or another road. ACHAR Aboriginal Cultural Heritage Assessment Report ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEF Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARIC Australian Soil Resources Information System		
Abutment An end support of a bridge. Access road A road providing access to a property or another road. ACHAR Aboriginal Cultural Heritage Assessment Report ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenties, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Soil Resources Information System		·
Access road A road providing access to a property or another road. ACHAR Aboriginal Cultural Heritage Assessment Report ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquiffer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Aremporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System		
ACHAR Aboriginal Cultural Heritage Assessment Report ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Impact Assessment ARI Annual Recurrence Interval ARIC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System		
ACHCRP Aboriginal Cultural Heritage Consultation Requirements for Proponents ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction ARI Annual Recurrence Interval ARI Annual Recurrence Interval ARI Annual Recurrence Interval ARI Annual Recurrence Interval ARIC Australian Soil Resources Information System		
ACHMP Aboriginal Cultural Heritage Management Plan ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Soil Resources Information System		Aboriginal Cultural Heritage Assessment Report
ACM Asbestos Containing Material ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Atemporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Soil Resources Information System	ACHCRP	Aboriginal Cultural Heritage Consultation Requirements for Proponents
ACT Australian Capital Territory ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility Atemporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	ACHMP	Aboriginal Cultural Heritage Management Plan
ADSS All-Dielectric Self-Supporting Fibre Optic ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	ACM	Asbestos Containing Material
ADWG Australian Drinking Water Guidelines AEP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Soil Resources Information System	ACT	Australian Capital Territory
AFP Annual Exceedance Probability The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AFP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	ADSS	All-Dielectric Self-Supporting Fibre Optic
The probability of a rainfall or flood event exceeding the nominated level in a year. The 1% AEP is the probability of an event exceeding a nominated level in 100 years. AFG Aboriginal Focus Group Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	ADWG	Australian Drinking Water Guidelines
Afflux An increase in water level resulting from a constriction in the flow path. AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AEP	The probability of a rainfall or flood event exceeding the nominated level in a year. The 1%
AHD Australian Height Datum AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AFG	Aboriginal Focus Group
AHIMS Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	Afflux	An increase in water level resulting from a constriction in the flow path.
AHIP Aboriginal Heritage Impact Permit AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AHD	Australian Height Datum
AIP The NSW Aquifer Interference Policy ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AHIMS	Aboriginal Heritage Information Management System
ALA Atlas of Living Australia Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AHIP	Aboriginal Heritage Impact Permit
Alignment The geometric layout (of a road) in plan (horizontal) and elevation (vertical). Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AIP	The NSW Aquifer Interference Policy
Ancillary facility A temporary facility for construction of the project. Typically, ancillary facilities would include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	ALA	Atlas of Living Australia
include temporary buildings (including offices, amenities, and first aid facilities), hardstand parking areas, materials laydown and storage areas, perimeter fencing, and workshops. AOPCR Area of Potential Contamination Risk APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	Alignment	The geometric layout (of a road) in plan (horizontal) and elevation (vertical).
APIC Aboriginal Participation in Construction AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	Ancillary facility	include temporary buildings (including offices, amenities, and first aid facilities), hardstand
AQIA Air Quality Impact Assessment AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AOPCR	Area of Potential Contamination Risk
AQMP Air Quality Management Plan ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	APIC	Aboriginal Participation in Construction
ARI Annual Recurrence Interval ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AQIA	Air Quality Impact Assessment
ARTC Australian Rail Track Corporation ASRIS Australian Soil Resources Information System	AQMP	Air Quality Management Plan
ASRIS Australian Soil Resources Information System	ARI	Annual Recurrence Interval
· ·	ARTC	Australian Rail Track Corporation
ASS Acid Sulfate Soil	ASRIS	Australian Soil Resources Information System
	ASS	Acid Sulfate Soil

Term / Abbreviation	Definition
ASSMAC	Acid Sulfate Soil Manual
ASSMP	Acid Sulfate Soil Management Plan
BAM	Biodiversity Assessment Method
BAR	Biodiversity Assessment Report
Batter	A receding slope of a wall, structure or earthwork.
BBCC	BioBanking Credit Calculator
BC Act	Biodiversity Conservation Act 2016 (NSW)
BFRMP	Bush Fire Risk Management Plan
Bilateral agreement	The bilateral agreement made under section 45 of the <i>Environment Protection and Biodiversity Conservation Act 1999</i> relating to environmental assessment
ВМР	Blast Management Plan
ВОМ	Australian Bureau of Meteorology
BOS	Biodiversity Offset Strategy
BVT	Biometric Vegetation Type
ccs	Community Communication Strategy
CCTV	Closed Circuit Television
CEMP	Construction Environmental Management Plan
CHL	Commonwealth Heritage List
CLG	Community Liaison Group
CLM Act	NSW Contaminated Land Management Act 1997
CLMP	Contaminated Land Management Plan
CNVG	Construction Noise and Vibration Guideline
CNVMP	Construction Noise and Vibration Management Plan
Construction footprint	The area required to build the project.
CPT	Cone Penetrometer Testing
CPTED	Crime Prevention Through Environmental Design
CSEP	Community and Stakeholder Engagement Plan
CSIRO	Commonwealth Scientific and Industrial Research Organisation
CSSI	Critical State Significant Infrastructure
CSWMP	Construction Soils and Water Management Plan
CTGM	Chichester Trunk Gravity Main
Culvert	One or more adjacent enclosed channels for conveying a stream below formation level.
Cut / cutting	Formation resulting from the construction of the road below existing ground level where the material is cut out or excavated.

Term / Abbreviation	Definition
dB / dB(A)	Decibel
	dB(A) is a weighted scale which corresponds to the hearing threshold of the human ear
DEC	Department of Environment and Conservation
DECC	Department of Environment and Climate Change
DECCW	Department of Environment, Climate Change and Water
Detailed design	The final stage of design for the project. It includes designs, plans and construction drawings for all project elements.
DGV	Default Guideline Value
DIPNR	Department of infrastructure, Planning and Natural Resources
DPE	Department of Planning and Environment
DPI	Department of Primary Industries
DPIE	Department of Planning, Industry and Environment
DSI	Detailed Site Investigation
DUAP	Department of Urban Affairs and Planning
Earthworks	All operations involved in loosening, excavating, placing, shaping and compacting soil or rock.
EC	Electrical Conductivity
EES Group	The Environment, Energy and Science Group of the Department of Planning, Industry and Environment (formerly the NSW Office of Environment and Heritage)
EIA	Environmental Impact Assessment
EIS	Environmental Impact Statement
EL	Exploration Licence
Embankment	An earthen structure where the road (or other infrastructure) subgrade level is above the natural surface.
EMS	Environmental Management System
ENM	Excavated Natural Material
ENMM	Environmental Noise Management Manual
EP&A Act	The Environmental Planning and Assessment Act 1979 (NSW)
EP&A Regulation	The Environmental Planning and Assessment Regulations 2000
EPA	Environment Protection Authority
EPBC Act	The Environment Protection and Biodiversity Conservation Act 1999 (Commonwealth)
EPL	Environmental Protection Licence
ESCP	Erosion and Sediment Control Plan
ESD	Ecologically Sustainable Development
FBA	Framework for Biodiversity Assessment

Term / Abbreviation	Definition
FFMP	Flora and Fauna Management Plan
Fill	The material placed in an embankment.
FM Act	The Fisheries Management Act 1994
FMP	Flood Management Plan
GDE	Groundwater Dependent Ecosystem
GHG	Greenhouse Gas
GIS	Geographic Information System
Grade Separated Interchange	An interchange that is separated vertically (at different heights) involving bridges, underpasses and/or overpasses.
GREP	NSW Government Resource Efficiency Policy
HC	Hydrocarbons
Heritage Act	The Heritage Act 1977
HPV	High Productivity Vehicle Vehicles that can carry more payload than a B-double, such as Performance Based Standards vehicles, road trains, other restricted access vehicles including those operating at Higher Mass Limits and double decker buses.
HRBG	Hunter Region Botanic Gardens
ICNG	Interim Construction Noise Guideline
ICOMOS	International Council on Monuments and Sites
Interchange	A grade-separated junction between roads where a road passes over or under the highway via a bridge or underpass structure with one or more interconnecting roads.
IPCC	Intergovernmental Panel on Climate Change
ISCA	Infrastructure Sustainability Council of Australia
ISO	International Organisation for Standardisation
ITS	Intelligent Traffic System
KFH	Key Fish Habitat
KRAM	Koala Rapid Assessment Method
KTP	Key Threatening Process
LALC	Local Aboriginal Land Council
LCZ	Landscape Character Zone
LEP	Local Environmental Plan
LGA	Local Government Area
LHFC	Lower Hunter Freight Corridor
LOS/LoS	Level of Service
LUCRA	Land Use Conflict Risk Assessment

Term / Abbreviation	Definition
M1 Pacific Motorway	A key north-south corridor linking Sydney to the Central Coast, Newcastle and Hunter region. It is a dual carriageway road with two lanes in each direction and a 110km/h speed limit.
Main alignment	The main component of the M1 Pacific Motorway extension to Raymond Terrace. The main alignment would typically consist of two 3.5 metre traffic lanes in each direction with a median that would range from six to 15 metres.
ML	Mining Lease
MLEP	Maitland Local Environmental Plan
MNES	Matters of National Environmental Significance
MPN	Most Probable Number
NAHMP	Non-Aboriginal Heritage Management Plan
NCA	Noise Catchment Area
NCG	Noise Criteria Guideline
NEPC	National Environment Protection Council
NHL	National Heritage List
NLEP	Newcastle Local Environmental Plan
NLTN	National Land Transport Network
NMG	Noise Mitigation Guideline
NML	Noise Management Level
NNTR	National Native Title Register
NNTT	National Native Title Tribunal
NORM	Naturally Occurring Radioactive Material
NPW Act	The National Parks and Wildlife Act 1974 (NSW)
NPWS	National Parks and Wildlife Service
NSW	New South Wales
NTAR	National Trust of Australia (NSW) Register
NTU	Nephelometric Turbidity Units
OEH	The (former) Office of Environment and Heritage
ONVR	Operational Noise and Vibration Review
Operational footprint	Generally includes the M1 Pacific Motorway extension to Raymond Terrace and additional areas required for operation and maintenance of the project
ORP	Oxygen Reduction Potential
OSOM	Oversize overmass
PACHCI	Procedure of Aboriginal Cultural Heritage Consultation and Investigation
PAD	Potential Archaeological Deposit

Term / Abbreviation	Definition
PAH	Polycyclic Aromatic Hydrocarbons
PAS	Potential Archaeological Sensitivity
PASS	Potential Acid Sulfate Soils
PBS	Performance Based Standard
PCT	Plant Community Type
PEI	Preliminary Environmental Investigation
PFAS	Per- and Poly-fluoroalkyl Substances
PIR	Preferred Infrastructure Report
PMF	Probable Maximum Flood
PMST	Protected Matters Search Tool
POEO Act	The Protection of the Environment Operations Act 1997 (NSW)
PSI	Preliminary Site Investigation
PSLEP	Post Stephens Local Environmental Plan
RAAF	Royal Australian Air Force
RAP	Registered Aboriginal Party
RBL	Rated Background Level
RCP	Representative Concentration Pathway
Receiver	An environmental modelling term used to describe a map reference point where the impact is predicted. A sensitive receiver is a home, work place, school or other place where people spend some time.
RFS	NSW Rural Fire Service
RL	Reduced Level
RMS	Roads and Maritime Services (now Transport for NSW)
RNE	Register of the National Estate
RNP	Road Noise Policy
ROL	Road Occupancy Licence
SEARs	Secretary's Environmental Assessment Requirements
SEPP	State Environmental Planning Policy
SES	State Emergency Services
SHI	NSW State Heritage Inventory
SHR	NSW State Heritage Register
SIS	State Infrastructure Strategy
SMP	Sustainability Management Plan
SOHI	Statement of Heritage Impact

Term / Abbreviation	Definition
SRE	Sensitive Receiving Environment
SSI	State Significant Infrastructure
SSIA	State Significant Infrastructure Application
STFM	Sydney Traffic Forecasting Model
Stockpile	Temporarily stored materials such as soil, sand, gravel and spoil/waste.
Study area	Describes the area investigated as part of this EIS. References to study area varies according to the specific environmental issue under consideration (e.g. traffic, heritage, visual amenity etc.) and is described within each relevant section of the EIS.
TAGG	Transport Authorities Greenhouse Group
TEC	Threatened Ecological Community
The project	M1 Pacific Motorway extension to Raymond Terrace
TKN	Total Kjeldahl Nitrogen
TMC	Traffic Management Centre
TMP	Traffic Management Plan
TN	Total Nitrogen
TP	Total Phosphorus
Transport	Transport for NSW
TSC Act	The Threatened Species Conservation Act 1995 (NSW) (repealed)
TSF	Train Support Facility
TSP	Total Suspended Particles
TSS	Total Suspended Solids
UBD	Universal Business Directory
UDLP	Urban Design and Landscape Plan
VEM	Visual Envelope Map
VENM	Virgin Excavated Natural Material
VKT	Vehicle Kilometres Travelled
VMS	Variable Message Signs
VP	Viewpoint
WHL	World Heritage List
WM Act	The Water Management Act 2000
WMP	Waste Management Plan
WQO	Water Quality Objectives
WSP	Water Sharing Plan