327-335 BURLEY ROAD, HORSLEY PARK

ROAD & DRAINAGE DESIGN
ISSUED FOR DEVELOPMENT APPLICATION



LOCALITY PLAN

LGA FAIRFIELD CITY COUNCIL LOT 1, D.P. 106143









DRAWING LIST

000	COVER SHEET
001	STANDARD NOTES & LEGEND
002	GENERAL LAYOUT PLAN
ROA	DWORKS
101	ENGINEERING PLAN SHEET 01 OF 04
102	ENGINEERING PLAN SHEET 02 OF 04
103	ENGINEERING PLAN SHEET 03 OF 04
104	ENGINEERING PLAN SHEET 04 OF 04
105	INTERSECTION PLAN
201	ROAD No.01 LONGITUDINAL SECTION
202	ROAD No.01 LONGITUDINAL & TYPICAL CROSS SECTIONS
SITE	REGRADING
601	SITE REGRADING PLAN
602	SITE SECTIONS SHEET 01 OF 02
603	SITE SECTIONS SHEET 02 OF 02
604	EARTH BUND LAYOUT PLAN
605	EARTH BUND SECTIONS
SED	IMENT & EROSION CONTROL
701	SEDIMENT & EROSION CONTROL PLAN

SEDIMENT & EROSION CONTROL NOTES & DETAILS

327-335 BURLEY ROAD, HORSLEY PARK ROAD & DRAINAGE DESIGN

 Project No.:
 Stage:
 Milestone:
 Drawing No.: Revision:

 X13044.002
 1, 2 & 3
 DA
 000
 07

STANDARD NOTES

- 1. ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S STANDARDS AND SPECIFICATIONS AND/OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL LOCATE AND LEVEL ALL EXISTING SERVICES PRIOR TO COMMENCING
 CONSTRUCTION AND SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE RELEVANT AUTHORITY TO
 RELOCATE OR ADJUST AS FOUND NECESSARY. ALL COSTS TO BE BORNE BY THE APPLICANT, (NOT AT
 ADJUST AS TO SERVICE AND THE APPLICANT, (NOT AT
 ADJUST AS TO SERVICE AND THE APPLICANT.)
- 3. THE CONTRACTOR SHALL NOT ENTER UPON OR DO ANY WORK WITHIN ADJACENT LANDS WITHOUT PRIOR WRITTEN PERMISSION OF THE LAND OWNER.
- 4. SURVEY MARKS SHOWN THUS SHALL BE MAINTAINED AT ALL TIMES. WHERE RETENTION IS NOT POSSIBLE
- 5. ALL NEW WORKS SHALL MAKE SMOOTH JUNCTION WITH EXISTING CONDITIONS.
- 6. SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO SOIL DISTURBANCE IN KEEPING WITH THE "MANAGING STORMWATER MANUAL", 2004 BY LANDCOM AND TO THE SATISFACTION OF THE ENGINEER AND AS SHOWN IN THESE DRAWINGS.
- THE CONTRACTOR SHALL CLEAR AND DISPOSE OF ONLY THOSE TREES THAT ARE CONDEMNED BY THE ENGINEER. COUNCIL'S TREE PRESERVATION ORDER SHALL BE OBSERVED AND NO TREE SHALL BE FELLED, LOPPED OR REMOVED WITHOUT PRIOR APPROVAL.
- 8. THE CONTRACTOR SHALL CLEAR THE SITE BY REMOVING ALL RUBBISH, FENCES, OUT HOUSES, CAR BODIES, DEBRIS ETC. THE CONTRACTOR SHALL NOT DISPOSE OF ANY DEBRIS BY BURNING OFF IN AN OPEN
- 9. UNSOUND MATERIALS AS DETERMINED BY THE ENGINEER SHALL BE REMOVED FROM ROADS AND LOTS
- 10. ALL SITE REGRADING AREAS SHALL BE GRADED IN ACCORDANCE WITH FAIRFIELD CITY COUNCIL GUIDELINES AND WORK SPECIFICATIONS. THE CONTRACTOR SHALL TAKE LEVELS ON THE EXISTING SURFACE AFTER STRIPPING TOPSOIL AND PRIOR TO COMMENCING ANY FILL OPERATIONS.
- 11. SURPLUS EXCAVATED MATERIAL SHALL BE PLACED WHERE DIRECTED BY THE ENGINEER.
- 12. 100 DIA. SUBSOIL DRAINAGE PIPE 3000 LONG WRAPPED IN FABRIC SOCK TO BE PROVIDED ADJACENT TO
- 13. MINIMUM 100mm THICK TOPSOIL SHALL BE SPREAD ON ALL FOOTPATHS, BERMS, BATTERS AND SITE REGRADING AREAS. EXCESS TOPSOIL SHALL BE DISPOSED OF AS DIRECTED BY THE ENGINEER.
- 14 ALLI AND DISTURBED BY FARTHWORKS SHALL BE SPRAY-GRASSED, OR SIMILARLY TREATED TO ESTABLISH GRASS COVER. SEED MIXTURES ARE TO BE APPROVED BY COUNCIL PRIOR TO SPRAYING. ALL GRASSED AREAS SHALL BE REGULARLY WATERED AND MAINTAINED UNTIL EXPIRATION OF THE MAINTENANCE
- 15. THE CONTRACTOR SHALL MAINTAIN DUST CONTROL THROUGHOUT THE DURATION OF THE PROJECT.
- 16. ALL PITS DEEPER THAN 1.2m SHALL HAVE STEP IRONS PROVIDED IN ACCORDANCE WITH COUNCIL'S
- 17. ALL DRAINAGE LINES THROUGH LOTS SHALL BE CONTAINED WITHIN THEIR EASEMENTS AND CONFORM
- 18. ALL DRAINAGE LINES ON HIGH SIDE AND UNDER ROADS SHALL BE BACKFILLED WITH SHARP SAND AND HAVE 3.0m OF AGRICULTURAL LINE WRAPPED IN AN APPROVED FILTER FABRIC, DISCHARGING INTO THE DOWNSTREAM PIT.
- 19. SUBSOIL DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH BCC GUIDELINES AND SPECIFICATIONS.
- 20. PRECAST KERB INLET LINTELS SHALL BE USED ON GULLY PITS. GULLY PITS SHALL BE IN ACCORDANCE
- 21. INTERALLOTMENT DRAINAGE LINES SHALL HAVE A MINIMUM 300mm COVER AND DESIRABLE MINIMUM
- 22. 100mm DIAMETER ROOF DRAINAGE HOLES SHALL BE PROVIDED TO ALL LOTS DRAINING TO THE KERB AT
- 23. PROVIDE VEHICULAR CROSSING IN KERB AND GUTTER WHERE SHOWN VC OR WHERE DIRECTED BY THE ENGINEER.
- 24. GUIDE POSTS SHALL BE 100mm X 50mm HARDWOOD, PAINTED WHITE WITH REFLECTORS. 25. FRECT STREET NAME SIGNS, CONDUIT WARNING SIGNS AND NO THROUGH ROAD SIGNS WHERE SHOWN

- 26. ERECT STREET NAME SIGNS, CONDUIT WARNING SIGNS AND NO THROUGH ROAD SIGNS WHERE SHOWN
 - 27. CONDUITS SHALL BE LAID AFTER POSITIONS HAVE BEEN DETERMINED BY THE RELEVANT AUTHORITIES AND BEFORE FINAL A.C. IS LAID.
 - 28. POSITION OF ALL CONDUITS SHALL BE MARKED ON THE KERB.

THUS SP OR WHERE DIRECTED BY THE ENGINEER.

- 29. FELLED TREES SHALL BE SALVAGED FOR REUSE AS WOODCHIP MULCH OR LOG FORM FOR SITE REHABILITATION, NON-SALVAGEABLE MATERIAL SUCH AS STUMPS AND ROOTS SHALL BE DISPOSED OF OFF
- 30. THE CONTRACTOR SHALL PROVIDE MINIMUM 24 HOURS NOTICE TO THE ENGINEER AND COUNCIL INSPECTOR FOR ALL INSPECTIONS.
- 31. THE CONTRACTOR SHALL MAINTAIN SERVICES AND ALL WEATHER ACCESS AT ALL TIMES TO THE
- 32. THE CONTRACTOR SHALL UNDERTAKE TRAFFIC CONTROL MEASURES TO ENGINEERS SATISFACTION AND
- 33. ALL NATURAL SURFACE DATA HAS BEEN DETERMINED BY TERRAIN MODELLING. ALL CONSTRUCTION SITE WORKS MUST BE CARRIED OUT USING THE BENCH MARKS SHOWN ON THESE DRAWINGS.
- 34. THAT ALL LIGHT POLES, STREET NAME POLES AND BUS SHELTERS IN THIS SUBDIVISION WILL BE BLACK POWDER COATED TO THE SATISFACTION OF THE FAIRFIELD CITY COUNCIL.
- 35. PRAM RAMPS AND PATHPAVING TO BE CONSTRUCTED AS SHOWN ON PLANS AND AS DIRECTED BY
- 36. ALL BATTERS ARE TO HAVE A MAXIMUM SLOPE OF 4(H):1(V).
- 37. PRIOR TO CONSTRUCTION THE CONTRACTOR SHOULD OBTAIN COPIES OF ALL RELEVANT GEOTECHNICAL REPORTS. WORKS SHOULD BE UNDERTAKEN IN ACCORDANCE WITH ADVICE AND RECOMMENDATIONS
- 38, UPON COMPLETION OF THE SITE REGRADE & APPROVED ROAD AND DRAINAGE WORKS AND PRIOR TO THE UPON COMPLETION OF THE SILE REGRADE A PHYROVED ROAD AND DYNINGSE WORKS AND PRIOR TO THE ISSUE OF THE SUBDIVISION CERTIFICATE, THE APPLICANT IS REQUIRED TO SUBMIT TO COUNCIL WRITTEN CERTIFICATION FROM APPROPRIATELY QUALIFIED GEOTECHNICAL CONSULTANTS THAT ALL THE RECOMMENDATIONS IN THE REPORTS REFERRED TO IN ITEM 37 ABOVE HAVE BEEN COMPILED WITH.
- 39. 100 YEAR FLOW PATHS TO BE FORMED AT TIME OF CONSTRUCTION.
- 40. A TRAFFIC CONTROL PLAN IS TO BE PROVIDED TO COUNCIL PRIOR TO COMMENCEMENT OF WORKS.

LEGEND

DESCRIPTION	PROPOSED	EXISTING	FUTURE
STORMWATER PIPELINE	375¢		
STORMWATER DRAINAGE PITS			
DRAINAGE LINE No. 3 DRAINAGE PIT No. 10	(3710)		3/10
CONCRETE HEADWALL		· — (
SUBSOIL DRAIN	ssss		
STANDARD 150mm KERB AND GUTTER	K&G		=====
STANDARD ROLL KERB AND GUTTER	RK		=====
STANDARD KERB ONLY	ко		=====
STANDARD EDGE STRIP	ES		
STANDARD MOUNTABLE KERB	MK		
STANDARD DISH CROSSING	<u>DC</u>		=====
VEHICULAR CROSSING	VC		-4::::
PEDESTRIAN RAMP	PR		41
EDGE OF BITUMEN	<u>E0B</u>		
ROAD PAVEMENT			
BENCHMARK		▲ BM: 115 RL: 165.332	
BATTERS	11111111		
CONCRETE PATHWAY			
CONTOURS	99.5	99.5	-99.5-
SITE REGRADING AREA	CUT FILL		
SERVICE LINES SEWER, GAS, WATER, ELECTRICITY	S	S — S — — — — — — — — — — — — — — — — —	S
COMMUNICATION LINES TELSTRA, FIBRE OPTIC	т	T	T
OVER HEAD LINES AND POLES	PP	PP	PP
SERVICE PITS TELECOM PIT, ACCESS CHAMBER, HYDRANT, STOP VALVE, AIR VALVE	TP AC H SV AV		
LIMIT OF CONSTRUCTION			
LIMIT OF STAGE			
FENCE POST AND RAIL FENCE SECURITY FENCE			
LOT NUMBERS	LOTNO	LOTNO	LOTNO
TREES TO REMOVE			
TREES		6	
RETAINING WALL			

ISSUED FOR DEVELOPMENT APPLICATION

12/12/2014 ISSUED FOR CLIENT REVIEW
 JM
 JM
 SG
 17/12/2014
 ISSUED FOR CLIENT REVIEW

 JM
 JM
 TW
 SG
 18/12/2014
 ISSUED FOR DEVELOPMENT APPLICATION
 JM JM SG SG 4/03/2015 AMENDED SOUTHERN BOUNDARY RETAINING WALL
 JM
 JM
 SG
 SG
 6/03/2015
 AMENDED SOUTHERN BOUNDARY RETAINING WALL DETAIL

 JM
 JM
 CB
 SG
 6/12/2013
 Details
 Details
 Details
 Revision Details

sclaimer and Copyright: ALL DIMENSIONS TO BE CHECKED ON SITE BY

FIEAust. CPEng,

v-STUART GREEN

CSR LIMITED

327-335 BURLEY ROAD, HORSLEY PARK


ROAD & DRAINAGE DESIGN





STANDARD NOTES & LEGEND


X13044.002 1.2 & 3 DA 001


07
















ISSUED FOR DEVELOPMENT APPLICATION

HE H	Issue		Drawn	Design	Check	Appd.	Date	Revision Details
100130	Fir	st	JM	JM	CB	SG	6/12/2013	Revision Details
X1304	l	07	JM	JM	SG	SG	6/03/2015	AMENDED SOUTHERN BOUNDARY RETAINING WALL DETAIL
4-CSRHORSLEY	ď	06	JM	JM	SG	SG	4/03/2015	AMENDED SOUTHERN BOUNDARY RETAINING WALL
	evis	05	JM	JM	TW	SG	18/12/2014	ISSUED FOR DEVELOPMENT APPLICATION
	sions	04	JM	JM	SG		17/12/2014	ISSUED FOR CLIENT REVIEW
A PROL		03	JM	JM	TW		12/12/2014	ISSUED FOR CLIENT REVIEW
DRWA		02	JM	JM			5/12/2014	ISSUED FOR CLIENT REVIEW





	Authorised for Issue:
	BY:STUART GREEN
1	FIEAust. CPEng,
4	Manager - Urban Development
	SIGN:
4	SAL
ity	01.19
ed	DATE: 1.7


	CSR LIMITED
t	327-335 BURLEY ROAD, HORSLEY PARK


ROAD & DRAINAGE DESIGN

BROWN
Smart Consulting ©2014 www.brownconsulting.com.au


Drawing Title:
INTERSECTION PLAN

 Project No.:	Stage:	Milestone:	Dwg No.:	Revision:
X13044.002	1, 2 & 3	DA	105	07
booooi	Ī		Į	






LONGITUDINAL SECTION CENTRELINE - ROAD No.01 CONT.




TYPICAL CROSS SECTION - ROAD No.01 CH 0 to CH 720 & CH 998.03 to END SCALE 1:100 (NATURAL)



TYPICAL CROSS SECTION - ROAD No.01 CH 720 to CH 998.03 SCALE 1:100 (NATURAL)

ISSUED FOR DEVELOPMENT APPLICATION

HO	Fir	st	JM	JM Design	Chook	SG	6/12/2013 Date	Revision Details
±X13X13044		07			0.00.00	AMENDED SOUTHERN BOUNDARY RETAINING WALL DETAIL		
M-CS	œ	06	JM	JM	SG	SG	4/03/2015	AMENDED SOUTHERN BOUNDARY RETAINING WALL
RHOR.	evis	05	JM	JM	TW	SG	18/12/2014	ISSUED FOR DEVELOPMENT APPLICATION
S.EY	ions	04	JM	JM	SG		17/12/2014	ISSUED FOR CLIENT REVIEW
PARKDRA		03	JM	JM	TW		12/12/2014	ISSUED FOR CLIENT REVIEW
8		02	JM	JM			5/12/2014	ISSUED FOR CLIENT REVIEW









CSR LIMITED


327-335 BURLEY ROAD, HORSLEY PARK ROAD & DRAINAGE DESIGN




ROAD No.01 LONGITUDINAL & TYPICAL CROSS SECTIONS

Stage: Milestone: Dwg No.: Revisi 1, 2 & 3 DA 202 07 X13044.002











SOURCE OF AERIAL IMAGE: NEARMAP, DATED: 21/11/2014

ISSUED FOR DEVELOPMENT APPLICATION

E	Issi	ue	Drawn	Design	Check	Appd.	Date	Revision Details
WISKISH - CSRHORSLEY PARKI	Fir	st	JM	JM	CB	SG	6/12/2013	Devision Detella
	ш	07	JM	JM	SG	SG	6/03/2015	AMENDED SOUTHERN BOUNDARY RETAINING WALL DETAIL
	œ	06	JM	JM	SG	SG	4/03/2015	AMENDED SOUTHERN BOUNDARY RETAINING WALL
	evis	05	JM	JM	TW	SG	18/12/2014	ISSUED FOR DEVELOPMENT APPLICATION
	ons	04	JM	JM	SG		17/12/2014	ISSUED FOR CLIENT REVIEW
APRIDRAM								

0 20 40 60 80 100 120 140 160 180 200 SCALE 1:2000 (A1) SCALE 1:4000 (A3)

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE BY
CONTRACTOR PRIOR TO CONSTRUCTION. USE
WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting Pty Ltd

CONSULT AUSTRALA

Enc.



CSR LIMITED


327-335 BURLEY ROAD, HORSLEY PARK ROAD & DRAINAGE DESIGN

B	ROWN
©)2014	Smart Consulting

Drawing Title:
EARTH BUND LAYOUT PLAN


 Project No.:
 Stage:
 Milestone:
 Dwg No.:
 Revision

 X13044.002
 1, 2 & 3 DA
 604
 07



ISSUED FOR DEVELOPMENT APPLICATION

86 04 JM JM SG 17/12/2014 ISSUED FOR CLIENT REVIEW 98 00 05 JM JM TW SG 18/12/2014 ISSUED FOR DEVELOPMENT APPLICATION	0 20 40 60 80 100 120 140 160 180 200	Disclaimer and Copyright: ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.	Authorised for Issue: BY:STUART GREEN FIEAust. CPEng, Manager - Urban Development	CSR LIMITED	BROWN	Drawing Title: EARTH BUND SECTIONS
March Marc	SCALE 1:2000 (A1) SCALE 1:4000 (A3)	© Brown Consulting Pty Ltd CONSULT AUSTRALIA Quality Endorsed Company	DATE:	Project: 327-335 BURLEY ROAD, HORSLEY PARK ROAD & DRAINAGE DESIGN	Smart Consulting ©2014 www.brownconsulting.com.au	Project No : Stage: Milestone: Dwg No.: Revision: X13044.002 1, 2 & 3 DA 605 07



SEDIMENT & EROSION CONTROL NOTES


- THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL THE CONTRACT LOS SHALL IMPLEMENT ALL SOIL EROSION AND SEMINENT CURT ROL MEASURES PRIOR TO THE COMMENCEMENT OF ANY WORKS BEING CARRIED OUT. ALL SOIL AND EROSION MEASURES SHALL BE MAINTAINED AND KEPT IN PLACE FOR THE FULL DURATION OF THE WORKS AND SHALL ONLY BE REMOVED AT FINAL STABILISATION OF THE WORKS. WHERE IT IS NECESSARY TO UNDERTAKE STRIPPING IN ORDER TO CONSTRUCT A SEDIMENT CONTROL DEVICE ONLY SUFFICIENT GROUND SHALL BE STRIPPED TO ALLOW CONSTRUCTION.
- 2. ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED AS INDICATED ON THESE DRAWINGS. LOCATION AND EXTENT OF SOIL AND WATER MANAGEMENT DEVICES IS DIAGRAMMATIC ONLY AND THE ACTUAL REQUIREMENTS SHALL BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT
- CONFORMITY WITH THIS PLAN SHALL IN NO WAY REDUCE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AGAINST WATER DAMAGE DURING THE COURSE OF THE CONTRACT. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ANY NECESSARY CONTROL IS IN PLACE EVEN THOUGH SUCH CONTROL MAY NOT BE SHOWN
- THE CONTRACTOR SHALL INFORM ALL SUBCONTRACTORS AND ALL EMPLOYEES OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSTREAM AREAS
- APART FROM SEDIMENT BASINS, THE CONTRACTOR SHALL REGULARLY MAINTAIN SEDIMENT AND EROSION CONTROL STRUCTURES AND DESILT SUCH STRUCTURES PRIOR TO THE REDUCTION IN CAPACITY OF 30% DUE TO ACCUMULATED SEDIMENT. THE SEDIMENT SHALL BE DISPOSED OF ON SITE IN A MANNER APPROVED BY THE ENGINEER.
- 6 THE CONTRACTOR SHALL TEMPORARILY REHABILITATE WITHIN TEN (10) DAYS AND DISTURBED AREAS PROVIDING A MINIMUM 60% COVER. FINAL REHABILITATION IS TO BE PROVIDED WITHIN A FURTHER 60 DAYS WITH A MINIMUM 70% COVER.
- THE CONTRACTOR SHALL PROVIDE WATERING OF THE VEGETATED BATTERS FOR MAINTENANCE PERIOD. PLANT, MACHINERY AND VEHICLES SHALL NOT BE DRIVEN OVER GRASSED AREAS UNLESS ON AN APPROVED HAULAGE ROUTE.
- ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS QUICKLY AS POSSIBLE TO MINIMISE RISK OF EROSION.
- SITE ACCESS SHALL BE RESTRICTED TO THE NOMINATED POINTS. THE CONTRACTOR SHALL PROVIDE STABILISED SITE ACCESS.
- LARGE, UNPROTECTED AREAS MUST BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO REDUCE WIND EROSION. ERECT BARRIER FENCING TO MINIMISE LAND DISTURBANCE BY PREVENTING VEHICULAR AND PEDESTRIAN ACCESS. TO AREAS BEING REHABILATATED AND LANDS THAT DO NOT NEED TO BE DISTURBED BY THIS PROJECT.
- 11. STOCKPILE TOPSOILS, SUBSOILS AND OTHER MATERIALS SEPARATELY.
- TOPSOIL SHALL BE STORED IN LOW MOUNDS NO MORE THAN 2 METRES HIGH AND RE-USED WITHIN TWO MONTHS TO MAINTAIN ACTIVE POPULATIONS OF BENEFICIAL SOIL
- 13. PLACE ALL STOCKPILES AT LEAST FIVE METRES FROM AREAS OF LIKELY
 CONCENTRATED OR HIGH VELOCITY FLOWS, ESPECIALLY EARTH BANKS AND ROADS. IF
 NECESSARY, EARTH BANKS OR DRAINS WILL BE CONSTRUCTED TO DIVERT LOCALISED
- TURN TOPSOIL STOCKPILES OVER TO AERATE THEM AT MONTHLY INTERVALS. ENSURE VEGETATION IS NOT INCORPORATED INTO THE SOIL.

- 15. AVOID REVERSING THE SOIL PROFILE MATERIALS DURING FILL OPERATIONS REPLACE DISTURBED SOILS IN THEIR ORIGINAL ORDER.
- 16. ON COMPLETION OF MAJOR EARTHWORKS AND BEFORE ADDING TOPSOIL, LEAVE DISTURBED LANDS WITH A LOOSE SURFACE. ALTERNATELY, DISTURBED AREAS PREVIOUSLY COMPACTED BY CONSTRUCTION WORKS WILL BE RIPPED TO MORE THAN 200-MM ALONG THE CONTOUR BEFORE APPLYING TOPSOIL
- 17. PROVIDING MATERIALS ARE AVAILABLE, SPREAD TOPSOIL TO A MINIMUM DEPTH OF 75mm IN REVEGETATION AREAS ON SLOPES OF 4(H):1(V) OR LESS AND TO A DEPTH OF 40 TO 60mm IN REVEGETATION AREAS STEEPER THAN 4:1.
- 18. LEAVE TOPSOIL IN A SCARIFIED OR ROUGH CONDITION ONCE REPLACED TO HELP MOISTURE INFILTRATION AND REDUCE SOIL EROSION.
- 19. ENSURE SOIL IS THOROUGHLY SOAKED TO A DEPTH OF 75mm (RAIN OR IRRIGATION) IMMEDIATELY BEFORE PLANTING.
- 20. HANDLE TOPSOIL ONLY WHEN IT IS MOIST (NOT WET OR DRY) TO AVOID DECLINE OF
- 21. THE CONTRACTOR SHALL MAINTAIN A LOG BOOK DETAILING:
 RECORDS OF ALL RAINFALL

 - CONDITION OF SOIL AND WATER MANAGEMENT STRUCTURES
 ANY APPLICATION OF FLOCCULATING AGENTS TO SEDIMENT BASIN
 - VOLUMES OF ALL WATER DISCHARGED FROM SEDIMENT BASINS
- ANY ADDITIONAL REMEDIAL WORKS REQUIRED
- 22. THE LOG BOOK SHALL BE MAINTAINED ON A WEEKLY BASIS AND BE MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. THE ORIGINAL LOG BOOK SHALL BE ISSUED TO THE PROJECT MANAGER AT THE COMPLETION OF WORKS
- 23. ALL ROAD EMBANKMENTS TO BE STABILISED AS PER LANDSCAPE ARCHITECTS
- 24. A SELF AUDITING PROGRAM SHOULD BE ESTABLISHED BASED ON A CHECK SHEET A SECH ADDITION POWDART SHOULD BE 23 MADIEND BASED ON A CHECK SHEET SHOULD BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE AND IMMEDIATELY FOLLOWING RAINFALL EVENTS THAT CAUSE RUNOFF.
- WALKING AROUND THE SITE SYSTEMATICALLY (E.G. CLOCKWISE)
- RECORDING THE CONDITION OF EVERY BMP EMPLOYED
- RECORDING MAINTENANCE REQUIREMENTS (IF ANY) FOR EACH BMF RECORDING THE SITE WHERE SEDIMENT IS DISPOSED.
- FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET TO THE PROJECT MANAGER/DEVELOPER/SITE OPERATOR FOR THEIR INFORMATION

- LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE - ALL INSTALLED EROSION AND SEDIMENT CONTROL MEASURES, ENSURING THEY ARE
- · ARFAS THAT MIGHT SHOW WHETHER SEDIMENT OR OTHER POLLUTANTS ARE
- AREAS THAI FINIOT SHOW WHICH THEY SEUMENT OR OTHER POLLOTANTS ARE
 LEAVING THE SITE OR HAVE POTENTIAL TO DO SO

 ALL DISCHARGE POINTS, TO ASSESS WHETHER THE EROSION AND SEDIMENT
 CONTROL MEASURES ARE EFFECTIVE IN PREVENTING IMPACTS TO THE RECEIVING
- 27. A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE, AND IMMEDIATELY FOLLOWING RAINFALL EVENTS GREATER THAN 5mm IN 24 HOURS.



- Construct sediment fences as close as possible to being parallel to the contours of the site, but with small returns as shown in the drawing to limit the catchment area of any one section. The catchment area should be small enough to limit water flow if concentrated at one point to 50 litres per second in the design storm event, usually the 10-year event.
- Cut a 150-mm deep trench along the upslope line of the fence for the bottom of the fabric to
- pe entrenched.

 3. Drive 15 metre long star pickets into ground at 2.5 metre intervals (max) at the downslope edge of the trench. Ensure any star pickets are fitted with safety caps.

 5. Fix self-supporting geotextile to the upslope side of the posts ensuring it goes to the base of the trench. Fix the geotextile with wire ties or as recommended by the manufacturer. Only use geotextile specifically produced for sediment fencing. The use of shade cloth for this purpose is not satisfactory.
- purpose is not sairs acrory. S. Join sections of fabric at a support post with a 150-mm overlap. 6. Backfill the trench over the base of the fabric and compact it thoroughly over the geotextile

which the water originated. Approval might be required to discharge into other subcatchments SEDIMENT FENCE SD 5-6

> sclaimer and Copyright ALL DIMENSIONS TO BE CHECKED ON SITE BY

FIEAust. CPEng, Manager - Urban Development

DO

#

GEOTEXTILE INLET FILTER

In Sabricate a sediment barrier made from geotextile or straw bales.

2. Follow Standard Drawing 6-8 for installation procedures for geofabric. Reduce the picket spacing to 1 metre centres.

3. In waterways, artificial sag points can be created with sandbags or earth banks as shown in the drawing.

4. Do not cover the inlet with geotextile unless the design is adequate to allow for all waters to bypass it.

1. Install a 400 mm minimum wide roll of turf on the footpath next to the kerb and at the same level as the top of the kerb.

2. Lay 1.4 metre long turf strips normal to the kerb every 10 metres.

3. Rehabilitate disturbed soil behind the turf strip following the ESCP/SWMP.

KERBSIDE TURF STRIP

Direction of flow

Construction Notes

Construction Notes

SD 6-12

SD 6-13

All batter grades 2(H):1(V) max.

STUART GREEN

EARTH BANK (LOW FLOW)

1. Build with gradients between 1 percent and 5 percent 2. Avoid removing trees and shrubs if possible - work around them 3. Ensure the structures are free of projections or other irregularities that could

4. Build the drains with circular, parabolic or trapezoidal cross sections, not

5. Ensure the banks are properly compacted to prevent failure.
6. Complete permanent or temporary stabilisation within 10 days of construction.

CSR LIMITED

Construction Notes Construct the straw bale filter as close as possible to being parallel to the contours of the site.
 Place bales lengthwise in a row with ends tightly abutting. Use straw to fill any gaps between 2. Place bales lengthwise in a row with enus ugriny abutting. Use straw to minary gaps between bales. Straws are to be placed parallel to ground.
3. Ensure that the maximum height of the filter is one bale.
4. Embed each bale in the ground 75 mm to 100 mm and anchor with two 1.2 metre star pickets or stakes. Angle the first star picket or stake in each bale towards the previously laid bale. Drive them 600 mm into the ground and, if possible, flush with the top of the bales. Where star pickets are used and they protrude above the bales, ensure they are fitted with esofaby rane.

ELEVATION


satery caps.


5. Where a straw bale filter is constructed downslope from a disturbed batter, ensure the bales are placed 1 to 2 metres downslope from the toe.

6. Establish a maintenance program that ensures the integrity of the bales is retained - they could require replacement each two to four months.

STRAW BALE FILTER

SD 6-7





4. Where they are to be in place for more than 10 days, stabilise following the approved ESCP or SWMP to reduce the C-factor to less than 0.10.

5. Construct earth banks (Standard Drawing 5-5) on the upslope side to divert water around.

stockpiles and sediment fences (Standard Drawing 6-8) 1 to 2 metres downslope.

STOCKPILES

ISSUED FOR DEVELOPMENT APPLICATION

327-335 BURLEY ROAD, HORSLEY PARK



SEDIMENT & EROSION CONTROL NOTES & DETAILS

X13044 002 1.2 & 3 DA 702 07

 JM
 JM
 SG
 17/12/2014
 ISSUED FOR CLIENT REVIEW

 JM
 JM
 TW
 SG
 18/12/2014
 ISSUED FOR DEVELOPMENT APPLICATION
 JM JM SG SG 4/03/2015 AMENDED SOUTHERN BOUNDARY RETAINING WALI
 JM
 JM
 SG
 SG
 6/03/2015
 AMENDED SOUTHERN BOUNDARY RETAINING WALL DET

 JM
 JM
 CB
 SG
 6/12/2013
 Participan
 Revision Details

EARTH BANK (HIGH FLOWS)

12/12/2014 ISSUED FOR CLIENT REVIEW

Construction Notes

1. Construct at the gradient specified on the ESCP or SWMP, normally between 1 and 5 percent

2. Avoid removing trees and shrubs if possible – work around them.

3. Ensure the structures are free of projections or other irregularities that could impede water flow.

4. Build the drains with circular, parabolic or trapezoidal cross sections, not V-shaped, at the dimensions shown on the SWMP.

5. Ensure the banks are properly compacted to prevent failure.

6. Complete permanent or temporary stabilisation within 10 days of construction following Table 5.2 in Landcom (2044).

7. Where discharging to erodible lands, ensure they outlet through a properly constructed level spreader.

8. Construct the level spreader at the gradient specified on the ESCP or SWMP, normally less than 1 percent or level.

9. Where possible, ensure they discharge waters onto either stabilised or undisturbed disposal sites within the same subcarchment area from which the water originated. Approval might be required to discharge into other s

Level Spreader (or Sill)

Construction Notes

SD 6-8

ROAD & DRAINAGE DESIGN

SD 5-5